OEM7
Commands and Logs
Reference Manual

OEM7 Commands and Logs Reference Manual

Publication Number: D100404

Revision Level: v6A

Revision Date: September 2026

Firmware Version:

- 7.10.02 / OM7MR1002RN0000: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, GT7800
- 7.09.06 / OM7MR0906RN0000 SMART7, SMART2, OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, GT7800

Proprietary notice

This document and the information contained herein are the exclusive properties of the legal entities that comprise the Autonomous Solutions division of the Hexagon AB group of companies (“Hexagon”).

No part of this document may be reproduced, displayed, distributed, or used in any medium, in connection with any other materials, or for any purpose without prior written permission from Hexagon. Applications for permission may be directed to contact.ap@hexagon.com. Unauthorized reproduction, display, distribution or use may result in civil as well as criminal sanctions under the applicable laws. Hexagon aggressively protects and enforces its intellectual property rights to the fullest extent allowed by law.

This document and the information contained herein are provided AS IS and without any representation or warranty of any kind. Hexagon disclaims all warranties, express or implied, including but not limited to any warranties of merchantability, non-infringement, and fitness for a particular purpose. Nothing herein constitutes a binding obligation on Hexagon.

The information contained herein is subject to change without notice.

ALIGN, GLIDE, Inertial Explorer, NovAtel, OCEANIX, OEM6, OEM7, PwrPak7, RELAY, RTK ASSIST, SPAN, STEADYLINE, TerraStar and Waypoint are trademarks of Hexagon AB and/or its subsidiaries and affiliates, and/or their licensors. All other trademarks are properties of their respective owners.

© Copyright 2017 – 2026 Hexagon AB and/or its subsidiaries and affiliates. All rights reserved.

Table of contents

Figures

Tables

Customer Support

Foreword

Chapter 1 Messages

1.1 ASCII 35
1.2 Abbreviated ASCII 37
1.3 Binary 39
1.3.1 Virtual ports 44
1.4 Description of ASCII and binary logs with short headers 51
1.5 Message responses 52
1.5.1 Abbreviated ASCII response 52
1.5.2 ASCII response 52
1.5.3 Binary response 52
1.6 GLONASS slot and frequency numbers 54
1.6.1 PRN numbers 55
1.7 GPS reference time status 55
1.8 Message time stamps 57
1.9 Decoding of the GPS reference week number 57
1.10 32-bit CRC 57

Chapter 2 Commands

2.1 Command formats 61
2.1.1 Optional parameters 61
2.2 Command settings 61
2.3 Command defaults 62
2.4 ADJUST1PPS 63
2.5 ALIGNAUTOMATION 70
2.6 ANTENNAPOWER 72
2.7 ANTENNATYPE 74
2.8 APPROXPOSTIMEOUT 76
2.9 ASSIGN 77
2.10 ASSIGNALL 80
2.11 ASSIGNLBANDBEAM 83
2.12 AUTH 85
2.13 AUTOSURVEY 89
2.14 BASEANTENNAPCO 92
2.15 BASEANTENNAPCV 94
2.16 BASEANTENNATYPE 95
2.17 BDSECUTOFF 107

2.18 BESTVELTYPE 109
2.19 BLUETOOTHCONTROL 110
2.20 CANCONFIG 112
2.21 CCOMCONFIG 114
2.22 CLOCKADJUST 117
2.23 CLOCKCALIBRATE 119
2.24 CLOCKOFFSET 122
2.25 CNOUPDATE 123
2.26 COMCONTROL 124
2.27 CONFIGCODE 127
2.28 DATADECODESIGNAL 129
2.29 DATUM 133
2.30 DATUMTRANSFORMATION 135
2.31 DGPSTXID 138
2.32 DIFFCODEBIASCONTROL 140
2.33 DISPATCHSET 141
2.34 DLLTIMECONST 143
2.35 DNSCONFIG 146
2.36 DOPPLERWINDOW 147
2.37 DUALANTENNAALIGN 149
2.38 DYNAMICS 150
2.39 ECHO 152
2.40 ECUTOFF 155
2.41 ELEVATIONCUTOFF 157
2.42 ETHCONFIG 160
2.43 EVENTINCONTROL 162
2.44 EVENTOUTCONTROL 164
2.45 EXTERNALCLOCK 168
2.46 FILEAUTOTRANSFER 171
2.47 FILECONFIG 173
2.48 FILEDELETE 175
2.49 FILEMEDIACONFIG 176
2.50 FILEROTATECONFIG 178
2.51 FILETRANSFER 180
2.52 FIX 182
2.53 FORCEGALE6CODE 185
2.54 FORCEGLOL2CODE 186
2.55 FORCEGPSL2CODE 187
2.56 FREQUENCYOUT 189
2.57 FRESET 192
2.58 GALECUTOFF 195
2.59 GENERATEALIGNCORRECTIONS 197
2.60 GENERATEDIFFCORRECTIONS 199
2.61 GENERATERTKCORRECTIONS 200

2.62 GEODETICDATUM 203
2.63 GGAQUALITY 205
2.64 GLIDEINITIALIZATIONPERIOD 207
2.65 GLOECUTOFF 208
2.66 HDTOUTTHRESHOLD 210
2.67 HEADINGOFFSET 211
2.68 ICOMCONFIG 213
2.69 INTERFACEMODE 217
2.69.1 SPAN systems 217
2.70 IONOCONDITION 223
2.71 IPCONFIG 224
2.72 IPSERVICE 226
2.73 ITBANDPASSCONFIG 229
2.74 ITDETECTCONFIG 231
2.75 ITFRONTENDMODE 233
2.76 ITPROGFILTCONFIG 236
2.77 ITSPECTRALANALYSIS 239
2.78 ITWARNINGCONFIG 243
2.79 J1939CONFIG 244
2.80 LOCKOUT 246
2.81 LOCKOUTSATELLITE 247
2.82 LOCKOUTSYSTEM 248
2.83 LOG 249
2.83.1 Binary 250
2.83.2 ASCII 252
2.84 LOGIN 254
2.85 LOGOUT 256
2.86 LUA 257
2.87 MAGVAR 259
2.88 MARKCONTROL 261
2.89 MEDIAFORMAT 264
2.90 MODEL 265
2.91 MOVINGBASESTATION 267
2.92 NAVICECUTOFF 269
2.93 NMEABEIDOUTALKER 271
2.94 NMEAFORMAT 272
2.95 NMEANUMERICSTATIONID 275
2.96 NMEATALKER 276
2.97 NMEAVERSION 278
2.98 NTRIPCONFIG 279
2.99 NTRIPSOURCETABLE 281
2.100 NVMRESTORE 282
2.101 NVMUSERDATA 283
2.102 OUTPUTDATUM 284
2.103 PDPFILTER 286

2.103.1 GLIDE position filter 286
2.104 PDPMODE 288
2.105 PGNCONFIG 290
2.106 $PMDT 291
2.107 POSAVE 293
2.108 POSTIMEOUT 295
2.109 PPPBASICCONVERGEDCRITERIA 296
2.110 PPPCONVERGEDCRITERIA 297
2.111 PPPDYNAMICS 298
2.112 PPPDYNAMICSEED 299
2.113 PPPRESET 301
2.114 PPPSEED 302
2.115 PPPSOURCE 305
2.116 PPPTIMEOUT 306
2.117 PPSCONTROL 307
2.118 PPSCONTROL2 309
2.119 PRNMAPPING 311
2.120 PROFILE 313
2.121 PSRDIFFSOURCE 316
2.122 PSRDIFFSOURCETIMEOUT 318
2.123 PSRDIFFTIMEOUT 319
2.124 PTPMODE 320
2.125 PTPPROFILE 321
2.126 PTPTIMESCALE 323
2.127 QZSSECUTOFF 324
2.128 RADARCONFIG 326
2.129 RAIMMODE 328
2.129.1 Detection strategy 328
2.129.2 Isolation strategy 328
2.130 REFERENCESTATIONTIMEOUT 331
2.131 RESET 332
2.132 RFINPUTGAIN 333
2.133 RTKANTENNA 335
2.134 RTKASSIST 337
2.135 RTKASSISTTIMEOUT 338
2.136 RTKDYNAMICS 339
2.137 RTKINTEGERCRITERIA 340
2.138 RTKIONORESILIENCE 341
2.139 RTKMATCHEDTIMEOUT 342
2.140 RTKNETWORK 343
2.141 RTKPORTMODE 345
2.142 RTKQUALITYLEVEL 347
2.143 RTKRESET 348
2.144 RTKSOURCE 349
2.145 RTKSOURCETIMEOUT 351

2.146 RTKSVENTRIES 352
2.147 RTKTIMEOUT 353
2.148 RTKTRACKINGCONTROL 354
2.149 SATEL4CONFIG 355
2.150 SATEL9CONFIG 358
2.151 SATEL9CONFIGL 360
2.152 SATEL9CONFIGN 362
2.153 SATELCONTROL 364
2.154 SATELDETECT 365
2.155 SATELSTARTUPDETECT 366
2.156 SAVECONFIG 367
2.157 SAVEETHERNETDATA 368
2.158 SBASCONTROL 370
2.159 SBASECUTOFF 373
2.160 SBASTIMEOUT 374
2.161 SELECTCHANCONFIG 375
2.162 SEND 380
2.163 SENDHEX 382
2.164 SERIALCONFIG 383
2.165 SERIALPROTOCOL 387
2.166 SET4BITSBASPREAMBLE 389
2.167 SETADMINPASSWORD 390
2.168 SETAPPROXPOS 393
2.169 SETAPPROXTIME 394
2.170 SETBASERECEIVERTYPE 396
2.171 SETBESTPOSCRITERIA 397
2.172 SETDIFFCODEBIASES 398
2.173 SETIONOTYPE 400
2.174 SETNAV 401
2.175 SETROVERID 403
2.176 SETTIMEBASE 404
2.177 SETTIMESOURCE 406
2.178 SETTROPOMODEL 408
2.179 SETUTCLEAPSECONDS 409
2.180 SOFTLOADCOMMIT 410
2.181 SOFTLOADDATA 411
2.182 SOFTLOADFILE 412
2.183 SOFTLOADRESET 414
2.184 SOFTLOADSETUP 415
2.185 SOFTLOADSREC 417
2.186 STATUSCONFIG 418
2.187 STEADYLINE 420
2.188 STEADYLINEDIFFERENTIALTIMEOUT 422
2.189 SURVEYPOSITION 423

2.190 TECTONICSCOMPENSATIONSOURCE 425
2.191 TERRASTARAUTOCHANCONFIG 426
2.192 THISANTENNAPCO 428
2.193 THISANTENNAPCV 429
2.194 THISANTENNATYPE 430
2.195 TILTCOMPENSATIONCONTROL 431
2.196 TILTFILTER 432
2.197 TILTZERO 433
2.198 TRACKSIGNAL 435
2.199 TRACKSV 437
2.200 TUNNELESCAPE 439
2.201 UALCONTROL 441
2.202 UNASSIGN 443
2.203 UNASSIGNALL 445
2.204 UNDULATION 446
2.205 UNLOCKOUT 448
2.206 UNLOCKOUTALL 449
2.207 UNLOCKOUTSATELLITE 450
2.208 UNLOCKOUTSYSTEM 451
2.209 UNLOG 452
2.209.1 Binary 452
2.209.2 ASCII 453
2.210 UNLOGALL 454
2.211 USBSTICKEJECT 455
2.212 USERCANCLOSE 456
2.213 USERCANOPEN 457
2.214 USERCANWRITE 460
2.215 USERDATUM 463
2.216 USEREXPDATUM 465
2.217 USERI2CBITRATE 468
2.218 USERI2CREAD 469
2.219 USERI2CWRITE 471
2.220 UTMZONE 474
2.221 WIFIALIGNAUTOMATION 476
2.222 WIFIAPCHANNEL 479
2.223 WIFIAPIPCONFIG 480
2.224 WIFIAPPASSKEY 481
2.225 WIFIAPSSID 483
2.226 WIFIMODE 484
2.227 WIFINETCONFIG 486

Chapter 3 Logs

3.1 Log types 489
3.1.1 Log type examples 489
3.2 ALIGNBSLNENU 491

3.3 ALIGNBSLNXYZ 493
3.4 ALIGNDOP 495
3.5 ALMANAC 496
3.6 AUTHCODES 498
3.7 AVEPOS 500
3.8 BDSALMANAC 502
3.9 BDSBCNAV1EPHEMERIS 504
3.10 BDSBCNAV1RAWMESSAGE 507
3.11 BDSBCNAV2EPHEMERIS 508
3.12 BDSBCNAV2RAWMESSAGE 511
3.13 BDSBCNAV3EPHEMERIS 512
3.14 BDSBCNAV3RAWMESSAGE 515
3.15 BDSBCNAV3RAWMESSAGE2 516
3.16 BDSCLOCK 517
3.17 BDSEPHEMERIS 519
3.18 BDSIONO 522
3.19 BDSRAWNAVSUBFRAME 523
3.20 BESTDATUMINFO 524
3.21 BESTGNSSDATUMINFO 526
3.22 BESTPOS 527
3.23 BESTSATS 535
3.24 BESTUTM 539
3.25 BESTVEL 542
3.26 BESTXYZ 545
3.27 BSLNXYZ 548
3.28 CHANCONFIGLIST 550
3.29 CLOCKMODEL 555
3.30 CLOCKSTEERING 557
3.31 CYBERSECEVENTS 560
3.32 DATUMTRANSFORMATIONS 563
3.33 DISPATCHMESSAGES 566
3.34 DISPATCHRECEIPT 569
3.35 DISPATCHSCHEDULE 571
3.36 DUALANTENNAHEADING 579
3.37 ETHSTATUS 581
3.38 FILELIST 582
3.39 FILESTATUS 584
3.40 FILESYSTEMCAPACITY 586
3.41 FILESYSTEMSTATUS 588
3.42 FILETRANSFERSTATUS 590
3.43 GALALMANAC 592
3.44 GALCLOCK 594
3.45 GALCNAVRAWPAGE 596
3.46 GALFNAVEPHEMERIS 597

3.47 GALFNAVRAWALMANAC 600
3.48 GALFNAVRAWEPHEMERIS 601
3.49 GALFNAVRAWPAGE 603
3.50 GALHASRAWMT 604
3.51 GALINAVEPHEMERIS 606
3.52 GALINAVRAWALMANAC 609
3.53 GALINAVRAWDATA 610
3.54 GALINAVRAWEPHEMERIS 611
3.55 GALINAVRAWWORD 612
3.56 GALIONO 613
3.57 GEODETICDATUMS 614
3.58 GLMLA 616
3.59 GLOALMANAC 618
3.60 GLOCLOCK 620
3.61 GLOEPHEMERIS 622
3.62 GLORAWALM 626
3.63 GLORAWEPHEM 628
3.64 GLORAWFRAME 630
3.65 GLORAWSTRING 632
3.66 GPALM 633
3.67 GPGGA 635
3.68 GPGGALONG 638
3.69 GPGLL 640
3.70 GPGRS 642
3.71 GPGSA 646
3.72 GPGST 648
3.73 GPGSV 650
3.74 GPHDT 653
3.75 GPHDTDUALANTENNA 654
3.76 GPRMB 655
3.77 GPRMC 658
3.78 GPSCNAVRAWMESSAGE 660
3.79 GPSEPHEM 661
3.80 GPVTG 665
3.81 GPZDA 667
3.82 HEADING2 668
3.83 HEADINGEXT 671
3.84 HEADINGEXT2 672
3.85 HEADINGRATE 673
3.86 HEADINGSATS 675
3.87 HWMONITOR 677
3.88 IONUTC 680
3.89 IPSTATS 682
3.90 IPSTATUS 683

3.91 ITBANDPASSBANK ... 685
3.92 ITDETECTSTATUS ... 687
3.93 ITFILTTABLE ... 690
3.94 ITPROGFILTBANK ... 695
3.95 ITPSDDETECT ... 697
3.95.1 PSD samples ... 697
3.96 ITPSDFINAL ... 701
3.97 J1939STATUS ... 705
3.98 LBANDBEAMTABLE ... 707
3.99 LBANDTRACKSTAT ... 709
3.100 LOGLIST ... 712
3.100.1 Binary ... 713
3.100.2 ASCII ... 714
3.101 LUAFILELIST ... 715
3.102 LUAFILESYSTEMSTATUS ... 717
3.103 LUAOUTPUT ... 718
3.104 LUASTATUS ... 719
3.105 MARKPOS, MARK2POS, MARK3POS and MARK4POS ... 720
3.106 MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME ... 723
3.107 MASTERPOS ... 726
3.108 MATCHEDPOS ... 728
3.109 MATCHEDSATS ... 731
3.110 MATCHEDXYZ ... 733
3.111 MODELFEATURES ... 735
3.112 NAVICALMANAC ... 739
3.113 NAVICEPHEMERIS ... 741
3.114 NAVICIONO ... 744
3.115 NAVICRAWSUBFRAME ... 746
3.116 NAVICSYSCLOCK ... 747
3.117 NAVIGATE ... 749
3.118 NMEA standard logs ... 752
3.119 NOVATELXOBS ... 754
3.120 NOVATELXREF ... 755
3.121 OCEANIXINFO ... 756
3.122 OCEANIXSTATUS ... 758
3.123 PASSCOM, PASSAUX, PASSUSB, PASSICOM, PASSNCOM ... 760
3.124 PASSTHROUGH ... 764
3.125 PDPDATUMINFO ... 765
3.126 PDPDOP ... 766
3.127 PDPDOP2 ... 768
3.128 PDPPOS ... 770
3.129 PDPSATS ... 772
3.130 PDPVEL ... 774
3.131 PDPXYZ ... 775
3.132 PORTSTATS ... 777

3.133 PPPDATUMINFO 779
3.134 PPPPOS 780
3.135 PPPSATS 782
3.136 PPPSEEDAPPLICATIONSTATUS 784
3.137 PPPSEEDSTORESTATUS 786
3.138 PPPXYZ 787
3.139 PROFILEINFO 789
3.140 PROFILERESPONSE 793
3.141 PSRDATUMINFO 795
3.142 PSRDOP 796
3.143 PSRDOP2 798
3.144 PSRPOS 800
3.145 PSRSATS 802
3.146 PSRVEL 804
3.147 PSRXYZ 806
3.148 PTPDELTATIME 809
3.149 QZSSALMANAC 811
3.150 QZSSCNAVRAWMESSAGE 813
3.151 QZSSEPHEMERIS 815
3.152 QZSSIONUTC 818
3.153 QZSSRAWALMANAC 820
3.154 QZSSRAWCNAVMESSAGE 822
3.155 QZSSRAWEPHEM 823
3.156 QZSSRAWSUBFRAME 824
3.157 RADARSTATUS 825
3.158 RAIMSTATUS 827
3.159 RANGE 830
3.160 RANGECMP 838
3.161 RANGECMP2 843
3.162 RANGECMP4 851
3.163 RANGECMP5 863
3.164 RANGEGPSL1 873
3.165 RAWALM 875
3.166 RAWCNAVFRAME 877
3.167 RAWEPHEM 878
3.168 RAWGPSSUBFRAME 880
3.169 RAWGPSWORD 881
3.170 RAWSBASFRAME 882
3.171 RAWSBASFRAME2 883
3.172 REFSTATION 885
3.173 REFSTATIONINFO 887
3.174 ROVERPOS 889
3.175 RTCMV3 standard logs 891
3.175.1 Legacy observable messages 891
3.175.2 MSM observable messages 892

3.175.3 Station and antenna messages ... 893
3.175.4 Ephemeris messages ... 894
3.175.5 GLONASS bias information message ... 895
3.176 RTKASSISTSTATUS ... 896
3.177 RTKDATUMINFO ... 898
3.178 RTKDOP ... 899
3.179 RTKDOP2 ... 901
3.180 RTKPOS ... 903
3.181 RTKSATS ... 906
3.182 RTKVEL ... 908
3.183 RTKXYZ ... 910
3.184 RXCONFIG ... 913
3.185 RXCONFIGUSER ... 915
3.186 RXSTATUS ... 917
3.187 RXSTATUSEVENT ... 932
3.188 SAFEMODESTATUS ... 934
3.189 SATEL4INFO ... 937
3.190 SATEL9INFO ... 938
3.191 SATELSTATUS ... 940
3.192 SATVIS2 ... 942
3.193 SATXYZ2 ... 945
3.194 SAVEDSURVEYPOSITIONS ... 948
3.195 SBAS0 ... 950
3.196 SBAS1 ... 951
3.197 SBAS2 ... 952
3.198 SBAS3 ... 955
3.199 SBAS4 ... 957
3.200 SBAS5 ... 959
3.201 SBAS6 ... 961
3.202 SBAS7 ... 964
3.203 SBAS9 ... 967
3.204 SBAS10 ... 969
3.205 SBAS12 ... 971
3.206 SBAS17 ... 973
3.207 SBAS18 ... 975
3.208 SBAS24 ... 976
3.209 SBAS25 ... 978
3.210 SBAS26 ... 981
3.211 SBAS27 ... 983
3.212 SBASALMANAC ... 985
3.213 SOFTLOADSTATUS ... 987
3.214 SOURCETABLE ... 990
3.215 TECTONICSCOMPENSATION ... 993
3.216 TERRASTARINFO ... 994
3.217 TERRASTARSTATUS ... 997

3.218 TILTDATA 999
3.219 TIME 1000
3.220 TIMESYNC 1003
3.221 TRACKSTAT 1004
3.222 TRANSFERPORTSTATUS 1007
3.223 UPTIME 1009
3.224 USERANTENNA 1010
3.225 USERCANDATA 1012
3.226 USERCANSTATUS 1014
3.227 USERI2CRESPONSE 1016
3.228 VALIDMODELS 1018
3.229 VERIPOSINFO 1020
3.230 VERIPOSSTATUS 1022
3.231 VERSION 1023
3.232 WIFIAPSETTINGS 1029
3.233 WIFINETLIST 1032
3.234 WIFISTATUS 1034

Chapter 4 SPAN commands

4.1 ALIGNMENTMODE 1039
4.2 CONNECTIMU 1041
4.3 DMICONFIG 1044
4.4 EXTERNALPVAS 1046
4.5 INPUTGIMBALANGLE 1051
4.6 INSALIGNCONFIG 1053
4.7 INSCALIBRATE 1056
4.8 INSCOMMAND 1059
4.9 INSSEED 1060
4.10 INSTHRESHOLDS 1062
4.11 INSZUPT 1064
4.12 RELINSAUTOMATION 1065
4.13 RELINSCONFIG 1067
4.14 SETALIGNMENTORIENTATION 1069
4.15 SETALIGNMENTVEL 1070
4.16 SETHEAVEWINDOW 1071
4.17 SETIMUEVENT 1072
4.18 SETIMUPORTPROTOCOL 1073
4.19 SETIMUSPECS 1074
4.20 SETINITAZIMUTH 1076
4.21 SETINSPROFILE 1077
4.22 SETINSROTATION 1079
4.23 SETINSTRANSLATION 1082
4.24 SETINSUPDATE 1087
4.25 SETMAXALIGNMENTTIME 1088
4.26 SETRELINSOUTPUTFRAME 1089

4.27 SETUPSENSOR 1091
4.28 TAGNEXTMARK 1093
4.29 TIMEDEVENTPULSE 1094

Chapter 5 SPAN logs

5.1 Logs with INS or GNSS data 1097
5.2 BESTGNSSPOS 1098
5.3 BESTGNSSVEL 1100
5.4 CORRIMUDATA 1102
5.5 CORRIMUDATAS 1104
5.6 CORRIMUS 1106
5.7 DELAYEDHEAVE 1108
5.8 GIMBALLEDPVA 1109
5.9 HEAVE 1111
5.10 IMURATECORRIMUS 1112
5.11 IMURATEPVA 1114
5.12 IMURATEPVAS 1116
5.13 INSATT 1118
5.14 INSATTQS 1120
5.15 INSATTS 1122
5.16 INSATTX 1123
5.17 INSCALSTATUS 1127
5.18 INSCONFIG 1129
5.19 INSDATUMINFO 1133
5.20 INSPOS 1134
5.21 INSPOSS 1135
5.22 INSPOSX 1136
5.23 INSPVA 1138
5.24 INSPVACMP 1140
5.25 INSPVAS 1142
5.26 INSPVASDCMP 1144
5.27 INSPVAX 1146
5.28 INSSEEDSTATUS 1148
5.29 INSSPD 1150
5.30 INSSPDS 1151
5.31 INSSTDEV 1152
5.32 INSSTDEVS 1154
5.33 INSUPDATESTATUS 1156
5.34 INSVEL 1159
5.35 INSVELS 1160
5.36 INSVELUSER 1161
5.37 INSVELX 1164
5.38 MARK1PVA, MARK2PVA, MARK3PVA and MARK4PVA 1166
5.39 PASHR 1168
5.40 RAWDMI 1170

5.41 RAWIMU 1172
5.42 RAWIMUS 1176
5.43 RAWIMUSX 1179
5.44 RAWIMUX 1199
5.45 RELINSPVA 1203
5.46 SYNCHEAVE 1206
5.47 SYNCRELINSPVA 1207
5.48 SYNCRELINSPVACMP 1210
5.49 TAGGEDMARK1PVA, TAGGEDMARK2PVA, TAGGEDMARK3PVA and TAGGEDMARK4PVA 1214
5.50 TSS1 1216
5.51 VARIABLELEVERARM 1218

Chapter 6 Responses

Appendix A Example of bit parsing a RANGECMP4 log

A.1 Reference log decoding 1229
A.1.1 Reference header 1230
A.1.2 Reference satellite and signal block: GPS 1230
A.1.3 Reference measurement block header: GPS 1231
A.1.4 Reference measurement block: GPS 1232
A.1.5 Reference primary signal measurement block: GPS PRN 10 – L1CA 1233
A.1.6 Reference secondary signals measurement block: GPS PRN 10 – L2Y 1235
A.1.7 Reference third signals measurement block: GPS PRN 10 – L5Q 1236
A.1.8 Reference satellite and signal block: GLONASS 1238
A.1.9 Reference measurement block header: GLONASS PRN 38 1240
A.1.10 Reference primary signal measurement block: GLONASS PRN 38 – L1CA 1241
A.2 Differential log decoding 1243
A.2.1 Differential header 1243
A.2.2 Differential satellite and signal block 1243
A.2.3 Differential measurement block header 1245
A.2.4 Differential measurement block 1245
A.2.5 Differential primary signal measurement block GPS PRN 10 – L1CA 1246
A.2.6 Differential secondary signals measurement block GPS PRN 10 – L2Y 1248
A.2.7 Differential third signals measurement block GPS PRN 10 – L5Q 1250

Figures

Figure 1: Byte arrangements 35
Figure 2: 1PPS alignment 63
Figure 3: ADJUST1PPS connections 66
Figure 4: Pulse width and 1PPS coherency 190
Figure 5: HEADINGOFFSET example 211
Figure 6: Illustration of magnetic variation and correction 259
Figure 7: TTL pulse polarity 261
Figure 8: Moving base station ‘daisy chain’ effect 268
Figure 9: Using the SEND command 381
Figure 10: Default passwords 390
Figure 11: Illustration of SETNAV parameters 401
Figure 12: Illustration of undulation 446
Figure 13: WGS84 ECEF coordinate system 547
Figure 14: Navigation parameters 749
Figure 15: Pass through log data 762
Figure 16: Channel tracking example 832
Figure 17: STIM300 temperature word 1193

Tables

Table 1: Field type 34
Table 2: ASCII message header structure 36
Table 3: Abbreviated ASCII message header structure 37
Table 4: Binary message header structure 40
Table 5: Detailed port identifier 42
Table 6: Detailed port identifier – virtual ports 44
Table 7: Available port types 50
Table 8: Short ASCII message header structure 51
Table 9: Short binary message header structure 51
Table 10: Binary message response structure 53
Table 11: Binary message sequence 54
Table 12: PRN numbers for commands and logs 55
Table 13: GPS reference time status 55
Table 14: COM Port Signals Available for 1PPS 64
Table 15: ADJUST1PPS mode 68
Table 16: ANTENNAPOWER parameters 73
Table 17: User-defined antenna type 75
Table 18: Channel state 79
Table 19: Satellite system 81
Table 20: L-band assignment option 84
Table 21: AUTH command state 87
Table 22: Frequency type 93
Table 23: Antenna type 96
Table 24: Radome type 105
Table 25: CAN port speed 113
Table 26: CAN protocol 116
Table 27: Control options 125
Table 28: Port, signal and control availability on OEM7 receivers 126
Table 29: GNSS signal default and configurability 129
Table 30: Signal type 131
Table 31: Signal type 144
Table 32: Satellite system 148
Table 33: User dynamics 150
Table 34: Communications port identifiers 153

Table 35: Clock type 170
Table 36: Pre-defined values for oscillators 170
Table 37: Disk full action 179
Table 38: FIX parameters 183
Table 39: Fix types 184
Table 40: Signals tracked – channel configuration and L2type option 186
Table 41: GPS L2 code type 187
Table 42: Signals tracked – channel configuration and L2type option 188
Table 43: FRESET target 193
Table 44: Datum anchors 204
Table 45: ICOMCONFIG protocol 215
Table 46: Serial Port Interface Modes 220
Table 47: IP services 227
Table 48: RF path selection 232
Table 49: RF paths for OEM7 receivers 232
Table 50: Frequency bands 234
Table 51: Mode 234
Table 52: RF paths for OEM7 receivers 234
Table 53: Programmable filter ID 237
Table 54: Programmable filter mode 238
Table 55: Data sources for PSD samples 240
Table 56: Frequency types 241
Table 57: FFT sizes 242
Table 58: Log triggers 253
Table 59: Station ID conversion table 275
Table 60: NMEA talkers 277
Table 61: Epoch options 285
Table 62: Signal type 312
Table 63: Profile option 314
Table 64: PSRDIFFSOURCE type 317
Table 65: PTP profiles 321
Table 66: Response modes 327
Table 67: RAIM mode types 329
Table 68: RF paths for OEM7 receivers 334
Table 69: Network RTK mode 343
Table 70: RTK source type 350
Table 71: Base type 356

Table 72: Compatibility mode 357
Table 73: Radio control action 364
Table 74: System types 371
Table 75: SELECTCHANCONFIG factory defaults 375
Table 76: COM port identifiers 384
Table 77: Parity 385
Table 78: Handshaking 385
Table 79: Hardware handshaking compatibility 385
Table 80: Ports supporting RS-422 387
Table 81: Selection type 397
Table 82: System used for timing 405
Table 83: Systems used for time setting 407
Table 84: Available set up commands 416
Table 85: STEADYLINE mode 421
Table 86: Signal 436
Table 87: TRACKSV command condition 438
Table 88: User accuracy level supplemental position types and NMEA equivalents 441
Table 89: CAN bit rate 458
Table 90: UTM Zone commands 475
Table 91: Log type triggers 489
Table 92: Position averaging status 501
Table 93: Data source 523
Table 94: Transformation status 524
Table 95: Solution status 530
Table 96: Position or velocity type 531
Table 97: GPS and GLONASS signal-used mask 533
Table 98: Galileo and BeiDou signal-used mask 533
Table 99: Extended solution status 534
Table 100: Supplemental position types and NMEA equivalents 534
Table 101: Observation statuses 536
Table 102: GPS signal mask 537
Table 103: GLONASS signal mask 538
Table 104: Galileo signal mask 538
Table 105: BeiDou signal mask 538
Table 106: QZSS signal mask 538
Table 107: NavIC signal mask 538
Table 108: Definitions 547

Table 109: CHANCONFIGLIST signal type 552
Table 110: Clock model status 556
Table 111: Clock source 558
Table 112: Steering state 558
Table 113: Cyber-Security event type 561
Table 114: Dispatch message type 568
Table 115: Dispatch delivery method 568
Table 116: Active status 576
Table 117: Receiver features source 577
Table 118: Region restrictions 577
Table 119: Service period status 577
Table 120: Channel configuration optimization 578
Table 121: Baseline present 578
Table 122: File type 583
Table 123: Mass storage device 585
Table 124: File status 585
Table 125: Mass storage status 589
Table 126: File transfer status 591
Table 127: HAS status 605
Table 128: HAS message type 605
Table 129: Signal type 610
Table 130: Signal type 612
Table 131: Kp UTC leap second descriptions 621
Table 132: GLONASS ephemeris flags coding 625
Table 133: P1 flag range values 625
Table 134: GPS quality indicators 637
Table 135: Position precision of NMEA logs 639
Table 136: Position precision of NMEA logs 641
Table 137: NMEA positioning system mode indicator 641
Table 138: System and signal IDs 643
Table 139: NMEA positioning system mode indicator 657
Table 140: NMEA positioning system mode indicator 659
Table 141: Signal type 660
Table 142: URA variance 663
Table 143: NMEA positioning system mode indicator 666
Table 144: Solution Source 670
Table 145: Satellite system 676

Table 146: HWMONITOR Status 678
Table 147: RF paths for OEM7 receivers 689
Table 148: Filter warnings and constraints 690
Table 149: DDC filter type 692
Table 150: ITFILTTable status word 693
Table 151: Filter switches 694
Table 152: Interference detection status word 698
Table 153: RF frequency path 699
Table 154: RF paths for OEM7 receivers 700
Table 155: Spectral analysis status word 703
Table 156: Node status 705
Table 157: L-Band signal tracking status 710
Table 158: File system status 717
Table 159: Lua data source 718
Table 160: Script status 719
Table 161: Feature status 736
Table 162: Feature type 737
Table 163: GNSS time scales 748
Table 164: Navigation data type 751
Table 165: Oceanix subscription type 757
Table 166: Oceanix subscription details mask 757
Table 167: Oceanix region restriction 757
Table 168: Decoder data synchronization state 759
Table 169: Region restriction status 759
Table 170: System used for timing 769
Table 171: Position type 781
Table 172: PPP Seed application status 785
Table 173: PROFILEINFO Status word – Firmware 7.10.xx 790
Table 174: PROFILEINFO Status word – Firmware 7.09.xx 791
Table 175: System used for timing 799
Table 176: PTP states 810
Table 177: Signal type 814
Table 178: Emulated radar status 826
Table 179: RAIM mode types 828
Table 180: Integrity status 828
Table 181: Protection level status 829
Table 182: Channel tracking status 832

Table 183: Tracking state 835
Table 184: Correlator Type 835
Table 185: RINEX Mappings 836
Table 186: Range record format (RANGECMP only) 839
Table 187: StdDev-PSR values 841
Table 188: Satellite block of the range record format (RANGECMP2 only) 844
Table 189: Signal block of the range record format (RANGECMP2 only) 845
Table 190: Std Dev PSR scaling 846
Table 191: Std Dev ADR scaling 847
Table 192: L1/E1/B1 scaling 848
Table 193: Signal type (only in RANGECMP2) 849
Table 194: Header 853
Table 195: Satellite and signal block 853
Table 196: Measurement block header 854
Table 197: Primary reference signal measurement block 855
Table 198: Secondary reference signals measurement block 856
Table 199: Primary differential signal measurement block 857
Table 200: Secondary differential signals measurement block 858
Table 201: Signal bit mask 860
Table 202: Lock time 860
Table 203: ADR Std Dev 861
Table 204: Pseudorange Std Dev 862
Table 205: RANGECMP5 header 865
Table 206: Satellite and signal block 865
Table 207: Measurement block header 866
Table 208: Primary signal measurement block 867
Table 209: Secondary signal measurement block 867
Table 210: Signal bit mask 868
Table 211: Lock time 869
Table 212: Phaserange standard deviation 869
Table 213: Pseudorange standard deviation 871
Table 214: Base station status 886
Table 215: Base station type 886
Table 216: Legacy observable messages 892
Table 217: MSM type descriptions 892
Table 218: MSM log names 893
Table 219: MSM message IDs 893

Table 220: Station and antenna messages 894
Table 221: Ephemeris messages 894
Table 222: GLONASS bias information message 895
Table 223: System used for timing 902
Table 224: Receiver error 919
Table 225: Receiver status 921
Table 226: Version bits 923
Table 227: Auxiliary 1 status 923
Table 228: RF paths for OEM7 receivers 924
Table 229: Auxiliary 2 status 926
Table 230: Auxiliary 3 status 927
Table 231: Antenna gain state 928
Table 232: Memory usage state 929
Table 233: Auxiliary 4 status 929
Table 234: Status word 933
Table 235: Event type 933
Table 236: Safe Mode states 934
Table 237: Compatibility mode 937
Table 238: ASCII and binary values 939
Table 239: Radio state 941
Table 240: Error types 941
Table 241: Evaluation of UDREI 954
Table 242: SBAS subsystem types 986
Table 243: SoftLoad status type 987
Table 244: Tectonics compensation status 993
Table 245: TerraStar subscription type 995
Table 246: TerraStar subscription details mask 996
Table 247: TerraStar region restriction 996
Table 248: Decoder data synchronization state 998
Table 249: TerraStar geogating status 998
Table 250: USB detection type 1007
Table 251: USB mode 1008
Table 252: User-defined antenna type 1011
Table 253: CAN port ID 1013
Table 254: CAN message type 1013
Table 255: CAN port ID 1014
Table 256: Operation mode 1015

Table 257: CAN status message 1015
Table 258: Error code 1017
Table 259: Operation mode code 1017
Table 260: Veripos operating mode 1021
Table 261: Veripos subscription details mask 1021
Table 262: Decoder data synchronization state 1022
Table 263: Component types 1025
Table 264: Firmware and boot version field formats 1026
Table 265: Wi-Fi band 1030
Table 266: Wi-Fi security protocol 1030
Table 267: Wi-Fi encryption type 1030
Table 268: Regulatory region 1031
Table 269: Wi-Fi security type 1033
Table 270: Wi-Fi status 1035
Table 271: IMU type 1042
Table 272: EXTERNALPVAS updates mask 1048
Table 273: EXTERNALPVAS options mask 1049
Table 274: COM ports 1068
Table 275: Rotational offset types 1080
Table 276: Translation offset types 1084
Table 277: Translation input frame 1086
Table 278: Inertial solution status 1119
Table 279: Extended solution status 1124
Table 280: Alignment indication 1126
Table 281: NVM seed indication 1126
Table 282: Offset type 1128
Table 283: Source status 1128
Table 284: INS Seed injection options mask 1132
Table 285: Injection status 1149
Table 286: Validity status 1149
Table 287: DMI update status 1157
Table 288: ALIGN update values 1157
Table 289: INS update values 1158
Table 290: Extended velocity status 1162
Table 291: HG1700 IMU status 1182
Table 292: IMU-LN200 IMU status 1183
Table 293: IMU-ISA-100C IMU status 1184

Table 294: IMU-P1750 IMU status 1186
Table 295: HG1900 and HG1930 IMU status 1187
Table 296: OEM-IMU-HG4930 AN01 IMU status 1188
Table 297: OEM-IMU-HG4930 AN04 IMU status 1190
Table 298: OEM-IMU-STIM300 IMU status 1191
Table 299: IMU-µIMU-IC IMU status 1193
Table 300: OEM-IMU-EG320N IMU status 1194
Table 301: OEM-IMU-EG370N IMU status 1196
Table 302: Raw IMU scale factors 1197
Table 303: Relative INS extended solution status 1205
Table 304: Response messages 1219

Customer Support

NovAtel Knowledge Base

If you have a technical issue, visit the NovAtel Support page at novatel.com/support. Through the *Support* page you can contact Customer Support, find papers and tutorials or download the latest firmware. To access the latest user documentation, visit docs.novatel.com/OEM7.

Before contacting Customer Support

Before contacting NovAtel Customer Support about a software problem, perform the following steps:

If logging data over an RS-232 serial cable, ensure that the configured baud rate can support the data bandwidth (see **SERIALCONFIG** command). NovAtel recommends a minimum suggested baud rate of 230400 bps.

1. Use the information in the Troubleshooting section on the OEM7 Documentation Portal (docs.novatel.com/OEM7) to diagnose and troubleshoot your receiver's symptoms.
2. Log the data suggested in the appropriate *Troubleshooting Logs* section to a file on your computer for 15 minutes.
    - *General troubleshooting logs* on the next page
    - *Tracking and interference troubleshooting logs* on the next page
    - *SPAN troubleshooting logs* on page 29
    - *RTK troubleshooting logs* on page 29
    - *PPP troubleshooting logs* on page 30
    - *ALIGN troubleshooting logs* on page 31

    If using NovAtel Application Suite, log the Troubleshooting message set for 15 minutes.
3. Send the data file to NovAtel Customer Support: support.novatel@hexagon.com
4. You can also issue a **FRESET** command to the receiver to clear any unknown settings.

The **FRESET** command will erase all user settings. You should know your configuration (by requesting the RXCONFIGA log) and be able to reconfigure the receiver before you send the **FRESET** command.

If you are having a hardware problem, send a list of the troubleshooting steps taken and the results.

Contact information

Log a support request with NovAtel Customer Support using one of the following methods:

Log a case and search knowledge:

Website: novatel.com/support

Log a case, search knowledge and view your case history: (login access required)

Web Portal: shop.novatel.com/novatelstore/s/contactsupport

E-mail:

support.novatel@hexagon.com

Telephone:

U.S. and Canada: 1-800-NOVATEL (1-800-668-2835)

International: +1-403-295-4900

General troubleshooting logs

```
LOG RXSTATUSB ONCHANGED
LOG RAWEPHEMB ONNEW
LOG GLORAWEPHEMB ONNEW
LOG BESTPOSB ONTIME 1
LOG RANGEB ONTIME 0.5
LOG RXCONFIGA ONCE
LOG VERSIONA ONCE
LOG LOGLISTA ONCE
LOG PORTSTATSA ONTIME 10
LOG PROFILEINFOA ONCE
LOG HWMONITORA ONTIME 10
```

Tracking and interference troubleshooting logs

```
LOG VERSIONA ONCE
LOG RXCONFIGA ONCE
LOG CHANCONFIGLISTB ONCE
LOG PASSTHROUGHA ONNEW
LOG RXSTATUSB ONCHANGED
LOG CLOCKSTEERINGB ONCHANGED
LOG RAWEPHEMB ONNEW
LOG GLORAWEPHEMB ONNEW
LOG GALINAVRAWEPHEMERISB ONNEW
LOG BDSEPHEMERISB ONNEW
LOG QZSSEPHEMERISB ONNEW
LOG NAVICEPHEMERISB ONNEW
LOG RAWALMB ONNEW
LOG GLORAWALMB ONNEW
LOG GALALMANACB ONNEW
LOG BDSALMANACB ONNEW
LOG QZSSALMANACB ONNEW
LOG NAVICALMANACB ONNEW
LOG IONUTCB ONNEW
LOG GLOCLOCKB ONNEW
LOG GALCLOCKB ONNEW
LOG BDSCLOCKB ONNEW
LOG TRACKSTATB ONTIME 1
LOG RANGEB ONTIME 0.5
LOG BESTPOSB ONTIME 1
LOG SATVIS2B ONTIME 30
LOG ITDETECTSTATUSB ONCHANGED
```

For dual antenna receivers, add these logs:

```
LOG TRACKSTATB_1 ONTIME 1
LOG RANGEB_1 ONTIME 0.5
```

For interference issues add this log:

```
LOG ITPSDDETECTB ONNEW
```

For interference issues, when you have enough datalink bandwidth to handle large logs, add this log:

```
LOG ITPSDFINALB ONNEW
```

SPAN troubleshooting logs

```
LOG RXSTATUSB ONCHANGED
LOG RAWEPHEMB ONNEW
LOG GLORAWEPHEMB ONNEW
LOG GALINAVRAWEPHEMERISB ONNEW
LOG BDSEPHEMERISB ONNEW
LOG BESTPOSB ONTIME 1
LOG RANGEB ONTIME 0.5
LOG RXCONFIGA ONCE
LOG VERSIONA ONCE
LOG RAWIMUSXB ONNEW
LOG INSUPDATESTATUSB ONCHANGED
LOG INSPVAXB ONTIME 1
LOG INSCONFIGA ONCHANGED
LOG BESTGNSSPOSB ONTIME 1
```

RTK troubleshooting logs

```
LOG RXSTATUSB ONCHANGED
LOG RAWEPHEMB ONNEW
LOG GLORAWEPHEMB ONNEW
LOG QZSSRAWEPHEMB ONNEW
LOG BDSRAWNAVSUBFRAMEB ONNEW
LOG GALFNAVRAWEPHEMERISB ONNEW
LOG GALINAVRAWEPHEMERISB ONNEW
LOG RANGEB ONTIME 0.5
LOG BESTPOSB ONTIME 1.0
LOG RXCONFIGB ONCE
LOG VERSIONB ONCE
LOG TRACKSTATB ONTIME 1.0
LOG RTKPOSB ONTIME 1.0
LOG MATCHEDPOSB ONNEW
LOG MATCHEDSATSB ONNEW
LOG RTKSATSB ONTIME 1.0
LOG PSRPOSB ONTIME 1.0
LOG RAWALMB ONNEW
LOG IONUTCB ONNEW
LOG GLORAWALMB ONNEW
LOG GLOCLOCKB ONNEW
LOG PASSTHROUGHB ONNEW
LOG CLOCKMODELB ONTIME 1.0
LOG REFSTATIONB ONNEW
LOG RTKVELB ONTIME 1.0
```

PPP troubleshooting logs

```
LOG RXSTATUSB ONCHANGED
LOG GPSEPHEMB ONNEW
LOG GLOEPHEMERISB ONNEW
LOG QZSSEPHEMERISB ONNEW
LOG BDSEPHEMERISB ONNEW
LOG BDSBCNAV1EPHEMERISB ONNEW
LOG BDSBCNAV2EPHEMERISB ONNEW
LOG BDSBCNAV3EPHEMERISB ONNEW
LOG GALFNAVEPHEMERISB ONNEW
LOG GALINAVEPHEMERISB ONNEW
LOG RANGEB ONTIME 0.5
LOG BESTPOSB ONTIME 1.0
LOG RXCONFIGB ONCE
LOG VERSIONB ONCE
LOG TRACKSTATB ONTIME 10.0
LOG LBANDTRACKSTATB ONTIME 1.0
LOG PPPPOSB ONTIME 1.0
LOG PPPSATSB ONTIME 1.0
LOG TERRASTARINFOB ONCHANGED
LOG TERRASTARSTATUSB ONCHANGED
LOG PSRPOSB ONTIME 1.0
LOG ALMANACB ONNEW
LOG GLOALMANACB ONNEW
LOG GALALMANACB ONNEW
LOG BDSALMANACB ONNEW
LOG QZSSALMANACB ONNEW
LOG IONUTCB ONNEW
LOG GLOCLOCKB ONNEW
LOG LBANDBEAMTABLEB ONCHANGED
```

ALIGN troubleshooting logs

```
LOG RXSTATUSB ONCHANGED
LOG RAWEPHEMB ONNEW
LOG GLORAWEPHEMB ONNEW
LOG GALINAVRAWEPHEMERISB ONNEW
LOG BDSEPHEMERISB ONNEW
LOG BESTPOSB ONTIME 1
LOG RANGEB ONTIME 0.5
LOG RXCONFIGA ONCE
LOG VERSIONA ONCE
LOG LOGLISTA ONCE
LOG PORTSTATSA ONTIME 10
LOG ALIGNBSLNENUB ONNEW
LOG ALIGNBSLNXYZB ONNEW
LOG ALIGNDOPB ONNEW
LOG HEADING2B ONNEW
LOG MASTERPOSB ONNEW
LOG ROVERPOSB ONNEW
```
(This log can only be output on a receiver where ALIGN is enabled.)

```
LOG HEADINGSATSA ONNEW
```
(This log can only be output on a receiver where ALIGN is enabled and configured as the ALIGN rover.)

```
LOG DUALANTENNAHEADINGB ONTIME 1.0
LOG TRACKSTATB_1 ONTIME 1
```
(dual antenna receivers only)

```
LOG RANGEB_1 ONTIME 0.5
```
(dual antenna receivers only)

Foreword

This manual describes each command and log the OEM7 receivers and SMART2 receiver are capable of accepting or generating. Sufficient detail is provided so you can understand the purpose, syntax and structure of each command or log. You will also be able to communicate with the receiver, enabling you to effectively use and write custom interfacing software for specific applications.

Related documents and information

OEM7 and SMART2 products include the following:

- Support for all current and upcoming GNSS constellations
- Real-Time Kinematic (RTK)
- L-band capability including TerraStar licensed based corrections
- Satellite Based Augmentation System (SBAS) signal functionality
- Differential Global Positioning System (DGPS)
- National Marine Electronics Association (NMEA) standards, a protocol used by GNSS receivers to transmit data

For more information on these components, refer the Support page on our website at novatel.com/support. For introductory information on GNSS technology, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

This manual does not address any of the receiver hardware attributes or installation information. Consult the product specific Installation and Operation User Manuals for information about these topics (docs.novatel.com/OEM7). Furthermore, should you encounter any functional, operational or interfacing difficulties with the receiver, refer to the NovAtel website for warranty and support information.

Prerequisites

As this reference manual is focused on the OEM7 family commands and logging protocol, it is necessary to ensure the receiver has been properly installed and powered up according to the instructions outlined in the companion product specific user manuals (docs.novatel.com/OEM7).

Commands and logs defaults and structure

- The factory defaults for commands and logs are shown after the syntax but before the example in the command or log description.
- The letter H in the Binary Byte or Binary Offset columns of the commands and logs tables represents the header length for that command or log, see *Binary* on page 39.
- The number following 0x is a hexadecimal number.
- Default values shown in command tables indicate the assumed values when optional parameters have been omitted. Default values do not imply the factory default settings.
- Parameters surrounded by [and] are optional in a command or are required for only some instances of the command depending on the values of other parameters.
- Text displayed between < and > indicates the entry of a keystroke in the case of the command or an automatic entry in the case of carriage return <CR> and line feed <LF> in data output.
- In tables where no values are given they are assumed to be reserved for future use.

- Status words in ASCII logs are output as hexadecimal numbers and must be converted to binary format (and in some cases then also to decimal) to parse the fields because they are not fixed in 4-bits boundary. For an example of this type of conversion, see the RANGE log, *Table 182: Channel tracking status* on page 832.
- Conversions and their binary or decimal results are always read from right to left. For a complete list of hexadecimal, binary and decimal equivalents, refer to the Unit Conversions information available on our website at novatel.com/support.
- ASCII log examples may be split over several lines for readability. In reality, only a single [CR][LF] pair is transmitted at the end of an ASCII log.

You can download the most up-to-date version of this manual from the OEM7 Documentation Portal (docs.novatel.com/OEM7).

Conventions

The following conventions are used in this manual:



Information that supplements or clarifies text.



A caution that actions, operation or configuration may lead to incorrect or improper use of the hardware.



A warning that actions, operation or configuration may result in regulatory noncompliance, safety issues or equipment damage.



Identifies content that is specific to receivers using 7.09.xx firmware.



Identifies content that is specific to receivers using 7.10.xx firmware.

Chapter 1 Messages

The receiver handles incoming and outgoing NovAtel data in three different message formats: Abbreviated ASCII, ASCII and Binary. This allows for a great deal of versatility in the way the OEM7 receivers can be used. All NovAtel commands and logs can be entered, transmitted, output or received in any of the three formats. The receiver also supports RTCMV3, NOVATELX and NMEA format messaging.

When entering an ASCII or abbreviated ASCII command to request an output log, the message type is indicated by the character appended to the end of the message name. 'A' indicates the message is ASCII and 'B' indicates binary. No character means the message is Abbreviated ASCII. When issuing binary commands, the output message type is dependent on the bit format in the message's binary header (refer to *Binary* on page 39).

Table 1: Field type below below, describes the field types used in the description of messages.

Table 1: Field type

Type	Binary size (bytes)	Description
Char	1	The **char** type is an 8-bit integer in the range -128 to +127. As a binary value, a two's complement format is used. This integer value may be the ASCII code corresponding to the specified character. In ASCII or Abbreviated ASCII this comes out as an actual character.
Uchar	1	The **uchar** type is an 8-bit unsigned integer. Values are in the range from +0 to +255. In ASCII or Abbreviated ASCII this comes out as a number.
Short	2	The **short** type is 16-bit integer in the range -32768 to +32767. As a binary value, a two's complement format is used.
Ushort	2	The same as short except it is not signed. Values are in the range from +0 to +65535.
Long	4	The **long** type is 32-bit integer in the range -2147483648 to +2147483647. As a binary value, a two's complement format is used.
Ulong	4	The same as long except it is not signed. Values are in the range from +0 to +4294967295.
Double	8	The **double** type contains 64-bits: 1 for sign, 11 for the exponent and 52 for the mantissa. Its range is ±1.7E308 with at least 15 digits of precision. This is IEEE 754.
Float	4	The **float** type contains 32-bits: 1 for the sign, 8 for the exponent and 23 for the mantissa. Its range is ±3.4E38 with at least 7 digits of precision. This is IEEE 754.
Enum	4	A 4-byte enumerated type beginning at zero (an unsigned long). In binary, the enumerated value is output. In ASCII or Abbreviated ASCII, the enumeration label is spelled out.
GPSec	4	This type has two separate formats dependent on whether you requested a binary or an ASCII format output. For binary, the output is in milliseconds and is a **ulong** type. For ASCII, the output is in seconds and is a **float** type.
Hex	n	**Hex** is a packed, fixed length (n) array of bytes in binary but in ASCII or Abbreviated ASCII is converted into 2 character hexadecimal pairs.

Type	Binary size (bytes)	Description
Hex Ulong	4	An unsigned, 32-bit integer in hexadecimal format. Values are in the range from +0 to +4294967295.
String	n	**String** is a variable length array of bytes that is null-terminated in the binary case and additional bytes of padding are added to maintain 4-byte alignment. The maximum byte length for each String field is shown in the row in the log or command tables.

Figure 1: Byte arrangements



Figure 1: Byte arrangements **above shows the arrangement of bytes, within each field type, when used by IBM PC computers. All data sent to or from the OEM7 receivers is ordered least significant bit (LSB) first (little-endian). This is opposite to the most significant bit first (big-endian) ordering that is shown in *Figure 1: Byte arrangements* above. Data is then stored in the receiver LSB first. For example, in char type data, the LSB is bit 0 and the most significant bit (MSB) is bit 7. See *Table 182: Channel tracking status* on page 832 for a more detailed example.**

1.1 ASCII

ASCII messages are readable by both the user and a computer. The structures of all ASCII messages follow the general conventions as noted here:

1. The lead code identifier for each record is '#'.
2. Each log or command is of variable length depending on amount of data and formats.
3. All data fields are delimited by a comma ',' with two exceptions:

- The first exception is the last header field which is followed by a ';' to denote the start of the data message.
- The second exception is the last data field, which is followed by a * to indicate end of message data.

4. Each log ends with a hexadecimal number preceded by an asterisk and followed by a line termination using the carriage return and line feed characters.
   For example:
   *1234ABCD[CR][LF]. This value is a 32-bit CRC of all bytes in the log, excluding the '#' identifier and the asterisk preceding the eight CRC digits.
   See *32-bit CRC* on page 57 for the algorithm used to generate the CRC.
5. The receiver only accepts the following ASCII characters.
   - characters between space (ASCII value 32) and '~' (ASCII value 126) inclusive,
   - vertical tab (ASCII value 9)
   - line feed (ASCII value 10)
   - horizontal tab (ASCII value 11)
   - carriage return (ASCII value 13)

   Other values are discarded and can lead to unexpected results.
6. An ASCII string is one field and is surrounded by double quotation marks.
   For example:
   "ASCII string". If separators are surrounded by quotation marks then the string is still one field and the separator will be ignored (example, "xxx,xxx" is one field). Double quotation marks within a string are not allowed.
7. If the receiver detects an error parsing an input message, it returns an error response message. See *Responses* on page 1219 for a list of response messages from the receiver.

Message structure:

header;	data field...,	data field...,	data field...	*xxxxxxxx	[CR][LF]

The ASCII message header structure is described in *Table 2: ASCII message header structure* below.

Table 2: ASCII message header structure

Field	Field name	Field type	Description	Ignored on input
1	Sync	Char	Sync character. The ASCII message is always preceded by a single '#' symbol	N
2	Message	Char[]	The ASCII name of the log or command	N
3	Port	Char[]	The name of the port from which the log was generated. The string is made up of the port name followed by an _x where x is a number from 1 to 31 denoting the virtual address of the port. If no virtual address is indicated, it is assumed to be address 0	Y
4	Sequence #	Long	Used for multiple related logs. It is a number that counts down from N-1 to 0, where 0 means it is the last one of the set. Most logs only come out one at a time in which case this number is 0	N

Field	Field name	Field type	Description	Ignored on input
5	% Idle Time	Float	The minimum percentage of time the processor is idle, calculated once per second	Y
6	Time Status	Enum	The value indicates the quality of the GPS reference time (see *Table 13: GPS reference time status* on page 55)	Y
7	Week	Ulong	GPS reference week number	Y
8	Seconds	GPSec	Seconds from the beginning of the GPS reference week; accurate to the millisecond level	Y
9	Receiver Status	Ulong	An eight digit hexadecimal number representing the status of various hardware and software components of the receiver (see *Table 225: Receiver status* on page 921)	Y
10	Reserved	Ulong	Reserved for internal use	Y
11	Receiver S/W Version	Ulong	A value (0 - 65535) representing the receiver software build number	Y
12	;	Char	The character indicates the end of the header	N

Example log:

```
#RAWEPHEMA,COM1,0,55.5,SATTIME,2072,133140.000,02000000,58ba,15761;32,2072,
136800,8b00602b57a606100004389101eefa4e0eeed24e012f216600007608cd27,
8b00602b58282f02373454d33b986d01bd01a76ba710a2a10d008e21667f,
8b00602b58ae003384abe701001226ff6c6c1c9999f3c99fffa77c2f05c8*d3806ea3
```

1.2 Abbreviated ASCII

This message format is designed to make entering and viewing commands and logs simple. The data is represented as simple ASCII characters, separated by spaces or commas and arranged in an easy to understand format. There is no 32-bit CRC for error detection because it is meant for viewing by the user.

The Abbreviated ASCII message header structure is described in *Table 3: Abbreviated ASCII message header structure* below.

Table 3: Abbreviated ASCII message header structure

Field	Field name	Field type	Description	Ignored on input
1	Sync	Char	Sync character. The Abbreviated ASCII message is always preceded by a single ‘<’ symbol	N
2	Message	Char[]	The ASCII name of the log or command	N
3	Port	Char[]	The name of the port from which the log was generated. The string is made up of the port name followed by an _x where x is a number from 1 to 31 denoting the virtual address of the port. If no virtual address is indicated, it is assumed to be address 0	Y

Field	Field name	Field type	Description	Ignored on input
4	Sequence #	Long	Used for multiple related logs. It is a number that counts down from N-1 to 0, where 0 means it is the last one of the set. Most logs only come out one at a time in which case this number is 0	N
5	% Idle Time	Float	The minimum percentage of time the processor is idle, calculated once per second	Y
6	Time Status	Enum	The value indicates the quality of the GPS reference time (see *Table 13: GPS reference time status* on page 55)	Y
7	Week	Ulong	GPS reference week number	Y
8	Seconds	GPSec	Seconds from the beginning of the GPS reference week; accurate to the millisecond level	Y
9	Receiver Status	Ulong	An eight digit hexadecimal number representing the status of various hardware and software components of the receiver (see *Table 225: Receiver status* on page 921)	Y
10	Reserved	Ulong	Reserved for internal use	Y
11	Receiver S/W Version	Ulong	A value (0 - 65535) representing the receiver software build number	Y
12	CR/LF	Char	A carriage return / line feed indicates the end of the header	N

Example command:

```
log pppsats ontime 1
```

Resultant log:

```
<PPPSATS USB1 0 51.5 FINESTEERING 2209 510815.000 12000020 ce3f 16809
<     45
<           GPS 5 GOOD 00000003
<           GPS 2 GOOD 00000003
<           GPS 31 GOOD 00000003
<           GPS 9 SUPPLEMENTARY 00000007
<           GPS 18 GOOD 00000007
<           GPS 6 SUPPLEMENTARY 00000007
<           GPS 29 GOOD 00000003
<           GPS 20 GOOD 00000003
<           GPS 12 GOOD 00000003
<           GPS 25 SUPPLEMENTARY 00000007
<           QZSS 194 SUPPLEMENTARY 00000007
<           SBAS 135 NOTUSED 00000000
<           SBAS 138 NOTUSED 00000000
<           SBAS 131 NOTUSED 00000000
<           SBAS 133 NOTUSED 00000000
<           GLONASS 19+3 GOOD 00000003
<           GLONASS 2-4 GOOD 00000003
<           GLONASS 9-2 GOOD 00000003
<           GLONASS 3+5 GOOD 00000003
<           GLONASS 18-3 GOOD 00000003
```

```
<           GLONASS 15 SUPPLEMENTARY 00000003
<           GLONASS 1+1 GOOD 00000003
<           GLONASS 17+4 GOOD 00000003
<           GALILEO 36 GOOD 0000000f
<           GALILEO 2 GOOD 0000000f
<           GALILEO 30 GOOD 0000000f
<           GALILEO 34 GOOD 0000000f
<           GALILEO 4 SUPPLEMENTARY 0000000f
<           GALILEO 27 GOOD 0000000f
<           GALILEO 15 GOOD 0000000f
<           GALILEO 9 GOOD 0000000f
<           GALILEO 5 SUPPLEMENTARY 0000000f
<           BEIDOU 25 GOOD 0000001d
<           BEIDOU 34 GOOD 0000001d
<           BEIDOU 23 GOOD 0000001d
<           BEIDOU 22 GOOD 0000001d
<           BEIDOU 44 GOOD 0000001d
<           BEIDOU 43 GOOD 0000001d
<           BEIDOU 42 GOOD 0000001d
<           BEIDOU 28 SUPPLEMENTARY 0000001d
<           BEIDOU 37 GOOD 0000001d
<           BEIDOU 11 SUPPLEMENTARY 00000007
<           BEIDOU 12 SUPPLEMENTARY 00000007
<           BEIDOU 9 SUPPLEMENTARY 00000007
<           BEIDOU 21 GOOD 0000001d
```

The array of 45 entries are offset from the left hand side and start with '<'.

1.3 Binary

Binary messages are strictly machine readable format. They are ideal for applications where the amount of data transmitted is fairly high. Due to the inherent compactness of binary as opposed to ASCII data, messages are much smaller. The smaller message size allows a larger amount of data to be transmitted and received by the receiver's communication ports. The structure of all binary messages follows the general conventions as noted here:

1. Basic format of:
   - *Header*: 3 Sync bytes plus 25-bytes of header information. The header length is variable as fields may be appended in the future. Always check the header length.
   - *Data*: variable
   - *CRC*: 4 bytes
2. The 3 Sync bytes will always be:

Byte	Hex	Decimal
First	AA	170
Second	44	68
Third	12	18

3. The CRC is a 32-bit CRC (see *32-bit CRC* on page 57 for the CRC algorithm) performed on all data

including the header.

4. The header is in the format shown in *Table 4: Binary message header structure* below.


Example

To convert the command **RTKTIMEOUT 60** to binary, populate the following fields in the header:

Sync1, Sync2, Sync3, Header length, Message ID, Port Address, and Message Length.

Always use THISPORT (0xC0) for the port address.

The binary header for this command is:



The full binary command is:




Table 4: Binary message header structure

Field	Field name	Field type	Description	Binary bytes	Binary offset	Ignored on input
1	Sync	Uchar	Hexadecimal 0xAA	1	0	N
2	Sync	Uchar	Hexadecimal 0x44	1	1	N
3	Sync	Uchar	Hexadecimal 0x12	1	2	N
4	Header Length	Uchar	Length of the header	1	3	N
5	Message ID	Ushort	This is the Message ID number of the log (see the command or log descriptions for the Message ID values of individual commands or logs)	2	4	N

Field	Field name	Field type	Description	Binary bytes	Binary offset	Ignored on input
6	Message Type	Char	Bits 0-4 = Measurement source[1] Bits 5-6 = Format 00 = Binary 01 = ASCII 10 = Abbreviated ASCII, NMEA 11 = Reserved Bit 7 = Response bit (see *Message responses* on page 52) 0 = Original Message 1 = Response Message	1	6	N
7	Port Address	Uchar	See *Table 5: Detailed port identifier* on the next page (decimal values >=32 may be used) (lower 8-bits only) [2]	1	7	N [3]
8	Message Length	Ushort	The length in bytes of the body of the message, not including the header nor the CRC	2	8	N
9	Sequence	Ushort	Used for multiple related logs. It is a number that counts down from N-1 to 0 where N is the number of related logs and 0 means it is the last one of the set. Most logs only come out one at a time in which case this number is 0	2	10	N
10	Idle Time	Uchar	Time the processor is idle, calculated once per second. Take the time (0 – 200) and divide by two to give the percentage of time (0 – 100%). 0% indicates the processor is fully occupied. Other values indicate the availability of the processor to take on tasks.	1	12	Y
11	Time Status	Enum	Indicates the quality of the GPS reference time (see *Table 13: GPS reference time status* on page 55).	1 [4]	13	N [5]

1. Bits 0-4 are used to indicate the measurement source. For dual antenna receivers, if bit 0 is set, the log is from the secondary antenna.

2. The 8-bit size means you will only see 0xA0 to 0xBF when the top bits are dropped from a port value greater than 8-bits. For example, ASCII port USB1 will be seen as 0xA0 in the binary output.

3. Recommended value is THISPORT (decimal 192).

4. This ENUM is not 4-bytes long but, as indicated in the table, is only 1-byte.

5. Fields 12 and 13 (Week and ms) are ignored if Field 11 (Time Status) is invalid. In this case, the current receiver time is used. The recommended values for the three time fields are 0, 0, 0.

Field	Field name	Field type	Description	Binary bytes	Binary offset	Ignored on input
12	Week	Ushort	GPS reference week number	2	14	N
13	ms	GPSec	Milliseconds from the beginning of the GPS reference week	4	16	N
14	Receiver Status	Ulong	32-bits representing the status of various hardware and software components of the receiver (see *Table 225: Receiver status* on page 921)	4	20	Y
15	Reserved	Ushort	Reserved for internal use	2	24	Y
16	Receiver S/W Version	Ushort	A value (0 - 65535) representing the receiver software build number	2	26	Y

Table 5: Detailed port identifier

ASCII port name	Hex port value	Decimal port value	Description
NO_PORTS	0	0	No ports specified
COM1	20	32	COM1
COM2	40	64	COM2
COM3	60	96	COM3
SPECIAL	a0	160	Unknown port
THISPORT	c0	192	Current COM port
FILE	e0	224	Port for logging to a file
USB1	5a0	1440	USB1
USB2	6a0	1696	USB2
USB3	7a0	1952	USB3
AUX	8a0	2208	AUX port
COM4	ba0	2976	COM4
ETH1	ca0	3232	ETH1
IMU	da0	3488	IMU
ICOM1	fa0	4000	ICOM1
ICOM2	10a0	4256	ICOM2
ICOM3	11a0	4512	ICOM3
NCOM1	12a0	4768	NCOM1
NCOM2	13a0	5024	NCOM2

ASCII port name	Hex port value	Decimal port value	Description
NCOM3	14a0	5280	NCOM3
ICOM4	15a0	5536	ICOM4
WCOM1	16a0	5792	WCOM1
COM5	17a0	6048	COM5
COM6	18a0	6304	COM6
BT1	19a0	6560	Bluetooth device
COM7	1aa0	6816	COM7
COM8	1ba0	7072	COM8
COM9	1ca0	7328	COM9
COM10	1da0	7584	COM10
CCOM1	1ea0	7840	CAN COM1
CCOM2	1fa0	8096	CAN COM2
CCOM3	20a0	8352	CAN COM3
CCOM4	21a0	8608	CAN COM4
CCOM5	22a0	8864	CAN COM5
CCOM6	23a0	9120	CAN COM6
ICOM5	26a0	9888	ICOM5
ICOM6	27a0	10144	ICOM6
ICOM7	28a0	10400	ICOM7
SCOM1	29a0	10656	SCOM1
SCOM2	2aa0	10912	SCOM2
SCOM3	2ba0	11168	SCOM3
SCOM4	2ca0	11424	SCOM4
LCOM1	39a0	14752	Lua COM port 1 (Firmware 7.10.xx)
LCOM2	3aa0	15008	Lua COM port 2 (Firmware 7.10.xx)
LCOM3	3ba0	15264	Lua COM port 3 (Firmware 7.10.xx)
LCOM4	3ca0	15520	Lua COM port 4 (Firmware 7.10.xx)

The ports available vary based on the receiver.

1.3.1 Virtual ports

Virtual ports can be used to create groups of logs which are all sent to the same physical port.

To remove logging to virtual ports, the virtual port must be specified or the _ALL port must be used. For example:

```
LOG COM2_1 BESTPOS ONTIME 1
LOG COM2_2 TRACKSTAT ONTIME 10
```

Logs on the virtual ports will not be cleared by UNLOGALL COM2. To clear the logs COM2_1, COM2_2 or COM2_ALL must be used.

Table 6: Detailed port identifier – virtual ports

ASCII port name	Hex port value	Decimal port value	Description
COM1_ALL	1	1	All virtual ports for COM1
COM2_ALL	2	2	All virtual ports for COM2
COM3_ALL	3	3	All virtual ports for COM3
THISPORT_ALL	6	6	All virtual ports for the current port
FILE_ALL	7	7	All virtual ports for logging to file
ALL_PORTS	8	8	All virtual ports for all ports
USB1_ALL	d	13	All virtual ports for USB1
USB2_ALL	e	14	All virtual ports for USB2
USB3_ALL	f	15	All virtual ports for USB3
AUX_ALL	10	16	All virtual ports for the AUX
COM4_ALL	13	19	All virtual ports for COM4
ETH1_ALL	14	20	All virtual ports for ETH1
IMU_ALL	15	21	All virtual ports for IMU
ICOM1_ALL	17	23	All virtual ports for ICOM1
ICOM2_ALL	18	24	All virtual ports for ICOM2
ICOM3_ALL	19	25	All virtual ports for ICOM3
NCOM1_ALL	1a	26	All virtual ports for NCOM1
NCOM2_ALL	1b	27	All virtual ports for NCOM2
NCOM3_ALL	1c	28	All virtual ports for NCOM3
ICOM4_ALL	1d	29	All virtual ports for ICOM4
WCOM1_ALL	1e	30	All virtual ports for WCOM1
COM1_1	21	33	COM1, virtual port 1
. . .			

ASCII port name	Hex port value	Decimal port value	Description
COM1_31	3f	63	COM1, virtual port 31
COM2_1	41	65	COM1, virtual port 1
. . .			
COM2_31	5f	95	COM2, virtual port 31
COM3_1	61	97	COM3, virtual port 1
. . .			
COM3_31	7f	127	COM3, virtual port 31
SPECIAL_1	a1	161	Unknown port, virtual port 1
. . .			
SPECIAL_31	bf	191	Unknown port, virtual port 31
THISPORT_1	c1	193	Current COM port, virtual port 1
. . .			
THISPORT_31	df	223	Current COM port, virtual port 31
FILE_1	e1	225	Virtual port 1 for logging to file
. . .			
FILE_31	ff	255	Virtual port 31 for logging to file
USB1_1	5a1	1441	USB1, virtual port 1
. . .			
USB1_31	5bf	1471	USB1, virtual port 31
USB2_1	6a1	1967	USB2, virtual port 1
. . .			
USB2_31	6bf	1727	USB2, virtual port 31
USB3_1	7a1	1953	USB3, virtual port 1
. . .			
USB3_31	7bf	1983	USB port 3, virtual port 31
AUX_1	8a1	2209	AUX port, virtual port 1
. . .			
AUX_31	8bf	2239	AUX port, virtual port 31
COM4_1	ba1	2977	COM4, virtual port 1
. . .			

ASCII port name	Hex port value	Decimal port value	Description
COM4_31	bbf	3007	COM4, virtual port 31
ETH1_1	ca1	3233	ETH1, virtual port 1
. . .			
ETH1_31	cbf	3263	ETH1, virtual port 31
IMU_1	da1	3489	IMU, virtual port 1
. . .			
IMU_31	dbf	3519	IMU, virtual port 31
ICOM1_1	fa1	4001	ICOM1, virtual port 1
. . .			
ICOM1_31	fbf	4031	ICOM1, virtual port 31
ICOM2_1	10a1	4257	ICOM2, virtual port 1
. . .			
ICOM2_31	10bf	4287	ICOM2, virtual port 31
ICOM3_1	11a1	4513	ICOM3, virtual port 1
. . .			
ICOM3_31	11bf	4543	ICOM3, virtual port 31
NCOM1_1	12a1	4769	NCOM1, virtual port 1
. . .			
NCOM1_31	12bf	4799	NCOM1, virtual port 31
NCOM2_1	13a1	5025	NCOM2, virtual port 1
. . .			
NCOM2_31	13bf	5055	NCOM2, virtual port 31
NCOM3_1	14a1	5281	NCOM3, virtual port 1
. . .			
NCOM3_31	14bf	5311	NCOM3, virtual port 31
ICOM4_1	15a1	5537	ICOM4, virtual port 1
. . .			
ICOM4_31	15bf	5567	ICOM4, virtual port 31
WCOM1_1	16a1	5793	WCOM1, virtual port 1
. . .			

ASCII port name	Hex port value	Decimal port value	Description
WCOM1_31	16bf	5823	WCOM1, virtual port 31
COM5_ALL	16c0	5824	All virtual ports for COM5
COM6_ALL	16c1	5825	All virtual ports for COM6
BT1_ALL	16c2	5826	All virtual ports for the Bluetooth device
COM7_ALL	16c3	5827	All virtual ports for COM7
COM8_ALL	16c4	5828	All virtual ports for COM8
COM9_ALL	16c5	5829	All virtual ports for COM9
COM10_ALL	16c6	5830	All virtual ports for COM10
CCOM1_ALL	16c7	5831	All virtual ports for CCOM1
CCOM2_ALL	16c8	5832	All virtual ports for CCOM2
CCOM3_ALL	16c9	5833	All virtual ports for CCOM3
CCOM4_ALL	16ca	5834	All virtual ports for CCOM4
CCOM5_ALL	16cb	5835	All virtual ports for CCOM5
CCOM6_ALL	16cc	5836	All virtual ports for CCOM6
ICOM5_ALL	16cf	5839	All virtual ports for ICOM5
ICOM6_ALL	16d0	5840	All virtual ports for ICOM6
ICOM7_ALL	16d1	5841	All virtual ports for ICOM7
SCOM1_ALL	16d2	5842	All virtual ports for SCOM1
SCOM2_ALL	16d3	5843	All virtual ports for SCOM2
SCOM3_ALL	16d4	5844	All virtual ports for SCOM3
SCOM4_ALL	16d5	5845	All virtual ports for SCOM4
LCOM1_ALL	16e2	5858	All virtual ports for LCOM1 (Firmware 7.10.xx)
LCOM2_ALL	16e3	5859	All virtual ports for LCOM2 (Firmware 7.10.xx)
LCOM3_ALL	16e4	5860	All virtual ports for LCOM3 (Firmware 7.10.xx)
LCOM4_ALL	16e5	5861	All virtual ports for LCOM4 (Firmware 7.10.xx)
COM5_1	17a1	6049	COM5, virtual port 1
. . .			

ASCII port name	Hex port value	Decimal port value	Description
COM5_31	17bf	6079	COM5, virtual port 31
COM6_1	18a1	6305	COM6, virtual port 1
. . .			
COM6_31	18bf	6335	COM6, virtual port 31
BT1_1	19a1	6561	Bluetooth device, virtual port 1
. . .			
BT1_31	19bf	6591	Bluetooth device, virtual port 31
COM7_1	1aa1	6817	COM7, virtual port 1
. . .			
COM7_31	1abf	6847	COM7, virtual port 31
COM8_1	1ba1	7073	COM8, virtual port 1
. . .			
COM8_31	1bbf	7103	COM8, virtual port 31
COM9_1	1ca1	7329	COM9, virtual port 1
. . .			
COM9_31	1cbf	7359	COM9, virtual port 31
COM10_1	1da1	7585	COM10, virtual port 1
. . .			
COM10_31	1dbf	7615	COM10, virtual port 31
CCOM1_1	1ea1	7841	CAN COM1, virtual port 1
. . .			
CCOM1_31	1ebf	7871	CAN COM1, virtual port 31
CCOM2_1	1fa1	8097	CAN COM2, virtual port 1
. . .			
CCOM2_31	1fbf	8127	CAN COM2, virtual port 31
CCOM3_1	20a1	8353	CAN COM3, virtual port 1
. . .			
CCOM3_31	20bf	8383	CAN COM3, virtual port 31
CCOM4_1	21a1	8609	CAN COM4, virtual port 1
. . .			

ASCII port name	Hex port value	Decimal port value	Description
CCOM4_31	21bf	8639	CAN COM4, virtual port 31
CCOM5_1	22a1	8865	CAN COM5, virtual port 1
. . .			
CCOM5_31	22bf	8895	CAN COM5, virtual port 31
CCOM6_1	23a1	9121	CAN COM6, virtual port 1
. . .			
CCOM6_31	23bf	9151	CAN COM6, virtual port 31
ICOM5_1	26a1	9889	ICOM5, virtual port 1
. . .			
ICOM5_31	26bf	9919	ICOM5, virtual port 31
ICOM6_1	27a1	10145	ICOM6, virtual port 1
. . .			
ICOM6_31	27bf	10175	ICOM6, virtual port 31
ICOM7_1	28a1	10401	ICOM7, virtual port 1
. . .			
ICOM7_31	28bf	10431	ICOM7, virtual port 31
SCOM1_1	29a1	10657	SCOM1, virtual port 1
. . .			
SCOM1-31	29bf	10687	SCOM1, virtual port 31
SCOM2_1	2aa1	10913	SCOM2, virtual port 1
. . .			
SCOM2_31	2abf	10943	SCOM2, virtual port 31
SCOM3_1	2ba1	11169	SCOM3, virtual port 1
. . .			
SCOM3_31	2bbf	11199	SCOM3, virtual port 31
SCOM4_1	2ca1	11425	SCOM4, virtual port 1
. . .			
SCOM4_31	2cbf	11455	SCOM4, virtual port 31
LCOM1_1	39a1	14753	LCOM1, virtual port 1 (Firmware 7.10.xx)

ASCII port name	Hex port value	Decimal port value	Description
. . .			
LCOM1_31	39bf	14783	LCOM1, virtual port 31 (Firmware 7.10.xx)
LCOM2_1	3aa1	15009	LCOM2, virtual port 1 (Firmware 7.10.xx)
. . .			
LCOM2_31	3abf	15039	LCOM2, virtual port 31 (Firmware 7.10.xx)
LCOM3_1	3ba1	15265	LCOM3, virtual port 1 (Firmware 7.10.xx)
. . .			
LCOM3_31	3bbf	15295	LCOM31, virtual port 31 (Firmware 7.10.xx)
LCOM4_1	3ca1	15521	LCOM4, virtual port 1 (Firmware 7.10.xx)
. . .			
LCOM4_31	3cbf	15551	LCOM4, virtual port 31 (Firmware 7.10.xx)

COM1_ALL, COM2_ALL, COM3_ALL, COM4_ALL, COM5_ALL, THISPORT_ALL, FILE_ALL, ALL_PORTS, USB1_ALL, USB2_ALL, USB3_ALL, AUX_ALL, ETH1_ALL, ICOM1_ALL, ICOM2_ALL, ICOM3_ALL, ICOM4_ALL, ICOM5_ALL, ICOM6_ALL, ICOM7_ALL, CCOM1_ALL, CCOM2_ALL, CCOM3_ALL, CCOM4_ALL, CCOM5_ALL, CCOM6_ALL, NCOM1_ALL, NCOM2_ALL, NCOM3_ALL, SCOM1_ALL, SCOM2_ALL, SCOM3_ALL, SCOM4_ALL. LCOM1_ALL, LCOM2_ALL, LCOM3_ALL, LCOM4_ALL, and WCOM1_ALL are only valid for the **UNLOGALL** command.

Table 7: Available port types below provides examples of where each port type might be used.

Table 7: Available port types

Port type	Description	Example of where it might be used
AUX	Auxiliary "serial" ports	An additional UART serial port available only on certain platforms
BTx	Bluetooth ports	These ports are used to connect over Bluetooth devices, when the receiver is equipped with a BT device
COMx	Serial Port	UART serial ports. Used when there is a physical RS-232 or RS-422 connection to the receiver

Port type	Description	Example of where it might be used
ICOMx	Internet ports	These ports are used when establishing TCP or UDP connections to the receiver over a network
LCOMx	Script ports	Ports used by the Scripted User Interface (i.e. Lua) (firmware 7.10.xx)
NCOMx	NTRIP ports	These ports are used when establishing NTRIP connections to the receiver over a network
SCOMx	Script ports	Ports used by the Scripted User Interface (i.e. Lua)
USBx	USB "serial" ports	When the receiver is connected to an external host through USB, these ports are available
WCOMx	Web Server port	Ports used by Web Server applications, for receivers equipped with a web server

1.4 Description of ASCII and binary logs with short headers

One difference from the standard OEM7 logs is there are two possible headers for the ASCII and binary versions of the INS logs. Which header is used for a given log is described in the log definitions in the *SPAN logs* on page 1096 chapter. The reason for the alternate short headers is that the normal OEM7 binary header is quite long at 28 bytes. This is nearly as long as the data portion of many of the INS logs and creates excess storage and baud rate requirements.

These logs are set up in the same way as normal ASCII or binary logs except a normal ASCII or binary header is replaced with a short header (see *Table 8: Short ASCII message header structure* below and *Table 9: Short binary message header structure* below).

Table 8: Short ASCII message header structure

Field	Field name	Field type	Description
1	%	Char	% symbol
2	Message	Char	This is the name of the log
3	Week Number	Ushort	GNSS week number
4	Seconds	GPSec	Seconds from the beginning of the GNSS week (Same byte arrangement as a Float type)

Table 9: Short binary message header structure

Field	Field name	Field type	Description	Binary bytes	Binary offset
1	Synch	Char	Hex 0xAA	1	0
2	Synch	Char	Hex 0x44	1	1
3	Synch	Char	Hex 0x13	1	2
4	Message Length	Uchar	Message length, not including header or CRC	1	3
5	Message ID	Ushort	Message ID number	2	4

Field	Field name	Field type	Description	Binary bytes	Binary offset
6	Week Number	Ushort	GNSS week number	2	6
7	Milliseconds	GPSec	Milliseconds from the beginning of the GNSS week (Same byte arrangement as a Long type)	4	8

1.5 Message responses

By default, if you input a message you get back a response. If desired, the **INTERFACEMODE** command (see page 217) can be used to disable response messages. The response will be in the exact format you entered the message (that is, binary input = binary response).

1.5.1 Abbreviated ASCII response

The response is just the leading '<' followed by the response string, for example: <OK.

1.5.2 ASCII response

The response is the full header with the message name being identical except ending in an 'R' (for response). The body of the message consists of a string of characters for the response. For example:

```
#FRESETR,COM1,0,73.0,UNKNOWN,0,0.000,00000000,06e5,0;OK*55c70910
```

The prefix "ERROR:" is added to the response message (see *Table 304: Response messages* on page 1219) except when the command is accepted. When the command is accepted, the message response is "OK".

1.5.3 Binary response

The response is similar to an ASCII response except that it follows the binary protocols, see *Table 10: Binary message response structure* on the next page.

Table 11: Binary message sequence on page 54 is an example of the sequence for requesting and then receiving BESTPOSB. The example is in hex format. When you enter a hex command, you may need to add a '\x' or '0x' before each hex pair, depending on your code. For example:

0xAA0x440x120x1C0x010x000x02 and so on.

Table 10: Binary message response structure

	Field	Field name	Field type	Description	Binary bytes	Binary offset
BINARY HEADER	1	Sync	Char	Hexadecimal 0xAA	1	0
	2	Sync	Char	Hexadecimal 0x44	1	1
	3	Sync	Char	Hexadecimal 0x12	1	2
	4	Header Length	Uchar	Length of the header	1	3
	5	Message ID	Ushort	Message ID number	2	4
	6	Message Type	Char	Response Bit 1 = Response Message	1	6
	7	Port Address	Uchar	See *Table 5: Detailed port identifier* on page 42	1	7
	8	Message Length	Ushort	The length in bytes of the body of the message (not including the CRC)	2	8
	9	Sequence	Ushort	Normally 0	2	10
	10	Idle Time	Uchar	Idle time	1	12
	11	Time Status	Enum	*Table 13: GPS reference time status* on page 55	1 [1]	13
	12	Week	Ushort	GPS reference week number	2	14
	13	ms	GPSec	Milliseconds into GPS reference week	4	16
	14	Receiver Status	Ulong	*Table 225: Receiver status* on page 921	4	20
	15	Reserved	Ushort	Reserved	2	24
	16	Receiver S/W Version	Ushort	Receiver software build number	2	26
ID	17	Response ID	Enum	The enumeration value corresponding to the response message (*Table 304: Response messages* on page 1219)	4	28
HEX	18	Response	Hex	String containing the ASCII response in hex coding to match the ID above (for example, 0x4F4B = OK) The prefix "ERROR:" is added to the response message (see *Table 304: Response messages* on page 1219) except when the command is accepted. When the command is accepted, the message response is "OK".	variable	32

1. This ENUM is not 4-bytes long but as indicated in the table is only 1 byte.

Table 11: Binary message sequence

Direction	Sequence	Data
To receiver	LOG command header	AA44121C 01000240 20000000 1D1D0000 29160000 00004C00 55525A80
	LOG parameters	20000000 2A000000 02000000 00000000 0000F03F 00000000 00000000 00000000
	Checksum	2304B3F1
From receiver	LOG response header	AA44121C 01008220 06000000 FFB4EE04 605A0513 00004C00 FFFF5A80
	LOG response data	01000000 4F4B
	Checksum	DA8688EC
From receiver	BESTPOSB header	AA44121C 2A000220 48000000 90B49305 B0ABB912 00000000 4561BC0A
	BESTPOSB data	00000000 10000000 1B0450B3 F28E4940 16FA6BBE 7C825CC0 0060769F 449F9040 A62A82C1 3D000000 125ACB3F CD9E983F DB664040 00303030 00000000 00000000 0B0B0000 00060003
	Checksum	42DC4C48

1.6 GLONASS slot and frequency numbers

When a GLONASS PRN in a log is in the range 38 to 61, then that PRN represents a GLONASS Slot Number where the Slot Number shown is the actual GLONASS Slot Number plus 37.

Similarly, the GLONASS Frequency shown in logs is the actual GLONASS Frequency plus 7.

For example:

```
<RANGE COM1 0 82.0 FINESTEERING 1729 155076.000 02004000 5103 11465
46
31 0 24514687.250 0.064 -128825561.494675 0.010 3877.473 45.0 563.310
18109c04
...
46 5 24097664.754 0.213 -128680178.570435 0.014 -3740.543 40.6 10098.600
08119e44
'''
8 0 39844800.076 0.043 -160438471.200694 0.013 -392.547 42.5 12038.660
00349c84
```

when 31 is a GPS satellite, 8 is a BeiDou satellite and 46 is a GLONASS satellite. Its actual GLONASS Slot Number is 9 and its frequency is -2.

Refer to *PRN numbers* on the next page for more information about GLONASS PRN numbers. Also, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss for more information.

1.6.1 PRN numbers

The PRN and SVID ranges for the logs and commands that use them are shown in the following table.

Table 12: PRN numbers for commands and logs

Command/Log	GPS PRN	SBAS PRN	SBAS QZSS L1S PRN	GLONASS slot	Galileo SVID	QZSS PRN	BDS PRN	NavIC PRN
ASSIGN	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
ASSIGNALL	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
LOCKOUTSATELLITE	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
SBASCONTROL	-	120-158	183-191	-	-	-	-	-
TRACKSV	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
UNLOCKOUTSATELLITE	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
RANGE	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
RANGECMP	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14
RANGECMP2	1-32	120-158	183-191	1-24	1-36	193-202	1-63	1-14
RANGECMP4	1-32	120-158	183-191	1-24	1-36	193-202	1-63	1-14
RANGEGPSL1	1-32	-	-	-	-	-	-	-
SATVIS2	1-32	120-158	183-191	1-24	1-36	193-202	1-63	1-14
TRACKSTAT	1-32	120-158	183-191	38-61	1-36	193-202	1-63	1-14

1.7 GPS reference time status

All reported receiver times are subject to a qualifying time status. The status indicates how well a time is known (see *Table 13: GPS reference time status* below).

Table 13: GPS reference time status

GPS reference time status (decimal)	GPS reference time status (ASCII)	Description
20	UNKNOWN	Time validity is unknown
60	APPROXIMATE	Time is set approximately
80	COARSEADJUSTING	Time is approaching coarse precision
100	COARSE	This time is valid to coarse precision
120	COARSESTEERING	Time is coarse set and is being steered
130	FREEWHEELING	Position is lost and the range bias cannot be calculated
140	FINEADJUSTING	Time is adjusting to fine precision

GPS reference time status (decimal)	GPS reference time status (ASCII)	Description
160	FINE	Time has fine precision
170	FINEBACKUPSTEERING	Time is fine set and is being steered by the backup system
180	FINESTEERING	Time is fine set and is being steered
200	SATTIME	Time from satellite. Only used in logs containing satellite data such as ephemeris and almanac

There are several distinct states the receiver goes through.

When the **CLOCKADJUST** command (see page 117) is enabled:

- UNKNOWN (initial state)
- COARSESTEERING (initial coarse time set)
- FINESTEERING (normal operating state)
- FINEBACKUPSTEERING (when the backup system is used for a time)
- FREEWHEELING (when range bias becomes unknown)

When the **CLOCKADJUST** command (see page 117) is disabled:

- UNKNOWN (initial state)
- COARSE (initial coarse time set)
- FINE (normal operating state)

On startup and before any satellites are tracked, the receiver can not possibly know the current time. As such, the receiver time starts counting at GPS reference week 0 and second 0.0. The time status flag is set to UNKNOWN.

If time is input to the receiver using the **SETAPPROXTIME** command (see page 394), the time status will be APPROXIMATE.

After time information is decoded from the navigation data and validated, the receiver time is set with an accuracy of approximately ±10 milliseconds. This state is qualified by the COARSE or COARSESTEERING time status flag depending on the state of the CLOCKADJUST switch (for more information, refer to the **CLOCKADJUST** command on page 117).

Once a position is known and range biases are being calculated, the internal clock model will begin modelling the range biases also known as the receiver clock offset.

Modelling will continue until the model is a good estimation of the actual receiver clock behaviour. At this time, the receiver time will again be adjusted, this time to an accuracy of ±1 microsecond. This state is qualified by the FINE time status flag.

The final logical time status flag depends on whether **CLOCKADJUST** is enabled or not. If CLOCKADJUST is disabled, the time status flag will never improve on FINE. The time will only be adjusted again to within ±1 microsecond if the range bias gets larger than ±250 milliseconds. If CLOCKADJUST is enabled, the time status flag is set to FINESTEERING and the receiver time is continuously updated (steered) to minimize the receiver range bias.

If a solution cannot be computed with the primary satellite system, it will attempt to use a backup system (if available). When the backup system is used and time is computed, the time status is set to

FINEBACKUPSTEERING. If the position is lost and the range bias cannot be calculated, the time status is degraded to FREEWHEELING.



See also *Message time stamps* below and the **SETTIMEBASE** command on page 404.

1.8 Message time stamps

All NovAtel format messages generated by the OEM7 and SMART2 receivers have a GPS reference time stamp in their header. GPS reference time is referenced to UTC with zero point defined as midnight on the night of January 5, 1980. The time stamp consists of the number of weeks since that zero point and the number of seconds since the last week number change (0 to 604,799). GPS reference time differs from UTC time since leap seconds are occasionally inserted into UTC and GPS reference time is continuous. In addition, a small error (less than 1 microsecond) can exist in synchronization between UTC and GPS reference time. The TIME log reports both GNSS and UTC time and the offset between the two.

The data in synchronous logs (for example, RANGE, BESTPOS, TIME) are based on a periodic measurement of satellite pseudoranges. The time stamp on these logs is the receiver estimate of GPS reference time at the time of the measurement.

Other log types (asynchronous and polled) are triggered by an external event and the time in the header may not be synchronized to the current GPS reference time. Logs that contain satellite broadcast data (for example, ALMANAC, GPSEPHEM) have the transmit time of their last subframe in the header. In the header of differential time matched logs (for example, MATCHEDPOS) is the time of the matched reference and local observation that they are based on. Logs triggered by a mark event (for example, MARKPOS, MARK1TIME) have the estimated GPS reference time of the mark event in their header. In the header of polled logs (for example, LOGLIST, PORTSTATS, VERSION) is the approximate GPS reference time when their data was generated. However, when asynchronous logs are triggered ONTIME, the time stamp will represent the time the log was generated and not the time given in the data.

For more information about log types, see *Log types* on page 489.

1.9 Decoding of the GPS reference week number

The GPS reference week number provided in the raw satellite data is the 10 least significant bits (or 8 least significant bits in the case of the almanac data) of the full week number. When the receiver processes the satellite data, the full week number is determined. In all log headers, the full week number is given starting from week 0 or January 6, 1980.

1.10 32-bit CRC

The ASCII and Binary OEM7 family and SMART2 message formats all contain a 32-bit CRC for data verification. This allows the user to ensure the data received (or transmitted) is valid with a high level of certainty.

The C functions below may be implemented to generate the CRC of a block of data.

```
#define CRC32_POLYNOMIAL 0xEDB88320L
/* --------------------------------------------------------------------------
Calculate a CRC value to be used by CRC calculation functions.
-------------------------------------------------------------------------- */
unsigned long CRC32Value(int i) {
     int j;
     unsigned long ulCRC;
     ulCRC = i;
```

```
        for ( j = 8 ; j > 0; j-- ) {
            if ( ulCRC & 1 )
                ulCRC = ( ulCRC >> 1 ) ^ CRC32_POLYNOMIAL;
            else
                ulCRC >>= 1;
        }
        return ulCRC;
    }

    /* --------------------------------------------------------------------
    Calculates the CRC-32 of a block of data all at once
    ulCount - Number of bytes in the data block
    ucBuffer - Data block
    -------------------------------------------------------------------- */
    unsigned long CalculateBlockCRC32( unsigned long ulCount, unsigned char
    *ucBuffer ) {
        unsigned long ulTemp1;
        unsigned long ulTemp2;
        unsigned long ulCRC = 0;
        while ( ulCount-- != 0 ) {
            ulTemp1 = ( ulCRC >> 8 ) & 0x00FFFFFFL;
            ulTemp2 = CRC32Value( ((int) ulCRC ^ *ucBuffer++ ) & 0xFF );
            ulCRC = ulTemp1 ^ ulTemp2;
        }
        return( ulCRC );
    }
```

The NMEA checksum is an XOR of all the bytes (including delimiters such as ',' but excluding the * and $) in the message output. It is therefore an 8-bit and not a 32-bit checksum.

Not all logs may be available. Every effort is made to ensure examples are correct, however, a checksum may be created for promptness in publication. In this case it will appear as ‘9999’.

Example:

BESTPOSB and BESTPOSA from an OEM7 or SMART2 receiver.

Binary log message:

```
0xAA, 0x44, 0x12, 0x1C, 0x2A, 0x00, 0x02, 0x20, 0x48, 0x00, 0x00, 0x00, 0x90,
0xB4, 0x93, 0x05, 0xB0, 0xAB, 0xB9, 0x12, 0x00, 0x00, 0x00, 0x00, 0x45, 0x61,
0xBC, 0x0A, 0x00, 0x00, 0x00, 0x00, 0x10, 0x00, 0x00, 0x00, 0x1B, 0x04, 0x50,
0xB3, 0xF2, 0x8E, 0x49, 0x40, 0x16, 0xFA, 0x6B, 0xBE, 0x7C, 0x82, 0x5C, 0xC0,
0x00, 0x60, 0x76, 0x9F, 0x44, 0x9F, 0x90, 0x40, 0xA6, 0x2A, 0x82, 0xC1, 0x3D,
0x00, 0x00, 0x00, 0x12, 0x5A, 0xCB, 0x3F, 0xCD, 0x9E, 0x98, 0x3F, 0xDB, 0x66,
0x40, 0x40, 0x00, 0x30, 0x30, 0x30, 0x00, 0x00, 0x00, 0x00, 0x00, 0x00, 0x00,
0x00, 0x0B, 0x0B, 0x00, 0x00, 0x00, 0x06, 0x00, 0x03, 0x42, 0xdc, 0x4c,0x48
```

Below is a demonstration of how to generate the CRC from both ASCII and BINARY messages using the function described above.

When you pass the data into the code that follows, exclude the checksum shown in ***bold italics*** above. It is *42dc4c48*.

Binary checksum calculation:

```
#include <stdio.h>
#include <string.h>
#include <inttypes.h>

void main() {
     // Expect checksum 0x42, 0xDC, 0x4C, 0x48 (42dc4c48)
     unsigned char buffer[] = {0xAA, 0x44, 0x12, 0x1C, 0x2A, 0x00, 0x02, 0x20,
0x48, 0x00,
                               0x00, 0x00, 0x90, 0xB4, 0x93, 0x05, 0xB0, 0xAB,
0xB9, 0x12,
                               0x00, 0x00, 0x00, 0x00, 0x45, 0x61, 0xBC, 0x0A,
0x00, 0x00,
                               0x00, 0x00, 0x10, 0x00, 0x00, 0x00, 0x1B, 0x04,
0x50, 0xB3,
                               0xF2, 0x8E, 0x49, 0x40, 0x16, 0xFA, 0x6B, 0xBE,
0x7C, 0x82,
                               0x5C, 0xC0, 0x00, 0x60, 0x76, 0x9F, 0x44, 0x9F,
0x90, 0x40,
                               0xA6, 0x2A, 0x82, 0xC1, 0x3D, 0x00, 0x00, 0x00,
0x12, 0x5A,
                               0xCB, 0x3F, 0xCD, 0x9E, 0x98, 0x3F, 0xDB, 0x66,
0x40, 0x40,
                               0x00, 0x30, 0x30, 0x30, 0x00, 0x00, 0x00, 0x00,
0x00, 0x00,
                               0x00, 0x00, 0x0B, 0x0B, 0x00, 0x00, 0x00, 0x06,
0x00, 0x03};

     //Note that the CRC on the binary data will be little-endian ordered.
     unsigned long CRCle = CalculateBlockCRC32(sizeof(buffer), buffer);

     //big-endian users (such as Atmel AVR32 users) may swap endianness as
follows
     unsigned long CRCbe = __builtin_bswap32(CRCle);

     printf("\n\n%s %lx \n", "Computed binary checksum (little-endian): ",
CRCle);
     printf("%s %" PRIx32 "\n", "Computed binary checksum (big-endian): ",
CRCbe);

}
```

Note that the above checksum function (`CalculateBlockCRC32`) must also be included to execute this code.

ASCII log message:

```
#BESTPOSA,COM1,0,78.0,FINESTEERING,1427,325298.000,00000000,6145,2748;
SOL_COMPUTED,SINGLE,51.11678928753,-114.03886216575,1064.3470,-16.2708,
WGS84,2.3434,1.3043,4.7300,"",0.000,0.000,7,7,0,0,0,06,0,03*9c9a92bb
```

The checksum for this log is given above, it is *9c9a92bb*.

ASCII:

```
#include <stdio.h>
#include <string.h>

void main() {
     //Remember to escape " characters as \"
     char *msgBlock =
"BESTPOSA,COM1,0,78.0,FINESTEERING,1427,325298.000,00000000,\
6145,2748;SOL_COMPUTED,SINGLE,51.11678928753,-114.03886216575,\
1064.3470,-
16.2708,WGS84,2.3434,1.3043,4.7300,\"\",0.000,0.000,7,7,0,0,0,06,0,03";

     unsigned long CRC = CalculateBlockCRC32(strlen(msgBlock), (unsigned
char*)msgBlock);

     printf("\n%s %s\n", "Demonstrating CRC computed for the block:", msgBlock);
     printf("\n\n%s %lu\n", "CRC32 in Decimal is: ", CRC);
     printf("%s %lx\n", "CRC32 in Hex is: ", CRC);
}
```

Note that the above checksum function (`CalculateBlockCRC32`) must also be included to execute this code.

Chapter 2 Commands

Commands are used to control and configure OEM7 receivers.

2.1 Command formats

The receiver accepts commands in 3 formats as described in *Messages* on page 34:

- Abbreviated ASCII
- ASCII
- Binary

Abbreviated ASCII is the easiest to use for your input. The other two formats include a CRC for error checking and are intended for use when interfacing with other electronic equipment.

The following are examples of the same command in each format:

Abbreviated ASCII example:

```
LOG COM1 BESTPOSB ONTIME 1[CR]
```

ASCII example:

```
#LOGA,THISPORT,0,0,UNKNOWN,0,0.0,0,0,0;COM1,BESTPOSB,ONTIME,1.000000,0.000000,N
OHOLD*ec9ce601[CR]
```

Binary example:

```
AA44121C 010000C0 20000000 00FF0000 00000000 00000000 00000000 20000000 2A000000
02000000 00000000 0000F03F 00000000 00000000 00000000 34D32DC1
```

2.1.1 Optional parameters

Many commands have nested optional parameters where an optional parameter requires the optional parameter before it to be present. This is noted in the Abbreviated ASCII Syntax as:

```
Command [OPT_1 [OPT_2 [OPT_3]]]
```

In this syntax example, OPT_1 and OPT_2 must be provided if you want to provide a value for OPT_3. These leading two options are required even if you want to use the defaults for OPT_1 and OPT_2.

2.2 Command settings

There are several ways to determine the current command settings of the receiver:

1. Request an **RXCONFIG** log (see page 913). This log provides a listing of all commands issued to the receiver and their parameter settings. It also provides the most complete information.
2. For some specific commands, logs are available to indicate all their parameter settings. The **LOGLIST** log (see page 712) shows all active logs in the receiver beginning with the **LOG** command (see page 249).
3. Request a log of the specific command of interest to show the parameters last entered for that command. The format of the log produced is exactly the same as the format of the specific command with updated header information.

Requesting a log for specific command is useful for most commands. For commands repeated with different parameters (for example, **SERIALCONFIG** and **LOG**), only the most recent set of parameters used is shown. To view all sets of parameters, try method 1 or 2 above.

Abbreviated ASCII example:

```
log fix
<FIX COM1 0 49.5 FINESTEERING 2072 405099.446 02000008 37d7 15761
<     NONE -10000.00000000000 -10000.00000000000 -10000.0000
```

2.3 Command defaults

When the receiver is first powered up or after a **FRESET** command (see page 192), all commands revert to their factory default settings. When you use a command without specifying its optional parameters, it may have a different command default than the factory default. The **SAVECONFIG** command (see page 367) can be used to save these defaults. Use the **RXCONFIG** log (see page 913) to reference any default command and log settings.

Factory default settings for individual commands are stated in the following commands, organized alphabetically by command name.

FRESET STANDARD causes all previously stored user configurations saved to non-volatile memory to be erased (including Saved Config, Saved Almanac, Saved Ephemeris and L-band-related data, excluding subscription information).

Ensure that all windows, other than the Console window, are closed in NovAtel's Connect user interface application before you issue the **SAVECONFIG** command (see page 367).

2.4 ADJUST1PPS

Adjusts the receiver clock

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to adjust the receiver clock or as part of the procedure to transfer time between receivers. The number of pulses per second (PPS) is always set to 1 Hz with this command. It is typically used when the receiver is not adjusting its own clock and is using an external reference frequency.

To disable the automatic clock adjustment, refer to the **CLOCKADJUST** command on page 117. To configure the receiver to use an external reference oscillator, see the **EXTERNALCLOCK** command on page 168.


The **ADJUST1PPS** command can be used to:

- Manually shift the phase of the clock
- Adjust the phase of the clock so the output 1PPS signal matches an external signal
- Set the receiver clock close to that of another GNSS receiver
- Set the receiver clock exactly in phase of another GNSS receiver

1. The resolution of the clock synchronization is 20 ns.
2. To adjust the 1PPS output, when the receiver's internal clock is being used and the **CLOCKADJUST** command is enabled, use the **CLOCKOFFSET** command on page 122.
3. If the 1PPS rate is adjusted, the new rate does not start until the next second begins.

Figure 2: 1PPS alignment below shows the 1PPS alignment between a Fine and a Warm Clock receiver. See also the **TIMESYNC** log on page 1003 and Transferring Time Between Receivers in the OEM7 Installation and Operation User Manual.

Figure 2: 1PPS alignment



The 1PPS is obtained from different receivers in different ways.

In *Figure 2: 1PPS alignment* on the previous page, the examples are for the transfer of time. If you need position, you must be tracking satellites and your receiver must have a valid almanac.

Alternatively, the 1PPS signal can be set up to be output on a COM port using the **COMCONTROL** command (see page 124). The accuracy of the 1PPS is less using this method, but may be more convenient in some circumstances.

Table 14: COM Port Signals Available for 1PPS

OEM719	OEM729	OEM7600	OEM7700	OEM7720	PwrPak7	CPT7
COM1 Tx	COM1 Tx	COM1 Tx	COM1 Tx	COM1 Tx	COM1 Tx	COM1 Tx
COM2 Tx	COM2 Tx	COM2 Tx	COM2 Tx	COM2 Tx	COM2 Tx	COM2 Tx
	COM2 RTS	COM2 RTS	COM2 RTS	COM2 RTS		
	COM3 Tx	COM3 Tx	COM3 Tx	COM3 Tx	COM3 Tx	
		COM4 Tx	COM4 Tx	COM4 Tx		
		COM5 Tx	COM5 Tx	COM5 Tx		

To find out the time of the last 1PPS output signal, use the TIMESYNCA/B output message (see the **TIMESYNC** log on page 1003) which can be output serially on any available COM port, for example:

```
LOG COM1 TIMESYNCA ONTIME 1
```

Message ID: 429

Abbreviated ASCII syntax:

```
ADJUST1PPS mode [period] [offset]
```

Factory default:

```
ADJUST1PPS OFF
```

ASCII example:

```
ADJUST1PPS MARK CONTINUOUS 250
```

Use the **ADJUST1PPS** command to synchronize two OEM7 cards in a primary/secondary relationship to a common external clock.

At the Primary Receiver:

```
LOG COM2 TIMESYNCA ONTIME 1
INTERFACEMODE COM2 NOVATEL NOVATEL OFF
CLOCKADJUST DISABLE
EXTERNALCLOCK OCXO 10MHZ
```
(choose rubidium, cesium or user instead and choose 5MHz instead if necessary)

At the Secondary Receiver:

```
INTERFACEMODE COM2 NOVATEL NOVATEL OFF
CLOCKADJUST DISABLE
ADJUST1PPS MARK
```
(or markwithtime or time depending on your connection (see *Figure 3: ADJUST1PPS connections* on the next page)

```
EXTERNALCLOCK OCXO 10MHZ
```
(you can choose rubidium, cesium or user instead and choose 5MHz instead if necessary)

Connections:

- Null modem cable connected from Primary COM2 to Secondary COM2
- OCXO signal sent through a splitter to feed both the Primary and Secondary Receiver external clock inputs
- Primary 1PPS connected to Secondary MKI


Connect everything before applying power. If power is applied and the OEM7 receivers have acquired satellites before the OCXO and/or 1PPS = MKI is set up, the times reported by the TIMESYNC logs still diverge. Note that after the clock model was stabilized at state 0, the time difference between the Primary and Secondary Receivers reported by the TIMESYNC log was less than 10 ns.

When connecting two receivers to transfer time, disable responses on the COM port used to connect the receivers by issuing the following command on both receivers:


```
INTERFACEMODE COM2 NOVATEL NOVATEL OFF
```

The following examples are for the transfer of time. If you need position, you must be tracking satellites and your receiver must have a valid almanac.


Figure 3: ADJUST1PPS connections



`adjust1pps mark` (if Receiver 2 is not in coarsetime, the input is ignored)



`adjust1pps markwithtime` (will get to finetime)



`adjust1pps time` (will only get to coarsetime)

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ADJUST1PPS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	See *Table 15: ADJUST1PPS mode* on the next page		Sets the ADJUST1PPS mode.	Enum	4	H
3	period	ONCE	0	The time is synchronized only once (default). The **ADJUST1PPS** command must be reissued if another synchronization is required	Enum	4	H+4
		CONTINUOUS	1	The time is continuously monitored and the receiver clock is corrected if an offset of more than 50 ns is detected			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	offset	-2147483648 to +2147483647 (ns)		Allows the operator to shift the Secondary clock in 20 ns increments. In MANUAL mode, this command applies an immediate shift of this offset in ns to the receiver clock. In MARK and MARKWITHTIME mode, this offset shifts the receiver clock with respect to the time of arrival of the MK1I event. If this offset is zero, the Secondary aligns its 1PPS to that of the signal received in its MK1I port. For example, if this value was set to 50, then the Secondary would set its 1PPS 50 ns ahead of the input signal and if this value was set to -100 then the would set its clock to 100 ns behind the input signal. Typically, this offset is used to correct for cable delay of the 1PPS signal (default=0)	Long	4	H+8

Table 15: ADJUST1PPS mode

ASCII value	Binary value	Description
OFF	0	Disables ADJUST1PPS
MANUAL	1	Immediately shifts the receivers time by the offset field in ns. The period field has no effect in this mode. This command does not affect the clock state.
MARK	2	Shifts the receiver time to align its 1PPS with the signal received in the MK1I port adjusted by the offset field in ns. The effective shift range is ± 0.5 s. Only the MK1I input can be used to synchronize the 1PPS signal. Synchronization cannot be done using the MK2I input offered on some receivers.

ASCII value	Binary value	Description
MARKWITHTIME	3	Shifts the receiver time to align its 1PPS with the signal received in the MK1I port adjusted by the offset field in ns, and sets the receiver TOW and week number, to that embedded in a received **TIMESYNC** log (see page 1003). Also sets the receiver Time Status to that embedded in the **TIMESYNC** log (see page 1003), which must have arrived between 800 and 1000 ms prior to the MK1I event (presumably the 1PPS from the Primary), or it is rejected as an invalid message. See *Figure 2: 1PPS alignment* on page 63 and *TIMESYNC* on page 1003. Also refer to Transferring Time Between Receivers in the OEM7 Installation and Operation User Manual.
TIME	4	If the receiver clock is not at least COARSEADJUSTED, this command enables the receiver to COARSE adjust its time upon receiving a valid **TIMESYNC** log (see page 1003) in any of the ports. The clock state embedded in the **TIMESYNC** log (see page 1003) must be at least FINE or FINESTEERING before it is considered. The receiver does not use the MK1I event in this mode.

2.5 ALIGNAUTOMATION

Configures ALIGN plug-and-play feature

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command configures the ALIGN plug and play feature. Use this command to enable/disable the plug and play feature, to set the Rover COM port to which the Base receiver is connected, to set the baud rate for communication, to set the intended operation rate using this command and to enable/disable sending the HEADINGEXTB/HEADINGEXT2B back to the Base receiver.

On issuing this command at the ALIGN Rover, the Rover will automatically sync with the ALIGN Base and configure it to send corrections at the specified baud rate and specified data rate.



This command should only be issued at ALIGN Rover.

Message ID: 1323

Abbreviated ASCII syntax:

```
ALIGNAUTOMATION option [comport] [baudrate] [datarate] [headingextboption]
[interfacemode]
```

Factory default:

```
ALIGNAUTOMATION disable
```

Example:

```
ALIGNAUTOMATION enable com2 230400 10 ON
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ALIGNAUTOMATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	ENABLE	1	Enable or disable the plug-and-play feature	Enum	4	H
		DISABLE	0				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	comport	COM1, COM2, COM3, COM4, or COM5		Rover COM port to which the Base is connected (*Table 76: COM port identifiers* on page 384) (default=COM2) COM4 and COM5 are available only on OEM7600, OEM7700. and OEM7720.	Enum	4	H+4
4	baudrate	9600, 19200, 38400, 57600, 115200, 230400, or 460800		Intended baud rate for data transmission (default=230400)	Ulong	4	H+8
5	datarate	1, 2, 4, 5, 10, or 20		Rate (in Hz) at which heading output is required (default=10 Hz)	Ulong	4	H+12
6	headingextb option	OFF	0	Enable or disable sending HEADINGEXTB/ HEADINGEXT2B back to the Base (default=ON)	Enum	4	H+16
		ON	1				
7	interfacemode	See *Table 46: Serial Port Interface Modes* on page 220		Serial port interface mode (default=None)	Enum	4	H+20

2.6 ANTENNAPOWER

Controls power to the antenna

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This command enables or disables the supply of electrical power from the internal power source of the receiver to the Low Noise Amplifier (LNA) of an active antenna. Refer to the OEM7 Installation and Operation User Manual for further information about supplying power to the antenna.

There are several bits in the receiver status that pertain to the antenna (see *Table 225: Receiver status* on page 921). These bits indicate whether the antenna is powered and whether it is open circuited or short circuited.

Message ID: 98

Abbreviated ASCII syntax:

```
ANTENNAPOWER switch
```

Factory default:

```
ANTENNAPOWER ON
```

ASCII examples:

```
ANTENNAPOWER ON
ANTENNAPOWER OFF
```

If a short circuit or other problem causes an overload of the current supplied to the antenna, the receiver hardware shuts down the power supplied to the antenna. To restore power, power cycle the receiver. The Receiver Status word, available in the RXSTATUS log (see page 917), provides more information about the cause of the problem.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ANTENNAPOWER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	See *Table 16: ANTENNAPOWER parameters* on the next page		Antenna power setting	Enum	4	H

Table 16: ANTENNAPOWER parameters

Binary	ASCII	Description
0	OFF	Disables antenna power. On dual antenna receivers, disables antenna power for both antennas.
1	ON	Enables antenna power. On dual antenna receivers, enables antenna power for both antennas.
3	PRIMARY_ON_SECONDARY_OFF	Enables primary antenna power and disables secondary antenna power. **Note**: Dual antenna receivers only
4	PRIMARY_OFF_SECONDARY_ON	Disables primary antenna power and enables secondary antenna power. **Note**: Dual antenna receivers only

The OEM7 dual antenna receivers are: OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2 and CPT7.

2.7 ANTENNATYPE

Store the user defined antenna type

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use the **ANTENNATYPE** command to control the storage of up to five user-defined antennas. Values are entered and interpreted according to the conventions in the IGS ANTEX format.

The current list of user-defined antennas stored by the receiver can be viewed using the **USERANTENNA** log on page 1010. The **THISANTENNATYPE** command (see page 430) and **BASEANTENNATYPE** command (see page 95) control the use of the antennas in RTK.

Message ID: 2281

Abbreviated ASCII syntax:

```
ANTENNATYPE Action AntennaType [AntennaName] [NumberOfFrequencies]
[Frequency] [NorthOffset] [EastOffset] [UpOffset] [PCVArray] ...
```

The “Number of frequencies” determines the number of frequencies for which Phase Centre Offsets (PCOs) and Phase Centre Variations (PCVs) are stored. For simplicity, the syntax above shows a single frequency. The ASCII Example 1 below shows two frequencies being added.
PCOs and PCVs can be defined for up to 24 frequencies.

ASCII example 1:

```
ANTENNATYPE ADD USER_ANTENNA_1 NOVCUSTOM 2 GPSL1 0.09 0.0 51.74 0 -0.03
-0.11 -0.20 0.23 -0.17 -0.04 0.14 0.26 0.25 0.07 -0.24 -0.54 -0.67 -0.49
-0.02 0.55 0.84 0.47 GPSL2 -1.54 1.66 52.00 0.00 0.0 0.0 -0.03 -0.13 -0.28
-0.48 -0.61 -0.56 -0.28 0.23 0.84 1.29 1.31 0.77 -0.16 -0.95 -0.81 0.97
```

ASCII example 2:

```
ANTENNATYPE REMOVE USER_ANTENNA_1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	ANTENNATYPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Action	ADD	0	Add a user antenna	Enum	4	H
		REMOVE	1	Delete a user antenna			
3	AntennaType	*Table 17: User-defined antenna type* on the next page		User defined antenna type	Enum	4	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	AntennaName			Name of the user defined antenna	Char[16]	16	H+8
5	NumberOf Frequencies			Number of frequencies for which corrections are stored	Ulong	8	H+24
6	Frequency	See *Table 22: Frequency type* on page 93		The frequency for which the phase centre corrections are valid.	Enum	4	H+32
7	NorthOffset			North phase centre offset (millimetres) Valid range: -326.66 to 326.66	Float	4	H+36
8	EastOffset			East phase centre offset (millimetres) Valid range: -326.66 to 326.66	Float	4	H+40
9	UpOffset			Up phase centre offset (millimetres) Valid range: -326.66 to 326.66	Float	4	H+44
10	PCVArray			19 element array of Phase Centre Variations in 5-degree elevation increments from 90 degrees elevation to 0 degrees (millimetres) Valid range: -326.66 to 326.66	Float[19]	76	H+48
11	Next Frequency = H + 32 + (Number of frequencies x 92)						

Table 17: User-defined antenna type

Binary	ASCII
1001	USER_ANTENNA_1
1002	USER_ANTENNA_2
1003	USER_ANTENNA_3
1004	USER_ANTENNA_4
1005	USER_ANTENNA_5

2.8 APPROXPOSTIMEOUT

Timeout for approximate positions in the receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the approximate position timeout of the receiver. Approximate positions are used upon startup of the receiver to populate the satellite visibility lists (see **SATVIS2** log on page 942) that aid in initial acquisition of signals. By default, an approximate position times out after 150 seconds and the receiver reverts to a cold search. This command is typically used in a high dynamic application where an initial position becomes inaccurate.

Message ID: 1513

Abbreviated ASCII syntax:

```
APPROXPOSTIMEOUT timeout
```

Factory default:

```
APPROXPOSTIMEOUT 150
```

ASCII example:

```
APPROXPOSTIMEOUT 20
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	APPROXPOSTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Timeout	0 to 86400		Timeout in seconds. Default = 150	Ulong	4	H

2.9 ASSIGN

Assigns a channel to a PRN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ASSIGN command should only be used by advanced users.

1. Assigning SV channel sets the forced assignment bit in the channel tracking status field which is reported in the RANGE and TRACKSTAT logs.
2. Assigning a PRN to a SV channel does not remove the PRN from the search space of the automatic searcher; only the SV channel is removed (that is, the searcher may search and lock onto the same PRN on another channel). See *Table 12: PRN numbers for commands and logs* on page 55 for the PRN available for the **ASSIGN** command.
3. GLONASS SVs cannot be assigned if there is no information on GLONASS frequencies and matching slot numbers.
4. OEM7 cards have 4 channels available for SBAS. They automatically use the healthy GEO satellites with the highest elevations. Use the **ASSIGN** command to enter a GEO PRN manually.
5. The **ASSIGN** and **UNASSIGN** commands are not accepted for L-band channels. The **ASSIGNLBANDBEAM** command (see page 83) should be used for L-band channels.
6. Manually assigned satellites are not reported in the **RANGECMP4** log (see page 851).

This command may be used to aid in the initial acquisition of a satellite by manually overriding the automatic satellite/channel assignment and reacquisition processes. The command specifies that the indicated tracking channel search for:

- a specified satellite
- at a specified Doppler frequency
- within a specified Doppler window

The instruction remains in effect for the specified SV channel and PRN, even if the assigned satellite is below the elevation cutoff. If the satellite Doppler offset of the assigned SV channel exceeds that specified by the window parameter of the **ASSIGN** command, the satellite may never be acquired or reacquired. If a channel has been manually assigned, and the channel is changed to AUTO tracking, then the channel is idled immediately and returns to automatic mode.

To cancel the effects of **ASSIGN**, issue one of the following:

- The **ASSIGN** command with the state set to AUTO
- The **UNASSIGN** command (see page 443)
- The **UNASSIGNALL** command (see page 445)

These immediately return SV channel control to the automatic search engine

Message ID: 27

Abbreviated ASCII syntax:

```
ASSIGN channel [state] [prn [Doppler [Doppler window]]]
```

ASCII example 1:

```
ASSIGN 0 ACTIVE 29 0 2000
```

In example 1, the first SV channel is searching for satellite PRN 29 in a range from -2000 Hz to 2000 Hz until the satellite signal is detected.

ASCII example 2:

```
ASSIGN 11 28 -250 0
```

SV channel 11 is searching for satellite PRN 28 at an offset of -250 Hz only.

ASCII example 3:

```
ASSIGN 11 IDLE
```

SV channel 11 is idled and does not attempt to search for satellites.

For dual antenna receivers:

- On the primary antenna, the SV channel is from 0 to N-1, where N is the number of channels in the primary antenna channel configuration.
- On the secondary antenna, the SV channel count is from at N to N+(M-1), where M is the number of channels in the secondary antenna SV channel configuration.
- Even though L-band channels cannot be configured with the **ASSIGN** command, they are included when determining N.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ASSIGN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	channel	0 to n-1, where n is the maximum number of GNSS channels in the current channel configuration		Desired SV channel number where channel 0 is the first SV channel. The last channel depends on the model configuration.	Ulong	4	H
3	state	Refer to *Table 18: Channel state* on the next page		Set the SV channel state. If a value is not given, the default of ACTIVE is used when the additional optional parameters are entered.	Enum	4	H+4
4	prn	Refer to *PRN numbers* on page 55		Optional satellite PRN number. A value must be entered unless the state parameter is IDLE or AUTO.	Ulong	4	H+8

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
5	Doppler	-100 000 to 100 000 Hz		Current Doppler offset of the satellite. (default=0) **Note**: Satellite motion, receiver antenna motion and receiver clock frequency error must be included in the calculation of Doppler frequency.	Long	4	H+12
6	Doppler window	0 to 10 000 Hz		Error or uncertainty in the Doppler estimate above. (default=4500) Note: This is a ± value. Example: 500 for ± 500 Hz	Ulong	4	H+16

Table 18: Channel state

Binary	ASCII	Description
0	IDLE	Set the SV channel to not track any satellites
1	ACTIVE[1]	Set the SV channel active (default)
2	AUTO	Tell the receiver to automatically assign PRN numbers to channels

1. A PRN number is required when using the ACTIVE channel state in this command.

2.10 ASSIGNALL

Assigns all channels of a satellite system

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ASSIGNALL command should only be used by advanced users.

This command is used to override the automatic satellite assignments for all channels for a satellite system.

Message ID: 28

Abbreviated ASCII syntax:

```
ASSIGNALL [system][state][prn [Doppler [Doppler window]]]
```

ASCII example 1:

```
ASSIGNALL GLONASS IDLE
```

In example 1, all GLONASS channels are idled, so the receiver does not track GLONASS.

ASCII example 2:

```
ASSIGNALL GLONASS AUTO
```

In example 2, all GLONASS channels are enabled in auto mode. This enables the receiver to automatically assign channels to track the available GLONASS satellites.

FW 7.09 For dual antenna receivers, an **ASSIGNALL** command configures both antennas.

FW 7.10 For dual antenna receivers, an **ASSIGNALL_1** command is used to configure only the second antenna. An **ASSIGNALL** command configures only the primary antenna.
The ASSIGNALL and ASSIGNALL_1 commands use the same message ID.

This command is the same as ASSIGN except that it affects all SV channels of the specified satellite system.

These command examples are only applicable to specific receiver models.

If the system field is used with this command and the receiver has no channels configured with that satellite system, the command is rejected.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ASSIGNALL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	system	See *Table 19: Satellite system* below		Satellite system to assign. If no value is specified, the value defaults to ALL.	Enum	4	H
3	state	Refer to *Table 18: Channel state* on page 79)		Set the SV channel state.	Enum	4	H+4
4	prn	Refer to *PRN numbers* on page 55		Optional satellite PRN code. A value must be entered if the state parameter is neither IDLE or AUTO.	Ulong	4	H+8
5	Doppler	-100 000 to 100 000		Current Doppler offset of the satellite in Hz. (default=0) **Note**: Satellite motion, receiver antenna motion and receiver clock frequency error must be included in the calculation of Doppler frequency.	Long	4	H+12
6	Doppler window	0 to 10 000		Error or uncertainty in the Doppler estimate above in Hz. (default=4500) **Note**: This is a ± value Example, 500 for ± 500 Hz	Ulong	4	H+16

Table 19: Satellite system

Binary	ASCII	Description
3	ALL	All systems
99	GPS	GPS system
100	SBAS	SBAS system
101	GLONASS	GLONASS system
102	GALILEO	GALILEO system
103	BEIDOU	BeiDou system
104	QZSS	QZSS system
105	NAVIC	NavIC system

GLONASS SVs cannot be assigned if there is no information on GLONASS frequencies and matching slot numbers.

2.11 ASSIGNLBANDBEAM

Configure L-band tracking

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command assigns TerraStar or Veripos beams to the L-band channels based on the defined L-band assignment option.

Logging the **ASSIGNLBANDBEAM** command may not display the correct values. To access the actual beam name, frequency and baud rate values, log the **LBANDTRACKSTAT** log (see page 709) or if the beam name is known, log the **LBANDBEAMTABLE** log (see page 707) and find the associated frequency and baud rate.

Message ID: 1733

Abbreviated ASCII syntax:

```
ASSIGNLBANDBEAM [option] [name] [frequency] [baudrate] [Dopplerwindow]
```

Factory default:

```
ASSIGNLBANDBEAM idle
```

```
ASSIGNLBANDBEAM auto
```
(SMART2 and SMART7)

ASCII examples:

```
ASSIGNLBANDBEAM auto
```

```
ASSIGNLBANDBEAM 98W
```

```
ASSIGNLBANDBEAM manual 98w 1545865000 1200
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Command header	ASSIGNLBANDBEAM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Option	Assignment option (see *Table 20: L-band assignment option* on the next page) (manual=default)	Enum	4	H
3	Name	Beam name (empty string=default)	Char[8]	8	H+4
4	Frequency	Beam frequency in Hz (0=default)	Ulong	4	H+12
5	Baud rate	Data baud rate (0=default)	Ulong	4	H+16
6	Doppler window	Doppler window to search (6000=default)	Ulong	4	H+20

Table 20: L-band assignment option

ASCII	Binary	Description
IDLE	0	Idle all L-band channels
AUTO	1	The receiver searches for multiple L-band beams on the L-band channels based on AUTO selection criteria. If the receiver position is known, the AUTO selection criteria is a ranking of granted access L-band beams by descending elevation angle. If the receiver position is not known, the AUTO selection criteria is a ranking of granted access L-band beams in the order they appear in the stored beam table (see the **LBANDBEAMTABLE** log on page 707).
MANUAL	2	The receiver assigns the specified beam on the first L-BAND channel and makes the other L-BAND channels IDLE.

2.12 AUTH

Authorization code for different model

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Software models can be delivered to the receiver in multiple ways:

- a model dispatch message is automatically delivered over L-band or an NTRIP corrections stream
- a model dispatch message is delivered through the **DISPATCHSET** command (see page 141)
- an auth-code is installed with the **AUTH** command
- an auth-code is embedded in a firmware upgrade

Dispatch messages are not available on older firmware versions. Specifically,

- 7.09.xx firmware previous to 7.09.06
- 7.10.xx firmware previous to 7.10.02

For information about software models, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

The **AUTH** command manages the list of auth codes that have been installed on the receiver.

The **AUTH** command does not affect models installed by dispatch message. See the **DISPATCHSET** command on page 141 for more information.

The **AUTHCODES** log (see page 498) lists all authorization codes stored on the receiver and the **VALIDMODELS** log (see page 1018) lists the currently available models, including those delivered by dispatch. The **MODEL** command (see page 265) can be used to switch between authorized models.

The **DISPATCHSCHEDULE** log (see page 571) indicates the selected model for use outside service periods as well as the currently active model. When the selected auth-code expires or is removed, the first valid model in the auth-code table is selected, if present, otherwise one delivered by dispatch message.

Message ID: 49

Abbreviated ASCII syntax:

```
AUTH [state] part1 part2 part3 part4 part5 model [date]
```

Input example:

```
AUTH add T48JF2,W25DBM,JH46BJ,2WGHMJ,8JW5TW,G2SR0RCCR,101114
AUTH erase_table PW5W2B,WW5TM9,WW2PCZ,WW3M4H,WW4HPG,ERASE_AUTH
```

When you are ready to upgrade from one model to another, call 1-800-NOVATEL to speak with our Customer Support/Sales Personnel, who can provide the authorization code that unlocks the additional features of your GNSS receiver. This procedure can be performed at your work site and takes only a few minutes.

Receiver models can also be downgraded. This is a two step handshaking process and is best performed in a location with e-mail access.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	AUTH header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	state	See *Table 21: AUTH command state* on the next page		Authorization code function to perform	Enum	4	H
3	part1	6 character ASCII string		Authorization code section 1	String [max. 16]	Variable[1]	H+4
4	part2	6 character ASCII string		Authorization code section 2	String [max. 16]	Variable[1]	H+20
5	part3	6 character ASCII string		Authorization code section 3	String [max. 16]	Variable[1]	H+36
6	part4	6 character ASCII string		Authorization code section 4	String [max. 16]	Variable[1]	H+52
7	part5	6 character ASCII string		Authorization code section 5	String [max. 16]	Variable[1]	H+68
8	model	Alpha numeric	Null terminated	Model name of the receiver	String [max. 16]	Variable[1]	H+84
9	date	Numeric	Null terminated	Expiry date entered as yymmdd in decimal For binary, if the authorization code does not have an expiry date, enter 4 null characters.	String [max 7]	Variable[1]	Variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

Table 21: AUTH command state

ASCII	Binary	Description
REMOVE	0	Marks the auth-code invalid so it cannot be used and the auth-code is not shown in the **AUTHCODES** log (see page 498). **AUTH REMOVE** does not reboot the receiver and no immediate change to capability (or the **VALIDMODELS** log (see page 1018)) occurs until the next receiver reset. The auth-code remains in the table until **AUTH CLEAN_TABLE** or **AUTH ERASE_ TABLE** is used, however it cannot be made valid again (unless the full-auth code is added again). If the selected permanent model is removed, the selection reverts to another model in the table. For this parameter, the Part1-Part5 fields can be entered as 0 0 0 0 0, and only the model name entered.
ADD	1	Installs an auth-code in a table in flash memory, selects that model as the one to use as the selected permanent model, and immediately reboots the receiver so it is applied. This is the default option. An auth-code entered incorrectly will be rejected. An auth-code for a different receiver will be installed, but the receiver will report an invalid auth-code with no tracking until a correct model is installed. The auth-codes table can hold up to 24 entries, including invalid, expired and removed codes. If **AUTH ADD** fails you may need to use **AUTH CLEAN_TABLE**. Selecting a model during a subscription service period will override the model provided with the service period (see **DISPATCHSCHEDULE** log on page 571 Receiver features field) and may interfere with or disable those service products. This override can be cancelled with the **MODEL** SERVICEPERIOD command. See the **DISPATCHSET** command on page 141 for a method of delivering models that does not interfere.
ADD_ DOWNLOAD	4	Add the auth-code to the system (Deprecated: Use ADD instead)

ASCII	Binary	Description
ERASE_ TABLE	7	Removes all auth-codes from the table. This option does not affect models installed by dispatch message. **A receiver with no model available performs no GNSS functions and is only capable of user interface commands so that a new model can be entered.** Requires a special auth-code to prevent against accidental erasing. The special auth-code required for this option is: PW5W2B,WW5TM9,WW2PCZ,WW3M4H,WW4HPG,ERASE_AUTH
CLEAN_ TABLE	8	Removes all expired and removed auth-codes from the table making space for new auth-codes. Requires a special auth-code to prevent against accidental erasing. The special auth-code required for this option is: 4DR69H,G369W8,34MNJJ,5NHXCJ,GW7C75,CLEAN_AUTH

2.13 AUTOSURVEY

Survey for accurate position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **AUTOSURVEY** command uses position averaging to automatically determine the position for a base station.

When the **AUTOSURVEY** command is sent, the receiver starts position averaging. The position averaging continues until a specified accuracy level is met or until the specified survey time expires. The current status of the position averaging can be found in the **AVEPOS** log on page 500. When position averaging is complete, the calculated position is saved as the fix position for the base station. This calculated position is then used when transmitting differential corrections to the rover.

The **AUTOSURVEY** command computes the base position in WGS84.

If the **FIX** command is entered by a user, the **SAVECONFIG** command must then be issued to save to NVM. If the **FIX** command is issued by the AUTOSURVEY feature, the **SAVECONFIG** command does not need to be issued, because it is automatically saved to NVM.

On subsequent power ups or resets, an AUTOSURVEY runs to determine if the base station has moved. As the AUTOSURVEY runs, the average position calculated is compared to the saved fix position. If the average position is within the AUTOSURVEY tolerance setting, the receiver assumes it has not moved and uses the previously saved fix position. If the average position is outside of the AUTOSURVEY tolerance setting, the receiver assumes it has moved and will continue calculating a position average until the accuracy level is met or until the specified survey time expires.

The surveyed positions saved using the **AUTOSURVEY** command can be viewed using the **SAVEDSURVEYPOSITIONS** log on page 948. Surveyed positions can be added or deleted using the **SURVEYPOSITION** command on page 423.

The maximum number of surveys that can be saved to memory is 32. If this number is exceeded, the new position entry will overwrite the last entry reported by the **SAVEDSURVEYPOSITIONS** log.

Message ID: 1795

Abbreviated ASCII syntax:

```
AUTOSURVEY control [time] [accuracy] [tolerance] [save_nvm] [position_id]
```

Input example:

In the following example, the receiver is set up to survey its position for up to 24 hours or until the averaged position accuracy is 10 cm. On subsequent power ups at the same location, the survey will terminate as soon as the receiver determines the position is within 4 m of its surveyed position. Once the receiver has fixed its position, it will transmit RTCMV3 corrections over COM2.

```
SERIALCONFIG COM2 115200 N 8 1 N ON
INTERFACEMODE COM2 NONE RTCMV3 OFF
```

```
LOG COM2 RTCM1004 ONTIME 1
LOG COM2 RTCM1012 ONTIME 1
LOG COM2 RTCM1006 ONTIME 10
LOG COM2 RTCM1033 ONTIME 10
LOG COM2 RTCM1019 ONTIME 120
AUTOSURVEY ENABLE 1440 .1 4
SAVECONFIG
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	AUTOSURVEY header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	control	disable	0	Disables the self-survey feature and halts any self-survey related activity (default = disable)	Enum	4	H
		enable	1	Enables the self-survey feature			
3	time	1 - 6000 minutes		Maximum amount of time to perform self-survey (default = 1440 minutes)	Ulong	4	H+4
4	accuracy	0 - 100 metres		Desired horizontal standard deviation (default = 0.1 metres)	Float	4	H+8
5	tolerance	3 - 100 metres		Maximum distance between calculated position and saved position. During the self-survey, if the distance between the calculated position and the previously surveyed position is less than this value, the previous position is used. (default = 10 metres)	Float	4	H+12
6	save_nvm	OFF	0	Do not save position in NVM	Enum	4	H+16
		ON	1	Save position in NVM (default = ON)			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
7	position_id	4 character string		ID for the saved position. If the ID is not specified or if the ID is entered as "AUTO", receiver automatically generates a unique ID for the position. This ID is the ID for the surveyed position, not the station ID set using the **DGPSTXID** command on page 138.	String[5]	4 or 8[1]	H+20

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.14 BASEANTENNAPCO

Sets the PCO model of the base receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use the **BASEANTENNAPCO** command to set the Phase Centre Offsets (PCO) for a given frequency on the remote base receiver from which this receiver is receiving corrections. The Offsets are defined as North, East and Up from the Antenna Reference Point to the Frequency Phase Centre in millimetres.

Message ID: 1415

Abbreviated ASCII syntax:

```
BASEANTENNAPCO Frequency NorthOffset EastOffset UpOffset [CorrectionType
[StationId]]
```

ASCII example:

```
BASEANTENNAPCO GPSL1 0.61 1.99 65.64
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	BASEANTENNAPCO header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Frequency	See *Table 22: Frequency type* on the next page		The frequency that the phase centre offsets are valid for.	Enum	4	H
3	NorthOffset			NGS standard Phase Centre North Offset in millimetres.	Double	8	H+4
4	EastOffset			NGS standard Phase Centre East Offset in millimetres.	Double	8	H+12
5	UpOffset			NGS standard Phase Centre Up Offset in millimetres.	Double	8	H+20
6	CorrectionType	See *Table 70: RTK source type* on page 350		Correction type (default = AUTO)	Enum	4	H+28
7	StationID	Char [8] or ANY		ID string for the base station (default = ANY)	Char	8	H+32

Table 22: Frequency type

Value	Name	Description
0	GPSL1	GPS L1 frequency
1	GPSL2	GPS L2 frequency
2	GLONASSL1	GLONASS L1 frequency
3	GLONASSL2	GLONASS L2 frequency
5	GPSL5	GPS L5 frequency
7	GALILEOE1	Galileo E1 frequency
8	GALILEOE5A	Galileo E5a frequency
9	GALILEOE5B	Galileo E5b frequency
10	GALILEOALTBOC	Galileo AltBOC frequency
11	BEIDOUB1	BeiDou B1 frequency
12	BEIDOUB2	BeiDou B2 frequency
13	QZSSL1	QZSS L1 frequency
14	QZSSL2	QZSS L2 frequency
15	QZSSL5	QZSS L5 frequency

2.15 BASEANTENNAPCV

Sets the PCV model of the base receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use the **BASEANTENNAPCV** command to set the Phase Centre Variation (PCV) for a given frequency on the remote base receiver from which this receiver is receiving corrections. The Phase Centre Variation entries follow the NGS standard and correspond to the phase elevation at 5 degree increments starting at 90 degrees and decreasing to 0.

Message ID: 1416

Abbreviated ASCII syntax:

```
BASEANTENNAPCV Frequency [PCVArray [CorrectionType [StationId]]]
```

ASCII example:

```
BASEANTENNAPCV GPSL1 0.00 -0.020 -0.07 -0.15 -0.24 -0.34 -0.43 -0.51 -0.56 -
0.61 -0.65 -0.69 -0.69 -0.62 -0.44 -0.13 0.28 0.70 1.02
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	BASEANTENNAPCV header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Frequency	See *Table 22: Frequency type* on the previous page		The frequency for which the phase centre variations are valid.	Enum	4	H
3	PCVArray			NGS standard 19 element array of phase centre variations, in millimetres, in 5 degree elevation increments from 90 to 0. Defaults to zero for all elevation increments.	Double [19]	152	H+4
4	CorrectionType	See *Table 70: RTK source type* on page 350		Correction type (default = AUTO)	Enum	4	H+156
5	StationID	Char [8] or ANY		ID string (default = ANY)	Char	8	H+160

2.16 BASEANTENNATYPE

Sets the antenna type of the base receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use the **BASEANTENNATYPE** command to set the type of antenna connected to the base receiver from which this receiver is receiving RTK corrections. There are two sources of antenna information:

- An internal table
  The firmware contains a set of predefined antenna and radome types taken from the IGS ANTEX file. Refer to *Table 23: Antenna type* on the next page and *Table 24: Radome type* on page 105 for the antennas currently supported.
- User-defined antennas
  User-defined antenna types can be entered using the **ANTENNATYPE** command (see page 74).

The **THISANTENNATYPE** command (see page 430) is used to set the type of antenna being used with this receiver.

Message ID: 1419

Abbreviated ASCII syntax:

```
BASEANTENNATYPE AntennaType [RadomeType] [CorrectionType] [StationId]
```

ASCII examples:

```
BASEANTENNATYPE NOV702

BASEANTENNATYPE USER_ANTENNA_1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	BASEANTENNATYPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	AntennaType	See *Table 23: Antenna type* on the next page or *Table 17: User-defined antenna type* on page 75		Antenna type	Enum	4	H
3	RadomeType	See *Table 24: Radome type* on page 105		Radome type (default = NONE)	Enum	4	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	CorrectionType	See *Table 70: RTK source type* on page 350		Correction type (default = AUTO)	Enum	4	H+8
5	StationID	Char [8] or ANY		Base station ID (default = ANY)	Char	8	H+12

The latest information can be obtained from the National Geodetic Survey (NGS) site www.ngs.noaa.gov/ANTCAL.

Table 23: Antenna type

Value	Name	Description
0	NONE	No antenna model
2	AUTO	Determine the antenna model from the RTK corrections (Not valid for THISANTENNATYPE)
3	AERAT2775_43	
4	AOAD_M_B	
5	AOAD_M_T	AOAD/M_T
6	AOAD_M_TA_NGS	AOAD/M_TA_NGS
7	APSAPS-3	
8	ASH700228A	
9	ASH700228B	
10	ASH700228C	
11	ASH700228D	
12	ASH700228E	
13	ASH700699.L1	
14	ASH700700.A	
15	ASH700700.B	
16	ASH700700.C	
17	ASH700718A	
18	ASH700718B	
19	ASH700829.2	
20	ASH700829.3	

Value	Name	Description
21	ASH700829.A	
22	ASH700829.A1	
23	ASH700936A_M	
24	ASH700936B_M	
25	ASH700936C_M	
26	ASH700936D_M	
27	ASH700936E	
28	ASH700936E_C	
29	ASH700936F_C	
30	ASH701008.01B	
31	ASH701073.1	
32	ASH701073.3	
33	ASH701933A_M	
34	ASH701933B_M	
35	ASH701933C_M	
36	ASH701941.1	
37	ASH701941.2	
38	ASH701941.A	
39	ASH701941.B	
40	ASH701945B_M	
41	ASH701945C_M	
42	ASH701945D_M	
43	ASH701945E_M	
44	ASH701945G_M	
45	ASH701946.2	
46	ASH701946.3	
47	ASH701975.01A	
48	ASH701975.01AGP	
49	JAV_GRANT-G3T	
50	JAV_RINGANT_G3T	

Value	Name	Description
51	JAVRINGANT_DM	
52	JNSMARANT_GGD	
53	JPLD/M_R	
54	JPLD/M_RA_SOP	
55	JPSLEGANT_E	
56	JPSODYSSEY_I	
57	JPSREGANT_DD_E	
58	JPSREGANT_SD_E	
59	LEIAR10	
60	LEIAR25	
61	LEIAR25.R3	
62	LEIAR25.R4	
63	LEIAS05	
64	LEIAX1202GG	
65	LEIAS10	
66	LEIAX1203+GNSS	
67	LEIAT202+GP	
68	LEIAT202-GP	
69	LEIAT302+GP	
70	LEIAT302-GP	
71	LEIAT303	
72	LEIAT502	
73	LEIAT503	
74	LEIAT504	
75	LEIAT504GG	
76	LEIATX1230	
77	LEIATX1230+GNSS	
78	LEIATX1230GG	
79	LEIAX1202	
80	LEIGG02PLUS	

Value	Name	Description
81	LEIGS08	
82	LEIGS09	
83	LEIGS12	
84	3S-02-TSADM	
85	3S-02-TSATE	
86	LEIGS15	
87	LEIMNA950GG	
88	LEISR299_INT	
89	LEISR399_INT	
90	LEISR399_INTA	
91	MAC4647942	
92	MPL_WAAS_ 2224NW	
93	MPL_WAAS_ 2225NW	
94	MPLL1_L2_SURV	
95	NAVAN2004T	
96	NAVAN2008T	
97	NAX3G+C	
98	NOV_WAAS_600	
99	NOV501	
100	NOV501+CR	
101	NOV502	
102	NOV502+CR	
103	NOV503+CR	
104	NOV531	
105	NOV531+CR	
106	NOV600	
107	NOV702	
108	NOV702GG	
109	NOV750.R4	

Value	Name	Description
110	SEN67157596+CR	
111	SOK_RADIAN_IS	
112	SOK502	
113	SOK600	
114	SOK702	
115	SPP571212238+GP	
116	STXS9SA7224V3.0	
117	TOP700779A	
118	TOP72110	
119	TPSCR.G3	
120	TPSCR3_GGD	
121	TPSCR4	
122	TPSG3_A1	
123	TPSHIPER_GD	
124	TPSHIPER_GGD	
125	TPSHIPER_LITE	
126	TPSHIPER_PLUS	
127	TPSLEGANT_G	
128	TPSLEGANT2	
129	TPSLEGANT3_UHF	
130	TPSODYSSEY_I	
131	TPSPG_A1	
132	TPSPG_A1+GP	
133	TRM14177.00	
134	TRM14532.00	
135	TRM14532.10	
136	TRM22020.00+GP	
137	TRM22020.00-GP	
138	TRM23903.00	
139	TRM27947.00+GP	

Value	Name	Description
140	TRM27947.00-GP	
141	TRM29659.00	
142	TRM33429.00+GP	
143	TRM33429.00-GP	
144	TRM33429.20+GP	
145	TRM39105.00	
146	TRM41249.00	
147	TRM41249USCG	
148	TRM4800	
149	TRM55971.00	
150	TRM57970.00	
151	TRM57971.00	
152	TRM5800	
153	TRM59800.00	
154	TRM59800.80	
155	TRM59900.00	
156	TRMR8_GNSS	
157	TRMR8_GNSS3	
158	ASH701023.A	
159	CHCC220GR	
160	CHCC220GR2	
161	CHCX91+S	
162	GMXZENITH10	
163	GMXZENITH20	
164	GMXZENITH25	
165	GMXZENITH25PRO	
166	GMXZENITH35	
167	JAVRINGANT_G5T	
168	JAVTRIUMPH_1M	
169	JAVTRIUMPH_1MR	

Value	Name	Description
170	JAVTRIUMPH_2A	
171	JAVTRIUMPH_LSA	
172	JNSCR_C146-22-1	
173	JPSREGANT_DD_E1	
174	JPSREGANT_DD_E2	
175	JPSREGANT_SD_E1	
176	JPSREGANT_SD_E2	
177	LEIAR20	
178	LEIGG03	
179	LEIGS08PLUS	
180	LEIGS14	
181	LEIICG60	
182	NOV533+CR	
183	NOV703GGG.R2	This value may also be used for the GPS-713-GGG-N and GPS-713-GGGL-N antennas.
184	NOV750.R5	
185	RNG80971.00	
186	SEPCHOKE_B3E6	
187	SEPCHOKE_MC	
188	STXS10SX017A	
189	STXS8PX003A	
190	STXS9PX001A	
191	TIAPENG2100B	
192	TIAPENG2100R	
193	TIAPENG3100R1	
194	TIAPENG3100R2	
195	TPSCR.G5	
196	TPSG5_A1	
197	TPSPN.A5	

Value	Name	Description
198	TRM55970.00	
199	TRMR10	
200	TRMR4-3	
201	TRMR6-4	
202	TRMR8-4	
203	TRMR8S	
204	TRMSPS985	
205	AERAT1675_120	
206	ITT3750323	
207	NOV702GGL	
208	NOV704WB	
209	ARFAS1FS	
210	CHAPS9017	
211	CHCI80	
212	GMXZENITH15	
213	HXCCGX601A	
214	IGAIG8	
215	LEICGA60	
216	LEIGS15.R2	
217	LEIGS16	
218	MVEGA152GNSSA	
219	SEPALTUS_NR3	
220	SJTTL111	
221	SOKGCX3	
222	SOKSA500	
223	STHCR3-G3	
224	STXS9I	
225	TPSCR.G5C	
226	TPSHIPER_HR	
227	TPSHIPER_HR+PS	

Value	Name	Description
228	TRM105000.10	
229	TRM115000.00	
230	TRM115000.10	
231	TRMR2	
232	TWIVP6000	
233	TWIVP6050_CONE	
234	JAVTRIUMPH_2A+G	
235	JAVTRIUMPH_2A+P	
236	LEIGS18	
237	LEIGG04PLUS	
238	STXS800	
239	STXS800A	
240	NOV850	This value may also be used for the GNSS-802, GNSS-802L, GNSS-804 and GNSS-804L antennas.
241	TRM159800.00	
242	TRM159900.00	
243	LEIGG04	
244	LEIICG70	
245	JAV_GRANT-G3T+G	
246	JAVGRANT_G5T+GP	
247	JAVTRIUMPH_3A	
248	TPSHIPER_VR	
249	TRM59800.00C	
250	TRM59800.99	
251	TRMR10-2	
252	TRMR12	
253	TRMSPS986	
254	TWIVC6050	
255	TWIVC6150	

Value	Name	Description
256	GMXZENITH60	
257	ASH701945B.99	
258	LEIAS11	
1001	USER_ANTENNA_1	User defined antenna type 1
1002	USER_ANTENNA_2	User defined antenna type 2
1003	USER_ANTENNA_3	User defined antenna type 3
1004	USER_ANTENNA_4	User defined antenna type 4
1005	USER_ANTENNA_5	User defined antenna type 5

Table 24: Radome type

Value	Name
0	NONE
1	SPKE
2	SNOW
3	SCIS
4	SCIT
5	OLGA
6	PFAN
7	JVDM
8	LEIT
9	LEIC
10	LEIS
11	MMAC
12	NOVS
13	TPSH
14	CONE
15	TPSD
16	TCWD
17	UNAV
18	TZGD
19	CHCD

Value	Name
20	JAVC
21	LEIM
22	NOVC
23	ARFC
24	HXCS
25	JVGR
26	STHC
27	DUTD
28	JAVD
29	JVSD

2.17 BDSECUTOFF

Sets elevation cut-off angle for BeiDou satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the elevation cut-off angle for tracked BeiDou satellites. The receiver does not start automatically searching for a BeiDou satellite until it rises above the cut-off angle (when satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they are manually assigned (see the **ASSIGN** command on page 77).

In either case, satellites below the BDSECUTOFF angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle; it could be used in these situations:

- The antenna is at a high altitude, and thus can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Care must be taken when using **BDSECUTOFF** command because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

Use the **ELEVATIONCUTOFF** command on page 157 to set the cut-off angle for all other systems.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

Message ID: 1582

Abbreviated ASCII syntax:

```
BDSECUTOFF angle
```

Factory default:

```
BDSECUTOFF 5.0
```

ASCII example:

```
BDSECUTOFF 10.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	BDSECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	angle	±90.0 degrees		Elevation cut-off angle relative to horizon	Float	4	H

2.18 BESTVELTYPE

Sets the velocity used in the BESTVEL and GPVTG logs

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command configures the source of the velocity that is output in the BESTVEL and GPVTG logs. Set the type to something other than BESTPOS when an unchanging velocity source with specific characteristics is needed.

The Doppler velocity is the highest-availability, lowest-latency velocity available from the receiver. Due to its low latency, it is also the noisiest velocity.

When the **RADARCONFIG** command (see page 326) is enabled, the **BESTVELTYPE** mode is set to **DOPPLER**.

Message ID: 1678

Abbreviated ASCII syntax:

```
BESTVELTYPE mode
```

Factory default:

```
BESTVELTYPE bestpos
```

ASCII example:

```
BESTVELTYPE doppler
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	BESTVELTYPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	BESTPOS	1	Use the velocity from the same positioning filter that is being used to fill BESTPOS and GPGGA.	Enum	4	H
		DOPPLER	2	Always fill BESTVEL and GPVTG using Doppler-derived velocities.			

2.19 BLUETOOTHCONTROL

Configure Bluetooth on the receiver

Platform: SMART2-B, SMART2-TB

The BLUETOOTHCONTROL command is used to set the Bluetooth operating mode.

Bluetooth support for Apple products requires that a custom application be developed.

Message ID: 2265

Abbreviated ASCII syntax:

```
BLUETOOTH switch
```

Factory default:

```
BLUETOOTHCONTROL ENABLE
```

Examples:

```
BLUETOOTHCONTROL ENABLE
BLUETOOTHCONTROL DISABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	BLUETOOTHCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	Switch	DISABLE	0	Power off Bluetooth module	Enum	4	H+4
		ENABLE	1	Power on Bluetooth module and configure to support Bluetooth Serial Port Profile			
		LOAD	2	Load the Bluetooth firmware **Note**: The LOAD switch should not normally be necessary. In rare situations, it might be possible for the Bluetooth module firmware to become corrupt. The LOAD switch can be used to force the Bluetooth image to be reloaded onto the module to correct the situation. Once the firmware is loaded onto the module, Bluetooth functionality is enabled automatically.			

2.20 CANCONFIG

Configure CAN ports

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use the CANCONFIG command to configure the hardware parameters of the CAN ports.

Message ID: 884

Abbreviated ASCII syntax:

```
CANCONFIG port switch [speed]
```

Factory default:

```
CANCONFIG CAN1 OFF 250K
CANCONFIG CAN2 OFF 250K
```

ASCII example:

```
CANCONFIG CAN1 OFF 500K
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CANCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	CAN1	1	Physical CAN port ID **Note**: The SMART2 supports the CAN1 port only. **Note**: The OEM7500 supports the CAN1 port only (firmware version 7.07.03 and later). With firmware versions earlier than 7.07.03, the OEM7500 supports the CAN2 port only.	Enum	4	H
		CAN2	2				
3	switch	ON	1	Sets the port to be On or Off the CAN bus	Enum	4	H+4
		OFF	0				
4	speed	See *Table 25: CAN port speed* on the next page		Physical CAN port speed (bits per second) Default = 250K	Enum	4	H+8

The CAN port must be set to OFF (using `CANCONFIG <port> OFF`) before the port speed can be changed.

Table 25: CAN port speed

ASCII value	Binary value
10K	0
20K	1
50K	2
100K	3
125K	4
250K	5
500K	6
1M	7

2.21 CCOMCONFIG

Configure the CAN COM port

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Bind a CAN communication port to a J1939 node (see **J1939CONFIG** command on page 244) and specify the CAN protocol, PGN, priority and address for messages transmitted and received over the CCOM port.



The SMART2 requires a "-C" model to use this command.

Message ID: 1902

Abbreviated ASCII syntax:

```
CCOMCONFIG port node protocol [pgn [priority [address]]]
```

Factory default:

```
CCOMCONFIG ccom1 node1 J1939 61184 7 fe
CCOMCONFIG ccom2 node2 J1939 61184 7 fe
CCOMCONFIG ccom3 node1 J1939 126720 7 fe
CCOMCONFIG ccom4 none none 0 0 0
CCOMCONFIG ccom5 none none 0 0 0
CCOMCONFIG ccom6 none none 0 0 0
```

ASCII example :

```
ccomconfig ccom1 node1 j1939 1792 6 1b
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CCOMCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	CCOM1	38	Name of CCOM port.	Enum	4	H
		CCOM2	39				
		CCOM3	40				
		CCOM4	41				
		CCOM5	42				
		CCOM6	43				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	node	NODE1	1	The J1939 node to use. This binds a CCOM port to the CAN name/address associated with the node.	Enum	4	H+4
		NODE2	2				
4	protocol	See *Table 26: CAN protocol* on the next page		CAN transport protocol to use. To use the TP (Transport Protocol) feature of the J1939 (SAE J1939/21), select **ISO11783** as the CAN protocol.	Enum	4	H+8
5	pgn	0 - 131071		Any valid PGN as defined by the J1939 protocol. All messages transmitted over this CCOM port will contain this PGN value. Only messages with this PGN will be received on this CCOM port. **Note**: This value is ignored if the protocol is NMEA2000.	Ulong	4	H+12
6	priority	0-7		Default CAN message priority for transmitted messages. (Priority 0 is the highest priority) **Note**: This value is ignored if the protocol is NMEA2000.	Uchar	1	H+16
7	address	00 – FF		**00 – FD**: Transmit and receive messages to/from this address only. **FE**: Transmit and receive message to/from the address of the first message received. **FF**: Broadcast messages and receive messages from all addresses. **Note**: This value is ignored if the protocol is NMEA2000.	Hex	1	H+17

Table 26: CAN protocol

Binary	ASCII	Description
2	J1939	J1939 single packet
3	NMEA2000	NMEA2000 (single packet, multi-packet, fast packet)
5	ISO11783	ISO 11783 transport protocol

2.22 CLOCKADJUST

Enables clock adjustments

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

All oscillators have some inherent drift. By default, the receiver attempts to steer the receiver's clock to accurately match GPS reference time. Use the **CLOCKADJUST** command to disable this function. The TIME log can then be used to monitor clock drift.

The CLOCKADJUST command should only be used by advanced users.

1. If the **CLOCKADJUST** command is ENABLED and the receiver is configured to use an external reference frequency (set in the **EXTERNALCLOCK** command (see page 168) for an external clock - TCXO, OCXO, RUBIDIUM, CESIUM, or USER), then the clock steering process takes over the VARF output pins and may conflict with a previously entered **EVENTOUTCONTROL** command (see page 164).
2. When using the **EXTERNALCLOCK** and **CLOCKADJUST** commands together, issue the **EXTERNALCLOCK** command (see page 168) first to avoid losing satellites.
3. When disabled, the range measurement bias errors continue to accumulate with clock drift.
4. Pseudorange, carrier phase and Doppler measurements may jump if the **CLOCKADJUST** mode is altered while the receiver is tracking.
5. When disabled, the time reported on all logs may be offset from GPS reference time. The 1PPS output may also be offset. The amount of this offset may be determined from the **TIME** log (see page 1000).
6. A discussion on GPS reference time may be found in *GPS reference time status* on page 55.

Message ID: 15

Abbreviated ASCII syntax:

```
CLOCKADJUST switch
```

Factory default:

```
CLOCKADJUST ENABLE
```

ASCII example:

```
CLOCKADJUST DISABLE
```

The **CLOCKADJUST** command can be used to calibrate an internal oscillator. Disable the CLOCKADJUST mode in order to find out what the actual drift is from the internal oscillator. Watch the CLOCKMODEL log to see the drift rate and adjust the oscillator until the drift stops.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CLOCKADJUST header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disallow adjustment of internal clock	Enum	4	H
		ENABLE	1	Allow adjustment of internal clock			

2.23 CLOCKCALIBRATE

Adjusts clock steering parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to adjust the control parameters of the clock steering loop. The receiver must be enabled for clock steering before these values can take effect. Refer to the **CLOCKADJUST** command on page 117 to enable or disable clock steering.

To disable the clock steering process, issue the **CLOCKADJUST DISABLE** command.

The current values used by the clock steering process are listed in the **CLOCKSTEERING** command (see page 557).

The values entered using the **CLOCKCALIBRATE** command are saved to non-volatile memory (NVM). To restore the values to their defaults, the **FRESET CLKCALIBRATION** command must be used. Issuing FRESET without the CLKCALIBRATION parameter will not clear the values (see **FRESET** command on page 192 for more details).

Message ID: 430

Abbreviated ASCII syntax:

```
CLOCKCALIBRATE [mode] [period] [pulsewidth] [slope] [bandwidth]
```

ASCII example:

```
CLOCKCALIBRATE AUTO
```

The receiver by default steers its INTERNAL VCTCXO but can be commanded to control an EXTERNAL reference oscillator. Use the **EXTERNALCLOCK** command (see page 168) to configure the receiver to use an external reference oscillator. If the receiver is configured for an external reference oscillator and configured to adjust its clock, then the clock steering loop attempts to steer the external reference oscillator through the use of the VARF signal. Note that the clock steering control process conflicts with the manual **EVENTOUTCONTROL** command (see page 164) and **FREQUENCYOUT** command (see page 189). It is expected that the VARF signal is used to provide a stable reference voltage by the use of a filtered charge pump type circuit (not supplied).

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CLOCKCALIBRATE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	mode	SET	0	Sets the period, pulsewidth, slope and bandwidth values into NVM for the currently selected steered oscillator. (INTERNAL or EXTERNAL)	Enum	4	H
		AUTO	1	Forces the receiver to do a clock steering calibration to measure the slope (change in clock drift rate with a 1 bit change in pulse width) and required pulsewidth to zero the clock drift rate. After the calibration, these values along with the period and bandwidth are entered into NVM and are then used from this point forward on the selected oscillator.			
		OFF	2	Terminates a calibration process currently underway. (default)			
3	period	0 to 262144		Signal period in 10 ns steps. Frequency Output = 100,000,000 / Period (default=11000)	Ulong	4	H+4
4	pulsewidth	The valid range for this parameter is 10% to 90% of the period		Sets the initial pulse width that should provide a near zero drift rate from the selected oscillator being steered. The valid range for this parameter is 10% to 90% of the period. If this value is not known, (in the case of a new external oscillator) then it should be set to ½ the period and the mode should be set to AUTO to force a calibration. (default=6600)	Ulong	4	H+8

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
5	slope			This value should correspond to how much the clock drift changes with a 1 bit change in the pulsewidth m/s/bit. The default values for the slope used for the INTERNAL and EXTERNAL clocks is -2.0 and -0.01 respectively. If this value is not known, then its value should be set to 1.0 and the mode should be set to AUTO to force a calibration. Once the calibration process is complete and using a slope value of 1.0, the receiver should be recalibrated using the measured slope and pulsewidth values (see the **CLOCKSTEERING** log on page 557). This process should be repeated until the measured slope value remains constant (less than a 5% change). (default=0.774)	Float	4	H+12
6	bandwidth			This is the value used to control the smoothness of the clock steering process. Smaller values result in slower and smoother changes to the receiver clock. Larger values result in faster responses to changes in oscillator frequency and faster start up clock pull in. The default values are 0.03 and 0.001 Hz respectively for the INTERNAL and EXTERNAL clocks. (default=0.03)	Float	4	H+16

2.24 CLOCKOFFSET

Adjusts for delay in 1PPS output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to remove a delay in the PPS output. The PPS signal is delayed from the actual measurement time due to two major factors:

- A delay in the signal path from the antenna to the receiver
- An intrinsic delay through the RF and digital sections of the receiver

The second delay is automatically accounted for by the receiver using a nominal value determined for each receiver type. However, since the delay from the antenna to the receiver cannot be determined by the receiver, an adjustment cannot automatically be made. The **CLOCKOFFSET** command can be used to adjust for this delay.

Message ID: 596

Abbreviated ASCII syntax:

```
CLOCKOFFSET offset
```

Factory default:

```
CLOCKOFFSET 0
```

ASCII example:

```
CLOCKOFFSET -15
```

For dual antenna receivers, a **CLOCKOFFSET_1** command adjusts the delay on the second antenna. A **CLOCKOFFSET** command adjusts the delay on only the primary antenna.

The CLOCKOFFSET and CLOCKOFFSET_1 commands use the same message ID.

There may be small variances in the delays for each cable or card. The **CLOCKOFFSET** command can be used to characterize each setup. For example, for a cable with a delay of 10 ns, the offset can be set to -10 to remove the delay from the PPS output.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CLOCKOFFSET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	offset	±200000		Specifies the offset in nanoseconds.	Long	4	H

2.25 CNOUPDATE

Sets the C/No update rate

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the C/No smoothing rate.

Message ID: 849

Abbreviated ASCII syntax:

```
CNOUPDATE rate
```

Factory default:

```
CNOUPDATE default
```

ASCII example:

```
CNOUPDATE 20Hz
```

Use the **CNOUPDATE** command to change the smoothing rate of the C/No measurements of the incoming GNSS signals. By default, the C/No values are smoothed at approximately 200 ms (5 Hz) but this command allows a user to change that to 50 ms (20 Hz).

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CNOUPDATE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	rate	DEFAULT	0	Default 5 Hz (200 ms) C/No smoothing rate	Enum	4	H
		20HZ	1	20 Hz (50 ms) C/No smoothing rate			

2.26 COMCONTROL

Controls the serial port hardware control lines

Platform: OEM719, OEM729, OEM7600, OEM7700, OEM7720

This command is typically used to control the hardware RTS control line of the serial communication (COM) ports; or, for SPAN applications, to output a 1PPS timing signal on a COM TX port. The TOGGLEPPS mode of this command is typically used to supply a timing signal to a host PC computer by using the RTS line. The PULSEPPSHIGH mode of this command is typically used to supply the timing pulse for SPAN applications by using the TX line. The accuracy of controlling the COM control signals is better than 900 µs. The other modes are typically used to control custom peripheral devices.

1. If handshaking is disabled, any of these modes can be used without affecting regular serial communications through the selected COM port. However, if handshaking is enabled, it may conflict with handshaking of the selected COM port, causing unexpected results.
2. To use the COM2 flow control signals, COM5 must be disabled. See OEM7600, OEM7700 and OEM7720 Multiplexed Port in the OEM7 Installation and Operation User Manual for more information.

Message ID: 431

Abbreviated ASCII syntax:

```
COMCONTROL [port] [signal] [control]
```

Factory default:

```
COMCONTROL COM1 TX DEFAULT
COMCONTROL COM2 TX DEFAULT
COMCONTROL COM3 TX DEFAULT
COMCONTROL COM4 TX DEFAULT
COMCONTROL COM5 TX DEFAULT
```

ASCII example 1:

```
INTERFACEMODE COM5 NONE NONE OFF (OEM7600, OEM7700 and OEM7720 only)
SERIALCONFIG COM2 9600 N 8 1 CTS (to enable handshaking)
COMCONTROL COM2 RTS FORCELOW
```

ASCII example 2:

To set a break condition on COM1:

```
COMCONTROL COM1 TX FORCEHIGH
```

A break condition remains in effect until it is cleared. To clear a break condition on COM1:

```
COMCONTROL COM1 TX DEFAULT
```

or

```
COMCONTROL COM1 TX FORCELOW
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	COMCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	COM1	1	Serial port to control.	Enum	4	H
		COM2	2				
		COM3	3				
		COM4	19				
		COM5	31				
3	signal	RTS	0	COM signal to control. The controllable COM signals are RTS and TX.	Enum	4	H+4
		TX	2				
4	control	See *Table 27: Control options* below		Control applied to the signal	Enum	4	H+8

Table 27: Control options

Binary	ASCII	Description
0	DEFAULT	Disables this command and returns the COM signal to its default state
1	FORCEHIGH	Immediately forces the signal high[1]
2	FORCELOW	Immediately forces the signal low[2]
3	TOGGLE	Immediately toggles the current state of the signal
4	TOGGLEPPS	Toggles the state of the selected signal within 900 µs after each 1PPS event. The state change of the signal lags the 1PPS by an average value of 450 µs. The delay of each pulse varies by a uniformly random amount less than 900 µs
5	PULSEPPSLOW	Pulses the line low at a 1PPS event and to high 1 ms after it.
6	PULSEPPSHIGH	Pulses the line high for 1 ms at the time of a 1PPS event

1. High on RS232; Low on UART
2. Low on RS232; High on UART

Table 28: Port, signal and control availability on OEM7 receivers

	OEM719	OEM729	OEM7600	OEM7700	OEM7720
COM1 TX	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH
COM2 TX	N/A	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH
COM2 RTS	N/A	DEFAULT FORCEHIGH FORCELOW TOGGLE TOGGLEPPS PULSEPPSLOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW TOGGLE TOGGLEPPS PULSEPPSLOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW TOGGLE TOGGLEPPS PULSEPPSLOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW TOGGLE TOGGLEPPS PULSEPPSLOW PULSEPPSHIGH
COM3 TX	N/A	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH
COM4 TX	N/A	N/A	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH
COM5 TX	N/A	N/A	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH	DEFAULT FORCEHIGH FORCELOW PULSEPPSHIGH

2.27 CONFIGCODE

Configuration code

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Configuration Codes can be used to make permanent changes to a receiver. These are configurations that persist even after non-volatile memory is cleared.

A configuration code is different from an auth-code, which controls the functionality the receiver firmware provides.

This command writes to and reads from non-volatile memory. Therefore, it is required that the receiver maintain power throughout the execution of this command. Loss of power during this critical step could result in an unrecoverable error.

Message ID: 1041

Abbreviated ASCII syntax:

```
CONFIGCODE [action] data1 data2 data3 data4 data5 description
```

Input example:

```
CONFIGCODE ERASE_TABLE WJ4HDW,GM5Z99,T2M7DP,KG2T8T,KF7GKR,TABLECLEAR
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	CONFIGCODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	action	REMOVE	0	Invalidate the specified configuration code.	Enum	4	H
		ADD	1	Add the specified configuration code. (default)			
		ADD_NO_RESET	3	Add the specified configuration code without resetting the receiver.			
3	data1			First data block	String [15]	Max. 16	H+4
4	data2			Second data block	String [15]	Max. 16	Variable

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
5	data3			Third data block	String [15]	Max. 16	Variable
6	data4			Fourth data block	String [15]	Max. 16	Variable
7	data5			Fifth data block	String [15]	Max. 16	Variable
8	description			Description of the config code	String [15]	Max. 16	Variable



For the fields with a format of **String [15]** (fields 3 to 8):

- The string must end with one or more '\0'.
- The number of valid characters should not be more than 14.
- The total number of characters (including padding '\0's) must be 4 byte aligned and not more than 16 bytes.

2.28 DATADECODESIGNAL

Enable/disable navigation data decoding for GNSS signal

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to enable or disable framing and decoding of the navigation message for each GNSS signal. When disabled, the receiver will no longer output raw frame data, ephemeris or almanac data from that signal. Signals which do not yet have the built in capability to output raw frame data are not configurable. Note that if a primary signal such as GPSL1CA is disabled, it may cause the receiver to no longer function normally because this signal's data is essential for setting receiver time and computing positions.

The default setting for each GNSS signal, and which signals can be configured, is available in *Table 29: GNSS signal default and configurability* below. The table also lists if the signal's navigation message is used to compute the satellite position. For the binary value and a longer description for each signal, see *Table 30: Signal type* on page 131.

Table 29: GNSS signal default and configurability

Signal	Primary signal	Default	Configurable	Used for satellite positioning
GPSL1C	No	Disabled	No	No
GPSL1CA	Yes	Enabled	Yes	Yes
GPSL2Y	No	Disabled	No	No
GPSL2C	No	Disabled	Yes	No
GPSL2P	No	Disabled	No	No
GPSL5	No	Disabled	Yes	No
GLOL1CA	Yes	Enabled	Yes	Yes
GLOL2CA	No	Disabled	No	No
GLOL2P	No	Disabled	No	No
GLOL3	No	Disabled	No	No
SBASL1	No	Enabled	Yes	Yes
SBASL5	No	Enabled	Yes	Yes
GALE1	Yes	Enabled	Yes	Yes
GALE5A	No	Enabled	Yes	No
GALE5B	No	Enabled	Yes	Yes
GALALTBOC	No	Disabled	No	No
GALE6B	No	Enabled	Yes	No
GALE6C	No	Enabled	Yes	No
BDSB1C	No	Enabled	Yes	Yes

Signal	Primary signal	Default	Configurable	Used for satellite positioning
BDSB1D1	Yes	Enabled	Yes	Yes
BDSB1D2	Yes	Enabled	Yes	Yes
BDSB2A	No	Enabled	Yes	Yes
BDSB2BI	Yes	Enabled	Yes	Yes
BDSB2D1	No	Disabled	No	No
BDSB2D2	No	Disabled	No	No
BDSB3D1	No	Disabled	No	No
BDSB3D2	No	Disabled	No	No
QZSSL1C	No	Disabled	No	No
QZSSL1CA	Yes	Enabled	Yes	Yes
QZSSL1CB	Yes	Enabled	Yes	Yes
QZSSL2C	No	Disabled	Yes	No
QZSSL5	No	Disabled	Yes	No
QZSSL6	No	Disabled	No	No
NAVICL5SPS	Yes	Enabled	Yes	Yes

Message ID: 1532

Abbreviated ASCII syntax:

```
DATADECODESIGNAL signaltype switch
```

Abbreviated ASCII example:

```
DATADECODESIGNAL GPSL2C enable
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	DATADECODESIGNAL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	signal type	See *Table 30: Signal type* on the next page		GNSS Signal Type	Enum	4	H
3	switch	Disable	0	Enable or disable the data decoding	Enum	4	H+4
		Enable	1				

Table 30: Signal type

Binary	ASCII	Description
33	GPSL1CA	GPS L1 C/A-code
47	GPSL1CP	GPS L1C P-code
68	GPSL2Y	GPS L2 P(Y)-code
69	GPSL2C	GPS L2 C-code
70	GPSL2P	GPS L2 P-code
103	GPSL5	GPS L5
2177	GLOL1CA	GLONASS L1 C/A-code
2211	GLOL2CA	GLONASS L2 C/A-code
2212	GLOL2P	GLONASS L2 P-code
2662	GLOL3	GLONASS L3
4129	SBASL1	SBAS L1
4194	SBASL5	SBAS L5
10433	GALE1	Galileo E1
10466	GALE5A	Galileo E5A
10499	GALE5B	Galileo E5B
10532	GALALTBOC	Galileo ALT-BOC
10565	GALE6C	Galileo E6C
10572	GALE6B	Galileo E6B
12673	BDSB1D1	BeiDou B1 with D1 navigation data
12674	BDSB1D2	BeiDou B1 with D2 navigation data
12803	BDSB2D1	BeiDou B2I with D1 navigation data
12804	BDSB2D2	BeiDou B2I with D2 navigation data
12877	BDSB3D1	BeiDou B3 with D1 navigation data
12880	BDSB3D2	BeiDou B3 with D2 navigation data
12979	BDSB1C	BeiDou B1C
13012	BDSB2A	BeiDou B2a
13077	BDSB2BI	BeiDou B2b (I)
14753	QZSSL1CA	QZSS L1 C/A-code
14754	QZSSL1CB	QZSS L1 C/B-code (FW 7.10.02 or greater)

Binary	ASCII	Description
14760	QZSSL1CP	QZSS L1C P-code
14787	QZSSL2C	QZSS L2 C-code
14820	QZSSL5	QZSS L5
14890	QZSSL6D	QZSS L6D (FW 7.10.xx)
14891	QZSSL6P	QZSS L6P (FW 7.09.xx)
19073	NAVICL5SPS	NavIC L5 SPS

2.29 DATUM

Select a datum transformation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to select the ellipsoid used for converting Cartesian co-ordinates to geodetic (latitude, longitude and height) and the transformation applied to positions calculated by the receiver before they are output.

The datum transformation selected by this command will be applied to **all** solutions calculated by the receiver. Solutions based on corrections, like RTK or pseudorange differential, will naturally be in the datum of the corrections; for example, RTK networks in North America will transmit corrections that position users in NAD83. Uncorrected solutions, meanwhile, will be in WGS84 or a datum closely-aligned to it. If different solutions are in different datums then a single transformation will not work in all cases. Care must therefore be taken when using this command.

With RTK, it is normally intended to position in the datum of the base station. A transformation applied to the natural solution will shift the solution out of the base station datum. Consequently, this command is generally not suitable for use with RTK.

Use of the factory default datum of WGS84 will result in no transformation being applied to any solution. User defined datums can also be used, after being created using the **USERDATUM** command (see page 463) or **USEREXPDATUM** command (see page 465).

Datum transformations matter mostly for precise solutions like PPP and RTK, where the difference between datums is large relative to the solution accuracy. As already outlined, RTK solutions are, typically, already in the desired datum. Therefore, in most cases only PPP solutions will need transforming. To transform only the PPP solution, use the **OUTPUTDATUM** command on page 284.

Do not mix the DATUM USER and OUTPUTDATUM commands.

Message ID: 160

Abbreviated ASCII syntax:

```
DATUM datum
```

Factory default:

```
DATUM WGS84
```

ASCII example:

```
DATUM USER
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	DATUM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	datum	WGS84	61	World Geodetic System 84	Enum	4	H
		USER	63	User defined datum set by the **USERDATUM** command (see page 463) and **USEREXPDATUM** command (see page 465).			

2.30 DATUMTRANSFORMATION

Set user-defined datum transformation parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to add or remove user-defined datum transformations. Each entry converts from one geodetic datum in the **GEODETICDATUMS** list to another. Generally, “From” is the native service datum for one of the position types, such as ITRF2020 for TerraStar or Veripos, and “To” is a desired output datum. Entries are indexed by the pair “From” “To”.

The **OUTPUTDATUM** command (see page 284) must be sent for any user-defined transformations to take effect.

The receiver firmware includes a default set of datum transformations. These default transformations cannot be deleted, but can be overwritten with user-defined parameters. A default transformation that has been overwritten can be reverted to the default parameters by deleting the transformation. User-defined transformations will persist a factory reset; all user-defined transformations can be removed by sending **FRESET USER_DATUM_TRANSFORMATION** (see the **FRESET** command on page 192).

The transformation used by this command is the 7 parameter Helmert transformation:

$$\begin{bmatrix} X_s \\ Y_s \\ Z_s \end{bmatrix} = \begin{bmatrix} T_x \\ T_y \\ T_z \end{bmatrix} + (1+s) \begin{bmatrix} 1 & -R_z & R_y \\ R_z & 1 & -R_x \\ -R_y & R_x & 1 \end{bmatrix} \begin{bmatrix} X \\ Y \\ Z \end{bmatrix}$$

Where:

X, **Y**, **Z** are the coordinates in the input datum

$\mathbf{X_s}$, $\mathbf{Y_s}$, $\mathbf{Z_s}$ are the coordinates in the output datum

$\mathbf{T_x}$, $\mathbf{T_y}$, $\mathbf{T_z}$ are the translation parameters corrected for translation rate (metres)

$\mathbf{R_x}$, $\mathbf{R_y}$, $\mathbf{R_z}$ are the rotation parameters corrected for rotation rate (radians)

s is the scale difference corrected for scale rate (unitless)

A given parameter P is corrected for rate:

$P(t)=P(t_r)+ \dot{P}(t_r) (t-t_r)$

Where:

$\mathbf{t_r}$ is the reference epoch of the parameters

t is the current epoch

$\mathbf{P(t_r)}$ is the parameter at the reference epoch

$\mathbf{\dot{P}(t_r)}$ is the rate of the parameter at the reference epoch

The entry contains the reference epoch, value of each parameter at the reference epoch and rate of each parameter at the reference epoch. Both the user-defined and default transformations are reported by the **DATUMTRANSFORMATIONS** log (see page 563).

Message ID: 2297

Abbreviated ASCII syntax:

```
DATUMTRANSFORMATION switch from to [epoch [tx [ty [tz [rx [ry [rz [scale [tx_
vel [ty_vel [tz_vel [rx_vel [ry_vel [rz_vel [scale_vel]]]]]]]]]]]]]]
```

ASCII examples:

Save a new transformation to NVM:

```
DATUMTRANSFORMATION save ITRF2008 NAD83(MA11) 1997.0 0.908 -2.0161 -0.5653
28.971 10.42 8.928 1.1 0.0001 0.0001 -0.0018 -0.02 0.105 -0.347 0.08
```

Delete an existing transformation from NVM:

```
DATUMTRANSFORMATION delete ITRF2008 NAD83(MA11)
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	DATUMTRANS FORMATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	switch	SAVE	1	Save the datum transformation defined by this command.	Enum	4	H
		DELETE	2	Delete the datum transformation.			
3	from			Name of the *From* datum in the **GEODETICDATUMS** log (see page 614).	Char[32]	Variable	H+4
4	to			Name of the *To* datum in the **GEODETICDATUMS** log (see page 614).	Char[32]	Variable	Variable
5	epoch	1900.000 – 3000.000		Reference epoch of the parameters (decimal year) Examples: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	Variable
6	tx			Translations at the reference epoch (metres)	Float	4	Variable
7	ty				Float	4	Variable
8	tz				Float	4	Variable
9	rx			Rotations at the reference epoch (milliarcseconds)	Float	4	Variable
10	ry				Float	4	Variable
11	rz				Float	4	Variable

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
12	scale			Scale difference at the reference epoch (parts per billion)	Float	4	Variable
13	tx_vel			Translation rates (metres/year)	Float	4	Variable
14	ty_vel				Float	4	Variable
15	tz_vel				Float	4	Variable
16	rx_vel			Rotation rates (milliarcsecond/year)	Float	4	Variable
17	ry_vel				Float	4	Variable
18	rz_vel				Float	4	Variable
19	scale_vel			Scale difference rate (parts per billion/year)	Float	4	Variable

2.31 DGPSTXID

Sets DGPS station ID

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the station ID value for the receiver when it is transmitting corrections. This allows for the easy identification of which base station was the source of the data.

For example, if you want to compare RTCM and RTCMV3 corrections, you would be easily able to identify their base stations by first setting their respective DGPSTXID values.



If `DGPSTXID AUTO` is sent, the Base Station ID String (field 3) is mandatory, but any ID entered is always replaced by **ANY**.

Message ID: 144

Abbreviated ASCII syntax:

```
DGPSTXID type ID
```

Factory default:

```
DGPSTXID auto ANY
```

ASCII examples:

`DGPSTXID RTCM 2` - using an RTCM type and ID

`DGPSTXID CMR 30` - using a CMR type and ID

`DGPSTXID CMR ANY` - using the default CMR ID

`DGPSTXID RTCA d36d` - using an RTCA type and ID

`DGPSTXID RTCMV3 2050` - using an RTCMV3 type and ID

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	DGPSTXID header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	type	RTCM	0	See *Table 70: RTK source type* on page 350	Enum	4	H
		RTCA	1				
		CMR	2				
		AUTO	10				
		RTCMV3	13				
		NOVATELX	14				
3	ID	Char[5]		Base Station ID String or ANY	Char[5]	8	H+4

2.32 DIFFCODEBIASCONTROL

Enables/disables satellite differential code biases



The **DIFFCODEBIASCONTROL** command has been deprecated. To disable differential code biases, use the **SETDIFFCODEBIASES** command (see page 398) to set the biases to zero.

Message ID: 913

2.33 DISPATCHSET

Installs dispatch messages to enable features and subscriptions

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **DISPATCHSET** command installs dispatch messages to provide feature authorizations and subscriptions to the receiver. This is used when L-band or NTRIP delivery is not available or direct control is desired. The string form of dispatch messages used by this command is provided through the NovAtel eStore on request after purchase (or trial) or modification of a subscription product or software model. The string begins with the OEM7 card product serial number (PSN), followed by '=', followed by a URL-safe string of ASCII characters from the RFC 4648 base64url character set. The dispatch message can be copied and distributed freely – it applies only to the receiver with the given PSN. The dispatch message includes all subscribed service periods or permanent software models.

Services and receiver features take effect on the first power on or reset after the start date of the service period, or the first one after the message is received for permanent models.

To confirm the messages have been installed, see the **DISPATCHSCHEDULE** log on page 571 and **VALIDMODELS** log on page 1018.
To retrieve the messages sent to a receiver, use the **DISPATCHMESSAGES** log (see page 566).
To retrieve proof of install, use the **DISPATCHRECEIPT** log (see page 569).

DISPATCHSET does not require a **SAVECONFIG** command. The message is saved immediately.

Dispatch messages are not deleted when a **FRESET STANDARD** command is issued.

For information about dispatch messages, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2554

Abbreviated ASCII Syntax:

```
DISPATCHSET [mode] [dispatch]
```

ASCII Example:

```
DISPATCHSET ADD BMHR17090005=bNYWJjZGVmZ2hpamtsbW5vc_HFyc3R1-dnd4eXpBQkNEhp
amtsbW5vcHFyc3R1dnd4eXpBQkNEhpamtsbW5vcHFyc3R1dnd4eXpBQkNE=
```

If an incorrect message is entered, the following response codes may be returned:

- 271 – `RESPONSE_DISPATCH_PSN_MISMATCH` – Message is not for this receiver
- 272 – `RESPONSE_DISPATCH_CHECK_FAIL` – Message has been corrupted or is incomplete
- 273 – `RESPONSE_DISPATCH_RETIRED` – Message is older than the current message

- 274 – RESPONSE_DISPATCH_INVALID – The content of the message is not understood
- 275 – RESPONSE_DISPATCH_INVALID_FOR_INPUT – Message is not the right type to input to this receiver
- 276 – RESPONSE_DISPATCH_INPUT_LOCKED – Too many invalid messages recently, pause a few seconds
- 281 – RESPONSE_DISPATCH_INVALID_MODEL – A model specified is incompatible with this hardware
- 285 – RESPONSE_DISPATCH_UNSUPPORTED_SERVICE – A service is not compatible with this firmware version

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	DISPATCHSET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	mode	ADD	0	Inserts the dispatch string into the receiver as a dispatch message.	Enum	4	H
3	dispatch	Variable length string – up to 2kB		Dispatch message in *Offline Dispatch String* format. This message carries a secure authorization message for receiver services and features.	String	Variable	H+4

2.34 DLLTIMECONST

Sets carrier smoothing

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the amount of carrier smoothing performed on the code measurements. An input value of 100 corresponds to approximately 100 seconds of smoothing. Upon issuing the command, the locktime (amount of continuous tracking in seconds) for all tracking satellites is reset to zero and each code smoothing filter is restarted. You must wait for at least the length of smoothing time for the new smoothing constant to take full effect. The optimum setting for this command depends on the application.

1. This command may not be suitable for every GNSS application.
2. When using DLLTIMECONST in differential mode with the same receivers, the same setting should be used at both the base and rover station. If the base and rover stations use different types of receivers, it is recommended that you use the command default value at each receiver (DLLTIMECONST <signaltype> 100).
3. There are several considerations when using the DLLTIMECONST command:
   - The attenuation of low frequency noise (multipath) in pseudorange measurements
   - The effect of time constants on the correlation of phase and code observations
   - The rate of “pulling-in” of the code tracking loop (step response)
   - The effect of ionospheric divergence on carrier smoothed pseudorange (ramp response)
4. To get unsmoothed pseudorange measurements, choose 0 as the time constant.

The primary reason for applying carrier smoothing to the measured pseudoranges is to mitigate the high frequency noise inherent in all code measurements. Adding more carrier smoothing by increasing the DLLTIMECONST value filters out lower frequency noise, including some multipath frequencies.

There are also some adverse effects of higher DLLTIMECONST values on some performance aspects of the receiver. Specifically, the time constant of the tracking loop is directly proportional to the DLLTIMECONST value and affects the degree of dependence between the carrier phase and pseudorange information. Carrier phase smoothing of the code measurements (pseudoranges) is accomplished by introducing data from the carrier tracking loops into the code tracking system. Phase and code data, collected at a sampling rate greater than about 3 time constants of the loop, are correlated (the greater the sampling rate, the greater the correlation). This correlation is not relevant if only positions are logged from the receiver, but is an important consideration if the data is combined in some other process such as post-mission carrier smoothing. Also, a narrow bandwidth in a feedback loop impedes the ability of the loop to track step functions. Steps in the pseudorange are encountered during initial lock-on of the satellite and when working in an environment conductive to multipath. A low DLLTIMECONST value allows the receiver to effectively adapt to these situations.

Also, increased carrier smoothing may cause problems when satellite signals are strongly affected by the ionosphere. The rate of divergence between the pseudoranges and phase-derived ranges is greatest when a satellite is low in the sky since the GPS signal must travel through a much “thicker” ionosphere. The tracking error of the receiver is greatest at these times when a lot of carrier smoothing is implemented. In addition, changing periods of ionospheric activity (diurnal changes and the 11-year cycle) influences the impact of large DLLTIMECONST values. It is important to realize that the advantages of carrier smoothing do not come without some trade off in receiver performance. The factory default DLLTIMECONST value of 100 was selected as an optimal compromise of the above considerations. For the majority of applications, this default value should be appropriate. However, the flexibility exists to adjust the parameter for specific applications by users who are familiar with the consequences.

Message ID: 1011

Abbreviated ASCII syntax:

```
DLLTIMECONST signaltype timeconst
```

Factory defaults:

```
DLLTIMECONST <signaltype> 100
```

Example:

```
DLLTIMECONST GPSL2C 100
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	DLLTIMECONST header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	signal type	See *Table 31: Signal type* below		Signal type	Enum	4	H
3	time const			Time constant (seconds) The maximum time constant value is 2000 seconds.	Ulong	4	H+4

Table 31: Signal type

Binary	ASCII	Description
33	GPSL1CA	GPS L1 C/A-code
47	GPSL1CP	GPS L1C P-code
68	GPSL2Y	GPS L2 P(Y)-code
69	GPSL2C	GPS L2 C-code

Binary	ASCII	Description
70	GPSL2P	GPS L2 P-code
103	GPSL5	GPS L5
2177	GLOL1CA	GLONASS L1 C/A-code
2211	GLOL2CA	GLONASS L2 C/A-code
2212	GLOL2P	GLONASS L2 P-code
2662	GLOL3	GLONASS L3
4129	SBASL1	SBAS L1
4194	SBASL5	SBAS L5
10433	GALE1	Galileo E1
10466	GALE5A	Galileo E5A
10499	GALE5B	Galileo E5B
10532	GALALTBOC	Galileo ALT-BOC
10565	GALE6C	Galileo E6C
10572	GALE6B	Galileo E6B
12673	BDSB1D1	BeiDou B1 with D1 navigation data
12674	BDSB1D2	BeiDou B1 with D2 navigation data
12803	BDSB2D1	BeiDou B2I with D1 navigation data
12804	BDSB2D2	BeiDou B2I with D2 navigation data
12877	BDSB3D1	BeiDou B3 with D1 navigation data
12880	BDSB3D2	BeiDou B3 with D2 navigation data
12979	BDSB1C	BeiDou B1C
13012	BDSB2A	BeiDou B2a
13077	BDSB2BI	BeiDou B2b (I)
14753	QZSSL1CA	QZSS L1 C/A-code
14754	QZSSL1CB	QZSS L1 C/B-code (FW 7.10.02 or greater)
14760	QZSSL1CP	QZSS L1C P-code
14787	QZSSL2C	QZSS L2 C-code
14820	QZSSL5	QZSS L5
14890	QZSSL6D	QZSS L6D (FW 7.10.xx)
14891	QZSSL6P	QZSS L6P (FW 7.09.xx)
19073	NAVICL5SPS	NavIC L5 SPS

2.35 DNSCONFIG

Manually configures Ethernet DNS servers

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command is part of the Ethernet set up. It is used to configure the Domain Name Servers (DNS) so that host names can be used instead of IP addresses.

The **DNSCONFIG** command configures a DNS server for the Ethernet interface, ETHA.

The **DNSCONFIG** command will fail if the IP address for the Ethernet interface, ETHA, is configured to use DHCP. Ensure the IP address for the Ethernet interface is configured to use a static IP address before entering the **DNSCONFIG** command.

When using DHCP, the DNS server received using DHCP is used and the DNS server configured by **DNSCONFIG** is ignored.

Message ID: 1244

Abbreviated ASCII syntax:

```
DNSCONFIG DNSServers IP
```

Factory default:

```
DNSCONFIG 0
```

ASCII example:

```
DNSCONFIG 1 192.168.1.5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	DNSCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	DNSServers	0	0	Number of DNS servers If this field is set to 0, an IP address is not required.	Enum	4	H
		1	1				
3	IP	ddd.ddd.ddd.ddd		IP address of primary DNS server	String [16]	variable[1]	H+4

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.36 DOPPLERWINDOW

Change the behaviour of the doppler search

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Change the behaviour of the doppler search for automatic channel assignments in the receiver. This command is used where the SV doppler may be outside of the normal receiver doppler search window of +/- 16000 Hz.

The DOPPLERWINDOW command should only be used by advanced users.

Message ID: 1512

Abbreviated ASCII syntax:

```
DOPPLERWINDOW system setting doppler_window
```

Factory default:

```
DOPPLERWINDOW ALL AUTO 0
```

ASCII example:

```
DOPPLERWINDOW GPS USER 20000
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	DOPPLERWINDOW header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	system	See *Table 32: Satellite system* on the next page		Satellite system to configure.	Enum	4	H
3	setting	AUTO	0	Doppler window mode	Enum	4	H+4
		USER	1				
4	doppler_ window	0 to 50000		Doppler window to search in Hz	Ulong	4	H+8
5	Reserved				Long	4	H+12

Table 32: Satellite system

System	Value
ALL	3
GPS	99
GLONASS	101
SBAS	100
GALILEO	102
BEIDOU	103
QZSS	104
NAVIC	105

2.37 DUALANTENNAALIGN

Dual antenna ALIGN configuration

Platform: OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2, CPT7

Use this command to enable or disable ALIGN and configure the ALIGN operation rates on a dual antenna receiver.

Message ID: 1761

Abbreviated ASCII syntax:

```
DUALANTENNAALIGN switch [obsrate] [posrate]
```

Factory default:

```
DUALANTENNAALIGN enable 1 1
```

Example:

```
DUALANTENNAALIGN enable 10 1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	DUALANTENNAALIGN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Switch	DISABLE	0	Disable the dual antenna ALIGN feature	Enum	4	H
		ENABLE	1	Enable the dual antenna ALIGN feature			
3	obsrate	1, 2, 4, 5, 10, 20		Rate in Hz at which heading output is required (default = 1 Hz)	Ulong	4	H+4
4	posrate	1, 2, 4, 5, 10, 20		Rate in Hz at which MASTERPOS output is required (default = 1 Hz)	Ulong	4	H+8

Dual antenna ALIGN rates (*obsrate* and *posrate*) are limited to the maximum position rate allowed by the receiver model.

When a receiver with a SPAN model is reset, the dual antenna ALIGN rates (*obsrate* and *posrate*) return to the default values of 1 Hz. This occurs even if the command settings have been saved using the **SAVECONFIG** command.

2.38 DYNAMICS

Tunes receiver parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to adjust the receiver dynamics to that of an application. It is used to optimally tune receiver parameters.

The **DYNAMICS** command adjusts the Tracking State transition time out value of the receiver, see *3.159 RANGE* on page 830. When the receiver loses the position solution, see *Table 95: Solution status* on page 530, it attempts to steer the tracking loops for fast reacquisition (5 s time-out by default). The **DYNAMICS** command adjusts this time-out value, effectively increasing the steering time. The three states AIR, LAND or FOOT set the time-out to 5, 10 or 20 seconds respectively.

The DYNAMICS command should only be used by advanced users. The default of AUTO should not be changed except under very specific conditions.

Message ID: 258

Abbreviated ASCII syntax:

```
DYNAMICS settings
```

Factory default:

```
DYNAMICS AUTO
```

Example:

```
DYNAMICS FOOT
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	DYNAMICS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	settings	See *Table 33: User dynamics* below		Receiver dynamics based on the current environment	Enum	4	H

Table 33: User dynamics

Binary	ASCII	Description
0	AIR	Receiver is in an aircraft or a land vehicle, for example a high speed train, with velocity greater than 110 km/h (30 m/s). This is also the most suitable dynamic for a jittery vehicle at any speed.

Binary	ASCII	Description
1	LAND	Receiver is in a stable land vehicle with velocity less than 110 km/h (30 m/s).
2	FOOT	Receiver is being carried by a person with velocity less than 11 km/h (3 m/s).
3	AUTO	Receiver monitors dynamics and adapts behaviour accordingly

Qualifying North American Solar Challenge cars annually weave their way through 1000's of miles between the US and Canada. GNSS keeps them on track through many intersections on secondary highways and gives the Calgary team constant intelligence on the competition's every move. In this case, with average speeds of 46 miles/hour and at times a jittery vehicle, AIR is the most suitable dynamic.

2.39 ECHO

Sets port echo

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set a port to echo.

Message ID: 1247

Abbreviated ASCII syntax:

```
ECHO [port] echo
```

Factory default:

```
ECHO COM1 OFF
ECHO COM2 OFF
ECHO COM3 OFF    (not supported on OEM719)
ECHO COM4 OFF    (OEM7600, OEM7700 and OEM7720 only)
ECHO COM5 OFF    (OEM7600, OEM7700 and OEM7720 only)
ECHO USB1 OFF
ECHO USB2 OFF
ECHO USB3 OFF
ECHO ICOM1 OFF   (not supported on OEM719)
ECHO ICOM2 OFF   (not supported on OEM719)
ECHO ICOM3 OFF   (not supported on OEM719)
ECHO ICOM4 OFF   (not supported on OEM719)
ECHO ICOM5 OFF   (not supported on OEM719)
ECHO ICOM6 OFF   (not supported on OEM719)
ECHO ICOM7 OFF   (not supported on OEM719)
ECHO SCOM1 OFF
ECHO SCOM2 OFF
ECHO SCOM3 OFF
ECHO SCOM4 OFF
ECHO LCOM1 OFF   (firmware 7.10.xx only)
ECHO LCOM2 OFF   (firmware 7.10.xx only)
ECHO LCOM3 OFF   (firmware 7.10.xx only)
ECHO LCOM4 OFF   (firmware 7.10.xx only)
```

ASCII example:

```
ECHO COM1 ON
ECHO ON
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ECHO header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 34: Communications port identifiers* below		Port to configure (default = THISPORT)	Enum	4	H
3	echo	OFF	0	Sets port echo to off	Enum	4	H+4
		ON	1	Sets port echo to on			

Table 34: Communications port identifiers

ASCII port name	Binary value	Notes
ALL	8	
BT1	33	
CCOM1	38	
CCOM2	39	
CCOM3	40	
CCOM4	41	
CCOM5	42	
CCOM6	43	
COM1	1	
COM2	2	
COM3	3	
COM4	19	
COM5	31	
COM6	32	
COM7	34	
COM8	35	
COM9	36	
COM10	37	
ETH1	20	
FILE	7	

ASCII port name	Binary value	Notes
ICOM1	23	
ICOM2	24	
ICOM3	25	
ICOM4	29	
ICOM5	46	
ICOM6	47	
ICOM7	48	
IMU	21	
LCOM1	65	Firmware 7.10.xx only
LCOM2	66	Firmware 7.10.xx only
LCOM3	67	Firmware 7.10.xx only
LCOM4	68	Firmware 7.10.xx only
NCOM1	26	
NCOM2	27	
NCOM3	28	
NOPORT	0	
SCOM1	49	
SCOM2	50	
SCOM3	51	
SCOM4	52	
THISPORT	6	
USB1	13	
USB2	14	
USB3	15	
WCOM1	30	

2.40 ECUTOFF

Sets satellite elevation cut-off for GPS satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the elevation cut-off angle for tracked GPS satellites. The receiver does not start automatically searching for a GPS satellite until it rises above the cut-off angle (when satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they are manually assigned (see the **ASSIGN** command on page 77).

In either case, satellites below the ECUTOFF angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle; it could be used in these situations:

- The antenna is at a high altitude, and thus can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Care must be taken when using **ECUTOFF** command because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

Use the **ELEVATIONCUTOFF** command (see page 157) to set the cut-off angle for any system.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

A low elevation satellite is a satellite the receiver tracks just above the horizon. Generally, a satellite is considered low elevation if it is between 0 and 15 degrees above the horizon.

There is no difference between the data transmitted from a low elevation satellite and that transmitted from a higher elevation satellite. However, differences in the signal path of a low elevation satellite make their use less desirable. Low elevation satellite signals have more error due to the increased amount of atmosphere they must travel through. In addition, signals from low elevation satellites don't fit the assumption that a signal travels in air nearly the same as in a vacuum. As such, using low elevation satellites in the solution results in greater position inaccuracies.

The elevation cut-off angle is specified with **ECUTOFF** to ensure that noisy, low elevation satellite data below the cut-off is not used in computing a position. If post-processing data, it is still best to collect all data (even that below the cut-off angle). Experimenting with different cut-off angles can then be done to provide the best results. In cases where there are not enough satellites visible, a low elevation satellite may actually help in providing a useful solution.

Message ID: 50

Abbreviated ASCII syntax:

```
ECUTOFF angle
```

Factory default:

```
ECUTOFF 5.0
```

ASCII example:

```
ECUTOFF 10.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	angle	±90.0 degrees		Elevation cut-off angle relative to horizon	Float	4	H

2.41 ELEVATIONCUTOFF

Sets the elevation cut-off angle for tracked satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **ELEVATIONCUTOFF** command is used to set the elevation cut-off angle for tracked satellites. The receiver does not start automatically searching for a satellite until it rises above the cut-off angle (when the satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they are manually assigned (refer to the **ASSIGN** command on page 77).

In either case, satellites below the elevation cut-off angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle and can be used in the following situations:

- The antenna is at a high altitude and thus can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Care must be taken when using **ELEVATIONCUTOFF** command because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

This command combines the following commands into one convenient command: **ECUTOFF**, **GLOECUTOFF**, **GALECUTOFF**, **QZSSECUTOFF**, **SBASECUTOFF**, **BDSECUTOFF** and **NAVICECUTOFF**.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

A low elevation satellite is a satellite the receiver tracks just above the horizon. Generally, a satellite is considered low elevation if it is between 0 and 15 degrees above the horizon.

There is no difference between the data transmitted from a low elevation satellite and that transmitted from a higher elevation satellite. However, differences in the signal path of a low elevation satellite make their use less desirable. Low elevation satellite signals have more error due to the increased amount of atmosphere they must travel through. In addition, signals from low elevation satellites don't fit the assumption that a signal travels in air nearly the same as in a vacuum. As such, using low elevation satellites in the solution results in greater position inaccuracies.

The elevation cut-off angle is specified with the **ELEVATIONCUTOFF** command to ensure that noisy, low elevation satellite data below the cut-off is not used in computing a position. If post-processing data, it is still best to collect all data (even that below the cutoff angle). Experimenting with different cut-off angles can then be done to provide the best results. In cases where there are not enough satellites visible, a low elevation satellite may actually help in providing a useful solution.

Message ID: 1735

Abbreviated ASCII syntax:

```
ELEVATIONCUTOFF Constellation Angle [Reserved]
```

Factory default:

```
ELEVATIONCUTOFF ALL 5.0 0
```

ASCII example:

```
ELEVATIONCUTOFF GPS 5
ELEVATIONCUTOFF ALL 5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ELEVATIONCUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Constellation	GPS	0	Sets the cut-off angle for GPS Constellation satellites only.	Enum	4	H
		GLONASS	1	Sets the cut-off angle for GLONASS constellation satellites only.			
		SBAS	2	Sets the cut-off angle for SBAS constellation satellites only.			
		GALILEO	5	Sets the cut-off angle for Galileo constellation satellites only.			
		BEIDOU	6	Sets the cut-off angle for BeiDou constellation satellites only.			
		QZSS	7	Sets the cut-off angle for QZSS constellation satellites only.			
		NAVIC	9	Sets the cut-off angle for NavIC constellation satellites only.			
		ALL	32	Sets the cut-off angle for all satellites regardless of the constellation.			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	Angle	±90.0 degrees		Elevation cut-off angle relative to the horizon.	Float	4	H+4
4	Reserved	0		Reserved Field (optional)	Ulong	4	H+8

2.42 ETHCONFIG

Configures Ethernet physical layer

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command is used to configure the Ethernet physical layer.

Message ID: 1245

Abbreviated ASCII syntax:

```
ETHCONFIG interface_name [speed] [duplex] [crossover] [power_mode]
```

Factory default:

```
ETHCONFIG etha auto auto auto powerdown
```
(OEM7 receiver cards)

```
ETHCONFIG etha auto auto auto auto
```
(PwrPak7)

ASCII example:

```
ETHCONFIG etha 100 full mdix normal
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ETHCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	interface_ name	ETHA	2	Name of the Ethernet interface	Enum	4	H
3	speed	AUTO	1	Auto-negotiate speed (default) AUTO is the recommended value for the speed parameter. If setting speed to AUTO, duplex must be set to AUTO at the same time otherwise a “parameter 3 out of range” error occurs.	Enum	4	H+4
		10	2	Force 10BaseT			
		100	3	Force 100BaseT			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	duplex	AUTO	1	Auto-negotiate duplex (default) If setting duplex to AUTO, speed must be set to AUTO at the same time otherwise a “parameter 3 out of range” error occurs.	Enum	4	H+8
		HALF	2	Force half duplex			
		FULL	3	Force full duplex			
5	crossover	AUTO	1	Auto-detect crossover (default)	Enum	4	H+12
		MDI	2	Force MDI (straight through)			
		MDIX	3	Force MDIX (crossover)			
6	power_ mode	AUTO	1	Energy detect mode (default for PwrPak7)	Enum	4	H+16
		POWERDOWN	2	Soft power down mode (default for OEM7 receiver cards)			
		NORMAL	3	Normal mode			

The crossover parameter is ignored on OEM7 receivers, as the hardware automatically detects the cable connection and configures the interface for proper communication. For backwards compatibility, the crossover options are still accepted, but have no functional impact.

2.43 EVENTINCONTROL

Controls Event-In input triggers

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command controls up to four Event-In input triggers. Each input can be used as an event strobe.

When used as an event strobe, an accurate GPS time or position is applied to the rising or falling edge of the input event pulse (refer to the **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** log on page 723, **MARKPOS, MARK2POS, MARK3POS and MARK4POS** log on page 720 or **MARK1PVA, MARK2PVA, MARK3PVA and MARK4PVA** log on page 1166). Each input strobe is usually associated with a separate device, therefore different solution output lever arm offsets can be applied to each strobe. When used as an Event Input Trigger, it is possible to overwhelm the receiver with a very high rate of input events that impacts the performance of the receiver. For this reason, the receiver internally throttles the rate at which it responds to input events. The limit is 200 Hz.

Message ID: 1637

Abbreviated ASCII syntax:

```
EVENTINCONTROL mark switch [polarity] [t_bias] [t_guard]
```

ASCII example:

```
EVENTINCONTROL MARK1 ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	EVENTINCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	mark	MARK1	0	Choose which Event-In Mark to change. This value must be specified. MARK3 is available only on OEM7600, OEM7700, OEM7720, PwrPak7, CPT7 and CPT7700 receivers. MARK4 is available only on OEM7600, OEM7700 and OEM7720 receivers.	Enum	4	H
		MARK2	1				
		MARK3	2				
		MARK4	3				
3	switch	DISABLE	0	Disables Event Input	Enum	4	H+4
		EVENT	1	Enables Event Input			
		ENABLE	3	A synonym for the EVENT option (for compatibility with previous releases)			
4	polarity	NEGATIVE	0	Negative polarity (default)	Enum	4	H+8
		POSITIVE	1	Positive polarity			
5	t_bias	default: 0 minimum: -999,999,999 maximum: 999,999,999		A constant time bias in nanoseconds can be applied to each event pulse. Typically this is used to account for a transmission delay.	Long	4	H+12
6	t_guard	default: 4 minimum: 2 maximum: 3,599,999		The time guard specifies the minimum number of milliseconds between pulses. This is used to coarsely filter the input pulses.	Ulong	4	H+16

2.44 EVENTOUTCONTROL

Control Event Out properties

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This command configures up to seven Event Out output strobes. The event strobes toggle between 3.3 V and 0 V. The pulse consists of two periods: one active period followed by a not active period. The start of the active period is synchronized with the top of the GNSS time second and the signal polarity determines whether the active level is 3.3 V or 0 V. The not active period immediately follows the active period and has the alternate voltage.

The outputs that are available vary according to the platform.

A 100 MHz clock is used internally to create these output signals. As a result, all period values are limited to 10 ns steps.

The EVENTOUT outputs cannot synchronize with GPS time until the receiver reaches FINESTEERING time status. As the receiver transitions to GPS time, there may be additional, unexpected pulses on the EVENTOUT signals.

Message ID: 1636

Abbreviated ASCII syntax:

```
EVENTOUTCONTROL mark switch [polarity] [active_period] [non_active_period]
```

ASCII example:

```
EVENTOUTCONTROL MARK3 ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	EVENTOUTCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	mark	MARK1	0	Choose which Event Out Mark to change. This value must be specified. On OEM719 and OEM729 receivers, only MARK1 is available. On OEM7600, OEM7700 and OEM7720 receivers, only MARK1 through MARK4 are available. MARK4 is not available on the CPT7 and CPT7700. MARK3 defaults to a PPS type signal on the CPT7 and CPT7700.	Enum	4	H
		MARK2	1				
		MARK3	2				
		MARK4	3				
		MARK5	4				
		MARK6	5				
		MARK7	6				
3	switch	DISABLE	0	Disables the Event output	Enum	4	H+4
		ENABLE	1	Enables the Event output			
4	polarity	NEGATIVE	0	Negative polarity (active = 0V) (default)	Enum	4	H+8
		POSITIVE	1	Positive polarity (active = 3.3V)			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
5	active_ period	default: 500,000,000 minimum: 10 maximum: 999,999,990		Active period of the Event Out signal in nanoseconds. 10 ns steps must be used. If the value entered is not a multiple of 10, it will be rounded down to the nearest 10 ns. For PwrPak7, the minimum active period is 200 ns. See PwrPak7 strobe specifications. For CPT7. the minimum active period is 50 ns. See CPT7 strobe specifications.	Ulong	4	H+12

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
6	non_active_period	default: 500,000,000 minimum: 10 maximum: 999,999,990		Non-active period of the Event Out signal in nanoseconds. 10 ns steps must be used. If the value entered is not a multiple of 10, it will be rounded down to the nearest 10 ns. For PwrPak7, the minimum active period is 200 ns. See PwrPak7 strobe specifications. For CPT7. the minimum active period is 50 ns. See CPT7 strobe specifications.	Ulong	4	H+16

The sum of the active period and inactive period should total 1,000,000,000 ns. If the total exceeds one full second, both the active and inactive period duration will be as given and the EVENTOUT pulses will no longer be synchronized with the 1PPS output pulse.

Alternately, the sum of the active and inactive periods may be less than 1,000,000,000 ns, but should divide evenly into 1,000,000,000 ns. For example, if the active period is 150,000,000 and the inactive period is 50,000,000, the sum of the periods is 200,000,000 ns which divides evenly into one full second.

If the sum is less than one full second and does not divide evenly into one full second, the active and inactive period duration will be as given and the EVENTOUT pulses will no longer be synchronized with the 1PPS output pulse.

A 100 MHz clock is used internally to create these output signals. As a result, all period values are limited to 10 ns steps.

2.45 EXTERNALCLOCK

Sets external clock parameters

Platform: OEM729

The **EXTERNALCLOCK** command is used to enable the OEM7 card to operate with an optional external oscillator. You are able to optimally adjust the clock model parameters of these receivers for various types of external clocks.

1. This command affects the interpretation of the CLOCKMODEL log.
2. If the **EXTERNALCLOCK** command is enabled and set for an external clock (TCXO, OCXO, RUBIDIUM, CESIUM or USER) and the **CLOCKADJUST** command (see page 117) is ENABLED, then the clock steering process takes over the VARF output pins and may conflict with a previously entered **EVENTOUTCONTROL** command (see page 164). If clocksteering is not used with the external oscillator, the clocksteering process must be disabled by using the **CLOCKADJUST disable** command.
3. When using the **EXTERNALCLOCK** command and **CLOCKADJUST** command (see page 117) together, issue the **EXTERNALCLOCK** command first to avoid losing satellites.

There are three steps involved in using an external oscillator:

1. Follow the procedure outlined in the OEM7 Installation and Operation User Manual to connect an external oscillator to the OEM7.
2. Using the **EXTERNALCLOCK** command, select a standard oscillator and its operating frequency.
3. Using the **CLOCKADJUST** command (see page 117), disable the clocksteering process if external clocksteering is not used.

An unsteered oscillator can be approximated by a three-state clock model, with two states representing the range bias and range bias rate, and a third state assumed to be a Gauss-Markov (GM) process representing the range bias error generated from satellite clock dither. The third state is included because the Kalman filter assumes an (unmodeled) white input error. The significant correlated errors produced by satellite clock dither are obviously not white and the Markov process is an attempt to handle this kind of short term variation.

The internal units of the new clock model's three states (offset, drift and GM state) are metres, metres per second and metres. When scaled to time units for the output log, these become seconds, seconds per second and seconds, respectively.

The user has control over 3 process noise elements of the linear portion of the clock model. These are the h_0, h_{-1} and h_{-2} elements of the power law spectral density model used to describe the frequency noise characteristics of oscillators:

$$S_y\left(f\right) = \frac{h_{-2}}{f^2} + \frac{h_{-1}}{f} + h_0 + h_1 f + h_2 f^2$$

where *f* is the sampling frequency and *Sy(f)* is the clock's power spectrum. Typically only h_0, h_{-1}, and h_{-2} affect the clock's Allan variance and the clock model's process noise elements.

Before using an optional external oscillator, several clock model parameters must be set. There are default settings for a Voltage-Controlled Temperature-Compensated Crystal Oscillator (VCTCXO), Ovenized Crystal Oscillator (OCXO), Rubidium and Cesium standard, which are given in *Table 35: Clock type* on page 170. You may alternatively choose to supply customized settings.

The **EXTERNALCLOCK** command configures whether the receiver uses its own internal temperature-compensated crystal oscillator or that of an external oscillator as a frequency reference. It also sets which clock model is used for an external oscillator.

To force the OEM7 to use the internal oscillator, use the **EXTERNALCLOCK disable** command and physically disconnect the external oscillator input. Do not use the EXTERNALCLOCK OCXO, CESIUM, RUBIDIUM or USER parameters if there is no external oscillator connected to the OEM7.

Message ID: 230

Abbreviated ASCII syntax:

```
EXTERNALCLOCK clocktype [freq] [h0 [h-1 [h-2]]]
```

Factory default:

```
EXTERNALCLOCK disable
```

ASCII examples:

```
EXTERNALCLOCK USER 10MHZ 1.0167e-23 6.87621e-25 8.1762e-26
EXTERNALCLOCK TCXO 5MHZ
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	EXTERNALCLOCK header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	clocktype	See *Table 35: Clock type* on the next page		Clock type	Enum	4	H
3	freq	5MHz	1	Optional frequency. If a value is not specified, the default is 5 MHz	Enum	4	H+4
		10MHz	2				
4	h_0	1.0 e-35 to 1.0 e-18		Optional timing standards. These fields are only valid when the USER clocktype is selected. Do not use h values with VCTCXO, OCXO, CESIUM or RUBIDIUM clock types. The h values for these options are fixed, see *Table 36: Pre-defined values for oscillators* on the next page (default=0.0)	Double	8	H+8
5	h_{-1}	1.0 e-35 to 1.0 e-18			Double	8	H+16
6	h_{-2}	1.0 e-35 to 1.0 e-18			Double	8	H+24

Table 35: Clock type

ASCII	Binary	Description
DISABLE	0	Turns the external clock input off, reverts back to the on-board VCTCXO. When used in a binary command, use the parameter defaults (i.e. freq=1, h_0=0, h_{-1}=0, h_{-2}=0).
TCXO	1	Sets the predefined values for a VCTCXO
OCXO	2	Sets the predefined values for an OCXO
RUBIDIUM	3	Sets the predefined values for a rubidium oscillator
CESIUM	4	Sets the predefined values for a cesium oscillator
USER	5	Defines custom process noise elements

Table 36: Pre-defined values for oscillators

Clock Type	h_0	h_{-1}	h_{-2}
VCTCXO	1.0 e-21	1.0 e-20	1.0 e-20
OCXO	2.51 e-26	2.51 e-23	2.51 e-22
Rubidium	1.0 e-23	1.0 e-22	1.3 e-26
Cesium	2.0 e-20	7.0 e-23	4.0 e-29

2.46 FILEAUTOTRANSFER

Enables/disables automatic file transfer

Platform: PwrPak7

PwrPak7M variants do not support this command.

Use this command to configure the automatic transfer function from internal memory to an external USB stick. If the mode is set to COPY or MOVE, all log files, except the file currently being logged to, will be automatically transferred to a USB stick when the USB stick is inserted.

This command will transfer all recorded log files to the USB stick provided the USB stick has enough free space to hold all the data. **Files too large to fit in the remaining space on the USB stick are skipped**.

The command must be issued before the USB stick is inserted. If the command is not issued first, the USB stick must be removed and reinserted to trigger the auto transfer.

The status of the transfer can be viewed by logging the **FILETRANSFERSTATUS** log (see page 590).

A transfer in progress can be cancelled by issuing the **FILETRANSFER CANCEL** command.

The settings for this command can be saved using the **SAVECONFIG** command (see page 367).

Message ID: 2135

Abbreviated ASCII syntax:

```
FILEAUTOTRANSFER [TransferMode]
```

ASCII example:

```
FILEAUTOTRANSFER COPY
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FILEAUTOTRANSFER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	TransferMode	1	OFF	Automatic copy/move is disabled (default)	Ulong	4	H
		2	COPY	Automatically copies all files			
		3	MOVE	Automatically copies all files and then deletes them from internal memory after a successful copy			



For the fastest transfer of files to an external memory stick, it is recommended that logging to a file be stopped.

2.47 FILECONFIG

Open or close a log file

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this command.

To record logs, log requests are sent to the FILE port. Before the logs sent to the FILE port can be saved in a file, the file must be opened using the **FILECONFIG** command.

When configured to be open, a log file will be opened when the active file media is ready and has sufficient space. Once a log file is opened, any logs requested for the FILE port are recorded to the file.

Use the **FILESTATUS** log (see page 584) to determine the state of the log file.

The file media is separately configured:

- On receiver cards, this is always USBSTICK, which is the only media available.
- On the PwrPak7, the active file media is configured using the **FILEMEDIACONFIG** command on page 176.

When a file is opened, the file name is automatically generated based on the following format:

<PSN>_<INDEX>.LOG

where:

- <PSN> is the PSN of the receiver
- <INDEX> is a number from 1 to 511.

  The lowest number that produces an unused file name is selected. If there is no such number available, the **FILESTATUS** log (see page 584) will report an error.

  The number is not zero-padded (i.e. the sequence is as follows: 1,2, ... ,9,10,11,12, ... ,99,100, ... , 510,511).

When a file is closed and the receiver has a valid time, the file is renamed based on the following format:

<PSN>_<UTC Date>_<UTC Time>.LOG

where:

- <PSN> is the PSN of the receiver
- <UTC_Date> is the UTC date in the format YYYY-MM-DD
- <UTC_Time> is the UTC time in the format HH-MM-SS

Example file name: NOV12001200A_2017-01-10_12-14-34.LOG

When a file is closed, but the receiver does not have a valid time, the file is left with its automatically generated name.

Other notes:

- The FILE port represents the internal logging to flash memory. It has a NOVATEL Interface Mode - output only, no input is possible.
- Only logs that are published after the log file is open are recorded.

- Only one log file can be open at a time.
- Logs requested to the FILE port are still produced even if the log file is closed; however the logs are not recorded. (This is similar to requesting logs to COM4 when there's no cable on COM4.) If a new log file is opened, recording of the previously requested logs continues with the new file.
- When a file is closed, the log file is renamed to the format <PSN>_<UTC Date>_<UTC Time>.LOG, where the UTC time is the time when the file is closed. If the time is not available, the file is not renamed. If there is already a file with the intended name, the file is not renamed.
- After closing a file, the file system will be flushed to ensure that all data is written to the media.
- A disk is considered "full" when is has <= 10 MB of free space. This buffer is left in place to allow the system time and space to open up a new file if required.

Message ID: 2116

Abbreviated ASCII syntax:

```
FILECONFIG FileOperation
```

Factory default:

```
FILECONFIG CLOSE
```

Example:

```
FILECONFIG OPEN
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FILECONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	FileOperation	OPEN	1	Open (create) a new logging file	Enum	4	H
		CLOSE	2	Close the logging file			

2.48 FILEDELETE

Deletes files from the currently selected mass storage device

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this command.

Use this command to delete a single file, or use the wild card symbol (*) to delete all files, from the logging directory of the currently selected file media. This command will not delete a file if it is currently open for logging. Use the **FILESTATUS** log (see page 584) to determine the state of the log file.

The wild card symbol deletes all files in the directory. It cannot be used to delete a subset of the files in the directory. For example, the command `FILEDELETE *.LOG` will be rejected by the receiver.

The file media is separately configured:

- On receiver cards, the file media is always USBSTICK, which is the only media available.
- On enclosure products, the active file media is configured using a product-specific command, such as **FILEMEDIACONFIG** command (see page 176).

The list of files stored on the currently selected file media can be retrieved using the **FILELIST** log on page 582.

Message ID: 2190

Abbreviated ASCII syntax:

```
FILEDELETE FileName
```

Example:

`FILEDELETE NMNE17130016A_2017-12-11_18-17-06.LOG` – Delete the file NMNE17130016A_2017-12-11_18-17-06.LOG

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Command header	FILEDELETE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.		H	0
2	FileName	Name of file to delete, or the wild card symbol (*)	String (Max 128)	variable[1]	H

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.49 FILEMEDIACONFIG

Specify the file media

Platform: PwrPak7, CPT7, CPT7700

PwrPak7M variants do not support this command.

Use this command to specify which storage media is used for File operations.

To determine what storage device is currently being used for File operations, log this command. For example:

```
LOG FILEMEDIACONFIG
```

On OEM7 receiver cards, the file media is always USBSTICK, which is the only media available. On PwrPak7, CPT7 and CPT7700 products, the active file media is configured using the **FILEMEDIACONFIG** command.

Message ID: 2117

Abbreviated ASCII syntax:

```
FILEMEDIACONFIG MassStorage
```

ASCII example:

```
FILEMEDIACONFIG INTERNAL_FLASH      – Use internal flash as the media
FILEMEDIACONFIG USBSTICK            – Use a USB stick as the media
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FILEMEDIACONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	MassStorage	0	DEFAULT_ NO_ STORAGE	Disable logging to any media. Makes the internal storage accessible to a connected computer. (CPT7 and CPT7700 only)	Enum	4	H
		1	USBSTICK	Use a USB stick as the mass storage device. (Not supported on CPT7 or CPT7700)			
		2	INTERNAL_ FLASH	Use Internal storage as the mass storage device.			

2.50 FILEROTATECONFIG

Set the maximum size and duration of a log file

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this command.

Use this command to configure the maximum size and duration for a log file. This command also configures the action taken when the log file media is full.

A file rotation is when a new file is opened, the currently opened file is closed and logging on the FILE port is rerouted to this new file. There is no data loss during this process and individual logs within the file are not spread between log files.

Message ID: 2133

Abbreviated ASCII syntax:

```
FILEROTATECONFIG [MaxFileTime] [MaxFileSize] [DiskFullAction]
```

Factory default:

```
FILEROTATECONFIG 0 4096 STOP
```

Example:

```
FILEROTATECONFIG 2 4096 STOP
```

The file is left open for 2 hours or until the file size reaches 4096 MB. When the log file media is full, the file is closed.

```
FILEROTATECONFIG 4 4096 OVERWRITE
```

The file is left open for 4 hours or until the file size reaches 4096 MB. When the log media file is full, the oldest file on the log media file will be deleted.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FILEROTATECONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	MaxFileTime	0 to 24		Maximum number of hours to leave a file open before triggering a file rotation. Set to 0 for no maximum time. Maximum value is 24. Default is 0.	Ushort	2	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	MaxFileSize	1 to 4096		Maximum number of mega bytes (MB) for the file size. A file rotation is triggered when the file is within 1 MB of this size. Maximum value is 4096 MB Default is 4096 MB (4 GB).	Ushort	2	H+2
4	DiskFullAction	See *Table 37: Disk full action* below		Action to take when the log file media is full.	Enum	4	H+4

Table 37: Disk full action

Binary	ASCII	Description
0	STOP	Stops logging when the file media has 1 MB of free space or less or the file media has reached 512 files. Default is STOP.
1	OVERWRITE	Deletes the oldest log file when the file media has 10 MB of free space or less or the file media has exceeded 512 files. To be selected for deletion a file must satisfy these requirements: • The file must use the **FILECONFIG** command (see page 173) file name format. • The <PSN> value must match the current receiver. File age is determined using the **FILECONFIG** command (see page 173) file name format. • Temporary files (i.e. those with an <INDEX> value) are considered oldest. Such files will be sorted by their <INDEX> value with lower values considered older. • Non-temporary files will be sorted by the date reported in the file format.

2.51 FILETRANSFER

Copy files from internal memory

Platform: PwrPak7

PwrPak7M variants do not support this command.

Use this command to copy files from internal memory to a USB stick. This command can also be used to cancel the file transfer in progress.

This command returns a response immediately to show that the copy/move operation started. However, the actual transfer of files will take some time. Use the **FILETRANSFERSTATUS** log (see page 590) to monitor the status of the file transfer.

To view the names of the files in memory, log the **FILELIST** log (see page 582).

Message ID: 2109

Abbreviated ASCII syntax:

```
FILETRANSFER FileTransferOperation <FileName>
```

ASCII examples:

```
FILETRANSFER COPY ALL          – Copies all files on internal memory
FILETRANSFER MOVE BMHR16460033T_2017-3-16_21-18-48.log
FILETRANSFER CANCEL            – Cancels file transfer operation
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FILETRANSFER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	FileTransferOperation	1	COPY	Copy the file	Enum	4	H
		2	MOVE	Copy the file and then delete file from internal memory			
		3	CANCEL	Cancels the file transfer currently in progress			
3	FileName			The name of the file to be moved or copied. To move or copy all of the files on internal memory, use ALL.	String	Variable	H+4

When a **FILETRANSFER CANCEL ALL** command is issued, the file currently being transferred, and any pending files, are not transferred to the destination media. Any files already transferred are unaffected.

2.52 FIX

Constrains to fixed height or position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to fix height or position to the input values. For various applications, fixing these values can assist in improving acquisition times and accuracy of position or corrections. For example, fixing the position is a requirement for differential base stations as it provides the reference position to base the differential corrections from.

1. It is strongly recommended that the FIX POSITION entered be accurate to within a few metres. This level of accuracy can be obtained from a receiver using single point positioning once 5 or 6 satellites are being tracked.
2. FIX POSITION should only be used for base station receivers. Applying FIX POSITION to a rover switches it from RTK mode to a fixed position mode. Applying FIX POSITION to the rover does not speed up ambiguity resolution.
3. Any setting other than FIX POSITION disables output of differential corrections unless the **MOVINGBASESTATION** command (see page 267) is set to ENABLE.
4. You can fix the position of the receiver using latitude, longitude and height in Mean Sea Level (MSL) or ellipsoidal parameters depending on the UNDULATION setting. The factory default for the **UNDULATION** command (see page 446) setting is EGM96, where the height entered in the **FIX** command is set as MSL height. If you change the UNDULATION setting to USER 0, the height entered in the **FIX** command is set as ellipsoidal height (refer to *Table 38: FIX parameters* on the next page).

Error checking is performed on the entered fixed position by the integrity monitor. Depending on the result of this check, the position can be flagged with the following statuses.

- SOL_COMPUTED: The entered position has been confirmed by measurement.
- PENDING: Insufficient measurements are available to confirm the entered position.
- INTEGRITY_WARNING: First level of error when an incorrect position has been entered. The fixed position is off by approximately 25-50 metres.
- INVALID_FIX: Second level of error when an inaccurate position has been entered. The fixed position is off by a gross amount.

An incorrectly entered fixed position will be flagged either INTEGRITY_WARNING or INVALID_FIX. This will stop output of differential corrections or RTK measurements and can affect the clock steering and satellite signal search. Checks on the entered fixed position can be disabled using the **RAIMMODE** command (see page 328).

Message ID: 44

Abbreviated ASCII syntax:

```
FIX type [param1 [param2 [param3]]]
```

Factory default:

```
FIX none
```

ASCII example:

```
FIX none
FIX HEIGHT 4.567
FIX position 51.116 -114.038 1065.0
```

In order to maximize the absolute accuracy of RTK rover positions, the base station coordinates must be fixed to their known position using the **FIX POSITION [lat][lon][hgt]** command.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FIX header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	type	See *Table 39: Fix types* on the next page		Fix type	Enum	4	H
3	param1	See *Table 38: FIX parameters* below		Parameter 1	Double	8	H + 4
4	param2			Parameter 2	Double	8	H + 12
5	param3			Parameter 3	Double	8	H + 20

Table 38: FIX parameters

ASCII type name	Parameter 1	Parameter 2	Parameter 3
AUTO	Not used	Not used	Not used
HEIGHT	Default MSL height [1] (-1000 to 20000000 m)	Not used	Not used
NONE	Not used	Not used	Not used
POSITION	Lat (-90 to 90 degrees) where a '-' sign denotes south and a '+' sign denotes north	Lon (-360 to 360 degrees) where a '-' sign denotes west and a '+' sign denotes east	Default MSL height [1] (-1000 to 20000000 m)

For a discussion on height, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

1. See also Note #4 above.

Table 39: Fix types

ASCII	Binary	Description
NONE	0	Unfix. Clears any previous FIX commands
AUTO	1	Configures the receiver to fix the height at the last calculated value if the number of satellites available is insufficient for a 3-D solution. This provides a 2-D solution. Height calculation resumes when the number of satellites available allows a 3-D solution
HEIGHT	2	Configures the receiver in 2-D mode with its height constrained to a given value. This command is used mainly in marine applications where height in relation to mean sea level may be considered to be approximately constant. The height entered using this command is referenced to the mean sea level, see the **BESTPOS** log on page 527 (is in metres). The receiver is capable of receiving and applying differential corrections from a base station while fix height is in effect. The fix height command overrides any previous **FIX HEIGHT** or **FIX POSITION** command. This command only affects pseudorange corrections and solutions.
POSITION	3	Configures the receiver with its position fixed. This command is used when it is necessary to generate differential corrections. For both pseudorange and differential corrections, this command must be properly initialized before the receiver can operate as a GNSS base station. Once initialized, the receiver computes differential corrections for each satellite being tracked. The computed differential corrections can then be output to rover stations using the RTCMV3 differential corrections data log format. See Transmitting and Receiving Corrections in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual for information about using the receiver for differential applications. The values entered into the fix position command should reflect the precise position of the base station antenna phase centre. Any errors in the fix position coordinates directly bias the corrections calculated by the base receiver. The receiver performs all internal computations based on WGS84 and the **DATUM** command (see page 133) is defaulted as such. The datum in which you choose to operate (by changing the **DATUM** command (see page 133)) is internally converted to and from WGS84. Therefore, all differential corrections are based on WGS84, regardless of your operating datum. The **FIX POSITION** command overrides any previous **FIX HEIGHT** or **FIX POSITION** command settings.

2.53 FORCEGALE6CODE

Force receiver to track Galileo E6C or E6B signal

Platform: OEM719, OEM729, OEM7700, PwrPak7, CPT7700

Use this command to force Galileo E6 channels to track E6B or E6C.

Message ID: 2222

Abbreviated ASCII syntax:

```
FORCEGALE6CODE E6codetype
```

Factory default:

```
FORCEGALE6CODE E6B
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FORCEGALE6CODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	E6codetype	E6B	0	Galileo E6 code type (default = E6B)	Enum	4	H
		E6C	1				

2.54 FORCEGLOL2CODE

Forces receiver to track GLONASS satellite L2 P or L2 C/A code

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to force the receiver to track GLONASS satellite L2 P-code or L2 C/A code. This command has no effect if the channel configuration contains both GLONASS L2 P and L2 C/A channels.

Message ID: 1217

Abbreviated ASCII syntax:

```
FORCEGLOL2CODE L2type
```

Factory default:

```
FORCEGLOL2CODE default
```

ASCII example:

```
FORCEGLOL2CODE p
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FORCEGLOL2CODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	L2type	P	1	L2 P-code or L2 Precise code	Enum	4	H
		C	2	L2 C/A code or L2 Coarse/Acquisition code			
		DEFAULT	3	Set to channel default			

The following table lists which L2 signal is tracked based on the channel configuration and the setting used for the L2type parameter.

Table 40: Signals tracked – channel configuration and L2type option

Channel configuration for L2 signal	L2type setting		
	P	C	DEFAULT
L2	P	C	P
L2C	P	C	C
L2PL2C	Both	Both	Both

2.55 FORCEGPSL2CODE

Forces receiver to track GPS satellite L2 P or L2C code

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to force the receiver to track GPS L2 P-code or L2C code. AUTO tells the receiver to use L2C code type if available and L2 P-code if L2C code is not available. This command has no effect if the channel configuration contains both GPS L2 P and L2 C channels.

Message ID: 796

Abbreviated ASCII syntax:

```
FORCEGPSL2CODE L2type
```

Factory default:

```
FORCEGPSL2CODE default
```

ASCII example:

```
FORCEGPSL2CODE p
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FORCEGPSL2CODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	L2type	See *Table 41: GPS L2 code type* below		GPS L2 code type	Enum	4	H

Table 41: GPS L2 code type

Binary	ASCII	Description
0	AUTO	Receiver uses the L2C if available and L2 P otherwise. An exception is when the receiver is doing RTK positioning. In that case, AUTO changes the L2 code type being tracked to match the L2 code type found in the base station corrections, which ensures the greatest number of satellites are used in the solution.
1	P	L2 P-code or L2 Precise code
2	C	L2C code or L2 Civilian code
3	DEFAULT	Set to channel default

The following table lists which L2 signal is tracked based on the channel configuration and the setting used for the L2type parameter.

Table 42: Signals tracked – channel configuration and L2type option

Channel configuration for L2 signal	L2type setting			
	Auto	P	C	DEFAULT
L2	C if available, P(Y) otherwise	P(Y)	C	P(Y)
L2C	C if available, P(Y) otherwise	P(Y)	C	C
L2P	C if available, P(Y) otherwise	P(Y)	C	P(Y)
L2AUTO	C if available, P(Y) otherwise	P(Y)	C	C if available, P(Y) otherwise
L2PL2C	Both	Both	Both	Both

2.56 FREQUENCYOUT

Sets output pulse train available on VARF

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This command is used to set the output pulse train available on the Variable Frequency (VARF) or EVENT_OUT1 pin. The output waveform is coherent with the 1PPS output, see the usage note and *Figure 4: Pulse width and 1PPS coherency* on the next page.

The **FREQUENCYOUT** command is obsolete. Use the **EVENTOUTCONTROL** command (see page 164) to set the output pulse train on the VARF and EVENT_OUT pins.

If the **CLOCKADJUST** command (see page 117) is ENABLED and the receiver is configured to use an external reference frequency (set in the **EXTERNALCLOCK** command (see page 168) for an external clock - TCXO, OCXO, RUBIDIUM, CESIUM, or USER), then the clock steering process takes over the VARF output pins and may conflict with a previously entered **FREQUENCYOUT** command.

Figure 4: Pulse width and 1PPS coherency on the next page shows how the chosen pulse width is frequency locked but not necessarily phase locked when using ENABLE option. To synchronize the phase, use ENABLESYNC option.

The EVENTOUT outputs cannot synchronize with GPS time until the receiver reaches FINESTEERING time status. As the receiver transitions to GPS time, there may be additional, unexpected pulses on the EVENTOUT signals.

Message ID: 232

Abbreviated ASCII syntax:

```
FREQUENCYOUT [switch] [pulsewidth] [period]
```

Factory default:

```
FREQUENCYOUT disable
```


ASCII example:

```
FREQUENCYOUT ENABLE 50000 100000
```

This example generates a 50% duty cycle 1 kHz square wave.

Signal integrity will begin to degrade when generating a clock frequency greater than 10 MHz. It is not recommended to generate a clock frequency greater than 20 MHz.

Figure 4: Pulse width and 1PPS coherency



When using ENABLE option, the VARF and 1PPS are not necessarily in phase as described in *Figure 4: Pulse width and 1PPS coherency* above. To align the phase of the VARF with the 1PPS, use the ENABLESYNC option and the VARF phase will be synchronized to the leading edge of the 1PPS pulse. Note that if the VARF and 1PPS frequencies are not even multiples of each other, this may cause the VARF to have a shorter cycle pulse prior to each 1PPS pulse. 1PPS is not affected.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FREQUENCYOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disable causes the output to be fixed low. (if NONE specified, defaults to DISABLE)	Enum	4	H
		ENABLE	1	Enables customized frequency output.			
		ENABLESYNC	2	Enables customized frequency output synchronized to PPS.			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	pulsewidth	(0 to 1073741823)		Number of 10 ns steps for which the output is high. Duty cycle = pulsewidth / period. If pulsewidth is greater than or equal to the period, the output is a high DC signal. If pulsewidth is 1/2 the period, then the output is a square wave. (default = 0)	Ulong	4	H+4
4	period	(0 to 1073741823)		Signal period in 10 ns steps. Frequency Output = 100,000,000 / Period (default = 0)	Ulong	4	H+8

2.57 FRESET

Clears selected data from NVM and reset

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to clear data which is stored in non-volatile memory. Such data includes the almanac, ephemeris, and any user specific configurations. The commands, ephemeris, almanac, and L-band related data, excluding the subscription information, can be cleared by using the STANDARD target. The receiver is forced to reset.

FRESET STANDARD (which is also the default) causes most commands, ephemeris, GNSS and almanac data previously saved to NVM to be erased.

The **FRESET STANDARD** command will erase all user settings. You should know your configuration (by requesting the **RXCONFIG** log on page 913) and be able to reconfigure the receiver before you send the **FRESET** command.

Message ID: 20

Abbreviated ASCII syntax:

```
FRESET [target]
```

Input example:

```
FRESET COMMAND
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	FRESET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	target	See *Table 43: FRESET target* on the next page		What data is to be reset by the receiver (default = STANDARD)	Enum	4	H

If you are receiving no data or random data from your receiver, try the following before contacting NovAtel:

- Verify that the receiver is tracking satellites by logging the **TRACKSTAT** log (see page 1004) and checking that the receiver is tracking at least four satellites.
- Check the integrity and connectivity of power, antenna and data cables
- Verify the baud rate settings of the receiver and terminal device (your PC, data logger or laptop)
- Switch COM ports
- Issue the **FRESET** command.

Table 43: FRESET target

Binary	ASCII	Description
0	STANDARD	Resets commands (except **CLOCKCALIBRATION** and **MODEL**). Resets the stored ephemeris and almanac from all satellite systems. Resets all L-band related data except for the subscription information. Does not reset the Ethernet settings or stored Profile configurations. (default)
1	COMMAND	Resets the stored commands saved by the **SAVECONFIG** command (see page 367). Resets the Wi-Fi AP passkey if the **WIFIAPPASSKEY** command was saved via the **SAVECONFIG** command (see page 367). The Wi-Fi AP passkey is set to the factory configured default Wi-Fi AP passkey.
2	GPSALMANAC	Resets the stored GPS almanac
3	GPSEPHEM	Resets the stored GPS ephemeris
4	GLOEPHEM	Resets the stored GLONASS ephemeris
5	MODEL	Resets the currently selected model
10	USERDATA	Resets the user data saved using the **NVMUSERDATA** command (see page 283)
11	CLKCALIBRATION	Resets the parameters entered using the **CLOCKCALIBRATE** command (see page 119)
20	SBASALMANAC	Resets the stored SBAS almanac
21	LAST_POSITION	Resets the position using the last stored position
31	GLOALMANAC	Resets the stored GLONASS almanac
39	GALFNAV_EPH	Resets the stored GALFNAV ephemeris
40	GALINAV_EPH	Resets the stored GALINAV ephemeris
45	GALFNAV_ALM	Resets the stored GALFNAV almanac
46	GALINAV_ALM	Resets the stored GALINAV almanac
52	PROFILEINFO	Resets the stored profile configurations (see the **PROFILE** command on page 313)
54	QZSSALMANAC	Resets the QZSS almanac
55	QZSSEPHEMERIS	Resets the QZSS ephemeris
57	BDSALMANAC	Resets the BeiDou almanac
58	BDSEPHEMERIS	Resets the BeiDou ephemeris

Binary	ASCII	Description
60	USER_ACCOUNTS	Resets the admin password to the default password (see the **SETADMINPASSWORD** command on page 390). On a PwrPak7, SMART7, CPT7, or CPT7700 that was manufactured and/or factory configured with a default admin password, the admin password is set to the factory configured default admin password. This password is shown on the enclosure label. On a PwrPak7, SMART7, CPT7 or CPT7700 that was not manufactured and/or factory configured with a default admin password, the admin password is set to the enclosure PSN. On receiver cards, the admin password is set to the receiver card PSN.
64	ETHERNET	Resets the stored Ethernet settings saved by the **SAVEETHERNETDATA** command (see page 368)
76	COLDSTART	Resets the almanac and ephemeris for all constellations and position
87	NAVICEPHEMERIS	Resets the NavIC ephemeris
88	NAVICALMANAC	Resets the NavIC almanac
93	USER_DATUM	Resets the user datums (see the **GEODETICDATUM** command on page 203)
94	USER_DATUM_ TRANSFORMATION	Resets the user datums transformations (see the **DATUMTRANSFORMATION** command on page 135)
97	SKCALIBRATIONS	Resets the spoofing detection calibration values
128	DISPATCH	Delete all dispatch messages, including Service, Dictionary and Model. All subscription services will be lost until the messages are reapplied.

2.58 GALECUTOFF

Sets elevation cut-off angle for Galileo satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the elevation cut-off angle for tracked Galileo satellites. The receiver does not start automatically searching for a satellite until it rises above the cut-off angle (when satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they were manually assigned (see the **ASSIGN** command on page 77).

In either case, satellites below the GALECUTOFF angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle and can be used in the following situations:

- The antenna is at a high altitude and thus look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Care must be taken when using **GALECUTOFF** because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

Use the **ELEVATIONCUTOFF** command (see page 157) to set the cut-off angle for any system.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

Message ID: 1114

Abbreviated ASCII syntax:

```
GALECUTOFF angle
```

Factory default:

```
GALECUTOFF 5.0
```

ASCII example:

```
GALECUTOFF 10.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GALECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	angle	±90.0 degrees		Elevation cut-off angle relative to horizon	Float	4	H

2.59 GENERATEALIGNCORRECTIONS

Configure ALIGN base

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command is used to configure the ALIGN Base and starts sending out ALIGN corrections through the specified port. This command is like sending the following commands to the Base, assuming the use of a serial port and default ALIGN corrections:

```
unlogall [port]
fix none
movingbasestation enable
interfacemode [port] novatel rtca
serialconfig [port] [baud] N 8 1 N ON
log [port] rtcaobs3 ontime [rate = 1/ obsreqrate]
log [port] rtcarefext ontime [rate = 1/ refextreqrate]
```

Message ID: 1349

Abbreviated ASCII syntax:

```
GENERATEALIGNCORRECTIONS port [baud] [obsreqrate] [refextreqrate]
[interfacemode]
```

ASCII example:

```
GENERATEALIGNCORRECTIONS COM2 230400 10 10
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GENERATEALIGN CORRECTIONS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 34: Communications port identifiers* on page 153		Port identifier (default = THISPORT)	Enum	4	H
3	baud	9600, 19200, 38400, 57600, 115200, 230400 or 460800		Communication baud rate (bps) (default = 9600)	Ulong	4	H+4
4	obsreqrate	1, 2, 4, 5, 10, 20, 50 or 100		RTCAOBS3 data rate in Hz (default = 1)	Ulong	4	H+8

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
5	refextreqrate	0, 1, 2, 4, 5, 10, 20, 50 or 100		RTCAREFEXT data rate in Hz (default = 1)	Ulong	4	H+12
6	interfacemode	RTCA	3	Correction interface mode (default = RTCA)	Enum	4	H+16
		NOVATELX	35				

2.60 GENERATEDIFFCORRECTIONS

Sends a preconfigured set of differential corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to configure the receiver to send a preconfigured set of differential pseudorange corrections.

Message ID: 1296

Abbreviated ASCII syntax:

```
GENERATEDIFFCORRECTIONS mode port
```

ASCII example:

```
GENERATEDIFFCORRECTIONS rtcm com2
```

Preconfigured set of differential corrections sent when RTCM:

```
RTCM1 ontime 1
RTCM31 ontime 1
RTCM3 ontime 10
```

Preconfigured set of differential corrections sent when RTCA:

```
RTCA1 ontime 1
RTCAREF ontime 10
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GENERATEDIFF CORRECTIONS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	RTCM	2	Serial port interface mode identifier. See *Table 46: Serial Port Interface Modes* on page 220	Enum	4	H
		RTCA	3				
3	port	See *Table 76: COM port identifiers* on page 384		Port to configure	Enum	4	H+4

2.61 GENERATERTKCORRECTIONS

Sends a preconfigured set of RTK corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to configure the base station receiver to transmit a preconfigured set of RTK (carrier phase) corrections.

Message ID: 1260

Abbreviated ASCII syntax:

```
GENERATERTKCORRECTIONS mode port
```

ASCII example:

```
GENERATERTKCORRECTIONS rtcmv3 com2
```

Preconfigured set of differential corrections sent when mode is RTCM:

```
RTCM3 ONTIME 10
RTCM22 ONTIME 10 5
RTCM23 ONTIME 60
RTCM24 ONTIME 60 30
RTCM1819 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is RTCA:

```
RTCAREF ONTIME 10
RTCAOBS2 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is CMR:

```
CMRREF ONTIME 10
CMROBS ONTIME 1
CMRGLOOBS ONTIME 1
```

Preconfigured set of differential corrections sent when mode is MSM12:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1071 ONTIME 1
RTCM1072 ONTIME 1
RTCM1081 ONTIME 1
RTCM1082 ONTIME 1
RTCM1091 ONTIME 1
RTCM1092 ONTIME 1
RTCM1111 ONTIME 1
RTCM1112 ONTIME 1
RTCM1121 ONTIME 1
RTCM1122 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is MSM / MSM3:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1073 ONTIME 1
```

```
RTCM1083 ONTIME 1
RTCM1093 ONTIME 1
RTCM1113 ONTIME 1
RTCM1123 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is MSM4:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1074 ONTIME 1
RTCM1084 ONTIME 1
RTCM1094 ONTIME 1
RTCM1114 ONTIME 1
RTCM1124 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is MSM5:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1075 ONTIME 1
RTCM1085 ONTIME 1
RTCM1095 ONTIME 1
RTCM1115 ONTIME 1
RTCM1125 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is MSM6:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1076 ONTIME 1
RTCM1086 ONTIME 1
RTCM1096 ONTIME 1
RTCM1116 ONTIME 1
RTCM1126 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is MSM7:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1077 ONTIME 1
RTCM1087 ONTIME 1
RTCM1097 ONTIME 1
RTCM1117 ONTIME 1
RTCM1127 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is RTCMV3:

```
RTCM1006 ONTIME 10
RTCM1008 ONTIME 10 2
RTCM1033 ONTIME 10 4
RTCM1230 ONTIME 1
RTCM1004 ONTIME 1
RTCM1012 ONTIME 1
```

Preconfigured set of differential corrections sent when mode is NOVATELX:

```
NOVATELXOBS ONTIME 1
```

This command will disable all logs previously assigned to output from the COM port before logging the specified RTK messages.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GENERATERTK CORRECTIONS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	RTCM	2	Serial port interface mode identifier. For more information, see *Table 46: Serial Port Interface Modes* on page 220	Enum	4	H
		RTCA	3				
		CMR	4				
		MSM	5				
		MSM12	6				
		MSM3	7				
		MSM4	8				
		MSM5	9				
		MSM6	10				
		MSM7	11				
		RTCMV3	14				
		NOVATELX	35				
3	port	See *Table 76: COM port identifiers* on page 384		Port to configure	Enum	4	H+4

For information about the RTCM, RTCA and CMR messages, refer to the official standards document for those messages.

2.62 GEODETICDATUM

Set user-defined datum parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to add or remove user-defined datums. These are used by the **OUTPUTDATUM** command (see page 284) to select an entry from the **DATUMTRANSFORMATIONS** log (see page 563). They also define the parameters to convert between geodetic and Cartesian coordinates.



The **OUTPUTDATUM** command (see page 284) must be sent for any user-defined datums to be output.

The receiver firmware includes a default set of datums. These default datums cannot be deleted, but can be overwritten with user-defined parameters. A default datum that has been overwritten can be reverted to the default parameters by deleting the datum. User-defined datums will persist a factory reset; all user-defined datums can be removed by sending **FRESET USER_DATUM** (see the **FRESET** command on page 192). Both the user-defined and default datums are reported by the **GEODETICDATUMS** log (see page 614).

Datum entries are indexed by name, which must be unique. The name “USER” is reserved for the **USEREXPDATUM** entry. “ECEF” is reserved as a generic Earth-Centered Earth-Fixed datum. “UNKNOWN” is also reserved.

The EPSG Geodetic Parameter Dataset (epsg.io) is a commonly-referenced database of coordinate reference systems and coordinate transformations. The EPSG code in this log is intended to correspond to the “GeodeticDatum” data type within that database. If you are using a custom datum, the ESPG code should be 0.

Message ID: 2295

Abbreviated ASCII syntax:

```
GEODETICDATUM switch name epsg_code anchor semimajor_axis flattening
```

Factory default:

```
GEODETICDATUM none
```

ASCII example:

Save a new geodetic datum to NVM:

```
GEODETICDATUM save NAD83(MA11) 1118 EARTH_FIXED 6378137.0 298.257222101
```

Delete an existing geodetic datum from NVM:

```
GEODETICDATUM delete NAD83(MA11)
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	GEODETICDATUM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	switch	SAVE	1	Save the datum.	Enum	4	H
		DELETE	2	Delete the datum.			
3	name			Name of the datum.	Char [32]	variable	H+4
4	epsg_code			The EPSG code.	Ulong	4	variable
5	anchor	See *Table 44: Datum anchors* below		The datum type.	Enum	4	variable
6	semimajor_ axis	6300000.000 – 6400000.000		Semi-major axis of the datum's ellipsoid (metres)	Double	8	variable
7	flattening	290.000 – 305.000		Inverse flattening of the datum's ellipsoid (unitless)	Double	8	variable

Table 44: Datum anchors

Binary	ASCII	Description
0	UNKNOWN	The anchor is unknown.
1	EARTH_FIXED	The datum is not anchored to a specific tectonic plate (e.g., ITRF2005, WGS84).
2	PLATE_FIXED	The datum is anchored to a tectonic plate (e.g., NAD83, ETRF89).

2.63 GGAQUALITY

Customizes the GPGGA GPS quality indicator

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to customize the NMEA GPGGA GPS quality indicator. See also the **GPGGA** log on page 635.



This command also changes the GPS quality indicator in the NMEA2000 CAN logs.

Message ID: 691

Abbreviated ASCII syntax:

```
GGAQUALITY #entries pos_type quality
```

Input example 1:

```
GGAQUALITY 1 waas 2
```

Makes the WAAS solution type show 2 as the quality indicator.

Input example 2:

```
GGAQUALITY 2 waas 2 NARROW_FLOAT 3
```

Makes the WAAS solution type show 2 and the NARROW_FLOAT solution type show 3, as their quality indicators.

Input example 3:

```
GGAQUALITY 0
```

Sets all the quality indicators back to the default.



Some solution types, see *Table 96: Position or velocity type* on page 531, share a quality indicator. For example, converged PPP and NARROW_FLOAT all share an indicator of 5. This command can be used to customize an application to have unique indicators for each solution type. Sets all the quality indicators back to the default. Refer to *Table 134: GPS quality indicators* on page 637.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GGAQUALITY header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	#entries	0-20		The number of position types that are being remapped (20 max)	Ulong	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	pos_type	See *Table 96: Position or velocity type* on page 531		The position type that is being remapped	Enum	4	H+4
4	quality	See *Table 134: GPS quality indicators* on page 637		The remapped quality indicator value that will appear in the GPGGA log for this position type	Ulong	4	H+8
...	Next solution type and quality indicator set, if applicable				Variable		

2.64 GLIDEINITIALIZATIONPERIOD

Configures the GLIDE initialization period

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the initialization period for Relative PDP (GLIDE) when pseudorange measurements are used more heavily. During the initialization period, the PDP output position is not as smooth as during full GLIDE operation, but it helps to get better absolute accuracy at the start. The longer this period is, the better the absolute accuracy that can be attained. The maximum period that can be set through **GLIDEINITIALIZATIONPERIOD** is 1200 seconds.

Message ID: 1760

Abbreviated ASCII syntax:

```
GLIDEINITIALIZATIONPERIOD initialization
```

Factory default:

```
GLIDEINITIALIZATIONPERIOD 300
```

ASCII example:

```
GLIDEINITIALIZATIONPERIOD 100
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GLIDEINITIALIZATION PERIOD header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	initialization	0 -1200 s		Initialization period for GLIDE in seconds	Double	8	H

2.65 GLOECUTOFF

Sets GLONASS satellite elevation cut-off

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the elevation cut-off angle for tracked GLONASS satellites. The receiver does not start automatically searching for a satellite until it rises above the cut-off angle (when satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they were manually assigned (see the **ASSIGN** command on page 77).

In either case, satellites below the GLOECUTOFF angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle and can be used in the following situations:

- The antenna is at a high altitude and can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction
- However, for GLONASS it is not recommended to use negative values because a receiver should not track both antipodal satellites that are broadcasting on the same frequency.

Care must be taken when using **GLOECUTOFF** because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

Use the **ELEVATIONCUTOFF** command (see page 157) to set the cut-off angle for any system.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

Message ID: 735

Abbreviated ASCII syntax:

```
GLOECUTOFF angle
```

Factory default:

```
GLOECUTOFF 5.0
```

ASCII example:

```
GLOECUTOFF 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	GLOECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	angle	±90.0 degrees		Elevation cut-off angle relative to horizon	Float	4	H

2.66 HDTOUTTHRESHOLD

Controls GPHDT log output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command is used to control the output of the NMEA **GPHDT** log (see page 653). It sets a heading standard deviation threshold. Only heading information with a standard deviation less than this threshold can be output into a GPHDT message.

Message ID: 1062

Abbreviated ASCII syntax:

```
HDTOUTTHRESHOLD thresh
```

Factory default:

```
HDTOUTTHRESHOLD 2.0
```

ASCII example:

```
HDTOUTTHRESHOLD 12.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	HDTOUTTHRESHOLD header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	thresh	0.0 - 180.0		Heading standard deviation threshold (degrees)	Float	4	H

2.67 HEADINGOFFSET


Adds heading and pitch offset values

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command is used to add an offset in the heading and pitch values of the **HEADING2** log (see page 668) and **GPHDT** log (see page 653).

The unmodified heading value represents the angle from True North of the base to rover vector in a clockwise direction. In some installations, it may not be possible to place the rover antenna in the desired location, for instance to match the forward-facing direction of the vehicle.

Figure 5: HEADINGOFFSET example



In the example above, the rover antenna (in brown) is offset from the forward direction of travel and the provided heading will look as if the land vehicle is "slipping". A Heading offset can help to account for that difference between heading output and actual course over ground. It is up to the user to accurately determine the offset to be applied to suit their scenario.

HEADINGOFFSET is not required to configure Dual Antenna ALIGN with SPAN. If desired, see configuration details in Configuring Dual Antenna ALIGN with SPAN in the OEM7 SPAN Installation and Operation User Manual.

Most configurations of the HEADINGOFFSET command are not compatible with Waypoint Inertial Explorer and as such is not recommended for use if the data will be post processed. Contact support (see *Customer Support* on page 27) for more information.

Message ID: 1082

Abbreviated ASCII syntax:

```
HEADINGOFFSET headingoffsetindeg [pitchoffsetindeg]
```

Factory default:

```
HEADINGOFFSET 0 0
```

ASCII example:

```
HEADINGOFFSET 2 -1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	HEADINGOFFSET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	headingoffsetindeg	-180.0 - 180.0		Offset added to heading output (degrees). Default=0	Float	4	H
3	pitchoffsetindeg	-90.0 - 90.0		Offset added to pitch output (degrees). Default=0	Float	4	H+4

2.68 ICOMCONFIG

Configures IP virtual COM port

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command is used for Ethernet set up and to configure the transport/application layer of the configuration.

Access to the ICOM ports can be restricted by turning on ICOM security using the **IPSERVICE** command (see page 226).

Message ID: 1248

Abbreviated ASCII syntax:

```
ICOMCONFIG [port] protocol [endpoint [bindinterface]]
```

Factory default:

```
ICOMCONFIG ICOM1 TCP :3001
ICOMCONFIG ICOM2 TCP :3002
ICOMCONFIG ICOM3 TCP :3003
ICOMCONFIG ICOM4 TCP :3004
ICOMCONFIG ICOM5 TCP :3005
ICOMCONFIG ICOM6 TCP :3006
ICOMCONFIG ICOM7 TCP :3007
```

ASCII example:

```
ICOMCONFIG ICOM1 TCP :2000 All
```

Due to security concerns, configuring and enabling ICOM ports should only be done to receivers on a closed system, that is, board-to-board. NovAtel is not liable for any security breaches that may occur if not used on a closed system.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ICOMCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	THISPORT	6	Name of the port (default = THISPORT).	Enum	4	H
		ICOM1	23				
		ICOM2	24				
		ICOM3	25				
		ICOM4	29				
		ICOM5	46				
		ICOM6	47				
		ICOM7	48				
3	protocol	See *Table 45: ICOMCONFIG protocol* on the next page		Protocol used by the ICOM port.	Enum	4	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	endpoint	Host:DestinationPort:SourcePort For example: 10.0.3.1:8000 192.168.1.1:3006:3006 mybase.com:3000		Endpoint to wait on, or to connect to where host is a host name or IP address and port is the TCP/UDP port number. If host is blank, act as a server. If SourcePort is not specified, the default value is used. If DestinationPort is not specified, a value is automatically assigned to the DestinationPort (which will be a different value every time the receiver is power-cycled).	String [80]	variable[1]	H+8
5	bindInterface	ALL	1	Not supported. Set to *ALL* for future compatibility. (default)	Enum	4	H+88

Table 45: ICOMCONFIG protocol

Binary	ASCII	Description
1	DISABLED	Will disable the service
2	TCP	Use TCP The TCP protocol option provides a one to one connection between an OEM receiver and a client.
3	UDP	Use UDP

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

Binary	ASCII	Description
4	TCP_ SERVER	Allow multiple TCP connections The TCP_SERVER protocol option provides one to many connections so several clients can connect to the same ICOM port. All clients receive the same OEM receiver output, including command responses. When an ICOM port is configured as a TCP_ SERVER, it is suggested to not issue commands on the ICOM port or have responses disabled (see **INTERFACEMODE** command on the next page). There is a maximum of 20 TCP client connections to the receiver using ICOM ports configured as TCP_SERVER.

2.69 INTERFACEMODE

Sets receive or transmit modes for ports

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to specify what type of data a particular port on the receiver can transmit and receive. The receive type tells the receiver what type of data to accept on the specified port. The transmit type tells the receiver what kind of data it can generate. For example, to accept RTCMV3 differential corrections, set the receive type on the port to RTCMV3.

It is also possible to disable or enable the generation or transmission of command responses for a particular port. Disabling of responses is important for applications where data is required in a specific form and the introduction of extra bytes may cause problems, i.e., RTCA, RTCM, RTCMV3 or CMR. Disabling a port prompt is also useful when the port is connected to a modem or other device that responds with data the RECEIVER does not recognize.



For applications running in specific interface modes, see *Table 46: Serial Port Interface Modes* on page 220, set the appropriate interface modes before sending or receiving corrections. It is important that the port interface mode matches the data being received on that port. Mismatches between the interface mode and received data can result in CPU overloads.

When INTERFACEMODE port NONE NONE OFF is set, the specified port is disabled from interpreting any input or output data. Therefore, no commands or differential corrections are decoded by the specified port. When GENERIC is set for a port, it is also disabled but data can be passed through the disabled port and be output from an alternative port using the pass-through logs PASSCOM, PASSAUX and PASSUSB. See *PASSCOM, PASSAUX, PASSUSB, PASSICOM, PASSNCOM* on page 760 for details on these logs along with Pass-Through Logging in the OEM7 Installation and Operation User Manual. PwrPak7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual for information about pass-through logging. See also the **SERIALCONFIG** command on page 383.If you intend to use the **SERIALCONFIG** command (see page 383), ensure you do so before the **INTERFACEMODE** command on each port. The **SERIALCONFIG** command (see page 383) can remove the **INTERFACEMODE** command setting if the baud rate is changed after the interface mode is set. You should also turn break detection off using the **SERIALCONFIG** command (see page 383) to stop the port from resetting because it is interpreting incoming bits as a break command. If such a reset happens, the Interface mode will be set back to the default NOVATEL mode for both input and output.

Ensure that the **SERIALCONFIG** parameters match when configuring a tunnel between different communication ports using **INTERFACEMODE**.

2.69.1 SPAN systems

The INTERFACEMODE of the receiver is also configured for the serial port dedicated to the IMU. This mode changes automatically upon sending a **CONNECTIMU** command (see page 1041) and the change is reflected when logging this command. This is normal operation.



When the CONNECTIMU command (see page 1041) is used to configure the IMU connected to the receiver, the correct interface mode for the IMU port is automatically set. The IMU port should not be altered using the INTERFACEMODE command in normal operation. Doing so may result in the loss of IMU communication.

Message ID: 3

Abbreviated ASCII syntax:

```
INTERFACEMODE [port] rxtype txtype [responses]
```

Factory default:

```
INTERFACEMODE COM1 NOVATEL NOVATEL ON
INTERFACEMODE COM2 NOVATEL NOVATEL ON
INTERFACEMODE COM3 NOVATEL NOVATEL ON
INTERFACEMODE AUX NOVATEL NOVATEL ON
INTERFACEMODE USB1 NOVATEL NOVATEL ON
INTERFACEMODE USB2 NOVATEL NOVATEL ON
INTERFACEMODE USB3 NOVATEL NOVATEL ON
INTERFACEMODE ICOM1 NOVATEL NOVATEL ON
INTERFACEMODE ICOM2 NOVATEL NOVATEL ON
INTERFACEMODE ICOM3 NOVATEL NOVATEL ON
INTERFACEMODE ICOM4 NOVATEL NOVATEL ON
INTERFACEMODE ICOM5 NOVATEL NOVATEL ON
INTERFACEMODE ICOM6 NOVATEL NOVATEL ON
INTERFACEMODE ICOM7 NOVATEL NOVATEL ON
INTERFACEMODE NCOM1 RTCMV3 NONE OFF
INTERFACEMODE NCOM2 RTCMV3 NONE OFF
INTERFACEMODE NCOM3 RTCMV3 NONE OFF
INTERFACEMODE CCOM1 NOVATELBINARY NOVATELBINARY ON
INTERFACEMODE CCOM2 NOVATELBINARY NOVATELBINARY ON
INTERFACEMODE CCOM3 AUTO NOVATEL OFF
INTERFACEMODE CCOM4 AUTO NOVATEL OFF
INTERFACEMODE CCOM5 AUTO NOVATEL OFF
INTERFACEMODE CCOM6 AUTO NOVATEL OFF
INTERFACEMODE SCOM1 NOVATEL NOVATEL ON
INTERFACEMODE SCOM2 NOVATEL NOVATEL ON
INTERFACEMODE SCOM3 NOVATEL NOVATEL ON
INTERFACEMODE SCOM4 NOVATEL NOVATEL ON
INTERFACEMODE LCOM1 NOVATEL NOVATEL ON (firmware 7.10.xx)
INTERFACEMODE LCOM2 NOVATEL NOVATEL ON (firmware 7.10.xx)
INTERFACEMODE LCOM3 NOVATEL NOVATEL ON (firmware 7.10.xx)
INTERFACEMODE LCOM4 NOVATEL NOVATEL ON (firmware 7.10.xx)
```

ASCII example 1:

```
INTERFACEMODE COM1 RTCMV3 NOVATEL ON
```

ASCII example 2:

```
INTERFACEMODE COM2 MRTCA NONE
```

Are NovAtel receivers compatible with others on the market?

All GNSS receivers output two solutions: position and time. The manner in which they output them makes each receiver unique. Most geodetic and survey grade receivers output the position in electronic form (typically RS-232), which makes them compatible with most computers and data loggers. All NovAtel receivers have this ability. However, each manufacturer has a unique way of formatting the messages. A NovAtel receiver is not directly compatible with a Trimble or Ashtech receiver (which are also incompatible with each other) unless everyone uses a standard data format.

However, there are several standard data formats available. For position and navigation output there is the NMEA format. Real-time differential corrections use RTCM or RTCA format. For receiver code and phase data RINEX format is often used. NovAtel and all other major manufacturers support these formats and can work together using them. The NovAtel format measurement logs can be converted to RINEX using the utilities provided in NovAtel Convert.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INTERFACEMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 34: Communications port identifiers* on page 153		Serial port identifier (default = THISPORT) **Note**: On the SMART2, the INTERFACEMODE command cannot be used with CCOM ports.	Enum	4	H
3	rxtype	See *Table 46: Serial Port Interface Modes* on the next page		Receive interface mode	Enum	4	H+4
4	txtype	See *Table 46: Serial Port Interface Modes* on the next page		Transmit interface mode	Enum	4	H+8
5	responses	OFF	0	Turn response generation off	Enum	4	H+12
		ON	1	Turn response generation on (default)			

Table 46: Serial Port Interface Modes

Binary Value	ASCII Value	Description
0	NONE	The port accepts/generates nothing. The port is disabled.
1	NOVATEL	The port accepts/generates NovAtel commands and logs. The port also accepts/generates NOVATELX corrections.
2	RTCM	The port accepts/generates RTCM corrections.
3	RTCA	The port accepts/generates RTCA corrections.
4	CMR	The port accepts/generates CMR corrections.
5-6	Reserved	
7	IMU	This port supports communication with a NovAtel supported IMU.
8	RTCMNOCR	When RTCMNOCR is used as the *txtype*, the port generates RTCM corrections without the CR/LF appended. When RTCMNOCR is used as the *rxtype*, the port accepts RTCM corrections with or without the CR/LF appended.
9	Reserved	

10	TCOM1	INTERFACEMODE tunnel modes.
		To configure a full duplex tunnel, configure the baud rate on each port. Once a tunnel is established, the baud rate does not change. Special characters, such as a BREAK condition, do not route across the tunnel transparently and the serial port is altered, see the **SERIALCONFIG** command on page 383. Only serial ports may be in a tunnel configuration: COM1, COM2, COM3 or AUX may be used.
		For example, configure a tunnel at 115200 bps between COM1 and AUX:
		`SERIALCONFIG AUX 115200`
		`SERIALCONFIG COM1 115200`
		`INTERFACEMODE AUX TCOM1 NONE OFF`
		`INTERFACEMODE COM1 TAUX NONE OFF`
		The tunnel is fully configured to receive/transmit at a baud rate of 115200 bps.

11	TCOM2	
12	TCOM3	
13	TAUX [1]	
14	RTCMV3	The port accepts/generates RTCM Version 3.0 corrections.
15	NOVATELBINARY	The port only accepts/generates binary messages. If an ASCII command is entered when the mode is set to binary only, the command is ignored. Only properly formatted binary messages are responded to and the response is a binary message.
16-17	Reserved	

1. Only available on specific models.

Binary Value	ASCII Value	Description
18	GENERIC	The port accepts/generates nothing. The **SEND** command (see page 380) or **SENDHEX** command (see page 382) from another port generate data on this port. Any incoming data on this port can be seen with PASSCOM logs on another port, see **PASSCOM, PASSAUX, PASSUSB, PASSICOM, PASSNCOM** log on page 760.
19	IMARIMU	This port supports communication with an iMAR IMU.
20	MRTCA	The port accepts/generates Modified Radio Technical Commission for Aeronautics (MRTCA) corrections.
21-22	Reserved	
23	KVHIMU	This port supports communication with a KVH CG5100 IMU.
24-26	Reserved	
27	AUTO	For auto-detecting different RTK correction formats and incoming baud rate (over serial ports). The change of baud rate will not appear when **SERIALCONFIG** is logged as this shows the saved baud rate for that port.
28-34	Reserved	
35	NOVATELX	The port accepts/generates NOVATELX corrections.
36-40	Reserved	
41	KVH1750IMU	The port supports communication with an IMU-KVH1750 or IMU-P1750 IMU.
42	VERIPOS	This port supports Veripos, TerraStar and Oceanix PPP corrections.
43-45	Reserved	
46	TCCOM1	CCOM1 Tunnel
47	TCCOM2	CCOM2 Tunnel
48	TCCOM3	CCOM3 Tunnel
49	NOVATELMINBINARY	NovAtel binary message with a minimal header. Only available for CCOM ports.
50	TCCOM4	CCOM4 Tunnel
51	TCCOM5	CCOM5 Tunnel
52	TCCOM6	CCOM6 Tunnel
53-57	Reserved	
60	TSCOM1	SCOM1 Tunnel
61	TSCOM2	SCOM2 Tunnel

Binary Value	ASCII Value	Description
62	TSCOM3	SCOM3 Tunnel
63	TSCOM4	SCOM4 Tunnel
64	LUA	Lua stdin/stdout/stderr. Use the LUA PROMPT command to set this Interface Mode.
65	HONEYWELLIMU	This port supports communication with a Honeywell HG4930 IMU.
66-73	Reserved	
74	TICOM1	ICOM1 Tunnel
75	TICOM2	ICOM2 Tunnel
76	TICOM3	ICOM3 Tunnel
77	TICOM4	ICOM4 Tunnel
78	TICOM5	ICOM5 Tunnel
79	TICOM6	ICOM6 Tunnel
80	TICOM7	ICOM7 Tunnel

2.70 IONOCONDITION

Sets ionospheric condition

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to change the level of ionosphere activity that is assumed by the RTK positioning algorithms.

Only advanced users should use this command.

Message ID: 1215

Abbreviated ASCII syntax:

```
IONOCONDITION mode
```

Factory default:

```
IONOCONDITION AUTO
```

ASCII example:

```
IONOCONDITION normal
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	IONOCONDITION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.		H	
2	mode	quiet	0	Receiver assumes a low level of ionosphere activity	Enum	4	H
		normal	1	Receiver assumes a medium level of ionosphere activity			
		disturbed	2	Receiver assumes a high level of ionosphere activity			
		auto	10	Receiver monitors the ionosphere activity and adapts behaviour accordingly			

2.71 IPCONFIG

Configures network IP settings

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command is used to configure static/dynamic TCP/IP properties for the Ethernet connection.

In addition to configuring an IP address and netmask for the interface, this command also includes a gateway address.

For certain applications when **STATIC** IP address is used, it is necessary to specify a DNS server using the **DNSCONFIG** command (see page 146) in order to use host names.

Message ID: 1243

Abbreviated ASCII syntax:

```
IPCONFIG [interface_name] address_mode [IP_address [netmask [gateway]]]
```

Factory default:

```
IPCONFIG ETHA DHCP
```

ASCII examples:

```
IPCONFIG ETHA STATIC 192.168.74.10 255.255.255.0 192.168.74.1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	IPCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	interface_name	ETHA	2	Name of the Ethernet interface (default = ETHA)	Enum	4	H
3	address_mode	DHCP	1	Use Dynamic IP address	Enum	4	H+4
		STATIC	2	Use Static IP address			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	IP_address	ddd.ddd.ddd.ddd (For example: 10.0.0.2)		IP Address-decimal dot notation	String [16]	variable[1]	H+8
5	netmask	ddd.ddd.ddd.ddd (For example: 255.255.255.0)		Netmask-decimal dot notation	String [16]	variable[1]	H+24
6	gateway	ddd.ddd.ddd.ddd (For example: 10.0.0.1)		Gateway-decimal dot notation	String [16]	variable[1]	H+40

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.72 IPSERVICE

Configure availability of networks ports/services

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

Use the **IPSERVICE** command to configure the availability of specific network ports/services. When disabled, the service does not accept incoming connections.

On most OEM7 receivers, the FTP Server is disabled by default. The exception is the PwrPak7 which has FTP enabled by default.

We have found two problems in the Microsoft® FTP clients contained within the Internet Explorer® and Edge browsers which make them unsuitable for retrieving files from a NovAtel receiver. When using a Windows® computer to transfer files off a NovAtel receiver, we suggest using a 3rd party FTP client.

Message ID: 1575

Abbreviated ASCII syntax:

```
IPSERVICE IPService switch
```

Factory default:

`IPSERVICE WEB_SERVER DISABLE` (OEM719 and OEM7500)

`IPSERVICE WEB_SERVER ENABLE` (OEM729, OEM7600 OEM7700 and OEM7720)

`IPSERVICE SECURE_ICOM DISABLE`

ASCII example:

```
IPSERVICE FTP_SERVER ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	IPSERVICE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	ipservice	See *Table 47: IP services* on the next page		IP service	Enum	4	H
3	switch	DISABLE	0	Disable the IP service specified.	Enum	4	H+4
		ENABLE	1	Enable the IP service specified.			

Table 47: IP services

Value (binary)	IP service (ASCII)	Description
0	NO_PORT	No port
1	FTP_SERVER	FTP server port. For most OEM7 receivers the default = DISABLE. For the PwrPak7 the default = ENABLE.1 A username and password is required to access the FTP server. The default username is *admin*. For receiver cards, the default password is the receiver PSN. For enclosures such as the PwrPak7, CPT7 or SMART7: • The default password for enclosures with a manufactured and/or factory configured password is the password listed on the enclosure label. • The default password for enclosures without a manufactured or factory configured password is the enclosure PSN. To change the default password, see the **SETADMINPASSWORD** command on page 390. If an incorrect admin password is entered more than 5 times in a row, the receiver will respond with the message `431 Login suspended` and logins will be suspended for 5 or 10 seconds. The consecutive incorrect password count is accumulated across all ports and all commands that use the admin password.
2	WEB_SERVER	Web server port For most OEM7 receivers the default = ENABLE. For the OEM7500 and OEM719 the default = DISABLE.
3	SECURE_ICOM	Enables or disables security on ICOM ports. When security is enabled, a login is required as part of the connection process (see the **LOGIN** command on page 254). Default = DISABLE Security in this sense means users must supply a name and password before being allowed to enter commands on the ICOM ports. It does not mean there is data encryption

Value (binary)	IP service (ASCII)	Description
4	SOFTLOADFILE	Enables or disables SOFTLOADFILE. By default the receiver will not allow the **SOFTLOADFILE** command (see page 412) to operate until it is enabled using the **IPSERVICE** command.

2.73 ITBANDPASSCONFIG

Enable and configure bandpass filter on receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this command to apply a bandpass filter at a certain frequency to mitigate interference in the pass band of GNSS signals. The **ITBANDPASSBANK** log (see page 685) provides information on the allowable configuration settings for each frequency band. The bandpass filter is symmetrical in nature, which means that specifying one cutoff frequency will apply a cutoff on both the low side and high side of the signal's center frequency. Only one filter can be applied for each signal.

For dual antenna receivers, an **ITBANDPASSCONFIG_1** command is used to enable a filter on the signal received from only the second antenna. An **ITBANDPASSCONFIG** command enables a filter on the signal received from only the primary antenna.

The ITBANDPASSCONFIG and ITBANDPASSCONFIG_1 commands use the same message ID.

On dual antenna receivers, any filter enabled for GPS L2 or GLONASS L2 on the secondary antenna will be applied to both GPS L2 and GLONASS L2. For this reason, care must be taken to avoid attenuating the signals with a bandpass filter that is too narrow in bandwidth. The recommended maximum lower cutoff frequency is 1221 MHz. The recommended minimum upper cutoff frequency is 1254 MHz.

FW 7.09

When applying a filter to a signal using the MEC correlator, a brief interruption in tracking may occur on affected channels.

FW 7.10

The MEC correlator is not available on firmware 7.10.xx.

This command is not available for L-band.

This command is available only on some software models. Contact your NovAtel Sales representative (novatel.com/contactus/sales-offices) to obtain interference mitigation functionality.

For more details on recommended filter placement to ensure optimal performance, refer to *3.93 ITFILTTABLE* on page 690.

Users can activate digital filters in either HDR or CIC3 mode. For optimal performance, HDR mode is recommended. However, HDR mode results in increased power consumption.

Message ID: 1999

Abbreviated ASCII syntax:

```
ITBANDPASSCONFIG frequency switch [cutofffrequency]
```

ASCII example:

```
ITBANDPASSCONFIG gpsl5 enable 1165.975
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ITBANDPASSCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	frequency	See *Table 56: Frequency types* on page 241		Set the frequency band on which to apply the filter	Enum	4	H
3	switch	DISABLE	0	Disable filter	Enum	4	H+4
		ENABLE	1	Enable filter			
4	cutofffrequency			Cut off frequency for band pass filter (MHz). (default = 0) Refer to **ITBANDPASSBANK** log (see page 685) for the allowable values.	Float	4	H+8

2.74 ITDETECTCONFIG

Enable interference detection on receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command is used to enable or disable interference detection on the receiver. It is applicable to both Spectral Analysis Detection and Statistical Analysis Detection at the same time. Detection can be enabled on all RF paths, only one RF path (L1, L2, or L5), or no RF paths. By default, only the RF paths connecting to the first antenna are enabled.

For dual antenna receivers, an **ITDETECTCONFIG_1** command is used to start interference detection on only the second antenna. The interference detection results for the second antenna are shown in the **ITDETECTSTATUS_1** log. An **ITDETECTCONFIG** command starts interference detection on only the primary antenna. The interference detection results for the primary antenna are shown in the **ITDETECTSTATUS** log.

The ITDETECTCONFIG and ITDETECTCONFIG_1 commands use the same message ID.

Enabling interference detection on both antennas slows down interference detection. In most installations, the primary and secondary antennas will be impacted by the same interference signal. Therefore, enabling interference detection on both antennas will slow down detection and may provide only limited benefits.

Message ID: 2143

Abbreviated ASCII syntax:

```
ITDETECTCONFIG RFPath [reserved1] [reserved2] [reserved3]
```

Factory default:

```
ITDETECTCONFIG all
```

ASCII example:

```
ITDETECTCONFIG L1
ITDETECTCONFIG none
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ITDETECTCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	RFPath	See *Table 48: RF path selection* on the next page		RF path selected for detection. By default, all paths are turned on. The receiver will cycle through all active paths.	Enum	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	reserved1	0		Reserved parameter	Ulong	4	H+4
4	reserved2	0		Reserved parameter	Ulong	4	H+8
5	reserved3	0		Reserved parameter	Ulong	4	H+12

Table 48: RF path selection

Binary	ASCII	Description
0	NONE	Turn off detection on all paths
1	ALL	Turn on detection on all paths (cycle through all active paths)
2	L1	Turn on detection only on L1 path
3	L2	Turn on detection only on L2 path
4	L5	Turn on detection only on L5 path

Table 49: RF paths for OEM7 receivers

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, SMART2	OEM7600
L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1 LBand	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1
L2	GPS L2 GLONASS L2 Galileo E6 BDS B3 QZSS L2/L6	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5
L5	GPS L5 GLONASS L3 Galileo E5 BDS B2 QZSS L5 NavIC L5 SBAS L5			
LBAND	LBand	LBand		LBand

2.75 ITFRONTENDMODE

Configure the front end mode settings

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this command to configure the front end mode for the L1, L2 and L5 RF paths to use the default third-order CIC mode or HDR (High Dynamic Range) mode. The HDR mode is used in an interference environment to obtain best interference rejection in general. However, the power consumption will increase in this mode.

For dual antenna receivers, an **ITFRONTENDMODE_1** command is used to configure the front end mode settings for only the second antenna. An **ITFRONTENDMODE** command configures the front end mode settings for only the primary antenna.

The ITFRONTENDMODE and ITFRONTENDMODE_1 commands use the same message ID.

This command is available only on some software models. Contact your NovAtel Sales representative (novatel.com/contactus/sales-offices) to obtain interference mitigation functionality.

Message ID: 2039

Abbreviated ASCII syntax:

```
ITFRONTENDMODE frequency mode
```

Factory default

```
ITFRONTENDMODE L1 cic3
ITFRONTENDMODE L2 cic3
ITFRONTENDMODE LBAND cic3
ITFRONTENDMODE L5 cic3
```

ASCII example:

```
ITFRONTENDMODE L1 hdr
```

On the OEM7500, the default mode for all frequency bands is HDR.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ITFRONTENDMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	frequency	See *Table 50: Frequency bands* below		Set the frequency band for adjustment	Enum	4	H
3	mode	See *Table 51: Mode* below		Select the desired mode	Enum	4	H+4

Table 50: Frequency bands

Binary	ASCII	Description
2	L1	Selects the L1 frequency
3	L2	Selects the L2 frequency
4	LBAND	Selects the L-band frequency
5	L5	Selects the L5 frequency

Table 51: Mode

Binary	ASCII	Description
0	CIC3	3rd order CIC (CIC3) mode (default)
1	HDR	High Dynamic Range (HDR) mode

Table 52: RF paths for OEM7 receivers

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, SMART2	OEM7600
L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1 LBand	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1
L2	GPS L2 GLONASS L2 Galileo E6 BDS B3 QZSS L2/L6	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, SMART2	OEM7600
L5	GPS L5 GLONASS L3 Galileo E5 BDS B2 QZSS L5 NavIC L5 SBAS L5			
LBAND	LBand	LBand		LBand

2.76 ITPROGFILTCONFIG

Enable and configure filtering on the receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this command to set the programmable filter to be either a notch filter or a bandpass filter to mitigate interference in the pass band of GNSS signals. The notch filter is used to attenuate a very narrow band of frequencies (specified by the notch width) around the configured centre frequency.

The bandpass filter is symmetrical in nature, which means that specifying one cutoff frequency will apply a cutoff on both the low side and high side of the spectrum c entre frequency.

The **ITPROGFILTBANK** log (see page 695) provides information on the allowable configuration settings for the programmable filter (i.e. the allowable settings for the notch filter and bandpass filter) for each frequency band. Only one filter can be applied for each frequency.

For dual antenna receivers, an **ITPROGFILTCONFIG_1** command is used to enable a filter on the signal received from only the second antenna. An **ITPROGFILTCONFIG** command enables a filter on the signal received from only the primary antenna.

The ITPROGFILTCONFIG and ITPROGFILTCONFIG_1 commands use the same message ID.

FW 7.09

When applying a filter to a signal using the MEC correlator, a brief interruption in tracking may occur on affected channels.

FW 7.10

The MEC correlator is not available on firmware 7.10.xx.

This command is not available for L-band.

This command is available only on some software models. Contact your NovAtel Sales representative (novatel.com/contactus/sales-offices) to obtain interference mitigation functionality.

For more details on recommended filter placement to ensure optimal performance, refer to *3.93 ITFILTTABLE* on page 690.

Users can activate digital filters in either HDR or CIC3 mode. For optimal performance, HDR mode is recommended. However, HDR mode results in increased power consumption.

Message ID: 2000

Abbreviated ASCII syntax:

```
ITPROGFILTCONFIG frequency filterid switch [filtermode] [cutofffreq]
[notchwidth]
```

ASCII example:

```
ITPROGFILTCONFIG gpsl1 pf0 enable notchfilter 1580 1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ITPROGFILTCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	frequency	See *Table 56: Frequency types* on page 241		Set the frequency band on which to apply the filter	Enum	4	H
3	filterid	See *Table 53: Programmable filter ID* below		Select the filter ID to use	Enum	4	H+4
4	switch	DISABLE	0	Disable the filter	Enum	4	H+8
		ENABLE	1	Enable the filter			
5	filtermode	See *Table 54: Programmable filter mode* on the next page		Configure the type of filter to use (default = NONE)	Enum	4	H+12
6	cutofffreq			Centre frequency for notch filter or cut off frequency for bandpass filter (MHz). Refer to **ITPROGFILTBANK** log (see page 695) for the allowable values. (default = 0)	Float	4	H+16
7	notchwidth			Notch width (MHz). Refer to **ITPROGFILTBANK** log (see page 695) for the allowable values. (default = 0)	Float	4	H+20

Table 53: Programmable filter ID

Binary	ASCII	Description
0	PF0	Programmable Filter 0
1	PF1	Programmable Filter 1

Table 54: Programmable filter mode

Binary	ASCII	Description
0	NOTCHFILTER	Configure the filter as a notch filter
1	BANDPASSFILTER	Configure the filter as a bandpass filter
2	NONE	Turn off filter If the switch parameter is set to ENABLED while the filtermode parameter is set to NONE, the system will return a parameter out of range message.

2.77 ITSPECTRALANALYSIS

Enable and configure spectral analysis on receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this command to view the spectrum in a range of frequencies. The **ITSPECTRALANALYSIS** command enables and configures the spectral analysis. The spectrum is viewed by plotting the PSD samples in the **ITPSDFINAL** log (see page 701).

Decreasing the update period or increasing the FFT size will impact receiver idle time. The idle time should be monitored to prevent adverse effects on receiver performance.

Due to the high volume of data, a higher bandwidth medium, such as USB or Ethernet, is recommended when monitoring signals using the Interference Toolkit.

For dual antenna receivers, an **ITSPECTRALANALYSIS_1** command is used to enable and configure spectral analysis on only the second antenna. An **ITSPECTRALANALYSIS** command enables and configures spectral analysis on only the primary antenna.

The ITSPECTRALANALYSIS and ITSPECTRALANALYSIS_1 commands use the same message ID.

Message ID: 1967

Abbreviated ASCII syntax:

```
ITSPECTRALANALYSIS mode [frequency] [updateperiod] [FFTsize] [timeavg]
[integration_window]
```

Factory default:

```
ITSPECTRALANALYSIS off
```

ASCII example:

```
ITSPECTRALANALYSIS predecimation gps1 500 1K 20 1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ITSPECTRALANALYSIS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	mode	See *Table 55: Data sources for PSD samples* below		Set the view mode.	Enum	4	H
3	frequency	See *Table 56: Frequency types* on the next page		Set the frequency band to view.	Enum	4	H+4
4	updateperiod	50 to 100000		The spectrum update rate in milliseconds. The update period is limited by the FFT size chosen. For 32k the minimum update period is 100 ms and for 64k the minimum update period is 200 ms. (default = 1000)	Ulong	4	H+8
5	FFTsize	See *Table 57: FFT sizes* on page 242		The frequency resolution of the spectrum. (default = 1k)	Enum	4	H+12
6	timeavg	0 to 50		Time averaging window in seconds. 0 means no time averaging. (default = 10)	Ulong	4	H+16
7	integration window	1 to 1024		The integration window size of FFT samples. 1 means no integration. (default = 5)	Ulong	4	H+20

Table 55: Data sources for PSD samples

Binary	ASCII	Description
0	OFF	Disable spectral analysis
1	PREDECIMATION	Perform spectrum analysis on the pre-decimated spectrum. This can be used to see a wide view of the spectrum for an RF path (L1, L2 or L5).
2	POSTDECIMATION	Perform spectrum analysis on the post-decimated spectrum. This is narrower than pre-decimation and is used to see the spectrum for a given signal.
3	POSTFILTER	Perform spectrum analysis on the post-filtered spectrum. This can be used when either bandpass or notch filters have been enabled to see the spectrum after the filters are applied.

The post-filter spectrum is not available for the Galileo AltBOC frequency. Only the pre-decimation and post-decimation spectrums are available for Galileo AltBOC.

Table 56: Frequency types

Binary	ASCII	Description
0	GPSL1	GPS L1 frequency
1	GPSL2	GPS L2 frequency
2	GLONASSL1	GLONASS L1 frequency
3	GLONASSL2	GLONASS L2 frequency
4	Reserved	
5	GPSL5	GPS L5 frequency
6[1]	LBAND	Inmarsat L-Band frequency
7	GALILEOE1	Galileo E1 frequency
8	GALILEOE5A	Galileo E5A frequency
9	GALILEOE5B	Galileo E5B frequency
10	GALILEOALTBOC	Galileo AltBOC frequency
11	BEIDOUB1	BeiDou B1 frequency
12	BEIDOUB2	BeiDou B2I frequency
13	QZSSL1	QZSS L1 frequency
14	QZSSL2	QZSS L2 frequency
15	QZSSL5	QZSS L5 frequency
16	QZSSL6	QZSS L6 frequency
17	GALILEOE6	Galileo E6 frequency
18	BEIDOUB3	BeiDou B3 frequency
19	GLONASSL3	GLONASS L3 frequency
20	NAVICL5	NavIC L5 frequency
21	BEIDOUB1C	BeiDou B1C frequency
22	BEIDOUB2A	BeiDou B2a frequency
23	BEIDOUB2B	BeiDou B2b frequency

1. Must first enable L-band using the ASSIGNLBANDBEAM command.

Table 57: FFT sizes

Binary	ASCII	Description
0	1K	1K FFT, 1024 samples
1	2K	2K FFT, 2048 samples
2	4K	4K FFT, 4096 samples
3	8K	8K FFT, 8192 samples
4	16K	16K FFT, 16384 samples
5	32K	32K FFT, 32768 samples
6	64K	64K FFT, 65536 samples



The 64k FFT is not available in post-decimation or post-filter modes.

2.78 ITWARNINGCONFIG

Configure the sensitivity level for the Jammer Detected bit

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command is used to configure the sensitivity level for setting the Jammer Detected bit in the Receiver Status word in the **RXSTATUS** log (see page 917). Warning level 0 is the most sensitive, while level 3 is the least sensitive. Warning level 0 means the Jammer Detected bit can be set even when minor interference is detected. By default, the warning level is set at 3.



On dual antenna receivers (OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2 and CPT7), the **ITWARNINGCONFIG** setting applies to both antenna inputs.

Message ID: 2289

Abbreviated ASCII syntax

```
ITWARNINGCONFIG WarningLevel [Reserved]
```

Factory default:

```
ITWARNINGCONFIG 3
```

ASCII example:

```
ITWARNINGCONFIG 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	ITWARNINGCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	WarningLevel	0		Detection warning sensitivity level 0 = most sensitive 3 = least sensitive	Ulong	4	H
		1					
		2					
		3					
3	Reserved	0		Reserved	Ulong	4	H+4

2.79 J1939CONFIG

Configure CAN network-level parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to configure the CAN J1939 network-level parameters (NAME, etc).

Issuing this command may initiate a CAN 'Address Claim' procedure. The status of the node and address claim are reported in the **J1939STATUS** log (see page 705).

Once a "node" is configured using **J1939CONFIG**, and the "port" is configured to ON using CANCONFIG "port" ON, J1939CONFIG "node" cannot be entered again until the "port" is configured to "OFF" using CANCONFIG "port" OFF. (See the **CANCONFIG** command on page 112

Message ID: 1903

Abbreviated ASCII syntax:

```
J1939CONFIG node port [pref_addr [alt_addr_range_start] [alt_addr_range_end]
[mfgcode] [industry] [devclass] [devinstance] [func] [funcinstance]
[ECUinstance]]
```

Factory default:

```
J1939CONFIG NODE1 CAN1 1C 0 FD 305 2 0 0 23 0 0
J1939CONFIG NODE2 CAN2 1C 0 FD 305 2 0 0 23 0 0
```

ASCII example :

```
J1939CONFIG NODE1 CAN1 AA 0 FD 305 2 0 0 23 0 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	J1939CONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	node	NODE1	1	Identifies the J1939 Node (i.e., CAN NAME) SMART2 does not support NODE2.	Enum	4	H
		NODE2	2				
3	port	CAN1	1	Physical CAN port to use SMART2 does not support the CAN2 port.	Enum	4	H+4
		CAN2	2				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	pref_addr	0x0 - 0xFD		Preferred CAN address. The receiver attempts to claim this address (default = 0x0)	Ulong	4	H+8
5	alt_addr_ range_start	0x0 - 0xFD		When the pref_addr cannot be claimed, the receiver attempts to claim an address from this range. (default: 0x0)	Ulong	4	H+12
6	alt_addr_ range_end	0x0 - 0xFD		End of alternative address range. (default: 0xFD)	Ulong	4	H+16
7	mfgcode	0-2047		NAME: Manufacturer Code. Refer to ISO 11783-5. (default: 0)	Ulong	4	H+20
8	industry	0 - 7		NAME: Industry Group (default: 2)	Ulong	4	H+24
9	devclass	0 - 127		NAME: Device Class (default: 0)	Ulong	4	H+28
10	devinstance	0 - 15		NAME: Device Class Instance (default: 0)	Ulong	4	H+32
11	func	0 - 255		NAME: Function (default: 23)	Ulong	4	H+36
12	funcinstance	0 - 31		NAME: Function instance (default: 0)	Ulong	4	H+40
13	ECUinstance	0 - 7		NAME: ECU Instance (default: 0)	Ulong	4	H+44

Due to current limitations in the CAN stack, NODE1 can only be associated with CAN1 and NODE2 can only be associated with CAN2. A mismatch combination results in an 'invalid parameter' error.

Node statistics are reported in the **J1939STATUS** log (see page 705).

2.80 LOCKOUT

Prevents the receiver from using a satellite



The **LOCKOUT** command has been deprecated. To prevent the receiver from using a satellite in the solution computations, use the **LOCKOUTSATELLITE** command on the next page.

Message ID: 137

2.81 LOCKOUTSATELLITE

Prevents use of a satellite

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command locks a specified satellite out from being used in solution computations. This command only locks out single satellites and must be repeated for each satellite. See also the **UNLOCKOUTSATELLITE** command on page 450.

Message ID: 2415

Abbreviated ASCII syntax:

```
LOCKOUTSATELLITE system prn
```

ASCII example:

```
LOCKOUTSATELLITE gps 10
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	LOCKOUTSATELLITE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	system	See *Table 145: Satellite system* on page 676		The satellite system for the satellite being locked out.	Enum	4	H
3	prn	See *1.6.1 PRN numbers* on page 55		Unique identifier for the satellite being locked out.	Ulong	4	H+4

2.82 LOCKOUTSYSTEM

Prevents the receiver from using a system

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to prevent the receiver from using all satellites in a system in the solution computations.

The **LOCKOUTSYSTEM** command does not prevent the receiver from tracking an undesirable satellite.

This command must be repeated for each system to be locked out. See also the **UNLOCKOUTSYSTEM** command on page 451 and **UNLOCKOUTALL** command on page 449.

Message ID: 871

Abbreviated ASCII syntax:

```
LOCKOUTSYSTEM system
```

Factory defaults:

```
LOCKOUTSYSTEM sbas
LOCKOUTSYSTEM navic
```

The **LOCKOUTSYSTEM** command removes one or more systems from the solution while leaving other systems available.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	LOCKOUTSYSTEM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	system	See *Table 145: Satellite system* on page 676		A single satellite system to be locked out	Enum	4	H

2.83 LOG

Requests logs from the receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Many different types of data can be logged using different methods of triggering the log events. Every log element can be directed to any combination of the receiver's ports. The ontime trigger option requires the addition of the period parameter. See *Logs* on page 489 for further information and a complete list of data log structures. The LOG command tables in this section show the binary format followed by the ASCII command format.

The optional parameter [hold] prevents a log from being removed when the **UNLOGALL** command (see page 454), with its defaults, is issued. To remove a log which was invoked using the [hold] parameter requires the specific use of the **UNLOG** command (see page 452). To remove all logs that have the [hold] parameter, use the **UNLOGALL** command (see page 454) with the held field set to 1.

The [port] parameter is optional. If [port] is not specified, [port] is defaulted to the port that the command was received on.

1. The maximum number of logs the OEM7 family of receivers can handle at a time is 128 logs for firmware versions 7.10.xx and 7.09.xx or 80 logs for firmware versions prior to 7.09.00. If an attempt is made to log more than the maximum number of logs at a time, the receiver responds with an Insufficient Resources error. Note that **RXSTATUSEVENTA** logs are requested on most ports by default and these logs count against the maximum.
2. The user is cautioned that each log requested requires additional CPU time and memory buffer space. Too many logs may result in lost data and low CPU idle time. Receiver overload can be monitored using the idle-time field and buffer overload bits of the Receiver Status in any log header.
3. Only the **MARKPOS, MARK2POS, MARK3POS and MARK4POS** log (see page 720), **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** log (see page 723) and 'polled' log types are generated, on the fly, at the exact time of the mark. Synchronous and asynchronous logs output the most recently available data.
4. Use the ONNEW or ONALL trigger with the **MARKPOS, MARK2POS, MARK3POS and MARK4POS** log (see page 720) and **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** log (see page 723).
5. Polled log types do not all allow fractional offsets.
6. If ONTIME trigger is used with asynchronous logs, the time stamp in the log does not necessarily represent the time the data was generated but rather the time when the log is transmitted.
7. Published logs are not placed in a queue if there is no physical or virtual connection when the log is generated. Thus, a log requested ONNEW, ONCHANGED or ONALL that is in SAVECONFIG may not be received if it is published before connections are made. This can happen if there's no cable connected or if the communication protocol has not been established yet (e.g. CAN, Ethernet, USB, etc).
8. PwrPak7M variants do not support the FILE port.

Message ID: 1

Abbreviated ASCII syntax:

```
LOG [port] message ONNEW
LOG [port] message ONCHANGED
LOG [port] message ONTIME period [offset [hold]]
LOG [port] message ONNEXT
LOG [port] message ONCE
LOG [port] message ONMARK
```

Factory default:

```
LOG COM1 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG COM2 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG COM3 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG USB1 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG USB2 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG USB3 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM1 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM2 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM3 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM4 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM5 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM6 RXSTATUSEVENTA ONNEW 0 0 HOLD
LOG ICOM7 RXSTATUSEVENTA ONNEW 0 0 HOLD
```

Abbreviated ASCII example 1:

```
LOG COM1 BESTPOS ONTIME 7 0.5 HOLD
```

The above example shows **BESTPOS** logging to com port 1 at 7 second intervals and offset by 0.5 seconds (output at 0.5, 7.5, 14.5 seconds and so on). The [hold] parameter is set so that logging is not disrupted by the **UNLOGALL** command (see page 454).

To send a log once, the trigger option can be omitted.

Abbreviated ASCII example 2:

```
LOG COM1 BESTPOS ONCE
```

Using NovAtel Application Suite, there are two ways to initiate data logging from the receiver's serial ports. Either enter the **LOG** command in the *Terminal* window or use the interface provided in the *Logging Configuration* window. Ensure the Power Settings on the computer are not set to go into Hibernate or Standby modes. Data is lost if one of these modes occurs during a logging session.

2.83.1 Binary

Field	Field type	Binary value	Description	Format	Binary bytes	Binary offset
1	LOG (binary) header	See *Table 4: Binary message header structure* on page 40	This field contains the message header	-	H	0

Field	Field type	Binary value	Description	Format	Binary bytes	Binary offset
2	port	See *Table 5: Detailed port identifier* on page 42	Output port	Enum	4	H
3	message	Any valid message ID	Message ID of the log to output	Ushort	2	H+4
4	message type	Bits 0-4 = Measurement source[1] Bits 5-6 = Format 00 = Binary 01 = ASCII 10 = Abbreviated ASCII, NMEA 11 = Reserved Bit 7 = Response Bit (*Message responses* on page 52) 0 = Original Message 1 = Response Message	Message type of log	Char	1	H+6
5	Reserved			Char	1	H+7
6	trigger	See *Table 58: Log triggers* on page 253		Enum	4	H+8
7	period	Valid values for high rate logging are 0.01, 0.02, 0.05, 0.1, 0.2, 0.25 and 0.5. For logging slower than 1 Hz, any integer value is accepted. When logging ONCE, the corresponding period is 0.	Log period (for ONTIME trigger) in seconds If the value entered is lower than the minimum measurement period, the command will be rejected. Refer to Receiver Technical Specifications on the OEM7 Documentation Portal (docs.novatel.com/OEM7) for the maximum raw measurement rate to calculate the minimum period.	Double	8	H+12

1. Bits 0-4 are used to indicate the measurement source. For dual antenna receivers, if bit 0 is set, the log is from the secondary antenna.

Field	Field type	Binary value	Description	Format	Binary bytes	Binary offset
8	offset	Any positive integer value smaller than the period*	Offset for period (ONTIME trigger) in seconds. For example, to log data at 1 second after every minute, set the period to 60 and the offset to 1. * When supported by the message and the receiver software model's logging rate, these decimal values (and their multiples < 1.0), are also valid: 0.1, 0.2, 0.25 or 0.5	Double	8	H+20
9	hold	0 = NOHOLD	Allow log to be removed by the **UNLOGALL** command (see page 454) (default)	Enum	4	H+28
		1 = HOLD	Prevent log from being removed by the default **UNLOGALL** command (see page 454)			

2.83.2 ASCII

Field	Field name	ASCII value	Description	Format
1	LOG (ASCII) header	-	This field contains the command name or the message header depending on whether the command is abbreviated ASCII or ASCII respectively	-
2	port	*Table 5: Detailed port identifier* on page 42	Output port (default = THISPORT)	Enum
3	message	Any valid message name, with an optional A or B suffix	Message name of log to output	Char [ ]
4	trigger	See *Table 58: Log triggers* on the next page		Enum
5	period	Valid values for high rate logging are 0.01, 0.02, 0.05, 0.1, 0.2, 0.25 and 0.5. For logging slower than 1 Hz, any integer value is accepted. When logging ONCE, the corresponding period is 0.	Log period (for ONTIME trigger) in seconds (default = 0) If the value entered is lower than the minimum measurement period, the command will be rejected. Refer to Receiver Technical Specifications on the OEM7 Documentation Portal (docs.novatel.com/OEM7) for the maximum raw measurement rate to calculate the minimum period.	Double

Field	Field name	ASCII value	Description	Format
6	offset	Any positive integer value smaller than the period*	Offset for period (ONTIME trigger) in seconds (default = 0). For example, to log data at 1 second after every minute, set the period to 60 and the offset to 1. * When supported by the message and the receiver software model's logging rate, these decimal values (and their multiples < 1.0), are also valid: 0.1, 0.2, 0.25 or 0.5	Double
7	hold	NOHOLD	Allow log to be removed by the **UNLOGALL** command (see page 454) (default)	Enum
		HOLD	Prevent log from being removed by the default **UNLOGALL** command (see page 454)	

Table 58: Log triggers

Binary	ASCII	Description
0	ONNEW	Does not output the current message but outputs when the message is updated (not necessarily changed)
1	ONCHANGED	Outputs the current message and then continues to output when the message is changed
2	ONTIME	Output on a time interval
3	ONNEXT	Output only the next message
4	ONCE	Output only the current message (default). If no message is currently present, the next message is output when available.
5	ONMARK	Output when a pulse is detected on the mark 1 input, MK1I Refer to Receiver Technical Specifications on the OEM7 Documentation Portal (docs.novatel.com/OEM7) for more details on the MK1I pin. ONMARK only applies to MK1I. Events on MK2I (if available) do not trigger logs when ONMARK is used. Use the ONNEW trigger with the MARKTIME, MARK2TIME, MARKPOS or MARK2POS logs.* Once the 1PPS signal has hit a rising edge, for both MARKPOS and MARKTIME logs, a resolution of both measurements is 10 ns. As for the ONMARK trigger for other logs that measure latency, for example RANGE and POSITION logs such as BESTPOS, it takes typically 20-30 ms (50 ms maximum) for the logs to output information from the 1PPS signal. Latency is the time between the reception of the 1PPS pulse and the first byte of the associated log. See also the **MARKPOS, MARK2POS, MARK3POS and MARK4POS** log on page 720 and the **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** log on page 723.
6	ONALL	Outputs the current message and then continues to output when the message is updated (not necessarily changed).

2.84 LOGIN

Start a secure ICOM/SCOM connection to the receiver

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

When ICOM/SCOM ports have security enabled (see the **IPSERVICE** command on page 226), a session to the ICOM/SCOM port can be established but commands are refused until a valid **LOGIN** command is issued. Both the UserName and Password are required. The **LOGIN** command checks the supplied credentials against known UserNames/Passwords and determines if the login is successful or not. A successful login permits the secured ICOM/SCOM command interpreter to accept further commands and returns OK. An unsuccessful login does not release the secured ICOM/SCOM command interpreter and returns Login Failed.

The message `Login temporarily suspended` will be returned if an incorrect password is entered more than 5 times in a row and logins are suspended for 5 seconds after an incorrect password is entered. If an incorrect password is entered more than 10 times in a row, logins are suspended for 10 seconds after an incorrect password is entered.

The consecutive incorrect password count is accumulated across all ports and all commands that use the Admin password.

Entering a **LOGIN** command on any command port other than the ICOM/SCOM port has no effect, regardless of whether the UserName/Password is correct. In this case, the appropriate response (OK or Login Failed) is returned, but there is no effect on the command interpreter.

When security is enabled, access to the port is restricted unless a valid name and password are supplied. It does not mean there is data encryption enabled. Username is case-insensitive and password is case-sensitive.

Message ID: 1671

Abbreviated ASCII syntax:

```
LOGIN [commport] UserName Password
```

ASCII example:

```
LOGIN ADMIN ADMINPASSWORD
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	LOGIN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	commport	ICOM1	23	The ICOM or SCOM port to log into. This is an optional parameter. If no value is entered, logs in to the ICOM port currently being used. (default=THISPORT)	Enum	4	H
		ICOM2	24				
		ICOM3	25				
		ICOM4	29				
		ICOM5	46				
		ICOM6	47				
		ICOM7	48				
		SCOM1	49				
		SCOM2	50				
		SCOM3	51				
		SCOM4	52				
3	username			Provide the user name for the login command. The user name is not case sensitive.	String [32]	variable[1]	H+4
4	password			Provide the password for the user name. The password is case sensitive.	String [28]	variable[1]	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.85 LOGOUT

End a secure ICOM/SCOM session started using the LOGIN command

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

Use the **LOGOUT** command to sign out of an ICOM/SCOM connection after a user has successfully logged in using the **LOGIN** command. After the sending the **LOGOUT** command, the ICOM/SCOM connection will not accept further commands, other than a new LOGIN command. The session itself is not ended. This only applies to ICOM/SCOM ports that have had security enabled (see the **IPSERVICE** command on page 226).

Message ID: 1672

Abbreviated ASCII syntax:

```
LOGOUT [commport]
```

ASCII example:

```
LOGOUT
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	LOGOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	commport	ICOM1	23	The ICOM or SCOM port from which to log out. This is an optional parameter. If no value is entered, logs out from the ICOM/SCOM port currently being used.	Enum	4	H
		ICOM2	24				
		ICOM3	25				
		ICOM4	29				
		ICOM5	46				
		ICOM6	47				
		ICOM7	48				
		SCOM1	49				
		SCOM2	50				
		SCOM3	51				
		SCOM4	52				

2.86 LUA

Configure Lua interpreter

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this command to configure the execution of the Lua interpreter on the receiver. Scripts that appear within the **LUAFILELIST** log (see page 715) can be executed by the Lua interpreter.

Message ID: 2181

Abbreviated ASCII syntax:

```
LUA option [LuaInterpreterArguments]
```

Abbreviated ASCII example:

```
lua start "printarguments.lua 1 2 3 4 5"
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	LUA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	START	1	Start the Lua interpreter in the background. The file descriptors stdout, stdin and stderr will not be accessible outside the receiver.	Enum	4	H
		PROMPT	2	Start the Lua interpreter in interactive mode and connect stdout, stdio and stderr to the port on which the command was entered. The INTERFACEMODE of that port will be changed to LUA for both RX and TX.			
		STOP	3	Stop the Lua interpreter.			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	LuaInterpreter Arguments	STRING		String containing Lua interpreter options including the name of the script file to run and arguments to pass to the script. This string must be enclosed in quotes if it contains any spaces. String arguments within the field **must** be enclosed by single quotes.	String [400]	Variable	H+4

The format of the Lua Interpreter Arguments is as follows as adapted from the standard Lua 5.3 interpreter:

```
[options] [script [args]]
Available options are:
  -e stat  execute string 'stat'
  -i       enter interactive mode after executing 'script'.
           (This is added to the arguments when using the PROMPT option of the
           LUA command)
  -l name  require library 'name'
```

2.87 MAGVAR

Sets a magnetic variation correction

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The receiver computes directions referenced to True North (also known as geodetic north). The Magnetic Variation Correction command (MAGVAR) is used to navigate in agreement with magnetic compass bearings. The correction value entered here causes the "bearing" field of the navigate log to report bearing in degrees Magnetic. The receiver computes the magnetic variation correction when using the auto option. See *Figure 6: Illustration of magnetic variation and correction* below.

The receiver calculates values of magnetic variation for given values of latitude, longitude and time using the International Geomagnetic Reference Field (IGRF) 2020 spherical harmonic coefficients and IGRF time corrections to the harmonic coefficients. (IGRF-2020 is also referred to as IGRF-13.) The model is intended for use up to the year 2025. Furthermore, the receiver will compute for years beyond 2025, but accuracy may be further reduced depending on the behaviour of the magnetic pole.

Message ID: 180

Abbreviated ASCII syntax:

```
MAGVAR type [correction [std dev]]
```

Factory default:

```
MAGVAR correction 0 0
```


ASCII example 1:

```
MAGVAR AUTO
```

ASCII example 2:

```
MAGVAR CORRECTION 15 0
```

Figure 6: Illustration of magnetic variation and correction



Ref	Description
a	True Bearing
b	Local Magnetic Variation
c	Local Magnetic Variation Correction (Inverse of magnetic variation)
a + c	Magnetic Bearing
d	Heading: 50° True, 65° Magnetic
e	True North
f	Local Magnetic North

Magnetic North refers to the location of the Earth's Magnetic North Pole. Its position is constantly changing in various cycles over centuries, years and days. These rates of change vary and are not well understood. However, we are able to monitor the changes.

True North refers to the earth's spin axis, that is, at 90° north latitude or the location where the lines of longitude converge. The position of the spin axis does not vary with respect to the Earth.

The locations of these two poles do not coincide. Thus, a relationship is required between these two values for users to relate GNSS bearings to their compass bearings. This value is called the magnetic variation correction or declination.

GNSS does not determine where Magnetic North is nor do the satellites provide magnetic correction or declination values. However, OEM7 receivers store this information internally in look up tables so that when you specify that you want to navigate with respect to Magnetic North, this internal information is used. These values are also available from various information sources such as the United States Geological Survey (USGS). The USGS produces maps and has software which enables the determination of these correction values. By identifying your location (latitude and longitude), you can obtain the correction value. Refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	MAGVAR header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	type	AUTO	0	Use IGRF corrections	Enum	4	H
		CORRECTION	1	Use the correction supplied			
3	correction	± 180.0 degrees		Magnitude of correction (Required field if type = Correction)	Float	4	H+4
4	std_dev	± 180.0 degrees		Standard deviation of correction (default = 0)	Float	4	H+8

2.88 MARKCONTROL

Controls processing of mark inputs

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This command is used to control the processing of the mark inputs. Using this command, the mark inputs can be enabled or disabled, polarity can be changed and a time offset and guard against extraneous pulses can be added.

The MARKxPOS and MARKxTIME logs have their outputs (and extrapolated time tags) pushed into the future (relative to the mark input (MKI) event) by the amount entered into the time bias field. In almost all cases, this value is set to 0, which is also the default setting (see *MARKPOS, MARK2POS, MARK3POS and MARK4POS* on page 720 and *MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME* on page 723).

Message ID: 614

Abbreviated ASCII syntax:

```
MARKCONTROL signal [switch [polarity [timebias [timeguard]]]]
```


Factory default:

```
MARKCONTROL MARK1 ENABLE
MARKCONTROL MARK2 ENABLE
```

ASCII example:

```
MARKCONTROL MARK1 ENABLE NEGATIVE 50 100
```

Figure 7: TTL pulse polarity



If using an external device, such as a camera, connect the device to the receiver's I/O port. Use a cable that is compatible with both the receiver and the device. A MARKIN pulse can be a trigger from the device to the receiver. See also the **MARKPOS, MARK2POS, MARK3POS and MARK4POS** command on page 720 and the **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** command on page 723.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	MARKCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	signal	MARK1	0	Specifies which mark input the command should be applied to. Set to MARK1 for the Event1 input, MARK2 for Event2, MARK3 for Event3 and MARK4 for Event4. All of the mark inputs have 10 K pull-up resistors to 3.3 V and are leading edge triggered. MARK3 and MARK4 are available only on the OEM7600, OEM7700 and OEM7720.	Enum	4	H
		MARK2	1				
		MARK3	2				
		MARK4	3				
3	switch	DISABLE	0	Disables or enables processing of the mark input signal for the input specified. If DISABLE is selected, the mark input signal is ignored. (default = ENABLE)	Enum	4	H+4
		ENABLE	1				
4	polarity	NEGATIVE	0	Optional field to specify the polarity of the pulse to be received on the mark input. See *Figure 7: TTL pulse polarity* on the previous page for more information. (default= NEGATIVE)	Enum	4	H+8
		POSITIVE	1				
5	timebias	Any valid long value		Optional value to specify an offset, in nanoseconds, to be applied to the time the mark input pulse occurs. (default =0)	Long	4	H+12

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
6	timeguard	default: 4 minimum: 2 Any valid Ulong value larger than the receiver's minimum raw measurement period		Optional field to specify a time period, in milliseconds, during which subsequent pulses after an initial pulse are ignored. See Receiver Technical Specifications on the OEM7 Documentation Portal (docs.novatel.com/OEM7) for the maximum raw measurement rate to determine the minimum period. If the value entered is lower than the minimum measurement period, the value is ignored and the minimum period is used.	Ulong	4	H+16

2.89 MEDIAFORMAT

Format the media for PwrPak7

Platform: PwrPak7, CPT7, CPT7700

PwrPak7M variants do not support this command.

Formats the specified media as FAT32, using enclosure specific cluster size and other parameters.

Only the internal flash memory can be formatted.

Entering this command results in complete loss of all data stored on the media.

Entering this command initiates the format operation. An error is reported if formatting could not be initiated, for example due to the media being disconnected.

Formatting progress can be observed using the **FILESYSTEMSTATUS** log on page 588, which will report *BUSY*, followed by *MOUNTED*.

The receiver may reboot in the process.

Message ID: 2128

Abbreviated ASCII syntax:

```
MEDIAFORMAT MassStorage
```

Example:

```
MEDIAFORMAT INTERNAL_FLASH
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	MEDIAFORMAT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	MassStorage	INTERNAL_FLASH	4	Format the internal memory in the enclosure.	Enum	4	H

2.90 MODEL

Switches to a previously authorized model

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Software models determine which receiver features are authorized for use.

The **MODEL** command is used to switch the receiver between software models previously added through a dispatch message (see **DISPATCHSET** command on page 141) or with the **AUTH** command (see page 85). The available models are listed in the **VALIDMODELS** log (see page 1018).

The **MODEL** command saves the specified model as the selected permanent model and immediately resets the receiver. The specified model is applied on all subsequent starts. The selected permanent model applies outside subscription service periods, as shown in the **DISPATCHSCHEDULE** log on page 571, but is routinely replaced by the model specified by a service period.

The **DISPATCHSCHEDULE** log (see page 571) shows both the selected permanent model (applied when no service periods are active) and the active model. The **VERSION** log (see page 1023) shows the active model (which may differ from the selected permanent model). Use the **AUTHCODES** log (see page 498) to output a list of the auth-codes present on the receiver.

Using the MODEL command (or AUTH ADD) during an active service period will override the model and receiver features specified by the service period for the duration of that service period (see the DISPATCHSCHEDULE *receiver features* field). This may interfere with or even disable the subscribed service products. Use only if you understand the consequences.

Use MODEL SERVICEPERIOD to revert to the service period receiver features. The specified model will remain the selected permanent model for use when no service period is active.

If the **MODEL** command is used to switch to an expired model, the receiver will reset and enter into an error state. Switch to a valid model to continue.

For information about software models, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

NovAtel uses the term models to refer to and control different levels of functionality in the receiver firmware. For example, a receiver may be purchased with an L1 only capability and be easily upgraded at a later time to a more feature intensive model, like L1/L2 dual-frequency. All that is required to upgrade is an authorization code for the higher model and the **AUTH** command (see page 85). Reloading the firmware or returning the receiver for service to upgrade the model is not required. Upgrades are available from novatel.com/support.

Message ID: 22

Abbreviated ASCII syntax:

```
MODEL model
```

Input example:

```
MODEL DDNRNNTBN
MODEL SERVICEPERIOD
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	MODEL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	model	Max 16 character null-terminated string (including the null)		Name of the Model to set as the selected permanent model. Use the term **SERVICEPERIOD** for this field to revert to the service period model. **MODEL SERVICEPERIOD** is rejected with a `RESPONSE_NO_CURRENT_DISPATCH_SERVICE_PERIOD` response code if no service period is current.	String [max 16]	Variable[1]	H

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.91 MOVINGBASESTATION

Enables the use of a moving base station

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to enable or disable a receiver from transmitting corrections without a fixed position.

The moving base function allows you to obtain a centimetre level xyz baseline estimate when the base station and possibly the rover are moving. It is very similar to normal RTK, with one stationary base station and a moving rover (refer to Transmitting and Receiving Corrections in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual). The BSLNXYZ log is an asynchronous 'matched' log that can be logged with the onchanged trigger to provide an accurate baseline between the base and rover.

Due to the latency of the reference station position messages, the following logs are not recommended to be used when in moving baseline mode: BESTXYZ, GPGST, MARKPOS, MARK2POS, MATCHEDPOS, MATCHEDXYZ, RTKPOS and RTKXYZ. The position error of these logs could exceed 100 m, depending on the latency of the reference station position message. If a rover position is required during moving basestation mode, then PSRPOS is recommended.

The **MOVINGBASESTATION** command must be used to allow the base to transmit messages without a fixed position.

1. Use the PSRPOS position log at the rover. It provides the best accuracy and standard deviations when the MOVINGBASESTATION mode is enabled.
2. This command supports RTCM V3 operation.
3. RTCM V3 support includes GPS + GLONASS operation.

Message ID: 763

Abbreviated ASCII syntax:

```
MOVINGBASESTATION switch
```

Factory default:


```
MOVINGBASESTATION disable
```

ASCII example:

```
MOVINGBASESTATION ENABLE
```

Consider the case where there is a fixed base, an airplane flying with a moving base station near its front and a rover station at its tail end.
Corrections can be sent between the receivers in a ‘daisy chain’ effect, where the fixed base station sends corrections to the moving base station, which in turn can send corrections to the rover.

Figure 8: Moving base station ‘daisy chain’ effect



When using this method, the position type is only checked at the fixed base station. Moving base stations will continue to operate under any conditions.

This command is useful for moving base stations doing RTK positioning at sea. A rover station is used to map out local areas (for marking shipping lanes, hydrographic surveying and so on), while the base station resides on the control ship. The control ship may not move much (parked at sea), but there is a certain amount of movement due to the fact that it is floating in the ocean. By using the **MOVINGBASESTATION** command, the control ship is able to use RTK positioning and move to new survey sites.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	MOVINGBASESTATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Do not transmit corrections without a fixed position.	Enum	4	H
		ENABLE	1	Transmit corrections without a fixed position.			

2.92 NAVICECUTOFF

Sets elevation cut-off angle for NavIC satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command is used to set the elevation cut-off angle for tracked NavIC satellites. The receiver does not start automatically searching for a NavIC satellite until it rises above the cut-off angle (when satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they are manually assigned (see the **ASSIGN** command on page 77).

In either case, satellites below the NAVICECUTOFF angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle; it could be used in these situations:

- The antenna is at a high altitude, and thus can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Care must be taken when using **NAVICECUTOFF** command because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

Use the **ELEVATIONCUTOFF** command on page 157 to set the cut-off angle for all other systems.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

Message ID: 2134

Abbreviated ASCII syntax:

```
NAVICECUTOFF angle
```

Factory default:

```
NAVICECUTOFF 5.0
```

ASCII example:

```
NAVICECUTOFF 10.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	NAVICECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	angle	±90.0 degrees		Elevation cut-off angle relative to horizon	Float	4	H

2.93 NMEABEIDOUTALKER

Sets the NMEA BeiDou talker ID

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to alter the behaviour of the NMEA BeiDou talker ID. The default behaviour is to use the legacy BeiDou Talker ID of 'BD' to maintain backward compatibility.

Message ID: 2258

Abbreviated ASCII syntax:

```
NMEABEIDOUTALKER id
```

Factory default:

```
NMEABEIDOUTALKER BD
```

ASCII example:

```
NMEABEIDOUTALKER GB
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	NMEABEIDOUTALKER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	id	GB	0	Use the NMEA ID	Enum	4	H
		BD	1	Use the legacy ID			

2.94 NMEAFORMAT

Customize NMEA output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use the NMEAFORMAT command to customize the NMEA GPGGA and GPGGALONG output.

Modifying the NMEA output will make it not compliant with the NMEA standard.

Message ID: 1861

Abbreviated ASCII syntax:

```
NMEAFORMAT field format
```

Factory default:

```
NMEAFORMAT GGA_LATITUDE 9.4
NMEAFORMAT GGA_LONGITUDE 10.4
NMEAFORMAT GGA_ALTITUDE .2
NMEAFORMAT GGALONG_LATITUDE 12.7
NMEAFORMAT GGALONG_LONGITUDE 13.7
NMEAFORMAT GGALONG_ALTITUDE .3
```

Example:

The following settings increase the precision of the GPGGA latitude and longitude fields:

```
NMEAFORMAT GGA_LATITUDE 11.6
NMEAFORMAT GGA_LONGITUDE 12.6
```

The following settings decrease the precision of the GPGGALONG latitude and longitude fields:

```
NMEAFORMAT GGALONG_LATITUDE 11.6
NMEAFORMAT GGALONG_LONGITUDE 12.6
```

The following setting stops the undulation fields of the GPGGALONG log being filled, making a log like the GPGGARTK log that was in NovAtel's OEM6 firmware:

```
NMEAFORMAT GGALONG_UNDULATION !0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	NMEAFORMAT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	Field	GGA_ LATITUDE	0	GPGGA latitude field	Enum	4	H
		GGA_ LONGITUDE	1	GPGGA longitude field			
		GGA_ ALTITUDE	2	GPGGA altitude (height) field			
		GGA_ UNDULATION	3	GPGGA undulation field			
		GGALONG_ LATITUDE	10	GPGGALONG latitude field			
		GGALONG_ LONGITUDE	11	GPGGALONG longitude field			
		GGALONG_ ALTITUDE	12	GPGGALONG altitude (height) field			
		GGALONG_ UNDULATION	13	GPGGALONG undulation field			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	Format	Char[8]		The Format field has a syntax similar to the printf function commonly found in programming languages. The format is: !x.y Where: **y** is the number of digits to display after the decimal point **x** sets the minimum field width including the decimal point. X is optional if ! is not used. If the value requires fewer digits than x, leading zeros are added to the output. **!** forces the field width to x. ! is optional. If a value exceeds the permitted width, the value will be saturated. If ! is used, y must be less than x. Examples (GGA_ LATITUDE): .5 = 5106.98120 2.3 = 5106.981 7.1 = 05107.0 !7.2 = 5106.98 !7.3 = 999.999	Char[8]	8	H+4

2.95 NMEANUMERICSTATIONID

Convert NovAtel station ID to NMEA

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to convert the NovAtel alphanumeric station ID to the NMEA numeric reference station ID for PPP correction sources.



This command does not change the station IDs from NOVATELX RTK/DGPS positions.

Message ID: 2527

Abbreviated ASCII syntax:

```
NMEANUMERICSTATIONID switch
```

Factory default:

```
NMEANUMERICSTATIONID DISABLE
```

ASCII example:

```
NMEANUMERICSTATIONID ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	NUMERICSTATIONID header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	switch	DISABLE	0	Alphanumeric station ID is not converted to numeric ID.	Enum	4	H
		ENABLE	1	Alphanumeric station ID is converted to numeric ID			

Table 59: Station ID conversion table

Correction source	NovAtel ASCII character ID	NMEA reference station ID
TerraStar C and TerraStar C PRO	TSTR	0700
TerraStar X	TSX	0701
TerraStar L	TSTL	0702
Oceanix H	OCXH	0710

2.96 NMEATALKER

Sets the NMEA talker ID

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to alter the behaviour of the NMEA talker ID. The talker is the first 2 characters after the $ sign (e.g. $XXGST) in the log header of the NMEA logs. The logs affected by the **NMEATALKER** command are GPHDT, GPGLL, GPGRS, GPGSA, GPGST, GPGSV, GPRMC, and GPVTG.

On SPAN systems, the GPGGA position is always based on the position solution from the BESTPOS log which incorporate GNSS + INS solutions as well.

When **NMEATALKER** is set to **GP**, the NMEA messages include information only about the GPS satellites that have a 'GP' talker solution, even when the receiver is tracking multi-constellation and with SPAN enabled.

When **NMEATALKER** is set to **AUTO**, the NMEA Talker ID changes as per the constellations enabled on the receiver. When there is one constellation in the solution and SPAN is disabled, the NMEA Talker ID is output as: **GP** for GPS, **GL** for GLONASS, **GA** for Galileo, and **GB/BD** for BeiDou (see **NMEABEIDOUTALKER** command on page 271). If more than one constellation is in the solution, the NMEA Talker ID is output as **GN** with the exception of GPGSV.

With SPAN enabled, the logs change theirs IDs to **IN** in single and multi-constellation use cases, except the GPGSA, GPGRS, GPHDT logs, which report a **GN** talker ID, and GPGSV.

For the **GPGSV** message with a single constellation in the solution, the output is its respective talker ID. When it is a multi-constellation solution, multiple sentences are output with their respective talker IDs. For example, if both GPS and GLONASS satellites are in the solution, two different sentences with **GP** and **GL** are output.

Message ID: 861

Abbreviated ASCII syntax:

```
NMEATALKER id
```

Factory default:

```
NMEATALKER gp
```

ASCII example:

```
NMEATALKER auto
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	NMEATALKER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	ID	GP	0	GPS (GP) only	Enum	4	H
		AUTO	1	GPS, GLONASS, Galileo, BeiDou, NavIC and/or QZSS			

The NMEATALKER command only affects NMEA logs that are capable of a GPS output. For example, GLMLA is a GLONASS-only log and the output will always use the GL talker. *Table 60: NMEA talkers* below shows the NMEA logs and whether they use GPS (GP), GLONASS (GL), Galileo (GA), BeiDou (GB/BD), NavIC (GI), QZSS (GQ) or combined (GN) talkers with NMEATALKER AUTO.

Table 60: NMEA talkers

Log	Talker IDs
GLMLA	GL
GPALM	GP
GPGGA	GP
GPGLL	GA or GB/BD or GI or GL or GN or GP or GQ
GPGRS	GA or GB/BD or GI or GL or GN or GP or GQ
GPGSA	GA or GB/BD or GI or GL or GN or GP or GQ
GPGST	GA or GB/BD or GI or GL or GN or GP or GQ
GPGSV	GA or GB/BD or GI or GL or GP or GQ
GPRMB	GA or GB/BD or GI or GL or GN or GP or GQ
GPRMC	GA or GB/BD or GI or GL or GN or GP or GQ
GPVTG	GA or GB/BD or GI or GL or GN or GP or GQ
GPZDA	GP

Which BeiDou NMEA Talker ID, GB or BD, is used in NMEA logs is determined by the setting in the **NMEABEIDOUTALKER** command on page 271.

2.97 NMEAVERSION

Sets the NMEA version for output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to set the output version of NMEA messages.

Message ID: 1574

Abbreviated ASCII syntax:

```
NMEAVERSION Version
```

Factory defaults:

```
NMEAVERSION V31
```

ASCII example:

```
NMEAVERSION V41
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	NMEAVERSION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Version	V31	0	NMEA messages will be output in NMEA version 3.01 format.	Enum	4	H
		V41	1	NMEA messages will be output in NMEA version 4.11 format.			

2.98 NTRIPCONFIG

Configures NTRIP

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command sets up and configures NTRIP communication.

Message ID: 1249

Abbreviated ASCII syntax:

```
NTRIPCONFIG port type [protocol [endpoint [mountpoint [username [password
[bindinterface]]]]]]
```

Mountpoint, username and password are all set up on the caster.

Factory default:

```
NTRIPCONFIG ncom1 disabled
NTRIPCONFIG ncom2 disabled
NTRIPCONFIG ncom3 disabled
NTRIPCONFIG ncomX disabled
```

ASCII example:

```
NTRIPCONFIG ncom1 client v1 :2000 calg0
```

ASCII example (NTRIP client):

```
NTRIPCONFIG ncom1 client v2 192.168.1.100:2101 RTCM3 calgaryuser calgarypwd
```

ASCII example (NTRIP server):

```
NTRIPCONFIG ncom1 server v1 192.168.1.100:2101 RTCM3 "" casterpwd
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	NTRIPCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	NCOM1	26	Name of the port see *Table 34: Communications port identifiers* on page 153	Enum	4	H
		NCOM2	27				
		NCOM3	28				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	type	DISABLED	1	NTRIP type	Enum	4	H+4
		CLIENT	2				
		SERVER	3				
4	protocol	DISABLED	1	Protocol (default V1)	Enum	4	H+8
		V1	2				
		V2	3				
5	endpoint	Max 80 character string		Endpoint to wait on or to connect to where host is a hostname or IP address and port is the TCP/UDP port number (default = 80)	String [80]	variable[1]	H+12
6	mountpoint	Max 80 character string		Which mount point to use	String [80]	variable[1]	variable
7	user name	Max 30 character string		Login user name	String [30]	variable[1]	variable
8	password	Max 30 character string		Password	String [30]	variable[1]	variable
9	bindInterface	ALL (default)	1	Not supported. Set to *ALL* for future compatibility.	Enum	4	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.99 NTRIPSOURCETABLE

Set NTRIP caster endpoints

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command is used to set the NTRIP caster endpoints to be used for the **SOURCETABLE** log (see page 990).

Message ID: 1343

Abbreviated ASCII syntax:

```
NTRIPSOURCETABLE endpoint [reserved1] [reserved2]
```

Factory default:

```
NTRIPSOURCETABLE none
```

ASCII example:

```
NTRIPSOURCETABLE base.station.novatel.ca:1001
NTRIPSOURCETABLE 192.168.1.100:1001
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-		NTRIPSOURCETABLE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Endpoint	Max 80 character string		Endpoint, in format of host:port, to connect to where the host is a hostname or IP address and port is the TCP/IP port number	String [80]	variable[1]	H
3	Reserved1	Reserved		Reserved	Ulong	4	variable
4	Reserved2	Reserved		Reserved	Ulong	4	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.100 NVMRESTORE

Restores NVM data after an NVM failure

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to restore Non-Volatile Memory (NVM) data after a NVM Fail error. This failure is indicated by bit 15 of the receiver error word being set (see also **RXSTATUS** command on page 917 and **RXSTATUSEVENT** command on page 932). If corrupt NVM data is detected, the receiver remains in the error state and continues to flash an error code on the Status LED until the **NVMRESTORE** command is issued (refer to Built-In Status Tests in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for further explanation).

After entering the **NVMRESTORE** command and resetting the receiver, the communications link may have to be reestablished at a different baud rate from the previous connection.

Message ID: 197

Abbreviated ASCII syntax:

```
NVMRESTORE
```

The possibility of NVM failure is extremely remote, however, if it should occur it is likely that only a small part of the data is corrupt. This command is used to remove the corrupt data and restore the receiver to an operational state. The data lost could be the user configuration, almanac, model or other reserved information.

2.101 NVMUSERDATA

Write user data to NVM

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command writes the data provided in the data array to NVM. This data can be retrieved by issuing the command **LOG NVMUSERDATA**.

The user data is maintained through power cycles and a standard **FRESET** command (see page 192). To clear the user data, use the **FRESET USERDATA** command.



The user data may be deleted if the **NVMRESTORE** command (see page 282) is sent. NVMRESTORE should be used with caution and is meant for use only in the event of a NVM receiver error.

Message ID: 1970

Abbreviated ASCII syntax:

```
NVMUSERDATA #bytes data
```

Field	Field type	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	NVMUSERDATA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	#bytes	-	Number of bytes of data to follow	Ulong	4	H
3	data	-	User input data up to a maximum of 2000 bytes. Data is entered in hexadecimal values with no separators between the values. For example, 1a2b3c4e	Uchar	2000	H+4

2.102 OUTPUTDATUM

Choose the datum to output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to select the geodetic datum and co-ordinate epoch in which solutions are output. If not set, the factory default value is the service datum and service epoch.

For either a plate-fixed or earth-fixed output datum, using a fixed epoch will compensate for plate motion such that you get repeatable co-ordinates over time for a location. Compensation is controlled using the **TECTONICSCOMPENSATIONSOURCE** command on page 425 and reported by the **TECTONICSCOMPENSATION** log (see page 993). The **TECTONICSCOMPENSATION** log will warn when operating in a region where tectonics compensation may be imprecise.

In order for solutions to be transformed to the requested datum, the datum selected must be in the list of datums shown in the **GEODETICDATUMS** log (see page 614).

When the base station datum is "UNKNOWN", an RTK position solution cannot be transformed via the **OUTPUTDATUM** command.

To view the current datum, use the **BESTDATUMINFO** log (see page 524).

Message ID: 1144

Abbreviated ASCII syntax:

```
OUTPUTDATUM name epoch_option epoch
```

Factory default:

```
OUTPUTDATUM SERVICE SERVICE_EPOCH 0
```

ASCII example:

To output co-ordinates in NAD83(CSRS), 2018:

```
OUTPUTDATUM NAD83(CSRS) FIXED_EPOCH 2018.000
```

To output co-ordinates in ITRF2014, 2010.00:

```
OUTPUTDATUM ITRF2014 FIXED_EPOCH 2010.000
```

The **OUTPUTDATUM** command only accepts a non-zero epoch if the FIXED_EPOCH option is specified. The earliest fixed epoch must be greater than 1900.

Do not mix the OUTPUTDATUM command and the DATUM USER commands.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	OUTPUTDATUM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	name			The datum output.	Char[32]	variable	H
3	epoch_ option	See *Table 61: Epoch options* below		Epoch type to enter coordinates in.	Enum	4	variable
4	epoch	0 = unknown (default), else >1900.00		Co-ordinate epoch (decimal year). Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable

Table 61: Epoch options

Binary	ASCII	Description
0	SERVICE_EPOCH	Output coordinates in the epoch of the corrections (default)
1	FIXED_EPOCH	Output coordinates in the specified epoch
2	CURRENT_EPOCH	Output coordinates in the current epoch

2.103 PDPFILTER

Enables, disables or resets the PDP filter

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to enable, disable or reset the Pseudorange/Delta-Phase (PDP) filter. The main advantages of the PDP implementation are:

- Smooths a jumpy position
- Bridges outages in satellite coverage (the solution is degraded from normal but there is at least a reasonable solution without gaps)

Enable the PDP filter to output the PDP solution in the **BESTPOS** log (see page 527), **BESTVEL** log (see page 542) and *NMEA standard logs* on page 752.

Refer to PDP and GLIDE Configurations in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for information on configuring your receiver for PDP or GLIDE operation.

2.103.1 GLIDE position filter

GLIDE is a mode of the PDP filter that optimizes the position for consistency over time rather than absolute accuracy. This is ideal in clear sky conditions where the user needs a tight, smooth and consistent output. The GLIDE filter works best with SBAS. The PDP filter is smoother than a least squares solution but is still noisy in places. The GLIDE filter produces a very smooth solution with relative rather than absolute position accuracy. There should typically be less than 1 centimetre difference in error from epoch to epoch. GLIDE also works in single point and DGPS modes. See also the **PDPMODE** command on page 288 and the **PDPPOS** log on page 770, **PDPVEL** log on page 774 and **PDPXYZ** log on page 775.

Refer also to the application note APN-038: Pseudorange/Delta-Phase (PDP) and GLIDE Filters, available at novatel.com/support/support-materials/application-notes.

Message ID: 424

Abbreviated ASCII syntax:

```
PDPFILTER switch
```

Factory default:

```
PDPFILTER disable
```

ASCII example:

```
PDPFILTER enable
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PDPFILTER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disable the PDP filter.	Enum	4	H
		ENABLE	1	Enable the PDP filter.			
		RESET	2	Reset the PDP filter. A reset clears the filter memory so that the PDP filter can start over.			

2.104 PDPMODE

Selects the PDP mode and dynamics

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to select the mode and dynamics of the PDP filter.

The **PDPFILTER ENABLE** command (see the **PDPFILTER** command on page 286) must be entered before the **PDPMODE** command.

It is recommended that the ionotype be left at AUTO when using either normal mode PDP or GLIDE. See also the **SETIONOTYPE** command on page 400.

Message ID: 970

Abbreviated ASCII syntax:

```
PDPMODE mode dynamics
```

Factory default:

```
PDPMODE normal auto
```

ASCII example:

```
PDPMODE relative dynamic
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PDPMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	NORMAL	0	In RELATIVE or GLIDE mode, GLIDE performance is optimized to obtain a consistent error in latitude and longitude over time periods of 15 minutes or less, rather than to obtain the smallest absolute position error. See also *GLIDE position filter* on page 286 for GLIDE mode additional information. GLIDE mode is the same as RELATIVE mode.	Enum	4	H
		RELATIVE	1				
		GLIDE	3				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	dynamics	AUTO	0	Auto detect dynamics mode	Enum	4	H+4
		STATIC	1	Static mode			
		DYNAMIC	2	Dynamic mode			

2.105 PGNCONFIG

Configure NMEA2000 PGNs.

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to configure the PGNs of the proprietary NMEA 2000 fast-packet messages the OEM7 receivers produce.

The receiver must be reset after issuing a **SAVECONFIG** command (see page 367) for all the configuration changes to take affect.

Message ID: 1892

Abbreviated ASCII syntax:

```
PGNCONFIG message_id pgn priority
```

Factory default:

```
PGNCONFIG INSPVACMP 130816 7
PGNCONFIG INSPVASDCMP 130817 7
PGNCONFIG SYNCRELINSPVACMP 130819 7
```

ASCII example:

```
PGNCONFIG INSPVACMP 129500 3
```

This example sets the INSPVACMP message to PGN 129500 with priority 3.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	PGNCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	message_id	INSPVACMP	1889	NovAtel message ID	Ulong	4	H
		INSPVASDCMP	1890				
		SYNCRELINSPVACMP	2538				
3	pgn	0 to 4294967295		PGN to use for message_id	Ulong	4	H+4
4	priority	0 - 7		CAN priority to use	Uchar	1	H+8

2.106 $PMDT

Configure terrain compensation

Platform: SMART7-I, SMART7-W, SMART2-TB

Use this NMEA style command to configure the Terrain Compensation feature. The Terrain Compensation filter must be enabled using the **TILTCOMPENSATIONCONTROL** command (see page 431) for the Terrain Compensation feature to function.

The maximum antenna height allowed is 500 inches (12.7 metres).

The **TILTFILTER** command (see page 432) and **TILTZERO** command (see page 433) can also be used to configure the Terrain Compensation filter. Either method will successfully configure the Terrain Compensation feature, however only the single-stage zeroing procedure is supported with the **$PMDT** command. For best performance, two-stage zeroing using the **TILTZERO** command (see page 433) is recommended.

Message ID: 2308

Syntax

```
$PMDT,a,x,x,x,x.x*hh[CR][LF]
```

ASCII Example:

```
$PMDT,u,,1,1*78
```

Field	Structure	Description	Format	Symbol	Example
1	$PMDT	Command header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	$PMDT	$PMDT
2	function	The function to perform, where: l = Set level state u = Set/Get antenna height x = Save level and height values r = Clear the saved level and height values Required field.	Char	a	,u
3	reserved	Reserved field, leave empty.	–	x	,

Field	Structure	Description	Format	Symbol	Example
4	antenna height feet	Antenna height in feet. Will be combined with the *antenna height inches* field. Cannot be combined with the *antenna height metres* field.	Integer	x	,1
5	antenna height inches	Antenna height in inches. Will be combined with the *antenna height feet* field. Cannot be combined with the *antenna height metres* field.	Integer	x	,1
6	antenna height metres	Antenna height in metres. Cannot be combined with the *antenna height feet* and *antenna height inches* fields.	Float	x.x	,2.2
7	*hh	NMEA check sum.		*hh	*78
8	[CR][LF]	Sentence terminator.			[CR][LF]

For more information about configuring the Terrain Compensation feature using the $PMDT command, see Configuring Terrain Compensation using NMEA Command in the SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual.

2.107 POSAVE

Implements base station position averaging

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command implements position averaging for base stations. Position averaging continues for a specified number of hours or until the estimated averaged position error is within specified accuracy limits. Averaging stops when the time limit or the horizontal standard deviation limit or the vertical standard deviation limit is achieved. The current status of the position averaging can be found in the **AVEPOS** log on page 500. When averaging is complete, the **FIX POSITION** command is automatically invoked. See the **FIX** command on page 182.

If differential logging is initiated, then issue the **POSAVE** command followed by the **SAVECONFIG** command (see page 367). The receiver averages positions after every power on or reset. It then invokes the **FIX POSITION** command to enable it to send differential corrections.

The **AUTOSURVEY** command on page 89 provides improved options and control for position averaging and is recommended over the **POSAVE** command.

Message ID: 173

Abbreviated ASCII syntax:

```
POSAVE state [maxtime [maxhstd [maxvstd]]]
```

Factory default:

```
POSAVE off
```

ASCII example 1:

```
POSAVE on 24 1 2
```

ASCII Example 2:

```
POSAVE OFF
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	POSAVE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	state	ON	1	Enable position averaging	Enum	4	H
		OFF	0	Disable position averaging			
3	maxtime	0.01 - 100 hours		Maximum amount of time that positions are to be averaged (default=0.01)	Float	4	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	maxhstd	0 - 100 m		Desired horizontal standard deviation (default = 0.0)	Float	4	H+8
5	maxvstd	0 - 100 m		Desired vertical standard deviation (default = 0.0)	Float	4	H+12

The **POSAVE** command can be used to establish a new base station, in any form of survey or RTK data collection, by occupying a site and averaging the position until either a certain amount of time has passed or position accuracy has reached a user-specified level. User-specified requirements can be based on time or horizontal or vertical quality of precision.

2.108 POSTIMEOUT

Sets the position time out

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the time out value for the position calculation in seconds.

In position logs, for example **BESTPOS** log (see page 527) or **PSRPOS** log (see page 800), when the position time out expires, the Position Type field is set to NONE. Other field values in these logs remain populated with the last available position data. Also, the position is no longer used in conjunction with the almanac to determine what satellites are visible.

Message ID: 612

Abbreviated ASCII syntax:

```
POSTIMEOUT sec
```

Factory default:

```
POSTIMEOUT 600
```

ASCII example:

```
POSTIMEOUT 1200
```

When performing data collection in a highly dynamic environment (for example, urban canyons or in high speed operations), you can use **POSTIMEOUT** to prevent the receiver from outputting calculated positions that are too old. Use **POSTIMEOUT** to force the receiver position type to NONE. This ensures that the position information being used in the **BESTPOS** log (see page 527) or **PSRPOS** log (see page 800) is based on a recent calculation. All position calculations are then recalculated using the most recent satellite information.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	POSTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	sec	0-86400		Time out in seconds	Ulong	4	H

2.109 PPPBASICCONVERGEDCRITERIA

Configures decision for PPP Basic convergence

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **PPPBASICCONVERGEDCRITERIA** command sets the threshold that determines if the solution has converged for lower accuracy PPP solutions. These are the PPP solutions reported with the PPP_BASIC and PPP_BASIC_CONVERGING position types.

The convergence threshold for high-accuracy PPP solutions (reported with PPP and PPP_CONVERGING position types) is set using the **PPPCONVERGEDCRITERIA** command (see page 297).

Relaxing the convergence threshold shortens the time before a PPP solution is reported as converged. However, it does not alter solution behaviour. During the initial PPP solution period, the positions can have decimetre error variation. Only relax the convergence threshold if the application can tolerate higher solution variability.

Message ID: 1949

Abbreviated ASCII syntax:

```
PPPBASICCONVERGEDCRITERIA criteria tolerance
```

Factory default:

```
PPPBASICCONVERGEDCRITERIA horizontal_stddev 0.60
```

ASCII example:

```
PPPBASICCONVERGEDCRITERIA total_stddev 0.45
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPBASIC CONVERGED CRITERIA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Criteria	TOTAL_STDDEV	1	Use the total, 3D, standard deviation	Enum	4	H
		HORIZONTAL_STDDEV	2	Use the horizontal, 2D, standard deviation			
3	Tolerance			Tolerance (m)	Float	4	H+4

2.110 PPPCONVERGEDCRITERIA

Configures decision for PPP convergence

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **PPPCONVERGEDCRITERIA** command sets the threshold that determines if the solution has converged for high-accuracy PPP solutions. These are the PPP solutions reported with the PPP and PPP_CONVERGING position types.

The convergence threshold for lower accuracy PPP solutions (reported with PPP_BASIC and PPP_BASIC_CONVERGING position types) is set using the **PPPBASICCONVERGEDCRITERIA** command (see page 296).

Relaxing the convergence threshold shortens the time before a PPP solution is reported as converged. However, it does not alter solution behaviour. During the initial PPP solution period, the positions can have decimetre error variation. Only relax the convergence threshold if the application can tolerate higher solution variability.

Message ID: 1566

Abbreviated ASCII syntax:

```
PPPCONVERGEDCRITERIA criteria tolerance
```

Factory default:

```
PPPCONVERGEDCRITERIA horizontal_stddev 0.32
```

ASCII example:

```
PPPCONVERGEDCRITERIA total_stddev 0.15
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPCONVERGED CRITERIA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Criteria	TOTAL_STDDEV	1	Use the total, 3D, standard deviation	Enum	4	H
		HORIZONTAL_STDDEV	2	Use the horizontal, 2D, standard deviation			
3	Tolerance			Tolerance (m)	Float	4	H+4

2.111 PPPDYNAMICS

Sets the PPP dynamics mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command configures the dynamics assumed by the PPP filter. AUTO detects the antenna dynamics and adapts filter operation accordingly.



The automatic dynamics detection may be fooled by very slow, “creeping” motion, where the antenna consistently moves less than 2 cm/s. In such cases, the mode should explicitly be set to DYNAMIC.

Message ID: 1551

Abbreviated ASCII syntax:

```
PPPDYNAMICS mode
```

Factory default:

```
PPPDYNAMICS dynamic
```

ASCII example:

```
PPPDYNAMICS auto
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPDYNAMICS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Mode	AUTO	0	Automatically determines dynamics mode	Enum	4	H
		STATIC	1	Static mode			
		DYNAMIC	2	Dynamic mode			

2.112 PPPDYNAMICSEED

Seed the PPP filter in any platform motion state

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command enables seeding of the PPP engine regardless of the receiver motion state. Accurate seeds can be used to improve initial PPP convergence and re-convergence following signal outages.

The seed position given by the **PPPDYNAMICSEED** command must be in a datum consistent with the PPP corrections that are in use. For TerraStar corrections, the datum is ITRF2020. The dynamic seed's time must refer to receiver time and cannot be more than 15 seconds in the past. A valid PPP solution (the **PPPPOS** log (see page 780) solution status is SOL_COMPUTED) must have been computed for the same epoch as the seed in order for the seed to be used.

See the **PPPSEED** command on page 302 for stationary-only seeding and for other control over seeding.

Message ID: 2071

Abbreviated ASCII syntax:

```
PPPDYNAMICSEED week seconds latitude longitude height northing_std_dev
easting_std_dev height_std_dev [northing_easting_covariance] [northing_
height_covariance] [easting_height_covariance]
```

Example :

```
PPPDYNAMICSEED 1817 247603 51.2086442297 -113.9810263055 1071.859 0.02 0.02
0.04
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPDYNAMICSEED header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.		H	0
2	week	0-9999		GPS Week number	Ulong	4	H
3	seconds	0-604800		Number of seconds into GPS week	Ulong	4	H+4
4	latitude	±90		Latitude (degrees)	Double	8	H+8
5	longitude	±180		Longitude (degrees)	Double	8	H+16
6	height	> -2000.0		Ellipsoidal height (metres)	Double	8	H+24
7	northing_ std_dev			Northing standard deviation (metres)	Float	4	H+32
8	easting_ std_dev			Easting standard deviation (metres)	Float	4	H+36
9	height_std_ dev			Ellipsoidal height standard deviation (metres)	Float	4	H+40

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
10	northing_ easting_ covariance			Covariance between northing and easting components (metres)	Float	4	H+44
11	northing_ height_ covariance			Covariance between northing and height components (metres)	Float	4	H+48
12	easting_ height_ covariance			Covariance between easting and height components (metres)	Float	4	H+52

2.113 PPPRESET

Reset the PPP filter

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command resets the PPP filter. After a reset, the PPP filter is restored to its initial state and PPP convergence will start over.



If deletion of the NVM-saved PPP seed information is also required, then a **PPPSEED CLEAR** command must be applied before the PPPRESET command. See the **PPPSEED** command on the next page.

Message ID: 1542

Abbreviated ASCII syntax:

```
PPPRESET [Option]
```

ASCII example :

```
PPPRESET
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPRESET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	H	-	0
2	Option	FILTER	1	Reset the PPP filter. (default = FILTER)	Enum	4	H
		ALL	10	Reset the PPP filter and Corrections			

2.114 PPPSEED

Control the seeding of the PPP filter

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **PPPSEED** command controls the seeding of the PPP filter. Accurate position seeding can accelerate PPP convergence.

PPPSEED SET is used to explicitly specify a seed position. The seed position must be in a datum consistent with the PPP corrections that will be used. For TerraStar corrections, this is ITRF2020. The **PPPSEED SET** command can only be used to give seed positions for stationary platforms. If the platform is moving, use the **PPPDYNAMICSEED** command (see page 299).

Caution must be exercised when using **PPPSEED SET**. While a good seed position can accelerate convergence, a bad seed position hurts performance. In some cases, a bad seed can prevent a solution from ever converging to a correct position. In other cases, a bad seed might be rejected immediately. In still other cases, the filter might operate with it for a time period only to reject it later. In this case, the filter position is partially reset, with a corresponding discontinuity in the PPP position.

PPPSEED STORE and **RESTORE** are intended to simplify seeding in operations where the antenna does not move between power-down and power-up. For example, in agricultural operations a tractor might be stopped in a field at the end of a day and then re-started the next day in the same position. Before the receiver is powered-down, the current PPP position could be saved to NVM using the **PPPSEED STORE** command, and then that position applied as a seed after power-up using **PPPSEED RESTORE**.

PPPSEED AUTO automates the STORE and RESTORE process. When this option is used, the PPP filter automatically starts using the stopping position of the previous day. For this command to work, the **PPPDYNAMICS** command (see page 298) setting must be AUTO so that the receiver can determine when it is static, or the filter must explicitly be told it is static using **PPPDYNAMIC STATIC**. Additionally, in order for the receiver to recall the saved seed, the **PPPSEED AUTO** command should be saved to NVM using the **SAVECONFIG** command (see page 367).

When **PPPSEED** is in AUTO mode and a **PPPSEED STORE** command is issued, there must be a minimum half second pause before a **SAVECONFIG** command is issued. This ensures the configuration persists through a power cycle.

For more guidance on using position seeding, refer to APN-104 Position Seeding Guide and Recommendations.

Message ID: 1544

Abbreviated ASCII syntax:

```
PPPSEED option [latitude] [longitude] [height] [northing_std_dev] [easting_
std_dev] [height_std_dev]
```

ASCII example:

```
PPPSEED set 51.11635322441 -114.03819311672 1064.5458 0.05 0.05 0.05
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	PPPSEED header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	option	CLEAR	0	Delete any stored seed and disable automatic store and restore of PPP seed positions. Sets the PPPSEED state to CLEAR.	Enum	4	H
		SET	1	Immediately apply the specified coordinates as a seed position. Sets the PPPSEED state to MANUAL.			
		STORE	2	Store the current PPP position in NVM for use as a future seed. Sets the PPPSEED state to MANUAL.			
		RESTORE	3	Retrieve and apply a seed position if a position was previously saved in NVM via the STORE or AUTO options. Sets the PPPSEED state to MANUAL.			
		AUTO	4	Automatically store and restore PPP seed positions. Sets the PPPSEED state to AUTO.			
		MANUAL	5	Disable automatic store and restore of PPP seed positions. This option does not clear any saved positions. Sets the PPPSEED state to MANUAL.			
3	latitude	±90		Latitude (degrees)	Double	8	H+4
4	longitude	±180		Longitude (degrees)	Double	8	H+12
5	height	> -2000.0		Ellipsoidal height (metres)	Double	8	H+20

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
6	northing_ std_dev			Northing standard deviation (metres)	Float	4	H+28
7	easting_ std_dev			Easting standard deviation (metres)	Float	4	H+32
8	height_std_ dev			Ellipsoidal height standard deviation (metres)	Float	4	H+36
9	Reserved				Float	4	H+40

2.115 PPPSOURCE

Specifies the PPP correction source

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command determines what corrections the PPP filter can use.

PPPSOURCE NONE disables PPP output.

Message ID: 1707

Abbreviated ASCII syntax:

```
PPPSOURCE source
```

Factory default:

```
PPPSOURCE auto
```

ASCII example:

```
PPPSOURCE none
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPSOURCE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	source	NONE	0	Disable PPP output	Enum	4	H
		TERRASTAR	1	Only accept TerraStar PPP corrections			
		VERIPOS	2	Only accept Veripos PPP corrections			
		GALHAS	12	Only accept Galileo HAS PPP corrections FW 7.10 This option is only available of firmware 7.10.02 and greater.			
		AUTO	100	Automatically select and use the best corrections			

2.116 PPPTIMEOUT

Sets the maximum age of the PPP corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the maximum age of the corrections that can be used to generate a PPP solution.

By default, the delay is 360 seconds. If the received corrections are older than the delay time set, the receiver will not produce a PPP solution.

For example, if L-band tracking (which is providing us the PPP corrections) is lost for some reason, the receiver will continue generating a PPP solution using last available corrections until the age of corrections is older than the delay time. Note that using older corrections degrades the PPP solution quality.

Message ID: 1560

Abbreviated ASCII syntax:

```
PPPTIMEOUT delay
```

Factory default:

```
PPPTIMEOUT 360
```

ASCII example:

```
PPPTIMEOUT 120
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPPTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	delay	5 to 900 s		Maximum corrections age	Ulong	4	H

2.117 PPSCONTROL

Controls the PPS output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command provides a method for controlling the polarity, period and pulse width of the PPS output on the OEM7. The PPS output can also be disabled using this command.



This command is used to setup the PPS signal coming from the receiver. For example, to take measurements such as temperature or pressure, in synch with your GNSS data, the PPS signal can be used to trigger measurements in other devices.

The leading edge of the 1 PPS pulse is always the trigger/reference. For example:

```
PPSCONTROL ENABLE NEGATIVE
```

generates a normally high, active low pulse with the falling edge as the reference, while:

```
PPSCONTROL ENABLE POSITIVE
```

generates a normally low, active high pulse with the rising edge as the reference.

The pulse width is user-adjustable. The adjustable pulse width feature supports triggers/systems that need longer, or shorter, pulse widths than the default to register the pulse enabling a type of GPIO line for manipulation of external hardware control lines.

The switch states allow more control over disabling/enabling the PPS. The ENABLE_FINETIME switch prevents the PPS from being enabled until FINE or FINESTEERING time status has been reached. The ENABLE_FINETIME_MINUTEALIGN switch is similar to ENABLE_FINETIME with caveat that the PPS will still not be enabled until the start of the next 60 seconds (a 1 minute modulus) after FINE or FINESTEERING time status has been reached.



If the value of a field shared with PPSCONTROL2 is changed in PPSCONTROL, the value of that field is also changed in PPSCONTROL2. For example, if the polarity is changed using the PPSCONTROL command, the polarity is also changed in PPSCONTROL2 command.

Message ID: 613

Abbreviated ASCII syntax:

```
PPSCONTROL [switch [polarity [period [pulsewidth]]]]
```

Factory default:

```
PPSCONTROL enable negative 1.0 1000
```

ASCII example:

```
PPSCONTROL enable positive 0.5 2000
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPSCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disable the PPS	Enum	4	H
		ENABLE	1	Enable the PPS (default)			
		ENABLE_ FINETIME	2	Enable the PPS only when FINE or FINESTEERING time status has been reached			
		ENABLE_ FINETIME_ MINUTEALIGN	3	Enable the PPS only when FINE or FINESTEERING time status has been reached AND the start of the next 60 seconds (1 minute modulus) has occurred			
3	polarity	NEGATIVE	0	Optional field to specify the polarity of the pulse to be generated on the PPS output. See *Figure 7: TTL pulse polarity* on page 261 for more information (default= NEGATIVE)	Enum	4	H+4
		POSITIVE	1				
4	period	0.05, 0.1, 0.2, 0.25, 0.5, 1.0, 2.0, 3.0,...20.0		Optional field to specify the period of the pulse, in seconds (default=1.0)	Double	8	H+8
5	pulsewidth	Any positive value less than or equal to half the period		Optional field to specify the pulse width of the PPS signal in microseconds. This value should always be less than or equal to half the period. (default=1000)	Ulong	4	H+16

2.118 PPSCONTROL2

Controls polarity, period, pulse width and estimated error limit of the PPS output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **PPSCONTROL2** command provides a method for controlling the polarity, period, pulse width, and estimated error limit of the PPS output on the OEM7. The PPS output can also be disabled using this command.

This command is identical to the **PPSCONTROL** command (see page 307) with the addition of a new parameter that represents the Estimated Error Limit.



If the value of a field shared with PPSCONTROL is changed in PPSCONTROL2, the value of that field is also changed in PPSCONTROL. For example, if the polarity is changed using the PPSCONTROL2 command, the polarity is also changed in PPSCONTROL command.

The estimated error limit sets an allowable ± range for the clock offset. The PPS output is only enabled when the clock offset is within this range.

Message ID: 1740

Abbreviated ASCII syntax:

```
PPSCONTROL2 [switch [polarity [period [pulsewidth [estimatederrorlimit]]]]]
```

Factory default:

```
PPSCONTROL2 enable negative 1.0 1000 0
```

ASCII example:

```
PPSCONTROL2 enable_finetime positive 0.5 2000 10
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PPSCONTROL2 header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	switch	DISABLE	0	Disable the PPS	Enum	4	H
		ENABLE	1	Enable the PPS (default)			
		ENABLE_ FINETIME	2	Enable the PPS only when FINE or FINESTEERING time status has been reached			
		ENABLE_ FINETIME_ MINUTEALIGN	3	Enable the PPS only when FINE or FINESTEERING time status has been reached AND the start of the next 60 seconds (1 minute modulus) has occurred			
3	polarity	NEGATIVE	0	Optional field to specify the polarity of the pulse to be generated on the PPS output. See *Figure 7: TTL pulse polarity* on page 261 for more information (default = NEGATIVE).	Enum	4	H+4
		POSITIVE	1				
4	period	0.05, 0.1, 0.2, 0.25, 0.5, 1.0, 2.0, 3.0,...20.0		Optional field to specify the period of the pulse in seconds (default = 1.0).	Double	8	H+8
5	pulse width	Any value less than or equal to half the pulse period in microseconds.		Optional field to specify the pulse width of the PPS signal in microseconds. This value should always be less than or equal to half the period. (default = 1000).	Ulong	4	H+16
6	estimated error limit	0 to 2147483647 in nanoseconds		Optional field to specify the ± estimated error limit (in nanoseconds) for the clock offset (default = 0). The PPS output is only enabled when the clock offset is within this limit. An estimated error limit of 0 removes the estimated error limit restraint on the PPS.	Long	4	H+20

2.119 PRNMAPPING

Update the PRN mapping pairs used by the receiver for tracking QZSS L1 C/B signals

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700**

Firmware: **This command is available only on 7.10.02 and greater firmware.**

Use this command to update the PRN mapping pairs used by the receiver for the tracking of QZSS L1C/B signals. This command is used to set the associated L1 C/B PRN that differs from the main PRN used by the QZSS satellite for L1C/A, L1C, L2C, and L5.

The first element of each PRN mapping pair is the main PRN used by the satellite. For QZSS, the main PRN is used for QZSS L1C/A, L1C, L2C, and L5 signals. The second element of each PRN mapping pair is the secondary PRN that is mapped to the main PRN. This is the PRN that will only be used when tracking the entered signal type. For QZSS, this is the PRN used for QZSS L1C/B tracking. The receiver uses these pairs to identify QZSS satellites whose primary signal channels (QZSS L1C/A or L1C/B) are configured to track L1C/B signals.

This command is required to properly acquire and track QZSS L1C/B satellites. The number of PRN mapping pairs must be explicitly specified. The user entered PRN pairings are stored with a **SAVECONFIG** and cleared with a **FRESET** command. The current list of mapped QZSS PRN pairs can be viewed by logging this command using the **LOG** command.

For QZSS, if a main PRN is not mapped, i.e. no record of that PRN in the **PRNMAPPING** command, the firmware will only search for QZSS L1C/A on that satellite's primary signal channel and will not attempt to acquire L1 C/B. If a main PRN is mapped, the firmware uses the secondary PRN to acquire and track L1 C/B signals on the satellite's primary signal channel without attempting to acquire QZSS L1 C/A. A PRN pair mapping with the same value can be entered to identify a L1C/B satellite.

The **PRNMAPPING** command can be used to clear all default and user-defined QZSS L1C/B PRNMAPPING pairs and configure all QZSS primary signal channels to track QZSS L1 C/A (see *ASCII Example 2*).

This command is intended for advanced users and should only be used when the QZSS PRN mapping pairs have changed. Refer to the *QZSS Satellite Positioning, Navigation and Timing Service ICD* or the latest QZSS constellation Information before using this command.

Message ID: 2636

Abbreviated ASCII syntax:

```
PRNMAPPING SignalType NumberOfPairs MainPRN SecondaryPRN ...
```

Factory default:

```
PRNMAPPING QZSSL1CB 4 196 203 197 204 200 205 201 206
```

ASCII example 1:

```
PRNMAPPING QZSSL1CB 5 196 203 198 207 199 208 200 205 201 206
```

ASCII example 2:

```
PRNMAPPING QZSSL1CB 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	PRNMAPPING header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	SignalType	See *Table 62: Signal type* below.		Signal type	Enum	4	H
3	NumberOfPairs	0 - 10		Number of QZSS PRN pairs to store. Enter 0 to clear all mappings.	Ulong	4	H+4
4	MainPRN	193 - 202		The main PRN used by the satellite. For QZSS, this is the PRN used for L1C/A, L1C, L2C, and L5.	Ulong	4	H+8
5	SecondaryPRN	191 - 210		The PRN that is mapped to the main PRN in this pair. This is the PRN that will only be used when tracking the entered signal type. For QZSS, this PRN will be used to track QZSS L1C/B.	Ulong	4	H+12
6	Next PRN pair = H + 16 + (number of pairs x 8)						

Table 62: Signal type

ASCII	Binary	Description
QZSSL1CB	14754	QZSS L1 C/B-code

2.120 PROFILE

Profile in Non-Volatile Memory (NVM)

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to configure multiple profiles in the NVM at receiver startup. The output is in the **PROFILEINFO** log (see page 789).

Message ID: 1411

Abbreviated ASCII syntax:

```
PROFILE Option Name [command]
```

ASCII examples:

```
PROFILE create Base
PROFILE createelement Base “log com1 versiona”
PROFILE createelement Base “serialconfig com2 115200”
PROFILE createelement Base “log com2 rtcm1004 ontime 1”
PROFILE activate Base
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PROFILE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Option	Refer to *Table 63: Profile option* on the next page		Profile options	Enum	4	H
3	Name			Profile name	String [Max 20]	variable[1]	H+4
4	Command			Profile command	String [Max 200]	variable[1]	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

FW 7.10

Restrictions: for firmware 7.10.00

1. Supports up to a maximum of 9 profiles.
2. Supports up to a maximum of 128 commands per profile.
3. Supports up to a maximum of 200 characters long for each command.
4. Supports up to a maximum of 4064 characters for all commands in one profile.
5. Only one profile can be active at a given time.
6. If one of the profiles is activated, the **SAVECONFIG** functionality is disabled.
7. All profiles are deleted by a FRESET PROFILEINFO command (see the **FRESET** command on page 192).
8. The receiver resets after a profile is activated.
9. Some commands optionally accept a port parameter and will default to THISPORT if no port is provided (e.g. **LOG** command). Since the commands in a profile are not sent from a port THISPORT is undefined in this case. When adding such commands to a profile, be sure to specify the port for the command rather than letting the command use the default, which may result in incorrect behaviour.
10. Commands that lead to a reset of the receiver are rejected by the **PROFILE** command.

FW 7.09

Restrictions for 7.09.xx firmware versions.

1. Supports up to a maximum of 9 profiles.
2. Supports up to a maximum of 20 commands per profile.
3. Supports up to a maximum of 200 characters long for each command.
4. Supports up to a maximum of 1500 characters for all commands in one profile.
5. Only one profile can be active at a given time.
6. If one of the profiles is activated, the **SAVECONFIG** functionality is disabled.
7. All profiles are deleted by a FRESET PROFILEINFO command (see the **FRESET** command on page 192).
8. Some commands optionally accept a port parameter and will default to THISPORT if no port is provided (e.g. **LOG** command). Since the commands in a profile are not sent from a port THISPORT is undefined in this case. When adding such commands to a profile, be sure to specify the port for the command rather than letting the command use the default, which may result in incorrect behaviour.
9. Commands that lead to a reset of the receiver are rejected by the **PROFILE** command.

Table 63: Profile option

Binary	ASCII	Description
0	Reserved	
1	CREATE	Create a profile
2	DELETE	Delete an existing profile

Binary	ASCII	Description
3	CREATEELEMENT	Create an element in an existing profile
4	DELETEELEMENT	Delete an existing element in an existing profile
5	ACTIVATE	Activate an existing profile and reset the receiver
6	DEACTIVATE	Deactivate a running profile
7	RUN	Activate an existing profile immediately without a receiver reset. FW 7.09 RUN is not available on 7.09.xx firmware.

2.121 PSRDIFFSOURCE

Sets the pseudorange differential correction source

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command determines what differential corrections the PSR and PDP (GLIDE) filters can use.

Differential corrections can be generated from RTK corrections. **PSRDIFFSOURCE RTK** enables this, allowing the PSR and PDP solutions to benefit from RTK corrections. An RTK-capable model is not required for this capability.

PSRDIFFSOURCE NONE stops any corrections from being used; the PSR and PDP solutions will revert to being uncorrected.



All types except NONE may revert to SBAS (if enabled) or SINGLE position types.

Message ID: 493

Abbreviated ASCII syntax:

```
PSRDIFFSOURCE type [id]
```

Factory default:

```
PSRDIFFSOURCE AUTO ANY
```

ASCII examples:

1. Enable only SBAS:

```
PSRDIFFSOURCE SBAS
SBASCONTROL ENABLE AUTO
```

2. Enable differential from RTCM, with a fall-back to SBAS:

```
PSRDIFFSOURCE RTCM ANY
SBASCONTROL ENABLE AUTO
```

3. Disable all corrections:

```
PSRDIFFSOURCE NONE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PSRDIFFSOURCE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	type	See *Table 64: PSRDIFFSOURCE type* on the next page		Correction type	Enum	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	id	Char[4] or ANY		Base station ID (default = ANY)	Char[4]	8	H+4

Table 64: PSRDIFFSOURCE type

Binary	ASCII	Description
0	RTCM	Use RTCM version 2 corrections from the given ID if available or SBAS otherwise. RTCM ID: 0 ≤ RTCM ID ≤ 1023 **or** ANY to accept all IDs.
1	RTCA	Use RTCA corrections from the given ID if available or SBAS otherwise. RTCA ID: A four-character string containing only alpha (a-z) or numeric characters (0-9) **or** ANY to accept all IDs.
5	SBAS	Use SBAS corrections such as WAAS, EGNOS and MSAS in the region they are available and applicable to. There are regions that are not covered by any SBAS satellite and so the solution will revert to uncorrected. The ID is ignored for this correction type.
6	RTK	Use differential corrections that are generated from RTK corrections if available or SBAS otherwise. The correction type used is determined by the setting of the **RTKSOURCE** command (see page 349).
10	AUTO	Use any available correction source. If both differential and SBAS sources are available, differential will be preferred.
11	NONE	Disables all differential correction types. Solution will revert to uncorrected.

2.122 PSRDIFFSOURCETIMEOUT

Sets pseudorange differential correction source timeout

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

When multiple differential correction sources are available, this command allows the user to set a time in seconds, that the receiver will wait before switching to another differential source, if corrections from the original source are lost.

Message ID: 1449

Abbreviated ASCII syntax:

```
PSRDIFFSOURCETIMEOUT option [timeout]
```

Factory default:

```
PSRDIFFSOURCETIMEOUT AUTO
```

ASCII example:

```
PSRDIFFSOURCETIMEOUT auto
PSRDIFFSOURCETIMEOUT set 180
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PSRDIFFSOURCETIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	AUTO	1	Use AUTO or SET to set the time	Enum	4	H
		SET	2				
3	timeout	0 to 3600 sec		Specify the timeout (default=0)	Ulong	4	H+4

2.123 PSRDIFFTIMEOUT

Sets maximum age of pseudorange differential data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the maximum age of pseudorange differential correction data to use when operating as a rover station. Received pseudorange differential correction data, older than the specified time, is ignored. This time out period also applies to differential corrections generated from RTK corrections.

The RTCA Standard for scat-i stipulates that the maximum age of differential correction messages cannot be greater than 22 seconds. Therefore, for RTCA rover users, the recommended PSRDIFF delay setting is 22.

Message ID: 1450

Abbreviated ASCII syntax:

```
PSRDIFFTIMEOUT delay
```

Factory default:

```
PSRDIFFTIMEOUT 300
```

ASCII example:

```
PSRDIFFTIMEOUT 60
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	PRSDIFFTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	delay	2 to 1000 s		Maximum pseudorange differential age	Ulong	4	H

2.124 PTPMODE

Enable or disable the PTP clock

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

Use this command to enable or disable the Precision Time Protocol (PTP) clock and configure the receiver's mode of operation.

Message ID: 2460

Abbreviated ASCII syntax:

```
PTPMODE <ptp_mode>
```

Factory default:

```
PTPMODE DISABLE
```

ASCII example:

```
PTPMODE ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	PTPMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	ptp_mode	DISABLE	0	Disable the PTP clock module.	Enum	4	H
		ENABLE	3	Enable standard operating mode with PTP functionality.			
		ENABLE_FINETIME	4	PTP functionality is enabled only after the receiver obtains GNSS time (GPS reference time status is FINESTEERING). Until that time, the PTP functionality remains idle. If the receiver loses FINESTEERING, PTP functionality continues. The deferral of PTP start up, if it occurs, only happens when the feature is enabled.			

2.125 PTPPROFILE

Select a PTP configuration profile

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

Use this command to select one of the pre-configured PTP profiles.

Message ID: 2461

Abbreviated ASCII syntax:

```
PTPPROFILE <ptp_profile>
```

Factory default:

```
PTPPROFILE PTP_UDP
```

ASCII example:

```
PTPPROFILE PTP_ETH_PEER
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	PTPPROFILE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	ptp_profile	Refer to *Table 65: PTP profiles* below		PTP profile to use	Enum	4	H

Table 65: PTP profiles

Binary	ASCII	Description
0	PTP_UDP	FW 7.09 PTP Default: Multicast, UDP, E2E_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128 FW 7.10 PTP Default: Multicast, UDP, E2E_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128, 1Hz Mean E2E Delay Request Interval

Binary	ASCII	Description
1	PTP_UDP_PEER	FW 7.09 PTP Default: Multicast, UDP, P2P_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128 FW 7.10 PTP Default: Multicast, UDP, P2P_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128, 1Hz P2P Delay Request Interval
2	PTP_ETH	FW 7.09 PTP Default: Multicast, Ethernet, E2E_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128 FW 7.10 PTP Default: Multicast, Ethernet, E2E_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128, 1Hz Mean E2E Delay Request Interval
3	PTP_ETH_PEER	FW 7.09 PTP Default: Multicast, Ethernet, P2P_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128 FW 7.10 PTP Default: Multicast, Ethernet, P2P_DELAY_REQUEST, 1 Hz Sync, 1/2 Hz Announce, Default BMCA, Domain 0, Priority1 128, Priority2 128, 1Hz P2P Delay Request Interval
6	ITUT_G.8275.1_ETH	FW 7.09 ITU-T: Multicast, Ethernet, E2E_DELAY_REQUEST, 16 Hz Sync, 8 Hz Announce, ITUT_G.8275_BMCA, Domain 24, Priority1 128, Priority2 128 FW 7.10 ITU-T: Multicast, Ethernet, E2E_DELAY_REQUEST, 16 Hz Sync, 8 Hz Announce, ITUT_G.8275_BMCA, Domain 24, Priority1 128, Priority2 128, 16Hz Mean E2E Delay Request Interval This is a Telecom Grandmaster (T_GM) configuration
9	IEEE_802.1AS_ETH_PEER	gPTP: Multicast, IEEE_802.1AS, P2P_DELAY_REQUEST, 8 Hz Sync, 1 Hz Announce, IEEE_802.1AS_BMCA, Domain 0, Priority1 246, Priority2 248, 1Hz P2P Delay Request Interval FW 7.10 This profile is available only on firmware version 7.10.02 and greater.

2.126 PTPTIMESCALE

Select the time scale used for PTP

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

Use this command to set the time scale used for PTP. PTP time scale does not correct for leap seconds while UTC time scale corrects for leap seconds. Usually, PTP time scale is used in hardware time stamping mode, while UTC time scale is used in software or legacy time stamping mode.

If possible, both the PTP master and slave should use PTP time scale. Since there is no leap second adjustment, the PTP hardware clock does not need to adjust the time when a leap second happens.

Message ID: 2463

Abbreviated ASCII syntax:

```
PTPTIMESCALE <ptp_timescale>
```

Factory default:

```
PTPTIMESCALE PTP_TIME
```

ASCII example:

```
PTPTIMESCALE UTC_TIME
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	PTPTIMESCALE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	ptp_ timescale	PTP_ TIME	0	PTP time scale to use	Enum	4	H
		UTC_ TIME	1				

2.127 QZSSECUTOFF

Sets QZSS satellite elevation cutoff

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the elevation cut-off angle for tracked QZSS satellites. The receiver does not start automatically searching for a QZSS satellite until it rises above the cut-off angle (when satellite position is known). Tracked satellites that fall below the cut-off angle are no longer tracked unless they are manually assigned (see the **ASSIGN** command on page 77).

In either case, satellites below the QZSSECUTOFF angle are eliminated from the internal position and clock offset solution computations.

This command permits a negative cut-off angle; it could be used in these situations:

- The antenna is at a high altitude, and thus can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Care must be taken when using **QZSSECUTOFF** command because the signals from lower elevation satellites are travelling through more atmosphere and are therefore degraded. Use of satellites below 5 degrees is not recommended.

Use the **ELEVATIONCUTOFF** command (see page 157) to set the cut-off angle for any system.

For dual antenna receivers, this command applies to both the primary and secondary antennas.

Message ID: 1350

Abbreviated ASCII syntax:

```
QZSSECUTOFF angle
```

Factory default:

```
QZSSECUTOFF 5.0
```

ASCII example

```
QZSSECUTOFF 10.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	QZSSECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	angle	±90 degrees		Elevation cutoff angle relative to the horizon	Float	4	H

2.128 RADARCONFIG

Configure the emulated radar output

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to configure the Emulated Radar (ER) output.

The ER signal is output on the **VARF** or **EVENT_OUT1** pin of the receiver.

When **RADARCONFIG** is enabled, the **BESTVELTYPE** command (see page 109) mode is set to **DOPPLER**.

Message ID: 1878

Abbreviated ASCII syntax:

```
RADARCONFIG switch [freq_step [update_rate [resp_mode [threshold]]]]
```

Factory default:

```
radarconfig disable
```

ASCII example:

```
radarconfig enable 26.11 5hz 2 3.5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RADARCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disables radar emulation	Enum	4	H
		ENABLE	1	Enables radar emulation			
3	freq_step	10.06 16.32 26.11 28.12 34.80 36.11		Frequency step per kilometre per hour. (default = 36.11 Hz/kph)	Double	8	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	update_rate	1HZ	1	Rate at which the output frequency is adjusted (default = 10HZ)[1]	Enum	4	H+12
		2HZ	2				
		5HZ	3				
		10HZ	4				
		20HZ	5				
5	resp_mode	See *Table 66: Response modes* below		Specify how responsive radar emulation is to changes in velocity (Default = 500)[1]	Integer	4	H+16
6	threshold	2 to 50 kph		The speed threshold at which to switch between response mode 1000 and response mode 500. The threshold is only applicable when the response mode is set to 2. (default = 5 kph)	Double	8	H+20

Table 66: Response modes

Mode	Description
1	Immediate. This results in the lowest latency at the cost of higher noise.
2	Automatically switch between 1000 and 500 depending on speed. When speed is below the Threshold parameter, use Response Mode 500. Otherwise, use Response Mode 1000.
500	Signal is minimally smoothed resulting in low latency but increased noise.
1000	Output signal is smoothed over a smaller window resulting in less latency than 2000 and less noise than 500.
2000	Output signal is smoothed to reduce noise at the cost of higher latency.

1. The number of samples used for smoothing depends on both the update_rate and resp_mode parameters. For instance, if the update_rate is 5 Hz and the resp_mode is 2000 ms, the number of samples used will be 10.

2.129 RAIMMODE

Configures RAIM mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to configure Receiver Autonomous Integrity Monitoring (RAIM) operation. This command uses RTCA MOPS characteristics which defines the positioning accuracy requirements for airborne lateral navigation (LNAV) and vertical navigation (VNAV) at 3 stages of flight:

1. En route travel
2. Terminal (within range of air terminal)
3. Non-precision approach

In order to ensure that the required level of accuracy is available in these phases of flight, MOPS requires the computation of protection levels (HPL and VPL). MOPS has the following definitions that apply to NovAtel's RAIM feature:

Horizontal Protection Level (HPL) is a radius of the circle in the horizontal plane. Its centre is at the true position, that describes the region, assured to contain the indicated horizontal position. It is the horizontal region where the missed alert and false alert requirements are met using autonomous fault detection.

Vertical Protection Level (VPL) is half the length of the segment on the vertical axis. Its centre is at the true position, that describes the region, assured to contain the indicated vertical position when autonomous fault detection is used.

Horizontal Alert Limit (HAL) is a radius of the circle in the horizontal plane. Its centre is at the true position, that describes the region, required to contain the indicated horizontal position with the required probability.

Vertical Alert Limit (VAL) is half the length of the segment on the vertical axis. Its centre is at the true position, that describes the region, required to contain the indicated vertical position with certain probability.

Probability of False Alert (P_{fa}) is a false alert defined as the indication of a positioning failure, when a positioning failure has not occurred (as a result of false detection). A false alert would cause a navigation alert.

2.129.1 Detection strategy

NovAtel's RAIM detection strategy uses the weighted Least-Squares Detection (LSA) method. This method computes a solution using a LSA and is based on the sum of squares of weighted residuals. It is a comparison between a root sum of squares of residuals and a decision threshold to determine a pass/fail decision.

2.129.2 Isolation strategy

NovAtel RAIM uses the maximum residual method. Logically it is implemented as a second part of Fault Detection and Exclusion (FDE) algorithm for LSA detection method. Weighted LSA residuals are standardized individually and the largest residual is compared to a decision threshold. If it is more than the threshold, the observation corresponding to this residual is declared faulty.



The Detection strategy and Isolation strategy are used for all RAIM modes (USER, DEFAULT, APPROACH, TERMINAL and ENROUTE.

Message ID: 1285

Abbreviated ASCII syntax:

```
RAIMMODE mode [hal [val [pfa]]]
```

Factory default:

```
RAIMMODE default
```

Input example:

```
RAIMMODE user 100 100 0.01
RAIMMODE terminal
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RAIMMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	MODE	See *Table 67: RAIM mode types* below When the MODE is set to DEFAULT, protection levels are not calculated meaning that values for HAL and VAL are set to the maximum. When the MODE is set to USER, APPROACH, TERMINAL or ENROUTE, protection levels are calculated.			Enum	4	H
3	HAL	5 ≤ HAL ≤ 9999.99		Horizontal alert limit (m) (Default = 9999.99)	Double	8	H+4
4	VAL	5 ≤ VAL ≤ 9999.99		Vertical alert limit (m) (Default = 9999.99)	Double	8	H+12
5	PFA	$(P_{fa}) = 1e^{-7} \leq P_{fa} \leq 0.25$		Probability of false alert (Default = 0.001)	Double	8	H+20

Table 67: RAIM mode types

Binary	ASCII	Description
0	DISABLE	Do not do integrity monitoring of least squares solution
1	USER	User will specify alert limits and probability of false alert
2	DEFAULT	Use NovAtel RAIM (default)

Binary	ASCII	Description
3	APPROACH	Default numbers for non-precision approach navigation modes are used - HAL = 556 m (0.3 nm), VAL = 50 m for LNAV/VNAV
4	TERMINAL	Default numbers for terminal navigation mode are used - HAL = 1 nm, no VAL requirement
5	ENROUTE	Default numbers for enroute navigation mode are used - HAL = 2 nm, no VAL requirement

2.130 REFERENCESTATIONTIMEOUT

Sets timeout for removing previously stored base stations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command sets how long the receiver will retain RTK base station co-ordinates. Shorter durations might be required if the receiver is operating in a VRS RTK network that recycles base station IDs quickly.

Message ID: 2033

Abbreviated ASCII syntax:

```
REFERENCESTATIONTIMEOUT option [timeout]
```

Factory default:

```
REFERENCESTATIONTIMEOUT AUTO
```

ASCII example:

```
REFERENCESTATIONTIMEOUT SET 90
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	REFERENCESTATION TIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	AUTO	1	Sets the Timeout to 90 seconds[1] The Timeout field is optional for AUTO and has no effect	Enum	4	H
		SET	2	Must set the timeout value using the Timeout field 0 is not accepted when using the SET option			
3	timeout	1 to 3600 s		Specify the time	Ulong	4	H+4

1. This behaviour is subject to change.

2.131 RESET

Performs a hardware reset

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command performs a hardware reset. The receiver configuration reverts either to the factory default, if no user configuration was saved or the last **SAVECONFIG** settings. Refer to the **FRESET** command on page 192 and **SAVECONFIG** command on page 367.

The optional delay field is used to set the number of seconds the receiver is to wait before resetting.

Message ID: 18

Abbreviated ASCII syntax:

```
RESET [delay]
```

Input example

```
RESET 30
```

The **RESET** command can be used to erase any unsaved changes to the receiver configuration.

Unlike the **FRESET** command on page 192, the **RESET** command does not erase data stored in the NVM, such as Almanac and Ephemeris data.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RESET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	delay (0-60)			Seconds to wait before resetting (default = 0)	Ulong	4	H

2.132 RFINPUTGAIN

Configure the Calibrated Antenna Gain (CAG)

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to select the mode (AUTO or MANUAL) of setting the CAG for the purpose of interference detection.

If auto mode is used, the receiver will automatically compute the CAG at start up. In this case it is assumed that the receiver is powered up with its antenna connected and no interference is present.



If the antenna is changed, either reset the receiver or reissue this command to allow receiver to re-compute the CAG.

If manual mode is used, the CAG input by the user is used by the receiver to detect interference.

The CAG is defined to be the cascaded RF gain before receiver input plus LNA noise figure (NF), counting active antenna LNA gain, in-line amplifier, RF cable or distribution loss prior to receiver input connector.

A typical GNSS active antenna (of reasonable quality) has a noise figure of ~2dB (dominated by the LNA in an active antenna).

RFINPUTGAIN = Cascaded Gain before receiver + LNA NF



For advanced users.
If using this command in manual mode, the antenna gain must be accurately measured when the system is not experiencing any interference. If an erroneous CAG is injected, the interference detection performance can be degraded.

Message ID: 1658

Abbreviated ASCII syntax:

```
RFINPUTGAIN RFPath [mode] [CAG]
```

Factory default:

```
RFINPUTGAIN L1 AUTO
RFINPUTGAIN L2 AUTO
RFINPUTGAIN L5 AUTO
```

ASCII example:

```
RFINPUTGAIN L1 MANUAL 30
RFINPUTGAIN L2 30
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RFINPUTGAIN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	RFPath	L1	2	RF path selection	Enum	4	H
		L2	3				
		L5	5				
3	mode	AUTO	0	Calibrated Antenna Gain (CAG) mode. Default = MANUAL	Enum	4	H+4
		MANUAL	1				
4	CAG	0.0-100.0		Calibrated Antenna Gain value If the mode is MANUAL, a value for CAG must be entered.	Float	4	H+8

Table 68: RF paths for OEM7 receivers

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, SMART2	OEM7600
L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1 LBand	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1
L2	GPS L2 GLONASS L2 Galileo E6 BDS B3 QZSS L2/L6	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5
L5	GPS L5 GLONASS L3 Galileo E5 BDS B2 QZSS L5 NavIC L5 SBAS L5			
LBAND	LBand	LBand		LBand

2.133 RTKANTENNA

Specifies L1 phase centre (PC) or ARP and enables/disables phase centre modeling

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to specify whether to use L1 phase centre or Antenna Reference Point (ARP) positioning.

There is also an option to apply phase centre variation modelling. If there are any conditions that make a selected mode impossible, the solution status in the position log will indicate an error or warning.

L1 ARP offsets and L2 ARP offsets can be entered using the **BASEANTENNAPCO** command on page 92 and **THISANTENNAPCO** command on page 428. Phase centre variation parameters can be entered using the **BASEANTENNAPCV** command on page 94 and **THISANTENNAPCV** command on page 429.

Error states occur if either the rover does not have the necessary antenna information entered or the base is not sending sufficient information to work in the requested mode. An example of these error conditions is:

- Position reference to the ARP is requested but no rover antenna model is available

Message ID: 858

Abbreviated ASCII syntax:

```
RTKANTENNA posref pcv
```

Factory default:

```
RTKANTENNA unknown disable
```

ASCII example:

```
RTKANTENNA arp enable
```



This command is used for high precision RTK positioning allowing application of antenna offset and phase centre variation parameters.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKANTENNA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	posref	L1PC	0	L1 phase centre position reference	Enum	4	H
		ARP	1	ARP position reference			
		UNKNOWN	2	Unknown position reference			
3	pcv	DISABLE	0	Disable PCV modelling	Enum	4	H+4
		ENABLE	1	Enable PCV modelling			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	Reserved				Bool	4	H+8
5	Reserved				Bool	4	H+12

2.134 RTKASSIST

Enable or disable RTK ASSIST

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command enables or disables RTK ASSIST.

RTK ASSIST uses L-band-delivered corrections to enable RTK operation to continue for extended durations if RTK corrections are lost. In order to use RTK ASSIST, a receiver with L-band tracking capability and RTK ASSIST capability is needed. The duration of RTK ASSIST operation can be limited using the **RTKASSISTTIMEOUT** command (see page 338).

When active, RTK ASSIST is shown in the RTKPOS and BESTPOS extended solution status field (see *Table 99: Extended solution status* on page 534). The active status and further details on the RTK ASSIST status are available through the **RTKASSISTSTATUS** log on page 896.

For reliable RTK ASSIST performance, the RTK base station position must be within 1 metre of its true WGS84 position.

Message ID: 1985

Abbreviated ASCII syntax:

```
RTKASSIST switch
```

Factory default:

```
RTKASSIST enable
```

ASCII example:

```
RTKASSIST disable
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKASSIST header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disable RTK ASSIST	Enum	4	H
		ENABLE	1	Enable RTK ASSIST			

2.135 RTKASSISTTIMEOUT

Set the maximum RTK ASSIST duration

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets how long the receiver will report an RTK solution when RTK is being maintained by RTK ASSIST. The maximum permitted duration of RTK ASSIST operation is determined by the subscription and receiver model. Values less than the subscription limit can be set using the **RTKASSISTTIMEOUT** command.

When RTK ASSIST is active, the **RTKTIMEOUT** command is disregarded. The maximum time that RTK will continue past an RTK corrections outage is controlled by **RTKASSISTTIMEOUT**.

Message ID: 2003

Abbreviated ASCII syntax:

```
RTKASSISTTIMEOUT limit_type [limit_value]
```

Factory default:

```
RTKASSISTTIMEOUT SUBSCRIPTION_LIMIT
```

ASCII example:

```
RTKASSISTTIMEOUT USER_LIMIT 900
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKASSISTTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	limit_type	SUBSCRIPTION_LIMIT	0	Use maximum permitted duration limit.	Enum	4	H
		USER_LIMIT	1	The maximum RTK ASSIST duration is user set, up to the limit permitted by the subscription and model.			
3	limit_value			Time out value in seconds. Only valid for the USER_LIMIT Limit Type.	Ulong	4	H+4

2.136 RTKDYNAMICS

Sets the RTK dynamics mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to specify how the receiver looks at the data. There are three modes: STATIC, DYNAMIC and AUTO. The STATIC mode forces the RTK software to treat the rover station as though it were stationary.

DYNAMIC mode forces the software to treat the rover as though it were in motion. If the receiver is undergoing very slow, steady motion (<2.5 cm/s for more than 5 seconds), use DYNAMIC mode (as opposed to AUTO) to prevent inaccurate results and possible resets.

For reliable performance, the antenna should not move more than 1-2 cm when in STATIC mode.

Message ID: 183

Abbreviated ASCII syntax:

```
RTKDYNAMICS mode
```

Factory default:

```
RTKDYNAMICS dynamic
```

ASCII example:

```
RTKDYNAMICS static
```

Use the STATIC option to decrease the time required to fix ambiguities and reduce the amount of noise in the position solution. If STATIC mode is used when the antenna is not static, the receiver will have erroneous solutions and unnecessary RTK resets.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKDYNAMICS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	AUTO	0	Automatically determines dynamics mode	Enum	4	H
		STATIC	1	Static mode			
		DYNAMIC	2	Dynamic mode			

2.137 RTKINTEGERCRITERIA

Report inaccurate fixed-integer RTK positions with float solution type

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command forces a fixed-integer RTK position to be reported as float if the estimated solution standard deviation exceeds a threshold.

Normally, a fixed-integer solution is very accurate. However, in some rarely-occurring situations, even a fixed-integer solution can become inaccurate; for example, if the DOP is high due to satellites not being visible. In such cases, the accuracy of the RTK solution might be worse than what is customarily expected from a fixed-integer solution. The **RTKINTEGERCRITERIA** command changes the solution type of these high standard deviation integer solutions to their float equivalent. NARROW_INT, for instance, becomes NARROW_FLOAT. Depending on the GGAQUALITY command setting, this will also impact the NMEA GGA quality flag.

Message ID: 2070

Abbreviated ASCII syntax:

```
RTKINTEGERCRITERIA criteria threshold
```

Factory default:

```
RTKINTEGERCRITERIA TOTAL_STDDEV 1.0
```

ASCII example:

```
RTKINTEGERCRITERIA HORIZONTAL_STDDEV 0.25
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKINTEGER CRITERIA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	criteria	TOTAL_ STDDEV	1	Test the threshold against the estimated total, 3D, standard deviation	Enum	4	H
		HORIZONTAL_ STDDEV	2	Test the threshold against the estimated horizontal standard deviation			
3	threshold	0.01 m and higher		Estimated solution standard deviation (m) required for solution to be reported as integer	Float	4	H+4

2.138 RTKIONORESILIENCE

Sets the RTK ionospheric optimization mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Only advanced users should use this command.

This command is used to enable RTK optimizations and tuning specific to a mode of ionosphere that presents challenges to which the RTK solution needs to adapt.

Message ID: 2568

Abbreviated ASCII Syntax:

```
RTKIONORESILIENCE mode
```

Factory Default:

```
RTKIONORESILIENCE NORMAL
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	RTKIONORESILIENCE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Mode	NORMAL	0	Enables normal RTK ionosphere resilience.	Enum	4	H
		SCINTILLATION	1	Enables RTK ionosphere resilience for environments with scintillation. SCINTILLATION mode is used when the receiver is providing an RTK solution in an environment with an elevated level of ionosphere where scintillation is occurring.			

2.139 RTKMATCHEDTIMEOUT

Sets RTK filter reset time after corrections are lost

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the length of time the receiver continues to use the last RTK correction data once the corrections stop. Once this time is reached, the RTK filter is reset.

Message ID: 1447

Abbreviated ASCII syntax:

```
RTKMATCHEDTIMEOUT timeout
```

ASCII example:

```
RTKMATCHEDTIMEOUT 180
```

Factory default

```
RTKMATCHEDTIMEOUT 300
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKMATCHEDTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	timeout	1 to 3600 s		Time out period	Ulong	4	H

2.140 RTKNETWORK

Specifies the RTK network mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Network RTK uses permanent base station installations, allowing kinematic GNSS users to achieve centimetre accuracies, without the need of setting up a GNSS base station, at a known site. This command sets the RTK network mode for a specific network. For more details on Network RTK, refer to the application note APN-041 Network RTK.

When using network RTK, it is important to ensure you are working within the region that is supported by the service provider.

Message ID: 951

Abbreviated ASCII syntax:

```
RTKNETWORK mode [network#]
```

Factory default:

```
RTKNETWORK AUTO
```

Input example:

```
RTKNETWORK imax
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKNETWORK header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	*Table 69: Network RTK mode* below		RTK network mode. The factory default is auto where the receiver switches to the first available network RTK source	Enum	4	H
3	network#	0 to 4294967295		Specify a number for the network (default = 0)	Ulong	4	H+4

Table 69: Network RTK mode

Binary	ASCII	Description
0	DISABLE	Single reference station RTK mode. All received network RTK corrections are ignored.
1-4	Reserved	

Binary	ASCII	Description
5	VRS	The Virtual Reference Station (VRS) or Virtual Base Station (VBS) idea introduced by Trimble, is that a base station is artificially created in the vicinity of a rover receiver. All baseline length dependent errors, such as abnormal troposphere variation, ionospheric disturbances and orbital errors, are reduced for this VRS. The rover receiving VRS information has a lower level of these errors than a distant base station. The VRS is calculated for a position, supplied by the rover during communication start up, with networking software. The VRS position can change if the rover is far away from the initial point. The format for sending the rover's position is standard NMEA format. Most rovers receive VRS data, for a calculated base station, within a couple of metres away. The VRS approach requires bi-directional communication for supplying the rover's position to the networking software.
6	IMAX	The iMAX idea, introduced by Leica Geosystems, is that networking software corrections, based on the rover's position, are calculated as with VRS. However, instead of calculating the base station observations for the provided position or another position closer to the base station, original observation information is corrected with the calculated corrections and broadcast. VRS works so that although the rover is unaware of the errors the VRS is taking care of, there still might be ionospheric remains in the base station observations. iMAX provides actual base station position information. The rover may assume the base station is at a distance and open its settings for estimation of the remaining ionospheric residuals. The iMAX method may trigger the rover to open its settings further than required, since the networking software removes at least part of the ionospheric disturbances. However, compared to VRS above, this approach is safer since it notifies the rover when there might be baseline length dependent errors in the observation information. iMAX requires bi-directional communication to the networking software for supplying the base station observation information.
7	FKP	The FKP method delivers the information from a base station network to the rover. No precise knowledge of the rover's position is required for providing the correct information. The corrections are deployed as gradients to be used for interpolating to the rover's actual position.
8	MAX	The basic principle of the master-auxiliary concept is to provide, in compact form, as much of the information from the network and the errors it is observing to the rover as possible. With more information about the state and distribution of the dispersive and non-dispersive errors across the network, the rover is able to use more intelligent algorithms in the determination of its position solution. Each supplier of reference station software will have their own proprietary algorithms for modelling or estimating these error sources. The rover system can decide to use or to neglect the network RTK information, depending on its own firmware algorithm performance.
9	Reserved	
10	AUTO	Default value, assume single base. If network RTK corrections are detected then the receiver will switch to the appropriate mode. iMAX and VRS can only be detected using RTCMV3, however, it is not possible to distinguish between iMAX or VRS. If iMAX or VRS is detected, then iMAX will be assumed.

2.141 RTKPORTMODE

Assigns the port for RTK and ALIGN messages

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command only applies to receivers with both RTK and ALIGN enabled.

A rover receiver with RTK and ALIGN enabled can receive RTK and ALIGN corrections at the same time. However, the two different sources (RTK and ALIGN) must be sent to different ports.

Use the RTKPORTMODE command to route correction feeds to different ports. RTK and ALIGN can be routed to any user specified ports.

Failing to specify the mode for the incoming source could cause unexpected behavior of RTK or ALIGN.

Ports configured using the **RTKPORTMODE** command must also be configured using the **INTERFACEMODE** command (see page 217).

Message ID: 1936

Abbreviated ASCII syntax:

```
RTKPORTMODE [port] mode
```

Factory default:

```
RTKPORTMODE COM1 RTK
RTKPORTMODE COM2 RTK
RTKPORTMODE COM3 RTK
RTKPORTMODE COM4 RTK
RTKPORTMODE COM5 RTK
RTKPORTMODE COM6 RTK
RTKPORTMODE ICOM1 RTK
RTKPORTMODE ICOM2 RTK
RTKPORTMODE ICOM3 RTK
RTKPORTMODE ICOM4 RTK
RTKPORTMODE ICOM5 RTK
RTKPORTMODE ICOM6 RTK
RTKPORTMODE ICOM7 RTK
RTKPORTMODE NCOM1 RTK
RTKPORTMODE NCOM2 RTK
RTKPORTMODE NCOM3 RTK
RTKPORTMODE USB1 RTK
RTKPORTMODE USB2 RTK
```

```
RTKPORTMODE USB3 RTK
RTKPORTMODE WCOM1 RTK
RTKPORTMODE BT1 RTK
RTKPORTMODE AUX RTK
RTKPORTMODE CCOM1 RTK
RTKPORTMODE CCOM2 RTK
RTKPORTMODE CCOM3 RTK
RTKPORTMODE CCOM4 RTK
RTKPORTMODE CCOM5 ALIGN
RTKPORTMODE CCOM6 RTK
```

ASCII example:

```
RTKPORTMODE COM2 RTK
RTKPORTMODE COM3 ALIGN
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKPORTMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Port	See *Table 34: Communications port identifiers* on page 153		Port identifier (default = THISPORT)	Enum	4	H
3	Mode	RTK	0	Mode for this port	Enum	4	H+4
		ALIGN	1				

2.142 RTKQUALITYLEVEL

Sets an RTK quality mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to select an RTK quality mode.

Message ID: 844

Abbreviated ASCII syntax:

```
RTKQUALITYLEVEL mode
```

Factory default:

```
RTKQUALITYLEVEL normal
```

ASCII example:

```
RTKQUALITYLEVEL extra_safe
```

The **EXTRA_SAFE** mode is needed in areas where the signal is partially blocked and the position solution in NORMAL mode shows NARROW_INT even though the real position solution is out by several metres. Using EXTRA_SAFE in these environments means the solution will be slower getting to NARROW_INT but it is less likely to be erroneous.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKQUALITYLEVEL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	NORMAL	1	Set the RTK quality level mode to Normal RTK	Enum	4	H
		EXTRA_ SAFE	4	Set the RTK quality level mode to Extra Safe RTK			

2.143 RTKRESET

Reset the RTK filter

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command resets the RTK filter and causes the AdVanceRTK filter to undergo a complete reset, forcing the system to restart the ambiguity resolution calculations.

Message ID: 2082

Abbreviated ASCII syntax:

```
RTKRESET [Switch]
```

Example :

```
RTKRESET
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary byte	Binary offset
1	Command header	-	-	RTKRESET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Switch	FILTER	1	Reset the RTK filter. This is an optional parameter	Enum	4	H

2.144 RTKSOURCE

Sets the RTK correction source

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command determines what corrections the RTK filter can use. This is useful when the receiver is receiving corrections from multiple base stations.

RTKSOURCE NONE stops any corrections from being used and immediately disables RTK and RTK ASSIST.

Message ID: 494

Abbreviated ASCII syntax:

```
RTKSOURCE type [id]
```

Factory default:

```
RTKSOURCE AUTO ANY
```

ASCII examples:

1. Use a specific format:

   ```
   RTKSOURCE RTCMV3
   ```

2. Use a specific format and base station:

   ```
   RTKSOURCE RTCMV3 1234
   ```

3. Disable RTK:

   ```
   RTKSOURCE NONE
   ```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKSOURCE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	type	See *Table 70: RTK source type* on the next page		Correction type	Enum	4	H
3	id	Char[4] or ANY		Base station ID (default = ANY)	Char[4]	8	H+4

Table 70: RTK source type

Binary	ASCII	Description
0	RTCM	Use only RTCM version 2 corrections from the given ID. ID: 0 ≤ RTCM ID ≤ 1023 **or** ANY to accept all IDs
1	RTCA	Use only RTCA corrections from the given ID. ID: A four-character string containing only alpha (a-z) or numeric characters (0-9) **or** ANY to accept all IDs
2	CMR	Use only CMR corrections from the given ID. ID: 0 ≤ CMR ID ≤ 31 **or** ANY to accept all IDs
10	AUTO	Use any correction type received. If multiple types are received, the first one received is used. If entered, the ID must be ANY.
11	NONE	Disable RTK
13	RTCMV3	Use only RTCM version 3 corrections from the given ID. ID: 0 ≤ RTCMV3 ID ≤ 4095 **or** ANY to accept all IDs.
14	NOVATELX	Use only NovAtel proprietary corrections from the given ID. ID: A four-character string containing alpha (a-z) or numeric characters (0-9) **or** ANY to accept all IDs.

2.145 RTKSOURCETIMEOUT

Sets RTK correction source timeout

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

When multiple RTK correction sources are available, this command allows the user to set a time, in seconds, that the receiver will wait before switching to another RTK correction source if corrections from the original source are lost.

Message ID: 1445

Abbreviated ASCII syntax:

```
RTKSOURCETIMEOUT option [timeout]
```

Factory default:

```
RTKSOURCETIMEOUT AUTO
```

ASCII example:

```
RTKSOURCETIMEOUT auto
RTKSOURCETIMEOUT set 180
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKSOURCETIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	AUTO	1	Sets the timeout according to network type or other self-detected conditions. Timeout field is optional for AUTO and has no effect	Enum	4	H
		SET	2	Sets the timeout to the value entered in the *timeout* field.			
3	timeout	1 to 3600 s (maximum)		Specify the time 0 is not accepted if *SET* is entered in the *option* field (default=0 for the AUTO option)	Ulong	4	H+4

2.146 RTKSVENTRIES

Sets number of satellites in corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the number of satellites (at the highest elevation) that are transmitted in the RTK corrections from a base station receiver. This is useful when the amount of bandwidth available for transmitting corrections is limited.

Message ID: 92

Abbreviated ASCII syntax:

```
RTKSVENTRIES number
```

Factory default:

```
RTKSVENTRIES 24
```

ASCII example:

```
RTKSVENTRIES 7
```

GPS devices have enabled many transit and fleet authorities to provide Automatic Vehicle Location (AVL). AVL systems track the position of individual vehicles and relay that data back to a remote dispatch location that can store or better utilize the information. Consider the implementation of an AVL system within a police department, to automatically log and keep track of the location of each cruiser. Typically a fleet uses a 9600 bps connection where AVL data is relayed back to headquarters. The limited bandwidth of the radio must be shared amongst the AVL and other systems in multiple cruisers.

When operating with a low baud rate radio transmitter (9600 or lower), especially over a long distance, the AVL system could limit the number of satellites for which corrections are sent using the **RTKSVENTRIES** command.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKSVENTRIES header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	number	4-24		The number of SVs to be transmitted in correction messages	Ulong	4	H

2.147 RTKTIMEOUT

Sets maximum age of RTK data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the maximum age of RTK data to use when operating as a rover station. RTK data received that is older than the specified time is ignored.



When RTK ASSIST is active, the **RTKTIMEOUT** command is disregarded. The maximum time that RTK will continue past an RTK corrections outage is controlled by the settings in the **RTKASSISTTIMEOUT** command (see page 338).

Message ID: 910

Abbreviated ASCII syntax:

```
RTKTIMEOUT delay
```

Factory default:

```
RTKTIMEOUT 60
```

ASCII example (rover):

```
RTKTIMEOUT 20
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RTKTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	delay	5 to 300 s		Maximum RTK data age	Ulong	4	H

2.148 RTKTRACKINGCONTROL

Automatic selection of tracking signal type based on incoming base station observations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Controls automatic selection of tracking signal type based on incoming base station observations. This command only applies to single GPS/GLO L2 channel configurations that can auto switch between L2P and L2C. The **RTKTRACKINGCONTROL** command setting takes precedence over the **FORCEGPSL2CODE** command (see page 187) and **FORCEGLOL2CODE** command (see page 186). If this command is set to AUTO, the receiver will always match signal types to incoming corrections.

Message ID: 1351

Abbreviated ASCII syntax:

```
RTKTRACKINGCONTROL [Mode]
```

Factory default:

```
RTKTRACKINGCONTROL AUTO
```

ASCII example:

```
RTKTRACKINGCONTROL DISABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	RTKTRACKINGCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Mode	Disable	0	Disable automatic selection of tracking signal	Enum	4	H
		Auto	1	Automatically match the signal type to the incoming corrections. Default = Auto			

2.149 SATEL4CONFIG

Configures the Satel 400 MHz radio

Platform: SMART7 with RELAY7

Refer to the Satel Radio user documentation for complete and detailed instructions regarding the correct operation of the radio.

This command is used to configure the Satel 400 MHz radio. Settings in this command are stored directly on the radio and not saved through the **SAVECONFIG** command on page 367.

The receiver responds to the command immediately, but the radio settings will take some time to be applied. Log `SATELSTATUS onchanged` to receive a notification that configuration is complete. See the **SATELSTATUS** log on page 940.

- Not all compatibility modes are available on every radio.
- The `radio_behavior` setting determines whether the receive or transmit frequency will be changed.
- If the TRIMTALK protocol is used, the base transmitter type (TRIMBLE or PACCREST) must be specified.
- If the `tx_power` value entered does not correspond to one of the power levels supported by the radio module, the output power is set to the nearest possible value.

Do not interrupt power while the radio is being configured.

Message ID: 2215

Abbreviated ASCII syntax:

```
SATEL4CONFIG <radio_behavior> <tx_power> <freq> <compatibility> <base_type>
```

ASCII example:

```
SATEL4CONFIG RX 0 438000000 7 TRIMBLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATEL4CONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	radio_ behavior	RX	0	Configure for receive	Enum	4	H
		TX	1	Configure for transmit			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	tx_power	0 - 35000		Transmit power (mW)	UInt	4	H+4
4	freq	403000000 - 473000000		Frequency (Hz)	UInt	4	H+8
5	compatibility	1-20 Refer to *Table 72: Compatibility mode* on the next page		Radio compatibility mode	UInt	4	H+12
6	base_type	0-5 Refer to *Table 71: Base type* below		Base transmitter type (required for TRIMTALK protocol only)	Enum	4	H+16
7	crc			32-bit CRC (ASCII and Binary only)	Hex	4	H+20

Table 71: Base type

Binary	ASCII	Description
0	PACCREST	PacCrest transmitter
4	TRIMBLE	Trimble transmitter
9	NONE	Unspecified base type

Table 72: Compatibility mode

Binary	Protocol	Modulation	Link rate (bps) / channel spacing (kHz)	FEC
1	Pacific Crest compatible	GMSK	4800 / 12.5	ON
2	Pacific Crest compatible	GMSK	4800 / 12.5	OFF[1]
3	Pacific Crest compatible	4FSK	9600 / 12.5	ON
4	Pacific Crest compatible	4FSK	9600 / 12.5	OFF[1]
5	Pacific Crest FST compatible	4FSK	9600 / 12.5	ON
6	Pacific Crest FST compatible	4FSK	9600 / 12.5	OFF[1]
7	Trimtalk compatible	GMSK	4800 / 12.5	
8	Trimtalk compatible	GMSK	8000[2]	
9	Satel 3AS	4FSK	9600 / 12.5	ON
10	Satel 3AS	4FSK	9600 / 12.5	OFF
11	Pacific Crest compatible	GMSK	9600 / 25.0	ON
12	Pacific Crest compatible	GMSK	9600 / 25.0	OFF[1]
13	Pacific Crest compatible	4FSK	19200 / 25.0	ON
14	Pacific Crest compatible	4FSK	19200 / 25.0	OFF[1]
15	Pacific Crest FST compatible	4FSK	19200 / 25.0	ON
16	Pacific Crest FST compatible	4FSK	19200 / 25.0	OFF[1]
17	Trimtalk compatible	GMSK	9600/ 25.0	
18	Trimtalk compatible	GMSK	16000[2]	
19	Satel 3AS	4FSK	19200 / 25.0	ON
20	Satel 3AS	4FSK	19200 / 25.0	OFF

Base Type is only required for receiving TRIMTALK protocol.

1. The Satel M3-R4 and EASy radio modules do not support disabling FEC for compatibility modes.
2. The Satel M3-R4 and EASy radio modules do not support Trimtalk 8000 and 16000 link rates.

2.150 SATEL9CONFIG

Configures the Satel 900 MHz radio

Platform: SMART7 with RELAY7

Refer to the Satel Radio user documentation for complete and detailed instructions regarding the correct operation of the radio.

This command is used to configure the Satel 900 MHz radio. Settings in this command are stored directly on the radio and not saved through the **SAVECONFIG** command on page 367. Commands can be sent immediately after each other with the last command issued is applied.

Log `SATELSTATUS onchanged` to send a notification configuration is complete. See the **SATELSTATUS** log on page 940.

If modem mode is set to P2MP_SLAVE or P2MP_RX_SLAVE , the receive frequency is changed.
If modem mode is set to P2MP_MASTER, the transmit frequency is changed.

Do not interrupt power while the radio is being configured.

Message ID: 2217

Abbreviated ASCII syntax:

```
SATEL9CONFIG <modem_mode> <freq_key> <nid> <minpkt> <maxpkt> <retrytimeout>
<subnet> <repeaters> <packetrepeat> <txpwr>
```

ASCII example:

```
SATEL9CONFIG P2MP_MASTER 1 4024 8 9 10 00 TRUE 1 1000
SATEL9CONFIG P2MP_RX_SLAVE 1 4024 8 9 10 00 FALSE 1 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATEL9CONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	modem_mode	P2MP_ MASTER	2	Radio role in the network	Enum	4	H
		P2MP_ SLAVE	3				
		P2MP_ RX_ SLAVE	8				
3	freq_key	0-14		Frequency key for hop table	Uint	4	H+4
4	nid	0-4095		Network ID	Uint	4	H+8
5	minpkt	0-9		Minimum packet size	Uint	4	H+12
6	maxpkt	0-9		Maximum packet size	Enum	4	H+16
7	retrytimeout	8-255		Number of failed attempts to receive packets before connection drops	Uint	4	H+20
8	subnet	0x00, 0xFF		Multi-point subnet 0x00=Roaming 0xFF=Disabled	Uint	4	H+24
9	repeaters	FALSE	0	Boolean to specify if repeaters are present in the network	Bool	4	H+28
		TRUE	1				
10	packetrepeat	0-9		Number of times the master repeats packets	Uint	4	H+32
11	txpwr	0-1000		Transmitter output power (mW)	Uint	4	H+36
12	crc			32-bit CRC (ASCII and Binary only)	Hex	4	H+40

2.151 SATEL9CONFIGL

Configures the 900 MHz radio network

Platform: SMART7 with RELAY7

The SATEL9CONFIGL command is used to configure the Satel 900 MHz radio network settings using a simplified Leica channel identifier.

Message ID: 2218

Abbreviated ASCII syntax:

```
SATEL9CONFIGL <modem_mode> <channel> <retrytimeout> <subnet> <repeaters>
<packetrepeat> <txpwr>
```

ASCII example:

```
SATEL9CONFIGL P2MP_MASTER 2 10 00 TRUE 1 1000
SATEL9CONFIGL P2MP_RX_SLAVE 4 10 FF FALSE 0 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATEL9CONFIGL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	modem_mode	P2MP_MASTER	2	Radio roll in network	Enum	4	H
		P2MP_SLAVE	3				
		P2MP_RX_SLAVE	8				
3	channel	1-9		Virtual channel	Uint	4	H+4
4	retrytimeout	8-255		Number of failed attempts to receive packets before connection is dropped	Uint	4	H+8
5	subnet	0x00, 0xFF		Multi-point subnet 0x00=Roaming, 0xFF=Disabled	Uint	4	H+12
6	repeaters	FALSE	0	Boolean to specify if repeaters are present in the network	Bool	4	H+16
		TRUE	1				
7	packetrepeat	0-9		Number of times master repeats packets	Uint	4	H+20

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
8	txpwr	0-1000		Transmitter output power (mW)	Uint	4	H+24
9	crc			32-bit CRC (ASCII and Binary only)	Hex	4	H+28

2.152 SATEL9CONFIGN

Configures the 900 MHz radio network

Platform: SMART7 with RELAY7

The SATEL9CONFIGN command is used to configure the Satel 900 MHz radio network settings using a simplified Novariant channel identifier.

Message ID: 2219

Abbreviated ASCII syntax:

```
SATEL9CONFIGN <modem_mode> <channel> <retrytimeout> <subnet> <repeaters>
<packetrepeat> <txpwr>
```

ASCII example:

```
SATEL9CONFIGN P2MP_MASTER 32 10 00 TRUE 1 1000
SATEL9CONFIGN P2MP_RX_SLAVE 32 10 00 FALSE 0 0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATEL9CONFIGN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	modem_mode	P2MP_MASTER	2	Radio roll in network	Enum	4	H
		P2MP_SLAVE	3				
		P2MP_RX_SLAVE	8				
3	channel	1-3824		Virtual channel	Uint	4	H+4
4	retrytimeout	8-255		Number of failed attempts to receive packets before connection is dropped	Uint	4	H+8
5	subnet	0x00, 0xFF		Multi-point subnet 0x00=Roaming, 0xFF=Disabled	Uint	4	H+12
6	repeaters	FALSE	0	Boolean to specify if repeaters are present in the network	Bool	4	H+16
		TRUE	1				
7	packetrepeat	0-9		Number of times master repeats packets	Uint	4	H+20

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
8	txpwr	0-1000		Transmitter output power (mW)	Uint	4	H+24
9	crc			32-bit CRC (ASCII and Binary only)	Hex	4	H+28

2.153 SATELCONTROL

Controls radio operations

Platform: SMART7 with RELAY7

The SATELCONTROL command is used to control the SATEL radio.

Message ID: 2203

Abbreviated ASCII syntax:

```
SATELCONTROL <Action> <Value>
```

ASCII example:

```
SATELCONTROL POWER ON
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATELCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	action	Refer to *Table 73: Radio control action* below		Action to perform	Enum	4	H
	value			Corresponding value for action	String [24]	24	H+4
3	crc			32-bit CRC (ASCII and Binary only)	Hex	4	H+28

Table 73: Radio control action

Action	Value	Description
POWER	ON	Toggles radio power (if available)
	OFF	
FRESET	-	Resets the radio to factory default settings

2.154 SATELDETECT

Detects the connected Satel radio

Platform: SMART7 with RELAY7

This command is used to detect the Satel radio connected to the serial port. Detection is only required to configure the radio settings. If previously configured, the radio can provide RTK corrections without issuing the SATELDETECT command.

Logging **SATELSTATUS** command on page 940 onchanged provides a notification of the completion of detection. If no radio is detected at the default baud rate of 38400, the RIL will attempt at additional baud rates (115200, 9600). If a radio is detected, the baud rate of the radio will be changed to 38400. Upon detection, the radio identity (version block) and settings (**SATEL4INFO** command on page 937 and **SATEL9INFO** command on page 938) will be queried. Regardless of the presence of a radio, the final state of the given serial port will be baud rate=38400, data bits=8, parity bits=N, stop bits=1. Interfacemode will be returned to its setting before SATELDETECT was issued.

Message ID: 2204

Abbreviated ASCII syntax:

```
SATELDETECT COMPort
```

ASCII example:

```
SATELDETECT COM3
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATELDETECT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 76: COM port identifiers* on page 384		Port to attempt detection (default=COM3)	Enum	4	H

2.155 SATELSTARTUPDETECT

Detects the Satel radio on the COM port during startup

Platform: SMART7 with RELAY7

This command is used to detect the Satel radio connected to the COM port during system startup. Detection functions the same as if the **SATELDETECT** command on the previous page was issued. SATELDETECT automatically begins at the next startup when the **SATELSTARTUPDETECT** command is used.

The **SAVECONFIG** command on the next page must be issued to set this command parameters.

Message ID: 2221

Abbreviated ASCII syntax:

```
SATELSTARTUPDETECT Switch COMPort
```

ASCII example:

```
SATELSTARTUPDETECT Enable COM3
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SATELSTARTUPDETECT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	Enable	-	Switch to enable detection (default=Disable)	Enum	4	H
		Disable	-				
3	port	See *Table 76: COM port identifiers* on page 384		Port to attempt detection (default=COM3)	Enum	4	H+4

2.156 SAVECONFIG

Save current configuration in NVM

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SAVECONFIG saves commands that were entered by a user to establish the desired receiver configuration on start up. This configuration is saved in Non-Volatile Memory (NVM) and is executed every time the receiver starts, whether by power-up or the **RESET** command on page 332. The commands that are saved as part of a configuration are typically **LOG** requests, **SERIALCONFIG** commands, **ICOMCONFIG** commands, a **FIX** command and others. Note that not all the commands can be saved using **SAVECONFIG**. All of the commands that set a configuration, including default commands for the receiver, are listed in the **RXCONFIG** log (see page 913). To clear the commands saved by **SAVECONFIG** and reset the receiver to the factory-set configuration, the **FRESET** command on page 192 can be used.

For commands that configure hardware, there is a delay between power being applied and the saved configuration being restored.

If using the SAVECONFIG command in NovAtel Connect, ensure that you have all windows other than the Console window closed. Otherwise, log requests used for the various windows are saved as well. This will result in unnecessary data being logged.

Message ID: 19

Abbreviated ASCII syntax:

```
SAVECONFIG
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SAVECONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

2.157 SAVEETHERNETDATA

Save the configuration data associated with an Ethernet interface

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

Saving the configuration data for an Ethernet interface allows the interface to start automatically at boot time and be configured with either a static IP address or to obtain an address using DHCP. The **SAVEETHERNETDATA** command saves the configuration for the interface previously entered using the **ETHCONFIG** command (see page 160), **IPCONFIG** command (see page 224) and **DNSCONFIG** command (see page 146). The configuration data that is saved will survive a **RESET** command (see page 332) and **FRESET** command (see page 192). To clear the Ethernet interface configuration data, the **FRESET ETHERNET** command is used. It is not necessary to issue the **SAVECONFIG** command (see page 367) to save the Ethernet interface configuration data. In fact, if **SAVECONFIG** is used to save the **ETHCONFIG**, **IPCONFIG** and **DNSCONFIG** commands, the configuration saved by **SAVEETHERNETDATA** will take precedence over the **SAVECONFIG** configuration.

Message ID: 1679

Abbreviated ASCII syntax:

```
SAVEETHERNETDATA [Interface]
```

ASCII example:

```
ETHCONFIG ETHA AUTO AUTO AUTO AUTO
IPCONFIG ETHA STATIC 192.168.8.11 255.255.255.0 192.168.8.1
DNSCONFIG 1 192.168.4.200
SAVEETHERNETDATA ETHA
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SAVEETHERNETDATA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Interface	ETHA	2	The Ethernet interface to save the configuration data for. The default is ETHA.	Enum	4	H

Note that the configurations set using the **ICOMCONFIG** command (see page 213) and **NTRIPCONFIG** command (see page 279) are not saved by the **SAVEETHERNETDATA** command. The following factory default ICOM configurations can be used if Ethernet access to the receiver is required immediately after the receiver is **RESET** or **FRESET**.

```
ICOMCONFIG ICOM1 TCP :3001
ICOMCONFIG ICOM2 TCP :3002
ICOMCONFIG ICOM3 TCP :3003
ICOMCONFIG ICOM4 TCP :3004
ICOMCONFIG ICOM5 TCP :3005
ICOMCONFIG ICOM6 TCP :3006
ICOMCONFIG ICOM7 TCP :3007
```

See also the following commands:

- **ETHCONFIG** command on page 160
- **IPCONFIG** command on page 224
- **DNSCONFIG** command on page 146
- **FRESET** command on page 192

2.158 SBASCONTROL

Sets SBAS test mode and PRN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to dictate how the receiver tracks and uses correction data from Satellite Based Augmentation Systems (SBAS).

To enable the position solution corrections, issue the **SBASCONTROL ENABLE** command. The receiver does not, by default, attempt to track or use any SBAS signals satellites unless told to do so by the **SBASCONTROL** command. When in AUTO mode, if the receiver is outside the defined satellite system's corrections grid, it reverts to ANY mode and chooses a system based on other criteria.

The "testmode" parameter in the example provides a method to use a particular satellite even if it is currently operating in test mode. The recommended setting for tracking satellites operating in test mode is ZEROTOTWO. On a simulator, you may want to leave this parameter off or specify NONE explicitly.

When using the **SBASCONTROL** command to direct the receiver to use a specific correction type, the receiver begins to search for and track the relevant GEO PRNs for that correction type only.

The receiver can be forced to track a specific PRN using the **ASSIGN** command (see page 77). The receiver can also be forced to use the corrections from a specific SBAS PRN using the **SBASCONTROL** command.

Disable stops the corrections from being used.

Message ID: 652

Abbreviated ASCII syntax:

```
SBASCONTROL switch [system] [prn] [testmode]
```

Factory default:

```
SBASCONTROL disable
```

ASCII example:

```
SBASCONTROL enable waas
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SBASCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Receiver does not use the SBAS corrections it receives (default)	Enum	4	H
		ENABLE	1	Receiver uses the SBAS corrections it receives			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	system	See *Table 74: System types* below		Choose the SBAS the receiver will use	Enum	4	H+4
4	prn	0		Receiver uses any PRN (default)	Ulong	4	H+8
		120-158 and 183-187		Receiver uses SBAS corrections only from this PRN if tracked, otherwise any PRN Using the **ASSIGN** command (see page 77) to manually assign an SBAS channel is recommended if a specific PRN is desired.			
5	testmode	NONE	0	Receiver interprets Type 0 messages as they are intended (as do not use) (default)	Enum	4	H+12
		ZEROTOTWO	1	Receiver interprets Type 0 messages as Type 2 messages			
		IGNOREZERO	2	Receiver ignores the usual interpretation of Type 0 messages (as do not use) and continues			

Table 74: System types

ASCII	Binary	Description
NONE	0	Does not use any SBAS satellites (Default for SBASCONTROL DISABLE)
AUTO	1	Automatically determines satellite system to use (Default for SBASCONTROL ENABLE)
ANY	2	Uses any and all SBAS satellites found
WAAS	3	Uses only WAAS satellites

ASCII	Binary	Description
EGNOS	4	Uses only EGNOS satellites
MSAS	5	Uses only MSAS satellites
GAGAN	6	Uses only GAGAN satellites
QZSS	7	Uses only QZSS L1S signals

2.159 SBASECUTOFF

Sets SBAS satellite elevation cut-off

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the elevation cut-off angle for tracked SBAS satellites. The receiver does not start automatically searching for an SBAS satellite until it rises above the cut-off angle (when satellite position is known). Tracked SBAS satellites that fall below the cut-off angle are no longer tracked unless they are manually assigned (see the **ASSIGN** command on page 77).

This command permits a negative cut-off angle and can be used in the following situations:

- The antenna is at a high altitude and can look below the local horizon
- Satellites are visible below the horizon due to atmospheric refraction

Use the **ELEVATIONCUTOFF** command (see page 157) to set the cut-off angle for any system.

Message ID: 1000

Abbreviated ASCII syntax:

```
SBASECUTOFF angle
```

Factory default:

```
SBASECUTOFF -5.0
```

ASCII example:

```
SBASECUTOFF 10.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SBASECUTOFF header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	angle	±90.0 degrees		Elevation cut-off angle relative to horizon	Float	4	H

2.160 SBASTIMEOUT

Sets the SBAS position time out

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to set the amount of time the receiver remains in an SBAS position if it stops receiving SBAS corrections.

Message ID: 1001

Abbreviated ASCII syntax:

```
SBASTIMEOUT mode [delay]
```

Factory default:

```
SBASTIMEOUT auto
```

ASCII example:

```
SBASTIMEOUT set 100
```



When the time out mode is AUTO, the time out delay is 180 s.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SBASTIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	Reserved	0	Reserved	Enum	4	H
		AUTO	1	Set to the default value (180 s)			
		SET	2	Set the delay in seconds			
3	delay	2 to 1000 s		Maximum SBAS position age (default=180)	Double	8	H+4
4	Reserved				Double	8	H+12

2.161 SELECTCHANCONFIG

Sets the channel configuration

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SELECTCHANCONFIG selects which channel configuration (set of GNSS signals to be tracked) is to be used from those made available by the active software model and as listed in the **CHANCONFIGLIST** log (see page 550). Subscription Managed Channel Configuration (SMCC) will override this selection when **TERRASTARAUTOCHANCONFIG** is enabled and a TerraStar subscription supporting SMCC is active. In that case, the **SELECTCHANCONFIG** command will be rejected. The **CHANCONFIGLIST** log *SetInUse* parameter indicates which configuration is currently active.

Issuing a **SELECTCHANCONFIG** command immediately reboots the receiver into the new configuration. The **SELECTCHANCONFIG** setting is reset to default when the selected permanent model changes.

The factory default value depends on the active software model.

Table 75: SELECTCHANCONFIG factory defaults

Active software model positioning character	Default channel configuration
N or L	1
P or R	3
B, with constellation and frequency characters FF	7
B, with constellation or frequency characters other than FF	5

For information about SMCC overriding this selection, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 1149

Abbreviated ASCII syntax:

```
SELECTCHANCONFIG chanconfigsetting
```

Factory default:

See *Table 75: SELECTCHANCONFIG factory defaults* above.

ASCII example:

```
SELECTCHANCONFIG 2
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SELECTCHANCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	chanconfigsetting	1 to n where n is the number of channel configurations in the **CHANCONFIGLIST** log (see page 550)		Channel configuration to use	Ulong	4	H

Example

Below is a use case example of the **SELECTCHANCONFIG** command. Abbreviated ASCII commands and logs are used to better illustrate the example.

1. LOG CHANCONFIGLIST to show what the channel configuration options are and which channel configuration set is being used.

```
<CHANCONFIGLIST COM1 0 76.5 UNKNOWN 0 11.470 024c0020 d1c0 32768
<     5 9
<          7
<          16 GPSL1L2PL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1
<          14 GLOL1L2
<          16 GALE1E5B
<          30 BEIDOUB1B2B2B
<          5 LBAND
<          7
<          16 GPSL1L2
<          4 QZSSL1CAL2C
<          4 SBASL1
<          14 GLOL1L2
<          16 GALE1E5B
<          30 BEIDOUB1B2B
<          5 LBAND
<          7
<          16 GPSL1L2PL2CL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1
<          14 GLOL1L2PL2C
<          16 GALE1E5AE5BALTBOC
<          30 BEIDOUB1B2B2B
<          5 LBAND
<          8
<          16 GPSL1L2PL2CL5
```

```
<           4 QZSSL1CAL2CL5
<           4 SBASL1L5
<           14 GLOL1L2PL2C
<           16 GALE1E5AE5BALTBOC
<           20 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5L1C
<           4 QZSSL1CAL2CL5L1CL6
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           11 GALE1E5AE5BALTBOCE6
<           16 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           6 QZSSL1CAL2CL5
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           9 GALE1E5AE5BALTBOCE6
<           24 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           4 QZSSL1CAL2CL5
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           16 GALE1E5AE5BALTBOCE6
<           16 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           4 QZSSL1CAL2CL5L1CL6
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           11 GALE1E5AE5BALTBOCE6
<           20 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5L1C
<           4 QZSSL1CAL2CL5L1C
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           16 GALE1E5AE5BALTBOC
<           20 BEIDOUB1B1CB2B2B
<           8 NAVICL5
<           5 LBAND
```

2. There are nine options given for the model and the fifth channel configuration set is currently being used.
3. If the user would like to use the third channel configuration set enter, **SELECTCHANCONFIG 3** command.

4. The receiver receives the command and resets. At startup, the third channel configuration set is configured.
5. To verify that setting has changed, enter LOG CHANCONFIGLIST.

```
<CHANCONFIGLIST COM1 0 76.5 UNKNOWN 0 11.470 024c0020 d1c0 32768
<     3 9
<          7
<          16 GPSL1L2PL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1
<          14 GLOL1L2
<          16 GALE1E5B
<          30 BEIDOUB1B2B2B
<          5 LBAND
<          7
<          16 GPSL1L2
<          4 QZSSL1CAL2C
<          4 SBASL1
<          14 GLOL1L2
<          16 GALE1E5B
<          30 BEIDOUB1B2B
<          5 LBAND
<          7
<          16 GPSL1L2PL2CL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1
<          14 GLOL1L2PL2C
<          16 GALE1E5AE5BALTBOC
<          30 BEIDOUB1B2B2B
<          5 LBAND
<          8
<          16 GPSL1L2PL2CL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1L5
<          14 GLOL1L2PL2C
<          16 GALE1E5AE5BALTBOC
<          20 BEIDOUB1B1CB2B2BB3
<          8 NAVICL5
<          5 LBAND
<          8
<          16 GPSL1L2PL2CL5L1C
<          4 QZSSL1CAL2CL5L1CL6
<          4 SBASL1L5
<          14 GLOL1L2PL2CL3
<          11 GALE1E5AE5BALTBOCE6
<          16 BEIDOUB1B1CB2B2BB3
<          8 NAVICL5
<          5 LBAND
<          8
<          16 GPSL1L2PL2CL5
<          6 QZSSL1CAL2CL5
<          4 SBASL1L5
<          14 GLOL1L2PL2CL3
<          9 GALE1E5AE5BALTBOCE6
<          24 BEIDOUB1B1CB2B2BB3
<          8 NAVICL5
```

```
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           4 QZSSL1CAL2CL5
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           16 GALE1E5AE5BALTBOCE6
<           16 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           4 QZSSL1CAL2CL5L1CL6
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           11 GALE1E5AE5BALTBOCE6
<           20 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5L1C
<           4 QZSSL1CAL2CL5L1C
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           16 GALE1E5AE5BALTBOC
<           20 BEIDOUB1B1CB2B2B
<           8 NAVICL5
<           5 LBAND
```

6. This log shows that the third set is selected. To further verify, enter **LOG TRACKSTAT** to show all the configured channels.

2.162 SEND

Sends an ASCII message to a COM port

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to send ASCII printable data from any of the COM or USB ports to a specified communications port. This is a one time command, therefore the data message must be preceded by the **SEND** command and followed by <CR> each time data is sent. If the data string contains delimiters (that is, spaces, commas, tabs and so on), the entire string must be contained within double quotation marks. Carriage return and line feed characters (for example, 0x0D, 0x0A) are appended to the sent ASCII data.

Message ID: 177

Abbreviated ASCII syntax:


```
SEND [port] data
```

ASCII example

```
SEND com1 “log com1 rtcaobs ontime 5”
```

Scenario: Assume you are operating receivers as base and rover stations. It could also be assumed that the base station is unattended but operational and you wish to control it from the rover station. From the rover station, you could establish the data link and command the base station receiver to send differential corrections.

Figure 9: Using the SEND command



Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SEND header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 5: Detailed port identifier* on page 42		Output port (default=THISPORT)	Enum	4	H
3	message	Max 100 character string (99 typed visible chars and a null char added by the firmware automatically)		ASCII data to send	String [max 100]	Variable[1]	H+4

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.163 SENDHEX

Send non-printable characters in hex pairs

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is like the **SEND** command (see page 380) except it is used to send non-printable characters expressed as hexadecimal pairs. Carriage return and line feed characters (for example, 0x0D, 0x0A) will not be appended to the sent data and so must be explicitly added to the data if needed.

Message ID: 178

Abbreviated ASCII syntax:

```
SENDHEX [port] length data
```

Input example:

```
SENDHEX COM1 6 143Ab5910D0A
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SENDHEX header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 5: Detailed port identifier* on page 42		Output port (default=THISPORT)	Enum	4	H
3	length	0 - 700		Number of hex pairs	Ulong	4	H+4
4	message	limited to a 700 maximum string (1400 pair hex). Even number of ASCII characters from set of 0-9, A-F. No spaces are allowed between pairs of characters		Data	String [max 700]	Variable[1]	H+8

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.164 SERIALCONFIG

Configures serial port settings

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to configure the receiver's asynchronous serial port communications drivers.

1. Also refer to the **ECHO** command on page 152.
2. The **SERIALCONFIG** command can be used as a log to confirm settings.
3. The entire content of the current log is sent before pausing due to the receipt of the XOFF character.

The current SERIALCONFIG port configuration can be reset to its default state by sending it two hardware break signals of 250 milliseconds each, spaced by fifteen hundred milliseconds (1.5 seconds) with a pause of at least 250 milliseconds following the second break. This will:

- Stop the logging of data on the current port (see the **UNLOGALL** command on page 454)
- Clear the transmit and receive buffers on the current port
- Return the current port to its default settings (see *Command defaults* on page 62 for details)
- Set the interface mode to NovAtel for both input and output (see the **INTERFACEMODE** command on page 217)

This break detection can be disabled using the **SERIALCONFIG** command.

1. The **COMCONTROL** command (see page 124) may conflict with handshaking of the selected COM port. If handshaking is enabled, then unexpected results may occur.
2. Baud rates higher than 115,200 bps are not supported by standard PC hardware. Special PC hardware may be required for higher rates, including 230400 bps and 460800 bps. Avoid having COM ports of two receivers connected together using baud rates that do not match. Data transmitted through a port operating at a slower baud rate may be misinterpreted as break signals by the receiving port if it is operating at a higher baud rate because data transmitted at the lower baud rate is stretched relative to the higher baud rate. In this case, configure the receiving port to break detection disabled using the **SERIALCONFIG** command.

Use the SERIALCONFIG command before using the INTERFACEMODE command on each port. Turn break detection off using the SERIALCONFIG command to stop the port from resetting because it is interpreting incoming bits as a break command.

Message ID: 1246

Abbreviated ASCII syntax:

```
SERIALCONFIG [port] baud [parity[databits[stopbits[handshaking[break]]]]]
```

Factory defaults:

```
SERIALCONFIG COM1 9600 N 8 1 N ON
SERIALCONFIG COM2 9600 N 8 1 N ON
```

```
SERIALCONFIG COM3 9600 N 8 1 N ON
SERIALCONFIG COM4 9600 N 8 1 N ON
SERIALCONFIG COM5 9600 N 8 1 N ON
```

ASCII example:

```
SERIALCONFIG com1 9600 n 8 1 n off
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SERIALCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 76: COM port identifiers* below		Port to configure (default = THISPORT)	Enum	4	H
3	bps/baud	2400, 4800, 9600, 19200, 38400, 57600, 115200, 230400 and 460800		Communication baud rate (bps).	Ulong	4	H+4
4	parity	See *Table 77: Parity* on the next page		Parity	Enum	4	H+8
5	databits	7 or 8		Number of data bits (default = 8)	Ulong	4	H+12
6	stopbits	1 or 2		Number of stop bits (default = 1)	Ulong	4	H+16
7	handshake	See *Table 78: Handshaking* on the next page		Handshaking Hardware handshaking is not supported on all receiver ports. See *Table 79: Hardware handshaking compatibility* on the next page.	Enum	4	H+20
8	break	OFF	0	Disable break detection	Enum	4	H+24
		ON	1	Enable break detection (default)			

Table 76: COM port identifiers

Binary	ASCII	Description	Applicable receiver
1	COM1	COM port 1	OEM719, OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, SMART7
2	COM2	COM port 2	OEM719, OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, SMART7

Binary	ASCII	Description	Applicable receiver
3	COM3	COM port 3	OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, SMART7
6	THISPORT	The current COM port	OEM719, OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7
19	COM4	COM port 4	OEM7700, OEM7600, OEM7720
21	IMU	IMU COM port	Dependent on hardware configuration
31	COM5	COM port 5	OEM7700, OEM7600, OEM7720
32	COM6	COM port 6	
33	BT1	Bluetooth COM port	Dependent on hardware configuration
34	COM7	COM port 7	
35	COM8	COM port 8	
36	COM9	COM port 9	
37	COM10	COM port 10	

Table 77: Parity

Binary	ASCII	Description
0	N	No parity (default)
1	E	Even parity
2	O	Odd parity

Table 78: Handshaking

Binary	ASCII	Description
0	N	No handshaking (default)
1	XON	XON/XOFF software handshaking
2	CTS	CTS/RTS hardware handshaking

Table 79: Hardware handshaking compatibility

Receiver	COM1	COM2	COM3	COM4	COM5
OEM719	No	No	No	–	–
OEM729	Supported	Supported	No	–	–
OEM7500	No	No	No	–	–
OEM7600	Supported	Supported	No	No	No

Receiver	COM1	COM2	COM3	COM4	COM5
OEM7700	Supported	Supported	No	No	No
OEM7720	Supported	Supported	No	No	No
PwrPak7/PwrPak7D	Supported	No	No	–	–
CPT7/CPT7700	No	No	–	–	–
SMART7	No	No	No	–	–
SMART2	No	No	No	–	–
GT7800	Supported	Supported	No	–	–

2.165 SERIALPROTOCOL

Sets the protocol to be used by a serial port

Platform: OEM729, PwrPak7

On some OEM7 receivers, selected ports can support either RS-232 or RS-422 signalling protocol. The default protocol is RS-232. The **SERIALPROTOCOL** command is used to select the protocol (RS-232 or RS-422) supported on the port.

RS-422/RS-232 selection is available only on COM1 of the OEM729 or COM1 and COM2 on the PwrPak7.

Message ID: 1444

Abbreviated ASCII syntax:

```
SERIALPROTOCOL port protocol
```

ASCII example:

```
SERIALPROTOCOL COM1 RS422
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SERIALPROTOCOL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 80: Ports supporting RS-422* below		Select the COM port on which the protocol is being set. The port that can be entered depends on the hardware platform being used.	Enum	4	H
3	protocol	RS232	0	Set the port to use RS-232 protocol	Enum	4	H+4
		RS422	1	Set the port to use RS-422 protocol			

After switching a COM port from RS-232 to RS-422, send a carriage return (CR) on the newly configured port to flush the buffer prior to sending new commands on the port.

Table 80: Ports supporting RS-422

OEM7 receiver type	Allowable ports	Binary value
OEM719	None	

OEM7 receiver type	Allowable ports	Binary value
OEM729	COM1	1
OEM7600	None	
OEM7700	None	
OEM7720	None	
PwrPak7	COM1	1
	COM2	2

2.166 SET4BITSBASPREAMBLE

Configure an SBAS PRN to use 4 bit preamble L5 data framing

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command controls whether a tracked SBAS PRN will use the 3x8 distributed preamble defined in RTCA/DO-229D or the 6x4 distributed preamble defined in the proposed SBAS L5 DFMC ICD when framing the L5 signal navigation data.

All SBAS SVs will eventually transition to the proposed L5 DFMC 6x4 preamble format. Therefore, in a future release the default behaviour of the receiver will be changed from the current 3x8 preamble to the new 6x4 preamble.

Message ID: 2066

Abbreviated ASCII syntax:

```
SET4BITSBASPREAMBLE prn switch
```

Factory default:

```
SET4BITSBASPREAMBLE <prn> disable
```

Example:

```
SET4BITSBASPREAMBLE 133 enable
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	SET4BITSBASPREAMBLE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	PRN	Refer to *Table 12: PRN numbers for commands and logs* on page 55		PRN number	Ulong	4	H
3	switch	DISABLE	0	Use 3x8 preamble	Enum	4	H+4
		ENABLE	1	Use 6x4 preamble			

2.167 SETADMINPASSWORD

Sets the administration password


Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This command sets the administration password used to log into various web services.

The administration password is required for Secure ICOM access.

The default admin password for receiver cards is the receiver PSN. For enclosures such as the PwrPak7, CPT7, CPT7700 or SMART7 that have the heading **Password** on the enclosure label, the default admin password is the 12 character password shown on the label. For a PwrPak7 or SMART7 that has the heading **WIFI Password**, the default password is the enclosure PSN. For a CPT7 or CPT7700 with no password listed on the label, the default admin password is the enclosure PSN.

Figure 10: Default passwords



On enclosures with a factory configured default Admin Password, performing a reset shall restore it to that default password.

The receiver PSN and enclosure PSN can be viewed using the **VERSION** log on page 1023

Message ID: 1579

Abbreviated ASCII syntax:

```
SETADMINPASSWORD oldpassword newpassword
```

Input example

```
SETADMINPASSWORD ABC123 XYZ789
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETADMINPASSWORD header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	OldPassword	Maximum 28 character string		Previous password. If the OldPassword is entered incorrectly more than 5 times in a row, the receiver will output the response `Login temporarily suspended` and logins will be suspended for 5 or 10 seconds. The consecutive incorrect password count is accumulated across all ports and all commands that use the admin password.	String [28]	variable[1]	H
3	NewPassword	Maximum 28 character string		New password. The new password cannot be blank. The password can contain upper case letters, lower case letters, numbers, punctuation and some symbols. Specifically, any 7-bit ASCII character from SPACE (decimal 32, hex 0x20) to TILDE (decimal 126, hex 0x7E) except QUOTE (decimal 34, hex 0x22). If the new password does not meet the above criteria, the receiver will output the response `New password is unacceptable`.	String [28]	variable[1]	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

If the OldPassword or NewPassword contains a SPACE (decimal 32, hex 0x20) or COMMA (decimal 44, hex 0x2C), the password must be enclosed in QUOTE characters (decimal 34, hex 0x22) when entered in ASCII or Abbreviated ASCII.

This password can be restored to default (the receiver PSN) by issuing the **FRESET USER_ ACCOUNTS** command (see the **FRESET** command on page 192).

2.168 SETAPPROXPOS

Sets an approximate position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets an approximate latitude, longitude and height in the receiver. Estimating these parameters, when used in conjunction with an approximate time (see the **SETAPPROXTIME** command on the next page), can improve satellite acquisition times and Time To First Fix (TTFF). For more information about TTFF and Satellite Acquisition, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

The horizontal position entered should be within 200 km of the actual receiver position. The approximate height is not critical and can normally be entered as zero. By default , if the receiver cannot calculate a valid position within 2.5 minutes of entering an approximate position, the approximate position is ignored.

The approximate position is not visible in any position logs. It can be seen by issuing a SETAPPROXPOS log.

Message ID: 377

Abbreviated ASCII syntax:

```
SETAPPROXPOS lat lon height
```

Input example:

```
SETAPPROXPOS 51.116 -114.038 0
```

For an example on the use of this command, refer to the **SETAPPROXTIME** command on the next page.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETAPPROXPOS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Lat	± 90 degrees		Approximate latitude	Double	8	H
3	Lon	± 180 degrees		Approximate longitude	Double	8	H+8
4	Height	-1000 to +20000000 m		Approximate height	Double	8	H+16

2.169 SETAPPROXTIME

Sets an approximate GPS reference time

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets an approximate time in the receiver. The receiver uses this time as system time until a coarse time can be acquired. This can be used in conjunction with an approximate position (see the **SETAPPROXPOS** command on the previous page) to improve Time To First Fix (TTFF). For more information TTFF and Satellite Acquisition, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

The time entered should be within 10 minutes of the actual GPS reference time. If the week number entered does not match the broadcast week number, the receiver resets once it is tracking.

Message ID: 102

Abbreviated ASCII syntax:

```
SETAPPROXTIME week sec
```

Input example:

```
SETAPPROXTIME 1930 501232
```

Upon power up, the receiver does not know its position or time and therefore cannot use almanac information to aid satellite acquisition. You can set an approximate GPS reference time using the **SETAPPROXPOS** command (see page 393).

Approximate time and position may be used in conjunction with a current almanac to aid satellite acquisition. See the table below for a summary of the OEM7 family commands used to inject an approximated time or position into the receiver:

Approximate	Command
Time	SETAPPROXTIME
Position	SETAPPROXPOS

Base station aiding can help in these environments. A set of ephemerides can be injected into a rover station by broadcasting the RTCAEPHEM message from a base station. This is also useful in environments where there is frequent loss of lock. GPS ephemeris is three frames long within a sequence of five frames. Each frame requires 6 s of continuous lock to collect the ephemeris data. This gives a minimum of 18 s and a maximum of 36 s continuous lock time or when no recent ephemerides (new or stored) are available.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETAPPROXTIME header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	week	0-9999		GPS reference week number	Ulong	4	H
3	sec	0-604800		Number of seconds into GPS reference week	Double	8	H+4

2.170 SETBASERECEIVERTYPE

Sets base receiver type

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command allows the user to specify the base receiver type to aid GLONASS ambiguity fixing in RTK. It can be used as a substitute for RTCM1033 messages that contains the information on the base receiver type. This command should be issued to the Rover.



An incorrect base type setting can significantly impair ambiguity resolution.

Message ID: 1374

Abbreviated ASCII syntax:

```
SETBASERECEIVERTYPE base_type
```

Factory default:

```
SETBASERECEIVERTYPE unknown
```

ASCII example:

```
SETBASERECEIVERTYPE novatel
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETBASERECEIVERTYPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	base_type	unknown	0	Unknown Base	Enum	4	H
		novatel	1	NovAtel Base			
		trimble	2	Trimble Base			
		topcon	3	Topcon Base			
		magellan	4	Magellan Base			
		leica	5	Leica Base			

2.171 SETBESTPOSCRITERIA

Sets selection criteria for BESTPOS

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to set the criteria for the **BESTPOS** log (see page 527) and choose between 2D and 3D standard deviation to obtain the best position from the **BESTPOS** log (see page 527). It also allows you to specify the number of seconds to wait before changing the position type. This delay provides a single transition that ensures position types do not skip back and forth.

The **SETBESTPOSCRITERIA** command is also used as the basis for the **UALCONTROL** command (see page 441) standard deviations.

Message ID: 839

Abbreviated ASCII syntax:

```
SETBESTPOSCRITERIA type [delay]
```

Factory default:

```
SETBESTPOSCRITERIA pos3d 0
```

Input example:

```
SETBESTPOSCRITERIA pos2d 5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETBESTPOSCRITERIA header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	type	See *Table 81: Selection type* below		Select a 2D or 3D standard deviation type to obtain the best position from the BESTPOS log	Enum	4	H
3	delay	0 to 100 s		Set the number of seconds to wait before changing the position type. Default=0	Ulong	4	H+4

Table 81: Selection type

ASCII	Binary	Description
POS3D	0	3D standard deviation
POS2D	1	2D standard deviation

2.172 SETDIFFCODEBIASES

Sets satellite differential code biases

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Changing the biases may negatively affect positioning accuracy. NovAtel recommends that only advanced users modify the biases.

Use this command to set the differential code biases that correct pseudorange errors affecting the L1/L2 ionospheric corrections. Bias values are restricted to between -10 ns and +10 ns. A set of biases is included in the firmware and use of the biases is enabled by default.

The receiver uses the C/A code on L1 and the P code on L2 to calculate a dual-frequency ionospheric correction. However, the GNSS clock corrections are broadcast as if the P codes on both L1 and L2 are used to calculate this correction. The biases account for the differences between the P and C/A codes on L1 and improve the estimate of the ionospheric correction.

The biases are calculated by the International GNSS Service (IGS). For more information, see https://igs.org/products/#differential_code_bias.

Message ID: 687

Abbreviated ASCII syntax:

```
SETDIFFCODEBIASES bias_type biases
```

ASCII example:

```
<SETDIFFCODEBIASES COM1 2 91.0 UNKNOWN 0 0.470 02440020 365b 32768

<   GPS_C1P1 1.302 -1.326 1.360 1.649 1.357 1.586 0.776 -0.079 -0.123 0.888 -
0.321 0.718 0.527 -0.720 1.193 -1.331 0.828 -1.061 -2.497 -2.106 -1.979 -2.747 -
0.254 1.202 -0.716 0.077 -0.180 -1.059 1.269 -0.481 0.734 1.516 0.000 0.000
0.000 0.000 0.000 0.000 0.000 0.000

<SETDIFFCODEBIASES COM1 1 91.0 UNKNOWN 0 0.471 02440020 365b 32768

<   GLONASS_C1P1 -0.092 0.381 0.581 1.033 0.642 -0.561 0.794 0.899 0.380 -0.832
-0.358 -0.606 -2.181 0.023 1.135 0.346 0.009 0.384 -1.394 0.224 -0.022 -0.824 -
0.133 -0.437 0.000 0.608 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000
0.000 0.000 0.000 0.000 0.000

<SETDIFFCODEBIASES COM1 0 91.0 UNKNOWN 0 0.473 02440020 365b 32768

<   GPS_C2P2 1.358 0.000 -0.381 0.000 -0.344 -0.707 0.306 -1.068 0.624 1.480
0.000 -0.401 0.000 0.000 -0.169 0.0 00 0.236 0.000 0.000 0.000 0.000 0.000 0.000
0.051 -0.711 1.082 -0.128 0.000 -0.101 -0.483 -0.630 -0.015 0.000 0.0 00 0.000
0.000 0.000 0.000 0.000 0.000
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETDIFFCODEBIASES header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	bias_type	GPS_C1P1	0	Code pair to which biases refer	Enum	4	H
		GPS_C2P2	1				
		GLONASS_C1P1	2				
3	biases	-10 to +10 ns		Array of 40 biases (ns)	Float[40]	160	H+4

2.173 SETIONOTYPE

Enables ionospheric models

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to set which ionospheric corrections model the receiver should use. If the selected model is not available, the receiver reverts to AUTO.

L1 only models automatically use SBAS ionospheric grid corrections, if available.

Message ID: 711

Abbreviated ASCII syntax:

```
SETIONOTYPE model
```

Factory default:

```
SETIONOTYPE auto
```

ASCII example:

```
SETIONOTYPE Klobuchar
```

An ionotype of AUTO is recommended for PDP and GLIDE.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETIONOTYPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	model	NONE	0	Do not use ionosphere modelling	Enum	4	H
		KLOBUCHAR	1	Use the Klobuchar model broadcast by GPS			
		GRID	2	Use the SBAS grid model			
		L1L2	3	Multi-frequency computed			
		AUTO	4	Automatically determine the ionospheric model to use			

2.174 SETNAV

Sets start and destination waypoints

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command permits entry of one set of navigation waypoints (see *Figure 11: Illustration of SETNAV parameters* below). The origin (from) and destination (to) waypoint coordinates entered are considered on the ellipsoidal surface of the current datum (default wgs84). Once **SETNAV** has been set, monitor the navigation calculations and progress by observing messages in the **NAVIGATE** log (see page 749).

Track offset is the perpendicular distance from the great circle line drawn between the from lat-lon and to lat-lon waypoints. It establishes the desired navigation path or track, that runs parallel to the great circle line, which now becomes the offset track, and is set by entering the track offset value in metres. A negative track offset value indicates that the offset track is to the left of the great circle line track. A positive track offset value (no sign required) indicates the offset track is to the right of the great circle line track (looking from origin to destination). See *Figure 11: Illustration of SETNAV parameters* below for clarification.

Message ID: 162

Abbreviated ASCII syntax:

```
SETNAV fromlat fromlon tolat tolon trackoffset from-point to-point
```


Factory default:

```
SETNAV 90.0 0.0 90.0 0.0 0.0 from to
```

ASCII example:

```
SETNAV 51.1516 -114.16263 51.16263 -114.1516 -125.23 FROM TO
```

Figure 11: Illustration of SETNAV parameters



Consider the case of setting waypoints in a deformation survey along a dam. The surveyor enters the From and To point locations, on either side of the dam using the **SETNAV** command. They then use the NAVIGATE log messages to record progress and show where they are in relation to the From and To points.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETNAV header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	fromlat	± 90 degrees		Origin latitude in units of degrees/decimal degrees. A negative sign for South latitude. No sign for North latitude	Double	8	H
3	fromlon	± 180 degrees		Origin longitude in units of degrees/decimal degrees. A negative sign for West longitude. No sign for East longitude	Double	8	H+8
4	tolat	± 90 degrees		Destination latitude in units of degrees/decimal degrees	Double	8	H+16
5	tolon	± 180 degrees		Destination longitude in units of degrees/decimal degrees	Double	8	H+24
6	trackoffset	± 1000 km		Waypoint great circle line offset (in metres) establishes offset track. Positive indicates right of great circle line and negative indicates left of great circle line	Double	8	H+32
7	from-point	5 characters maximum		ASCII origin station name	String [max 5]	Variable[1]	H+40
8	to-point	5 characters maximum		ASCII destination station name	String [max 5]	Variable[1]	Variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.175 SETROVERID

Set ID for ALIGN rovers

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This command sets the Rover ID output in the **ROVERPOS** log (see page 889), **HEADING2** log (see page 668), **ALIGNBSLNXYZ** log (see page 493) and **ALIGNBSLNENU** log (see page 491).

The default value for the ID is set using the last seven characters of the receiver PSN Number. For example, if the receiver PSN number is DMMU20240186H, the ID is set as Y86H, i.e., 24 is represented as Y and last three characters are filled in as is. The fourth and fifth last characters are ignored.

It is not guaranteed that each receiver will have a unique auto-generated ID. Use this command to set the ID in case the auto-generated ID overlaps with other rovers. It is the user's responsibility to ensure each receiver ID is unique (if they own multiple receivers). If the ID overlaps, use this command to set the ID.

Message ID: 1135

Abbreviated ASCII syntax:

```
SETROVERID rovid
```

Factory default:

If the receiver PSN is: DAB07170027

```
SETROVERID R027
```

Input example

```
SETROVERID rov1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETROVERID header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	rovid	4 Character String e.g., ROV1		ID String (maximum 4 characters plus NULL)	String[5]	4 or 8[1]	H

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.176 SETTIMEBASE

Sets primary and backup systems for time base

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command configures the primary and backup steering systems for timing.

- The primary system is the system to which the receiver steers the clock.
- The backup systems are used whenever the primary system is not present.

Upon start-up, the primary system must be present long enough to steer the clock to be valid once, otherwise, the backup system cannot be used.



This command does not control which systems are used to set the time. Use the **SETTIMESOURCE** command on page 406 to control which systems are used to set the time.



The system selected must be included in the solution before it can steer the clock.

As NavIC is a locked out system by default, it must be unlocked if selected by this command.

See **LOCKOUTSYSTEM** command on page 248 and **UNLOCKOUTSYSTEM** command on page 451 for more details.

Message ID: 1237

Abbreviated ASCII syntax:

```
SETTIMEBASE primarysystem numbackups[system[timeout]]
```

Factory default:

For GLONASS only receiver:

```
SETTIMEBASE glonass 0
```

For GPS capable receiver:

```
SETTIMEBASE gps 1 auto 0
```

For BeiDou only receiver:

```
SETTIMEBASE beidou 0
```

Input example:

```
SETTIMEBASE gps 1 glonass 30
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETTIMEBASE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	primarysystem	*Table 82: System used for timing* below		The primary system for steering the receiver clock	Enum	4	H
3	numbackups	0 or 4		The number of records to follow. When more than one backup system is specified, the backup systems are selected according to numeric order.	Ulong	4	H+4
4	system[1]	*Table 82: System used for timing* below		The system to be used for backup	Enum	4	H+8
5	timeout[1]	0 to +4294967295 (seconds)		Duration that the backup system is used to steer the clock. 0 means ongoing	Ulong	4	H+12

Table 82: System used for timing

Binary	ASCII
0	GPS[2]
1	GLONASS
2	GALILEO
3	BEIDOU
4	NAVIC
99	AUTO[3]

1. The *system* and *timeout* fields can repeat.
2. GPS setting includes QZSS satellites.
3. AUTO is used only as a backup system (not available for primary system field).

2.177 SETTIMESOURCE

Sets systems for setting time

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This command configures the satellite systems that may be used to set the receiver time. Any of the systems specified can set the time, however systems not specified cannot set the time.

This is different from the **SETTIMEBASE** command (see page 404), which configures the systems that can steer the receiver clock.

Once the time has been set by a particular system, the primary system specified in the **SETTIMEBASE** command (see page 404) must also be present to steer the receiver clock from COARSESTEERING to FINESTEERING.

Message ID: 2484

Abbreviated ASCII syntax:

```
SETTIMESOURCE numsystems system
```

Factory default:

```
SETTIMESOURCE 3 gps beidou galileo
```

ASCII examples:

```
SETTIMESOURCE 1 glonass
SETTIMESOURCE 2 gps galileo
SETTIMESOURCE 6 gps beidou glonass galileo navic qzss
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	SETTIMESOURCE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	numsystems	1 to 6		The number of systems that can set the time.	Ulong	4	H
3	system	See *Table 83: Systems used for time setting* on the next page		The systems used to set the time.	Enum	4	H+4

Table 83: Systems used for time setting

Binary	ASCII
0	GPS
1	GLONASS
5	GALILEO
6	BEIDOU
7	QZSS
9	NAVIC

2.178 SETTROPOMODEL

Sets troposphere model

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the troposphere model used to correct ranges used in the PSRPOS and PDPPOS solutions.

Message ID: 1434

Abbreviated ASCII syntax:

```
SETTROPOMODEL model
```

Factory default:

```
SETTROPOMODEL auto
```

Input example:

```
SETTROPOMODEL none
```

Disabling the troposphere model may negatively affect positioning accuracy. NovAtel recommends that only advanced users modify this setting.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETTROPOMODEL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	model	NONE	1	Do not apply any troposphere corrections	Enum	4	H
		AUTO	2	Automatically use an appropriate model			

2.179 SETUTCLEAPSECONDS

Sets future leap seconds

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command allows the user to force the UTC offset to be updated according to the input date.

Leap seconds will occur at the end of the UTC day specified. The receiver will use the leap second set by this command until a leap second can be obtained over the air.

Message ID: 1150

Abbreviated ASCII syntax:

```
SETUTCLEAPSECONDS seconds [futureweek [futureday [futureseconds]]]
```

Input example:

```
SETUTCLEAPSECONDS 18 1929 7 18
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETUTCLEAPSECONDS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Seconds[1]	0 – 4294967295		Current UTC leap second.	Ulong	4	H
3	Futureweek	0 – 10000		GPS Week when future leap seconds will take effect.	Ulong	4	H+4
4	Futureday	1 – 7		Day of the week when future leap seconds will take effect.	Ulong	4	H+8
5	Futureseconds	0 – 4294967295		Future leap second offset that will take effect at the end of the futureday number of the futureweek number.	Ulong	4	H+12

1. This value will only be applied if the UTC status in the TIME log is not Valid.

2.180 SOFTLOADCOMMIT

Completes the SoftLoad process

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command completes the SoftLoad process by verifying the downloaded image and activating it. Refer to Updating Using SoftLoad Commands in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for more information about the SoftLoad process.

This command can only be sent to the receiver when the **SOFTLOADSTATUS** log (see page 987) reports READY_FOR_DATA.

After issuing the **SOFTLOADCOMMIT** command the user must wait for the OK or ERROR command response before proceeding. This response is guaranteed to be output from the receiver within 300 seconds from the time the command was received by the receiver. If an error response is returned, consult the **SOFTLOADSTATUS** log on page 987 for more detail.

Message ID: 475

Abbreviated ASCII syntax:

```
SOFTLOADCOMMIT
```

Input example:

```
SOFTLOADCOMMIT
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SOFTLOADCOMMIT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Reserved	-		Reserved. Set to 1 in the binary case	Enum	4	H

2.181 SOFTLOADDATA

Sends firmware image data to the receiver for the SoftLoad process

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is only valid in binary mode.

This command is used to upload data to the receiver for the SoftLoad process. Refer to Updating Using SoftLoad Commands in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for more information about the SoftLoad process.

After each **SOFTLOADDATA** command, the user must wait for the OK or ERROR command response before proceeding. This response is guaranteed to be output from the receiver within 15 seconds from the time the command was received by the receiver. If an error response is returned, consult the **SOFTLOADSTATUS** log on page 987 for more detail.

This command can only be sent to the receiver after the **SOFTLOADSREC** command (see page 417) or **SOFTLOADSETUP** command (see page 415) have sent the content of the S0 records from the start of a firmware *.shex file. In these cases, the **SOFTLOADSTATUS** log (see page 987) reports READY_FOR_SETUP or READY_FOR_DATA.

Message ID: 1218

Abbreviated ASCII syntax:

Not applicable

Field	Field type	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	SOFTLOADDATA header NovAtel binary message header	-	H	0
2	offset	-	Offset of the data within the downloaded image	Ulong	4	H
3	data length	-	Number of bytes of data. This must match the number of bytes contained within the “data” field	Ulong	4	H+4
4	data	-	Incoming data up to a maximum of 4096 bytes When using a CAN interface, the incoming data has a maximum of 256 bytes.	Uchar	4096	H+8

2.182 SOFTLOADFILE

Updates firmware using file devices of the receiver

Platform: PwrPak7

The **SOFTLOADFILE** command applies only to receivers with internal data storage.

To use the **SOFTLOADFILE** command, the option must be enabled using the **IPSERVICE** command (see page 226).

Receivers with storage for data logging can also store firmware images to be flashed onto the receiver. Using FTP, .shex or .sbin files are uploaded and the **SOFTLOADFILE** command programs a firmware file to be used on next boot. ASCII **.shex** files contain the required metadata to be used directly without further user input. However, binary **.sbin** files do not and require other SOFTLOAD commands to reset the process and set the Version, Platform, and Type values. See docs.novatel.com/OEM7/Content/Firmware_Update/Updating_Using_SoftLoad.htm

Use of binary images is recommended as binary images (.sbin) take significantly less time to flash than ASCII images (.shex). Binary image files are available on request from NovAtel Support.

Message ID: 1302

Abbreviated ASCII syntax:

```
SOFTLOADFILE StorageDevice Filename [Reserved]
```

ASCII examples:

```
SOFTLOADFILE INTERNAL_FLASH OM7MR0705RN0000.sbin
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	SOFTLOADFILE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	StorageDevice	USBSTICK	1	This allows .shex files to be flashed on to the receiver from an attached USB stick containing the files.	Enum	4	H
		INTERNAL_ FLASH	4	The source device on which the firmware file is stored.			
3	Filename	Character string		File name of the firmware file. (128 characters maximum)	Char (max 128)	Variable[1]	H+4
4	Reserved				Int	4	H+132

Binary file example:

This example shows how to load the binary file EP7PR0705RN0000.sbin.

1. Upload the EP7PR0705RN0000.sbin firmware file via FTP.
2. Enter `LOG SOFTLOADSTATUS ONNEW`.
3. Enter `SOFTLOADRESET`.
4. Enter `SOFTLOADSETUP DATATYPE APP`.
5. Enter `SOFTLOADSETUP VERSION EP7PR0705RM0000` (version string).
6. Enter `SOFTLOADSETUP PLATFORM OEM7700` (must match receiver platform ID).
7. Enter `SOFTLOADFILE INTERNAL_FLASH EP7PR0705RN0000.sbin`.
8. Enter `RESET` when the SoftLoad status shows **COMPLETE**.

ASCII file example:

This example shows how to load the ASCII file EP7PR0705RN0000.shex.

1. Upload the EP7PR0705RN0000.shex firmware file via FTP.
2. Enter `LOG SOFTLOADSTATUS ONNEW`.
3. Enter `SOFTLOADFILE INTERNAL_FLASH EP7PR0705RN0000.shex`.
4. Enter `RESET` when the SoftLoad status shows **COMPLETE**.

1. In the binary case, the string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.183 SOFTLOADRESET

Initiates a new SoftLoad process

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command restarts the SoftLoad process. Refer to Updating Using SoftLoad Commands in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for more information about the SoftLoad process.

The command does not affect the flash and does not reset the receiver.

The **SOFTLOADRESET** command can be issued at any time. If it is issued while a SoftLoad process is currently in progress then that process is terminated and a new one is started. After the **SOFTLOADRESET** command is processed the SOFTLOADSTATUS log will report a status of READY_FOR_SETUP.

After issuing the **SOFTLOADRESET** command the user must wait for the OK or ERROR command response before proceeding. This response is guaranteed to be output from the receiver within 300 seconds from the time the command was received by the receiver. If an error response is returned, consult the **SOFTLOADSTATUS** log on page 987 for more detail.

Message ID: 476

Abbreviated ASCII syntax:

```
SOFTLOADRESET
```

Input example:

```
SOFTLOADRESET
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SOFTLOADRESET header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Reserved	-	-	Reserved. Set to 1 in the binary case	Enum	4	H

2.184 SOFTLOADSETUP

Sends configuration information to the receiver for the SoftLoad process

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **SOFTLOADSETUP** command can be used in place of the **SOFTLOADSREC** command when sending S0 Records. This command is meant to be used if the user requires that the entire SoftLoad process be performed in binary, but can also be used in ASCII or abbreviated ASCII. The examples below are given in abbreviated ASCII for simplicity.

Refer to Updating Using SoftLoad Commands in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for more information about the SoftLoad process.

This command can only be sent to the receiver when the SOFTLOADSTATUS log reports READY_FOR_ SETUP.

After each **SOFTLOADSETUP** command, the user must wait for the OK or ERROR command response before proceeding. This response is guaranteed to be output from the receiver within 15 seconds from the time the command was received by the receiver. If an error response is returned, consult the **SOFTLOADSTATUS** log on page 987 for more detail.

NovAtel S0 records use the following format: **S0~X~<<DATA>>**, where **X** is the Setup Type and **<<DATA>>** is a NULL terminated string. To convert from S0 record to the SOFTLOADSETUP command, convert the Setup Type to the appropriate Setup type enumeration, as described in *Table 84: Available set up commands* on the next page, and copy the <<DATA>> string in to the Setup data string.

Message ID: 1219

Abbreviated ASCII syntax:

```
SOFTLOADSETUP setuptype setupdata
```

Input example:

```
SOFTLOADSETUP datatype "APP"
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SOFTLOADSETUP header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Setuptype	See *Table 84: Available set up commands* on the next page		The type of setup command	Enum	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	Setupdata	-	-	ASCII setup data string. See *Table 84: Available set up commands* below for details on this data. This data can be pulled from the S0 records of the hex file being loaded onto the receiver. If the ASCII form of this command is used, this string must be enclosed in double quotes (“ “)	String [512]	variable[1]	H+4

Table 84: Available set up commands

Binary	ASCII	Description
1	Platform	Comma separated list of platforms supported by the data to be uploaded. This corresponds to S0~P~. For example, the S-Record S0~P~OEM729,OEM7700,OEM719, translates to SOFTLOADSETUP PLATFORM "OEM729,OEM7700,OEM719"
2	Version	Version of the data to be uploaded. This corresponds to S0~V~. For example, the S-Record S0~V~OMP070400RN0000, translates to SOFTLOADSETUP VERSION "OMP070400RN0000"
3	Datatype	Intended data block for the data to be uploaded. This corresponds to S0~T~. For example, the S-Record S0~T~APP, translates to SOFTLOADSETUP DATATYPE "APP"
4	Authcode	PSN and AUTH code for the data to be uploaded. The format is: PSN:AuthCode.Note that since there are commas within the AuthCode, double quotes must surround the PSN:AuthCode string. For example: SOFTLOADSETUP AUTHCODE "BFN10260115: T48JF2,W25DBM,JH46BJ,2WGHMJ,8JW5TW,G2SR0RCCR,101114"

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.185 SOFTLOADSREC

Sends an S-Record to the receiver for the SoftLoad process

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to send S-Records to the receiver for the SoftLoad process. Refer to Updating Using SoftLoad Commands in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for more information about the SoftLoad process.

After each **SOFTLOADDATA** command, the user must wait for the OK or ERROR command response before proceeding. This response is guaranteed to be output from the receiver within 15 seconds from the time the command was received by the receiver. If an error response is returned, consult the **SOFTLOADSTATUS** log on page 987 for more detail.

This command can only be sent to the receiver when the SOFTLOADSTATUS log reports READY_FOR_SETUP or READY_FOR_DATA.

Message ID: 477

Abbreviated ASCII syntax:

```
SOFTLOADSREC s-record
```

Input example:

```
SOFTLOADSREC "S30900283C10FAA9F000EF"
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SOFTLOADSREC header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	s-record	-		ASCII S-Record string copites from firmware *.shex file	String [515]	variable[1]	H
3	Reserved	-	1	Reserved. Set to 1 in the binary case	Ulong	4	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.186 STATUSCONFIG

Configures RXSTATUSEVENT mask fields

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to configure the various status mask fields in the **RXSTATUSEVENT** log (see page 932). These masks can modify whether various status fields generate errors or event messages when they are set or cleared.

Receiver Errors automatically generate event messages. These event messages are output in **RXSTATUSEVENT** log (see page 932). It is also possible to have status conditions trigger event messages to be generated by the receiver. This is done by setting/clearing the appropriate bits in the event set/clear masks. The set mask tells the receiver to generate an event message when the bit becomes set. Likewise, the clear mask causes messages to be generated when a bit is cleared. To disable all these messages without changing the bits, simply UNLOG the **RXSTATUSEVENT** log (see page 932) on the appropriate ports. Refer also to Built-In Status Tests in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual.



The receiver gives the user the ability to determine the importance of the status bits. In the case of the Receiver Status, setting a bit in the priority mask causes the condition to trigger an error. This causes the receiver to idle all channels, set the ERROR strobe line, flash an error code on the status LED, turn off the antenna (LNA power) and disable the RF hardware, the same as if a bit in the Receiver Error word is set. Setting a bit in an Auxiliary Status priority mask causes that condition to set the bit in the Receiver Status word corresponding to that Auxiliary Status.

Message ID: 95

Abbreviated ASCII syntax:

```
STATUSCONFIG type word mask
```

Factory default:

```
STATUSCONFIG PRIORITY STATUS 0
STATUSCONFIG PRIORITY AUX1 0x00001008
STATUSCONFIG PRIORITY AUX2 0x00000000
STATUSCONFIG PRIORITY AUX3 0x00200000
STATUSCONFIG SET STATUS 0
STATUSCONFIG SET AUX1 0x00000000
STATUSCONFIG SET AUX2 0x80000000
STATUSCONFIG SET AUX3 0x10000008
STATUSCONFIG SET AUX4 0xFFFFFFFF
STATUSCONFIG CLEAR STATUS 0
STATUSCONFIG CLEAR AUX1 0
STATUSCONFIG CLEAR AUX2 0
STATUSCONFIG CLEAR AUX4 0
```

ASCII example:

```
STATUSCONFIG SET STATUS 0028A51D
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	STATUSCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	type	PRIORITY	0	Replace the Priority mask	Enum	4	H
		SET	1	Replace the Set mask			
		CLEAR	2	Replace the Clear mask			
3	word	STATUS	1	Receiver Status word	Enum	4	H+4
		AUX1	2	Auxiliary 1 Status word			
		AUX2	3	Auxiliary 2 Status word			
		AUX3	4	Auxiliary 3 Status word			
		AUX4	5	Auxiliary 4 Status word			
4	mask	8 digit hexadecimal		The hexadecimal bit mask	Ulong	4	H+8

2.187 STEADYLINE

Configures position mode matching

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

The STEADYLINE functionality helps mitigate the discontinuities that often occur when a GNSS receiver changes positioning modes. The effect is especially evident when a receiver transitions from an RTK position mode solution to a lower accuracy “fall back” solution, such as DGPS, WAAS+GLIDE or even autonomous GLIDE. Smooth transitions are particularly important for agricultural steering applications where sudden jumps may be problematic.

The STEADYLINE internally monitors the position offsets between all the positioning modes present in the receiver. When the receiver experiences a position transition, the corresponding offset is applied to the output position to limit a potential real position jump. When the original accurate position type returns, the STEADYLINE algorithm will slowly transition back to the new accurate position at a default rate of 0.005 m/s. This creates a smoother pass-to-pass relative accuracy at the expense of a possible degradation of absolute accuracy.

For example, a receiver can be configured to do both RTK and GLIDE. If this receiver has a fixed RTK position and experiences a loss of correction data causing the loss of the RTK solution it will immediately apply the offset between the two position modes and uses the GLIDE position stability to maintain the previous trajectory. Over time the GLIDE (or non-RTK) position will experience some drift. Once the RTK position is achieved again the receiver will start using the RTK positions for position stability and will slowly transition back to the RTK positions at a default rate of 0.005 m/s.

Message ID: 1452

Abbreviated ASCII syntax:

```
STEADYLINE mode [transition_time]
```

Factory default:

```
STEADYLINE disable
```

ASCII example:

```
STEADYLINE prefer_accuracy 100
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	STEADYLINE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	mode	See *Table 85: STEADYLINE mode* on the next page		STEADYLINE mode	Enum	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	transition_ time			Time over which solutions will transition in seconds. The minimum rate of change is 0.005 m/s regardless of this parameter. Default = -1, which sets the parameter to the minimum value 0.005 m/s.	Ulong	4	H+4

Table 85: STEADYLINE mode

ASCII	Binary	Description
DISABLE	0	Disable STEADYLINE (default)
RESET	3	Reset the offsets, jump immediately to the current position and continue in the current mode.
PREFER_ ACCURACY	4	Slowly transition to the new reference position when changing from less accurate reference positioning type to more accurate reference positioning type. Maintains the position offset calculated when changing from more accurate reference positioning type to a less accurate reference positioning type.

2.188 STEADYLINEDIFFERENTIALTIMEOUT

Sets how long the receiver will report RTK/PPP after corrections are lost

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this command to set how long STEADYLINE will report RTK or PPP solutions after a loss of corrections. If able, STEADYLINE will report an RTK or PPP solution until this timeout expires or until the RTK/PPP timeout expires, whichever is higher.

For example:

- If the **RTKTIMEOUT** is 60 seconds and the **STEADYLINEDIFFERENTIALTIMEOUT** is 300 seconds, STEADYLINE will report an RTK solution for 300 seconds.
- If the **RTKTIMEOUT** is 60 seconds and the **STEADYLINEDIFFERENTIALTIMEOUT** is 30 seconds, STEADYLINE will report an RTK solution for 60 seconds.

Message ID: 2002

Abbreviated ASCII syntax:

```
STEADYLINEDIFFERENTIALTIMEOUT timeout
```

Factory default:

```
STEADYLINEDIFFERENTIALTIMEOUT 60
```

ASCII example:

```
STEADYLINEDIFFERENTIALTIMEOUT 300
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	STEADYLINEDIFFERENTIAL TIMEOUT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	timeout	5 to 1200		Timeout period in seconds	Float	4	H

2.189 SURVEYPOSITION

Saves or deletes a surveyed position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to add or delete a surveyed position saved in the receiver NVM.

The surveyed positions added or deleted with this command are used in conjunction with the **AUTOSURVEY** command on page 89.

The maximum number of surveys that can be saved to memory is 32. If this number is exceeded, the new position entry will overwrite the last entry reported by the **SAVEDSURVEYPOSITIONS** log.

Message ID: 1952

Abbreviated ASCII syntax:

```
SURVEYPOSITION option id [latitude] [longitude] [height] [tolerance]
```

ASCII examples:

```
SURVEYPOSITION save auto 51.116 -114.038 1065.0 10.0
SURVEYPOSITION delete cal2
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SURVEYPOSITION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	SAVE	1	Save the surveyed position in the receiver NVM	Enum	4	H
		DELETE	2	Delete the surveyed position from the receiver NVM			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	id			ID for the saved position When saving a position, "AUTO" can be entered and the receiver will automatically generate a unique ID for the position. "AUTO" cannot be used when deleting a position. To determine the ID for a saved position, use the **SAVEDSURVEYPOSITIONS** log on page 948.	String[5]	4 or 8[1]	H+4
4	latitude	-90 to 90		Latitude of the position in degrees (default=0.0) A "-" sign denotes south and a "+" sign denotes north	Double	8	H+8 or H+12
5	longitude	-360 to 360		Longitude of the position in degrees (default=0) A "-" sign denotes west and a "+" sign denotes east	Double	8	H+16 or H+20
6	height	-1000 to 20000000		Mean Sea Level height of the position in metres (default=0.0)	Double	8	H+24 or H+28
7	tolerance	3 - 100		Position tolerance in metres (default=10.0) The maximum distance between the position calculated during an self-survey and the saved position. During the self-survey, if the distance between the calculated position and the previously surveyed position is less than this value, the previous position is used.	Double	8	H+32 or H+36

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment. The next defined field starts immediately at the next 4-byte alignment following the NULL.

2.190 TECTONICSCOMPENSATIONSOURCE

Chooses the model to use for tectonics compensation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to enable tectonics (plate motion) compensation.

Message ID: 2290

Abbreviated ASCII syntax:

```
TECTONICSCOMPENSATIONSOURCE model
```

Factory default:

```
TECTONICSCOMPENSATIONSOURCE plate_motion_model
```

ASCII example:

```
TECTONICSCOMPENSATIONSOURCE none
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	TECTONICS COMPENSATION SOURCE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	model	NONE	0	Do not use a tectonics model.	Enum	4	H
		PLATE_ MOTION_ MODEL	1	Automatically determine the plate the receiver is on and use the plate motion model of that plate.			
3	reserved				Char[32]	variable	H+4

2.191 TERRASTARAUTOCHANCONFIG

Enable channel configurations granted by eligible TerraStar subscriptions

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command allows the receiver to use a subscription managed channel configuration while an eligible TerraStar or Oceanix subscription is active. This enables the receiver to make the best use of the subscription while computing PPP position solutions.

Subscription Managed Channel Configuration (SMCC) has precedence over **SELECTCHANCONFIG**. When the receiver is reset, any user selected channel configuration will be overwritten by the channel configuration chosen by SMCC.
The **SELECTCHANCONFIG** command (see page 375) is disabled while SMCC is active.

To enable this feature, issue the **TERRASTARAUTOCHANCONFIG ENABLE** command. If an eligible subscription is active, as reflected in the **TERRASTARINFO** log (see page 994) or **OCEANIXINFO** log (see page 756), the channel configuration (see **CHANCONFIGLIST** log on page 550) will be modified on the next reboot.

Eligible subscriptions include: TerraStar-X, TerraStar-C PRO, RTK ASSIST PRO, RTK ASSIST, or Oceanix-H.

Message ID: 2284

Abbreviated ASCII syntax:

```
TERRASTARAUTOCHANCONFIG switch
```

Factory default:

```
TERRASTARAUTOCHANCONFIG ENABLE
```

ASCII example:

```
TERRASTARAUTOCHANCONFIG ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	TERRASTARAUTOCHAN CONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	switch	DISABLE	0	The receiver does not use the channel configuration granted by the TerraStar/Oceanix subscription.	Enum	4	H
		ENABLE	1	The receiver uses the channel configuration granted by the TerraStar/Oceanix subscription.			

2.192 THISANTENNAPCO

Sets the PCO model of this receiver

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use the **THISANTENNAPCO** command to set the Phase Centre Offsets (PCO) for the given frequency of this receiver. The Offsets are defined as North, East and Up from the Antenna Reference Point to the Frequency Phase Centre in mm.

Additionally, for RTK, the position needs to be requested relative to the Antenna Reference Point (ARP) using the **RTKANTENNA** command (see page 335) to ensure that the **THISANTENNAPCO** settings are applied correctly. For PPP, the PCOs are applied to the position by default.

Message ID: 1417

Abbreviated ASCII syntax:

```
THISANTENNAPCO Frequency[NorthOffset][EastOffset][UpOffset]
```

ASCII example:

```
THISANTENNAPCO GPSL1 0.61 1.99 65.64
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	THISANTENNAPCO header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Frequency	See *Table 22: Frequency type* on page 93		The frequency for which the phase centre offsets are valid.	Enum	4	H
3	NorthOffset			NGS standard Phase Centre North Offset (millimetres).[1]	Double	8	H+4
4	EastOffset			NGS standard Phase Centre East Offset (millimetres).[1]	Double	8	H+12
5	UpOffset			NGS standard Phase Centre Up Offset (millimetres).[1]	Double	8	H+20

1. Enter values as per the NGS standards and tables to define which direction is plus or minus.

2.193 THISANTENNAPCV

Sets the PCV model of this receiver

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use the **THISANTENNAPCV** command to set the Phase Centre Variation (PVC) for the given frequency of this receiver. The Phase Center Variation entries follow the NGS standard and correspond to the phase elevation at 5 degree increments starting at 90 degrees and decreasing to 0.

Message ID: 1418

Abbreviated ASCII syntax:

```
THISANTENNAPCV Frequency[PCVArray]
```

ASCII example:

```
THISANTENNAPCV GPSL1 0.00 -0.020 -0.07 -0.15 -0.24 -0.34 -0.43 -0.51 -0.56 -
0.61 -0.65 -0.69 -0.69 -0.62 -0.44 -0.13 0.28 0.70 1.02
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	THISANTENNAPCV header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Frequency	See *Table 22: Frequency type* on page 93		The frequency for which the phase centre variations is valid.	Enum	4	H
3	PCVArray			NGS standard 19 Element array of Phase Centre Variations for phase variation for 5 degree elevation increments starting at 90 degrees and decreasing to 0. The variances are entered in millimetres.	Double Array [19]	152	H+4

2.194 THISANTENNATYPE

Sets the antenna type of this receiver

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use the **THISANTENNATYPE** command to set the type of antenna being used with the receiver. There are two sources of antenna information:

- An internal table
  The firmware contains a set of predefined antenna and radome types taken from the IGS ANTEX file. Refer to *Table 23: Antenna type* on page 96 and *Table 24: Radome type* on page 105 for the antennas currently supported.
- User-defined antennas
  User-defined antenna types can be entered using the **ANTENNATYPE** command (see page 74).

The **BASEANTENNATYPE** command (see page 95) is used to set the RTK base antenna type.

Message ID: 1420

Abbreviated ASCII syntax:

```
THISANTENNATYPE AntennaType [RadomeType]
```

ASCII examples:

```
THISANTENNATYPE NOV702
THISANTENNATYPE USER_ANTENNA_1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	THISANTENNATYPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	AntennaType	See *Table 23: Antenna type* on page 96 or *Table 17: User-defined antenna type* on page 75		Antenna type	Enum	4	H
3	RadomeType	See *Table 24: Radome type* on page 105		Radome type (default = NONE)	Enum	4	H+4

2.195 TILTCOMPENSATIONCONTROL

Control the application of position corrections for vehicle roll and pitch

Platform: SMART7-I, SMART7-W, SMART2-TB

Use this command to enable or disable the application of position corrections computed by the Terrain Compensation filter to output positions. If disabled, the Terrain Compensation filter will continue to run in the background but the reported position will be the antenna position.



The **TILTFILTER** command on the next page and **TILTZERO** command on page 433, or the **$PMDT** command on page 291, are used to configure the Terrain Compensation feature.

Message ID: 2309

Abbreviated ASCII syntax:

```
TILTCOMPENSATIONCONTROL switch
```

Abbreviated ASCII example:

```
TILTCOMPENSATIONCONTROL ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	TILTCOMPENSATION CONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	switch	DISABLE	0	Disable Terrain Compensation (Tilt) corrections.	Enum	4	H
		ENABLE	1	Enable Terrain Compensation (Tilt) corrections.			

2.196 TILTFILTER

Configure the Terrain Compensation filter

Platform: SMART7-I, SMART7-W, SMART2-TB

Use this command to enable or disable estimation of the system pitch and roll by the Terrain Compensation filter and to set the height of the GNSS antenna above the vehicle control point. The Terrain Compensation filter must be enabled for the Terrain Compensation feature to function.



The **$PMDT** command (see page 291) can also be used to enable and configure the Terrain Compensation filter.

Message ID: 1221

Abbreviated ASCII syntax:

```
TILTFILTER switch antennaheight
```

Abbreviated ASCII example:

```
TILTFILTER ENABLE 3.5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	TILTFILTER header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	switch	DISABLE	0	Disable the Tilt filter.	Enum	4	H
		ENABLE	1	Enable the Tilt filter.			
3	antennaheight	0.0 – 12.7		Height of the GNSS antenna above the vehicle control point (metres). (default = 0.0)	Float	4	H+4
4	Reserved				Ulong	4	H+8
5	Reserved				Ulong	4	H+12



Refer to Terrain Compensation in the SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for information about mounting the SMART antenna and measuring the antenna height.

2.197 TILTZERO

Set the zero level and save Terrain Compensation settings to NVM

Platform: SMART7-I, SMART7-W, SMART2-TB

Use this command to set the internal zero level for Terrain Compensation and to save the settings (including antenna height which is configured with the **TILTFILTER** command on the previous page) to NVM.

Sending this command with the **ZERO** option will set the current roll and pitch as the zero level. Setting the zero level allows the Terrain Compensation filter to account for any mounting offset between the receiver and the vehicle or any inherent tilt of the vehicle. It will also observe the internal sensor biases to allow for better performance of the filter. Zeroing must be conducted while the vehicle is stationary on a flat surface. This option is used for single-stage zeroing.

Sending this command with the **NEW** and **ADD** options will set the zero level when performing two-stage zeroing.

Sending this command with the **SAVE** option will save the zero level and antenna height settings to NVM. Theses settings will be automatically used on following startups.

Sending this command with the **RESTORE** option will clear the saved settings from NVM and restore the factory defaults.



The **$PMDT** command (see page 291) can also be used to zero the filter (single-stage levelling only) and save the settings to NVM.

Message ID: 1222

Abbreviated ASCII syntax:

```
TILTZERO action
```

ASCII example:

```
TILTZERO zero
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	TILTZERO header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	action	ZERO	0	Set the current orientation as zero (level) for single-stage zeroing.	Enum	4	H
		SAVE	1	Saves the current level setting and antenna height to NVM.			
		RESTORE	2	Clear the current Tilt filter settings saved in NVM and restore the factory defaults.			
		NEW	3	Begin a new two stage calibration.			
		ADD	4	Complete a two stage calibration and set the zero level.			

Use the **ZERO** option to perform a single-stage zeroing. Use the **NEW** and **ADD** options to perform a two-stage zeroing.
Refer to Levelling the Terrain Compensation Sensor in the SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for information about single-stage and two-stage zeroing.

2.198 TRACKSIGNAL

Enable or disable tracking of a signal

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Use this command to enable or disable tracking of a signal within the channel configuration signal list.

Primary signals (LBAND and L1/E1/B1I signals) can not be disabled using the **TRACKSIGNAL** command.

Channel configurations containing the B2 signal will either track B2I or B2a signals corresponding to the availability of BeiDou Phase II and Phase III satellites respectively. Due to this, using the BEIDOUB2 option will toggle tracking for both B2I and B2a signals.

By default, the receiver attempts to track all signals in the channel configuration without needing a **TRACKSIGNAL** command. The channel configuration can be determined from the **CHANCONFIGLIST** log (see page 550).

Message ID: 2311

Abbreviated ASCII syntax:

```
TRACKSIGNAL signal track
```

Abbreviated ASCII example:

```
TRACKSIGNAL GPSL2C DISABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	TRACKSIGNAL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	signal	See *Table 86: Signal* on the next page		The signal to enable or disable The signal is expected to match a signal in the current channel configuration.	Enum	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	track	DISABLE	0	Disable tracking of the signal	Enum	4	H+4
		ENABLE	1	Enable tracking of the signal			

Table 86: Signal

Binary	ASCII
1	GPSL2
2	GPSL2P
3	GPSL2C
4	GPSL5
5	GPSL1C
6	SBASL5
7	GLOL2
8	GLOL2P
9	GLOL2C
10	GLOL3
11	GALE5A
12	GALE5B
13	GALALTBOC
14	GALE6
15	QZSSL2C
16	QZSSL5
17	QZSSL1C
18	QZSSL6
19	BEIDOUB1C
20	BEIDOUB2
21	BEIDOUB3
22	BEIDOUB2B

2.199 TRACKSV

Overrides automatic satellite assignment criteria

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to override the automatic satellite/channel assignment for all satellites with manual instructions.

Message ID: 1326

Abbreviated ASCII syntax:

```
TRACKSV system SVID condition
```

Factory default:

```
GPS, GLONASS, GALILEO, QZSS, BeiDou and NavIC default = GOODHEALTH
SBAS default = ANYHEALTH

TRACKSV QZSS 198 NEVER

TRACKSV QZSS 202 NEVER
```

QZSS 198 and QZSS 202 are excluded because they are defined as test PRNs in the QZSS ICD.

Input example:

```
TRACKSV GALILEO 0 ANYHEALTH
```

For dual antenna receivers, this command applies to both the primary and secondary antennas.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	TRACKSV header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	System	See *Table 145: Satellite system* on page 676		System that the SVID belongs to	Enum	4	H
3	SVID	Refer to *PRN numbers* on page 55		Satellite SVID number "0" is allowed and applies to all SVIDs for the specified system type	Ulong	4	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	Condition	See *Table 87: TRACKSV command condition* below		Tracking condition	Enum	4	H+8

Table 87: TRACKSV command condition

Binary	ASCII	Description
1	NEVER	Never track this satellite
2	GOODHEALTH	Track this satellite if the health is indicated as healthy in both the almanac and ephemeris
3	ANYHEALTH	Track this satellite regardless of health status
4	ALWAYS	Always track this satellite

2.200 TUNNELESCAPE

Breaks out of an established tunnel

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The tunnel escape sequence feature allows you to break out of a tunnel between two ports by sending a predefined sequence of bytes through the tunnel in-line with the data stream.

Use the **TUNNELESCAPE** command to specify the tunnel escape sequence. The escape sequence is applied independently to all active tunnels. Use the **SAVECONFIG** command (see page 367) to save the escape sequence in case of a power cycle.

This command is used to define an escape sequence that, when detected in a byte stream between any two COM (or AUX) ports, resets the interface mode to **NOVATEL NOVATEL** on those ports. The baud rate and other port parameters remain unaffected.

The **TUNNELESCAPE** command accepts three parameters. The first is the *switch* parameter with **ENABLE** or **DISABLE** options. The second is the *length* parameter. It is a number from 1 to 8 and must be present if the switch parameter is set to ENABLE. The third parameter, *esc seq*, consists of a series of pairs of digits representing hexadecimal numbers, where the number of pairs are equal to the value entered for the second parameter. The series of hexadecimal pairs of digits represent the escape sequence. The receiver detects a sequence in a tunnel exactly as it was entered.

For example, the command **TUNNELESCAPE ENABLE 4 61626364** searches for the bytes representing “abcd” in a tunnel stream. **TUNNELESCAPE ENABLE 3 AA4412** searches for the NovAtel binary log sync bytes.

You must first set up a tunnel. For example, create a tunnel between COM1 and COM2 by entering **INTERFACEMODE COM1 TCOM2 NONE OFF**. The commands can be entered in any order.

1. All bytes, leading up to and including the escape sequence, pass through the tunnel before it is reset. Therefore, the escape sequence is the last sequence of bytes that passes through the tunnel. Configure the receiver to detect and interpret the escape sequence. For example, use this information to reset equipment or perform a shutdown process.
2. The receiver detects the escape sequence in all active tunnels in any direction.
3. Create tunnels using the **INTERFACEMODE** command (see page 217).

Message ID: 962

Abbreviated ASCII syntax:

```
TUNNELESCAPE switch length escseq
```

Factory default:

```
TUNNELESCAPE disable 0
```

ASCII example:

```
TUNNELESCAPE enable 1 aa
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	TUNNELESCAPE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	H	0	-
2	switch	DISABLE	0	Enable or disable the tunnel escape mode	Enum	4	H
		ENABLE	1				
3	length	1 to 8		Specifies the number of hex bytes to follow	Ulong	4	H+4
4	escseq			Escape sequence where Hex pairs are entered without spaces, for example, AA4412	Uchar[8]	8	H+8

If using the SAVECONFIG command (see page 367) in NovAtel Connect, ensure all windows other than the *Console* window are closed. If open, NovAtel Connect also saves log commands used for its various windows. This results in unnecessary data being logged.

2.201 UALCONTROL

Setup user accuracy levels

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **UALCONTROL** command is used to define User Accuracy Levels. User accuracy levels are user defined standard deviations thresholds, used to determine solution acceptability. Issuing the **UALCONTROL** command causes the BESTPOS and GPGGA solution types to be controlled via the specified thresholds, rather than by the solution source or mode. The new solution types are described in the table below.

Table 88: User accuracy level supplemental position types and NMEA equivalents

Value	BESTPOS position type[1]	NMEA equivalent[2]
70	OPERATIONAL	4
71	WARNING	5
72	OUT_OF_BOUNDS	1

1. As reported in the **BESTPOS** log (see page 527).
2. Refers to the GPGGA quality indicator (see the **GPGGA** log on page 635 for details).

The **SETBESTPOSCRITERIA** command (see page 397) determines which standard deviations are compared against the provided thresholds.



UAL is useful for applications that rely upon specific solutions types being present in the BESTPOS or GPGGA logs. For example, if an agricultural steering system commonly requires an RTK fixed GPGGA solution type (4) to operate, and interruptions in RTK conventionally cause the GPGGA to switch to another solution type. This causes the steering system to disengage.

Message ID: 1627

Abbreviated ASCII syntax:

```
UALCONTROL Action [Operational_limit] [Warning_limit]
```

Factory default:

```
UALCONTROL disable
```

ASCII example:

```
UALCONTROL enable 0.10 0.20
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UALCONTROL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Action	DISABLE	0	Disables this feature	Enum	4	H
		ENABLE	1	Replace BESTPOS and GPGGA position types with OPERATIONAL, WARNING or OUT_OF_BOUNDS based on the entered standard deviations (refer to *Table 88: User accuracy level supplemental position types and NMEA equivalents* on the previous page)			
		CLEAR	2	Disable this feature and reset the entered standard deviations.			
3	Operational_ Limit			Standard deviation in metres to report OPERATIONAL	Double	8	H+4
4	Warning_Limit			Standard deviation in metres to report WARNING OUT_OF_BOUND reports when the standard deviation exceeds this value	Double	8	H+12

2.202 UNASSIGN

Unassigns a previously assigned channel

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command cancels a previously issued **ASSIGN** command (see page 77) and the SV channel reverts to automatic control (the same as **ASSIGN AUTO**).

Message ID: 29

Abbreviated ASCII syntax:

```
UNASSIGN channel [state]
```

Input example:

```
UNASSIGN 11
```

Issuing the **UNASSIGN** command to a channel that was not previously assigned by the **ASSIGN** command (see page 77) has no effect.

For dual antenna receivers:

- On the primary antenna, the SV channel is from 0 to N-1, where N is the number of channels in the primary antenna channel configuration.
- On the secondary antenna, the SV channel count is from at N to N+(M-1), where M is the number of channels in the secondary antenna SV channel configuration.
- Even though L-band channels cannot be configured with **ASSIGN** or **UNASSIGN**, they are included when determining N.

The **ASSIGN** and **UNASSIGN** commands are not accepted for L-band channels. The **ASSIGNLBANDBEAM** command (see page 83) should be used for L-band channels.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UNASSIGN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	channel	0 to N-1, where N is the number of the last GNSS channel in the current channel configuration		Channel number reset to automatic search and acquisition mode	Ulong	4	H
3	state	These return SV channel control to the automatic search engine immediately (see *Table 18: Channel state* on page 79)		Set the SV channel state (currently ignored)	Enum	4	H+4

2.203 UNASSIGNALL

Unassigns all previously assigned channels

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command cancels all previously issued **ASSIGN** or **ASSIGNALL** commands for all SV channels for a satellite system (same as **ASSIGNALL AUTO**). Tracking and control for each SV channel reverts to automatic mode.

Message ID: 30

Abbreviated ASCII syntax:

```
UNASSIGNALL [system]
```

Input example:

```
UNASSIGNALL GPS
```

FW 7.09 For dual antenna receivers, an **UNASSIGNALL** command configures both antennas.

FW 7.10 For dual antenna receivers, an **UNASSIGNALL_1** command is used to configure only the second antenna. An **UNASSIGNALL** command configures only the primary antenna.
The UNASSIGNALL and UNASSIGNALL_1 commands use the same message ID.

Issuing the **UNASSIGNALL** command has no effect on channels that were not previously assigned using the **ASSIGN** command (see page 77) or **ASSIGNALL** command (see page 80).

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UNASSIGNALL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	system	See *Table 19: Satellite system* on page 81		System that will be affected by the **UNASSIGNALL** command (default = ALL)	Enum	4	H

2.204 UNDULATION

Chooses undulation


Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command permits you to enter a specific geoidal undulation value. In the option field, the EGM96 table provides ellipsoid heights at a 0.5° by 0.5° spacing while the OSU89B is implemented at a 2° by 3° spacing. In areas of rapidly changing elevation, you could be operating somewhere within the 2° by 3° grid with an erroneous height. EGM96 provides a more accurate model of the ellipsoid which results in a denser grid of heights. It is also more accurate because the accuracy of the grid points themselves has also improved from OSU89B to EGM96. For example, the default grid (EGM96) is useful where there are underwater canyons, steep drop-offs or mountains.

The undulation values reported in the position logs are in reference to the ellipsoid of the chosen datum.

Refer to the application note APN-006: Geoid Issue, available at novatel.com/support/support-materials/application-notes, for a description of the relationships in *Figure 12: Illustration of undulation* below.

Figure 12: Illustration of undulation



Message ID: 214

Abbreviated ASCII syntax:

```
UNDULATION option [separation]
```

Factory default:

```
UNDULATION egm96 0.0000
```

ASCII example 1:

```
UNDULATION osu89b
```

ASCII example 2:

```
UNDULATION USER -5.599999905
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UNDULATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	USER	1	Use the user specified undulation value	Enum	4	H
		OSU89B	2	Use the OSU89B undulation table			
		EGM96	3	Use global geoidal height model EGM96 table			
3	separation	±1000.0 m		The undulation value (required for the USER option) (default = 0.000)	Float	4	H+4

2.205 UNLOCKOUT

Reinstates a satellite in the solution

The **UNLOCKOUT** command has been deprecated. To allow a satellite that was previously locked out to be reinstated in the solution computation, use the **UNLOCKOUTSATELLITE** command on page 450.

Message ID: 138

2.206 UNLOCKOUTALL

Reinstates all previously locked out satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command allows all satellites or systems which have been previously locked out (**LOCKOUTSATELLITE** command on page 247 or **LOCKOUTSYSTEM** command on page 248) to be reinstated in the solution computation.

Message ID: 139

Abbreviated ASCII syntax:

```
UNLOCKOUTALL
```

Input example:

```
UNLOCKOUTALL
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UNLOCKOUTALL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

2.207 UNLOCKOUTSATELLITE

Reinstates a satellite into the solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command allows a satellite previously locked out using the **LOCKOUTSATELLITE** command (see page 247) to be added back into solution computations. To reinstate multiple satellites that have been locked out, this command must be issued multiple times.

Message ID: 2416

Abbreviated ASCII syntax:

```
UNLOCKOUTSATELLITE system prn
```

ASCII example:

```
UNLOCKOUTSATELLITE gps 10
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	UNLOCKOUTSATELLITE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	system	See *Table 145: Satellite system* on page 676		The satellite system for the satellite being unlocked.	Enum	4	H
3	prn	See *1.6.1 PRN numbers* on page 55		Unique identifier for the satellite being unlocked (added back into the solution).	Ulong	4	H+4

2.208 UNLOCKOUTSYSTEM

Reinstates previously locked out system

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command allows a system which has been previously locked out (refer to the **LOCKOUTSYSTEM** command on page 248) to be reinstated in the solution computation.

If more than one system is to be reinstated, this command must be reissued for each system reinstatement.

Message ID: 908

Abbreviated ASCII syntax:

```
UNLOCKOUTSYSTEM system
```

Input example:

```
UNLOCKOUTSYSTEM glonass
```

The **UNLOCKOUTSYSTEM** command is used to reinstate a system while leaving other locked out systems unchanged.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UNLOCKOUTSYSTEM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	system	See *Table 145: Satellite system* on page 676		A single satellite system to be reinstated	Enum	4	H

2.209 UNLOG

Removes a log from logging control

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is used to remove a specific log request from the system.

Message ID: 36

Abbreviated ASCII syntax:

```
UNLOG [port] message
```

Input example:

```
UNLOG com1 bestposa
UNLOG bestposa
```

The **UNLOG** command is used to remove one or more logs while leaving other logs unchanged.

2.209.1 Binary

Field	Field name	Binary value	Description	Format	Binary bytes	Binary offset
1	UNLOG (binary) header	(See *Table 4: Binary message header structure* on page 40)	This field contains the message header	-	H	0
2	port	See *Table 5: Detailed port identifier* on page 42 (decimal port values greater than 16 may be used)	Port to which log is being sent	Enum	4	H
3	message	Any valid message ID	Message ID of log to output	Ushort	2	H+4
4	message type	Bits 0-4 = Reserved Bits 5-6 = Format 00 = Binary 01 = ASCII 10 = Abbreviated ASCII, NMEA 11 = Reserved Bit 7 = Response Bit (*Message responses* on page 52) 0 = Original Message 1 = Response Message	Message type of log	Char	1	H+6
5	Reserved			Char	1	H+7

2.209.2 ASCII

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	UNLOG (ASCII) header	-	-	This field contains the command name or the message header depending on whether the command is abbreviated ASCII or ASCII, respectively	-	H	0
2	port	See *Table 5: Detailed port identifier* on page 42 (decimal port values greater than 16 may be used)		Port to which log is being sent (default = THISPORT)	Enum	4	H
3	message	Message Name	N/A	Message Name of log to be disabled	Ulong	4	H+4

2.210 UNLOGALL

Removes all logs from logging control

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

If [*port*] is specified, this command disables all logs on the specified port only. All other ports are unaffected. If [*port*] is not specified this command defaults to the ALL_PORTS setting.

Message ID: 38

Abbreviated ASCII syntax:

```
UNLOGALL [port] [held]
```

Input example:

```
UNLOGALL com2_15
UNLOGALL true
```

The **UNLOGALL** command is used to remove all log requests currently in use.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UNLOGALL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	port	See *Table 5: Detailed port identifier* on page 42 (decimal values greater than 16 may be used)		Port to clear (default = ALL_PORTS)	Enum	4	H
3	held	FALSE	0	Does not remove logs with the HOLD parameter (default)	Bool	4	H+4
		TRUE	1	Removes previously held logs, even those with the HOLD parameter			

2.211 USBSTICKEJECT

Prepare a USB stick for removal

Platform: OEM7600, OEM7700, OEM7720, PwrPak7

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this command.

Use this command to unmount the USB stick and prepare it for safe physical removal.

This command may fail with a *Busy* error if there is an ongoing USB stick mounting or unmounting operation.

The **FILETRANSFERSTATUS** log (see page 590) indicates the *USBSTICK UNMOUNTED* status when it is safe to physically remove the stick. This may take up to 10 seconds.

Message ID: 2115

Abbreviated ASCII syntax:

```
USBSTICKEJECT
```

Example:

```
USBSTICKEJECT
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	USBSTICKEJECT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

2.212 USERCANCLOSE

Disable a CAN port

Platform: OEM719, OEM729, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7

Use this command to disable a CAN port. The **USERCANSTATUS** log (see page 1014) can be used to check the completion or status of the operation. An optional user defined Transaction ID can be provided to help synchronize requests with responses in the **USERCANSTATUS** log (see page 1014).

This command is primarily intended to be used by Lua applications that need to interact with external devices.

Closing a CAN port requires the port ID. There are up to 2 CAN buses available on OEM7 receivers, CAN1 and CAN2.

Message ID: 2313

Abbreviated ASCII syntax:

```
USERCANCLOSE PortID [TransactionID]
```

Abbreviated ASCII examples:

```
USERCANCLOSE CAN1 1234
USERCANCLOSE CAN2
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	USERCANCLOSE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	PortID	CAN1	1	The CAN port Identifier.	Enum	4	H
		CAN2	2				
3	TransactionID			An optional user provided ID for this transaction. Default = 0. This transaction ID will copied to the **USERCANSTATUS** log (see page 1014) created for this operation.	Ulong	4	H+4

2.213 USERCANOPEN

Enable a CAN port

Platform: OEM719, OEM729, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7

Use this command to enable a CAN port. The **USERCANSTATUS** log (see page 1014) can be used to check the completion or status of the operation. An optional user defined Transaction ID can be provided to help synchronize requests with responses in the **USERCANSTATUS** log (see page 1014).

This command is primarily intended to be used by Lua applications that need to interact with external devices.

Opening a CAN port requires the port ID. There are up to 2 CAN buses available on OEM7 receivers, CAN1 and CAN2. The speed (i.e. bit rate) must also be specified.

For the CAN hardware to select certain messages on the bus, a set of hardware filters need to be associated with the port.

This command is rejected if the specified CAN port has already been opened. The CAN port can be opened by either a previous **USERCANOPEN** command or a **CANCONFIG** command (see page 112).

Message ID: 2312

Abbreviated ASCII syntax:

```
USERCANOPEN PortID BitRate ElementNum [HWFilters] [TransactionID]
```

Abbreviated ASCII examples:

```
USERCANOPEN CAN1 250K 3 EXT 11111111 00000000 EXT 12222222 00000000 STD 333
00000000 123456
```

```
USERCANOPEN CAN2 100K 0 123457
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	USERCANOPEN header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	PortID	CAN1	1	The CAN port Identifier.	Enum	4	H
		CAN2	2				
3	BitRate	See *Table 89: CAN bit rate* on the next page		The CAN speed.	Enum	4	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	ElementNum	0 - 16		Number of HWFilter Arrays	Ulong	4	H+8

5	HWFilters			An array of class CANHwFilter with the following structure:
				`{`
				`CanMessageTypeEnum eMessageType;`
				`ULONG ulAcceptCode;`
				`ULONG ulAcceptMask;`
				`}`
				Only filters in use need to be provided, so the format for this section (for N elements) is:
				{eMessageType1 ulAcceptCode1 ulAcceptMask1 ... eMessageTypeN ulAcceptCodeN ulAcceptMaskN}
				If N = 0, this whole field is omitted.
				N is the number of elements in the array, which is specified in the *ElementNum* field.
					HWFilter Array	12*N	H+12

6	TransactionID			An optional user provided ID for this transaction. Default = 0. This transaction ID will copied to the **USERCANSTATUS** log (see page 1014) created for this operation.	Ulong	4	H+12+ 12*N

Table 89: CAN bit rate

Binary	ASCII	Description
0	10K	10 Kbits/sec
1	20K	20 Kbits/sec
2	50K	50 Kbits/sec
3	100K	100 Kbits/sec
4	125K	125 Kbits/sec
5	250K	250 Kbits/sec

Binary	ASCII	Description
6	500K	500 Kbits/sec
7	1M	1 Mbits/sec

2.214 USERCANWRITE

Write frames to a CAN port

Platform: OEM719, OEM729, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7

Use this command to write a basic CAN frame to the specified CAN port. The **USERCANSTATUS** log (see page 1014) can be used to check the completion or status of the operation. An optional user defined Transaction ID can be provided to help synchronize requests with responses in the **USERCANSTATUS** log (see page 1014).

This command is primarily intended to be used by Lua applications that need to interact with external devices.

Writing a CAN frame requires a Port ID, which indicates the CAN bus to write to; a identifier type (STANDARD or EXTENDED) and an identifier number. The operation can be set as "blocked" (TimeOutMS > 0) or "non-blocked" (TimeOutMS == 0). If set to "blocked", the operation will wait a certain period of time for a slot in the TX FIFO buffer. For system health reasons, there is no option for the operation to be blocked indefinitely.

Message ID: 2255

Abbreviated ASCII syntax:

```
USERCANWRITE PortID MessageType MessageID Datalength Data [TimeOutMS]
[TransactionID]
```

Abbreviated ASCII examples:

```
USERCANWRITE CAN1 STD 123 8 3132333435363738 12 1234
USERCANWRITE CAN2 EXT 1767 3 ABCDED
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	USERCANWRITE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	Header	0
2	PortID	CAN1	1	The CAN port Identifier.	Enum	4	H
		CAN2	2				
3	MessageType	STD	1	Standard message	Enum	4	H+4
		EXT	2	Extended message			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	MessageID			The Standard message ID has 11 bits. The Extended message ID has 29 bits.	HexUlong	4	H+8
5	Datalength	0 to 8		The length of data to be written in bytes.	Ulong	4	H+12
6	Data			The data to be written. The number of bytes in this data block must match the *DataLength*. In particular, when *DataLength* is 0, this field is empty. For ASCII and Abbreviated ASCII commands, this field is a hexadecimal string of two digits for each byte in the data block. There is no 0x prefix and spaces are not allowed in the string. Data is streamed to the device as a series of bytes in the order provided.	Uchar Array	N[1]	H+16
7	TimeOutMS	0 to 5000		The number of milliseconds for the operation to timeout. Default is 0. If set to 0, there is no wait for a free slot in the TX FIFO. If no slot is available, the data drops and a flag is set in **USERCANSTATUS** log (see page 1014). Maximum value is 5000.	Ulong	4	H+16+4*INT ((N+3)/4)

1. In the binary command/log case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
8	TransactionID			An optional user provided ID for this transaction. Default = 0. This transaction ID is copied to the **USERCANSTATUS** log (see page 1014) created for this write operation.	Ulong	4	H+20+4*INT ((N+3)/4)

2.215 USERDATUM

Sets user customized ellipsoid and datum transformation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command is like the **USEREXPDATUM** command but without parameter rates. See the **USEREXPDATUM** command on page 465 for details on command usage and parameter meaning.

When the **USERDATUM** command is entered, the **USEREXPDATUM** command on page 465 is issued internally with the **USERDATUM** command values. It is the **USEREXPDATUM** command on page 465 that appears in the **RXCONFIG** log (see page 913). Only a single set of **USEREXPDATUM** or **USERDATUM** entered parameters is valid at one time. Newer parameters entered by either command will overwrite previously entered parameters.



See the **DATUM** command on page 133 for important guidance and details on datum operation.

Message ID: 78

Abbreviated ASCII syntax:

```
USERDATUM semi_major_axis flattening dx dy dz rx ry rz scale
```

Factory default:

```
USERDATUM 6378137.0 298.2572235628 0.0 0.0 0.0 0.0 0.0 0.0 0.0
```

ASCII example:

```
USERDATUM 6378206.400 294.97869820000 -12.0000 147.0000 192.0000 0.0000
0.0000 0.0000 0.000000000
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	USERDATUM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	semi_ major_axis	6300000.0 - 6400000.0		Datum semi-major axis (a) (metres)	Double	8	H
3	flattening	290.0 - 305.0		Reciprocal Flattening, 1/f = a/(a-b)	Double	8	H+8
4	dx	± 2000.0		Translation values (metres)	Double	8	H+16
5	dy	± 2000.0			Double	8	H+24
6	dz	± 2000.0			Double	8	H+32

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
7	rx	± 10.0 radians		Datum rotation angles A positive sign is for counter clockwise rotation and a negative sign is for clockwise rotation	Double	8	H+40
8	ry	± 10.0 radians			Double	8	H+48
9	rz	± 10.0 radians			Double	8	H+56
10	scale	± 10.0 ppm		Scale value is the difference in ppm	Double	8	H+64

2.216 USEREXPDATUM

Set custom expanded datum

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command permits entry of customized ellipsoid and datum transformation parameters. The command **DATUM USER** must be sent for the parameters set by **USERDATUM** to take effect.

Only a single set of **USEREXPDATUM** or **USERDATUM** entered parameters is valid at one time. Newer parameters entered by either command will overwrite previously entered parameters.

The transformation used by this command is the 7 parameter Helmert transformation, with the parameters provided being for the transformation from the user datum to WGS84:

$$\begin{bmatrix} X_s \\ Y_s \\ Z_s \end{bmatrix} = \begin{bmatrix} T_x \\ T_y \\ T_z \end{bmatrix} + (1+s) \begin{bmatrix} 1 & -R_z & R_y \\ R_z & 1 & -R_x \\ -R_y & R_x & 1 \end{bmatrix} \begin{bmatrix} X \\ Y \\ Z \end{bmatrix}$$

Where:

X, **Y**, **Z** are the coordinates in the user datum

$\mathbf{X_S}$, $\mathbf{Y_S}$, $\mathbf{Z_S}$ are the coordinates in WGS84

$\mathbf{T_x}$, $\mathbf{T_y}$, $\mathbf{T_z}$ are the translation parameters corrected for translation rate (metres)

$\mathbf{R_x}$, $\mathbf{R_y}$, $\mathbf{R_z}$ are the rotation parameters corrected for rotation rate (radians)

s is the scale difference corrected for scale rate (unitless)

A given parameter P is corrected for rate:

$P(t)=P(t_r)+ \dot{P}(t_r) (t-t_r)$

Where:

$\mathbf{t_r}$ is the reference epoch of the parameters

t is the current epoch

$\mathbf{P(t_r)}$ is the parameter at the reference epoch

$\mathbf{\dot{P}(t_r)}$ is the rate of the parameter at the reference epoch

The convention used by this command differs from that used by the **DATUMTRANSFORMATION** command on page 135, and from parameter conventions seen typically in transformation sources. Care should be taken that the parameter convention matches that in the equation above.



See the **DATUM** command on page 133 for important guidance and details on datum operation.

Message ID: 783

Abbreviated ASCII syntax:

```
USEREXPDATUM semi_major_axis flattening dx dy dz rx ry rz scale xvel yvel
zvel xrvel yrvel zrvel scalevel epoch
```

Factory default:

```
USEREXPDATUM 6378137.0 298.25722356280 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0
0.0 0.0 0.0 0.0 0.0 0.0
```

ASCII example:

```
USEREXPDATUM 6378137.000 298.25722356280 0.000000000 0.000000000 0.000000000
0.00000000 0.000000000 0.000000000 0.000000000 0.000000000 0.000000000
0.000000000 0.000000000 0.000000000 0.000000000 0.000000000 0.000000000
```

Use the **USEREXPDATUM** command in a survey to fix the position with values from another known datum so that the GPS calculated positions are reported in the known datum rather than WGS84. For example, it is useful for places like Australia, where the continent is moving several centimetres a year relative to WGS84. With **USEREXPDATUM**, you can also input the velocity of the movement to account for drift over the years.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	USEREXPDATUM header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	semi_ major_axis	6300000.0 - 6400000.0 m		Datum semi-major axis (a) (metres)	Double	8	H
3	flattening	290.0 - 305.0		Reciprocal Flattening, 1/f = a/(a-b)	Double	8	H+8
4	dx	± 2000.0 m		Translation values (metres)	Double	8	H+16
5	dy	± 2000.0 m			Double	8	H+24
6	dz	± 2000.0 m			Double	8	H+32
7	rx	± 10.0 radians		Datum rotation angles A positive sign is for counter clockwise rotation and a negative sign is for clockwise rotation	Double	8	H+40
8	ry	± 10.0 radians			Double	8	H+48
9	rz	± 10.0 radians			Double	8	H+56
10	scale	± 10.0 ppm		Scale value is the difference in ppm	Double	8	H+64
11	xvel	± 2000.0 m/yr		Velocity vector along X-axis	Double	8	H+72
12	yvel	± 2000.0 m/yr		Velocity vector along Y-axis	Double	8	H+80
13	zvel	± 2000.0 m/yr		Velocity vector along Z-axis	Double	8	H+88
14	xrvel	± 10.0 radians/yr		Change in the rotation about X over time	Double	8	H+96
15	yrvel	± 10.0 radians/yr		Change in the rotation about Y over time	Double	8	H+104

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
16	zrvel	± 10.0 radians/yr		Change in the rotation about Z over time	Double	8	H+112
17	scalevel	± 10.0 ppm/yr		Change in scale from WGS84 over time	Double	8	H+120
18	epoch	0.0 year		Reference epoch of parameters (decimal year) Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	H+128

2.217 USERI2CBITRATE

Set the communication rate for the User I2C bus

Platform: OEM7600, OEM7700, OEM7720

Use this command to set the communication bit rate for the User I2C bus.

Message ID: 2383

Abbreviated ASCII syntax:

```
USERI2CBITRATE BitRate
```

Factory default:

```
USERI2CBITRATE 400K
```

ASCII examples:

```
USERI2CBITRATE 100K
USERI2CBITRATE 400K
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	USERI2CBITRATE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	BitRate	100K	1	Set the User I2C bus communication rate to 100 kbits/s.	Enum	4	H
		400K	2	Set the User I2C bus communication rate to 400 kbits/s.			

2.218 USERI2CREAD

Read data from devices on the I2C bus

Platform: OEM7600, OEM7700, OEM7720

Use this command to read data from devices on the I2C bus.



This command only applies to OEM7 receivers that have I2C signals available on the interface connector. The compatible receivers are listed in the **Platform** section above.

The **USERI2CRESPONSE** log (see page 1016) can be used to check the completion or status of the read operation. An optional user defined Transaction ID can be provided to help synchronize requests with responses in the **USERI2CRESPONSE** log (see page 1016). This command is primarily intended to be used by Lua applications that need to interact with external devices.

Reading from an I2C device requires a device address, to distinguish which physical device is to be accessed, a register within the device, and the expected number of bytes to be read. Depending on the type of I2C device, register addresses can be 1 to 4 bytes in length, so the actual number of bytes for the register address must be specified.

For some I2C devices there are no registers within the device. In this case, the Register Address Length is 0 and no bytes are supplied for the Register Address.

The **USERI2CREAD** command is flexible to handle all of these situations.

Message ID: 2232

Abbreviated ASCII syntax:

```
USERI2CREAD DeviceAddress RegisterAddressLen RegisterAddress RequestReadLen
[TransactionID]
```

Examples:

```
USERI2CREAD 70 1 AB 12 1234

USERI2CREAD 74 3 ABCDEF 234 5678

USERI2CREAD 74 0 234 5678
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Command header	USERI2CREAD header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	DeviceAddress	The 7 bit address of the I2C device. Valid values are 0 through 127. For ASCII and Abbreviated commands, this field is a hexadecimal string of two digits. There is no 0x prefix and spaces are not allowed in the string.	Uchar	1[1]	H
3	RegisterAddressLen	The length of the register address that follows. Valid values are 0 through 4.	Ulong	4	H+4
4	RegisterAddress	The actual address of the register to be read. The number of bytes here must match the RegisterAddressLen. In particular, when RegisterAddressLen is 0, this field is empty (even for a binary command) For ASCII and Abbreviated commands, this field is a hexadecimal string of two digits for each byte in the register address. There is no 0x prefix and spaces are not allowed in the string.	Uchar Array	X[2]	H+8
5	RequestReadLen	The length of data expected to be retrieved from the device. Valid values are 1 through 256.	Ulong	4	H+12[3]
6	TransactionID	An optional user provided ID for this transaction. Default = 0. This transaction ID will be copied to the **USERI2CRESPONSE** log (see page 1016) created for this read operation.	Ulong	4	H+16[4]

1. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.
2. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.
3. H+8 if X=0
4. H+12 if X=0

2.219 USERI2CWRITE

Write data to device on I2C bus

Platform: OEM7600, OEM7700, OEM7720

Use this command to write data to devices on the I2C bus.



This command only applies to OEM7 receivers that have I2C signals available on the interface connector. The compatible receivers are listed in the **Platform** section above.

The **USERI2CRESPONSE** log (see page 1016) can be used to check the completion or status of the write operation. An optional user defined Transaction ID can be provided to help synchronize requests with responses in the **USERI2CRESPONSE** log (see page 1016). This command is primarily intended to be used by Lua applications that need to interact with external devices.

Writing to an I2C device requires a device address, to distinguish which physical device is to be accessed, a register within the device and the data. Depending on the type of I2C device, register addresses can be 1 to 4 bytes in length, and so the actual number of bytes for the register address must be specified.

For some I2C devices there are no registers within the device. In this case, the Register Address Length is 0, and no bytes are supplied for the Register Address.

For some other I2C devices, write operations are done in two stages:

1. The first stage sends a write command with a register address, but no data. This is a dummy write to set the register within the device for write operations that follow.
2. The second stage sends a write command with no register address, but does send a stream of data.

The **USERI2CWRITE** command is flexible to handle all of these situations.

Message ID: 2233

Abbreviated ASCII syntax:

```
USERI2CWRITE DeviceAddress RegisterAddressLen RegisterAddress WriteDataLength
WriteData [TransactionID]
```

Examples:

```
USERI2CWRITE 70 1 AB 12 3132333435363738393A3B3C 1234
USERI2CWRITE 74 3 ABCDED 5 1234567890 1234
USERI2CWRITE 40 0 5 1234567890 1234
USERI2CWRITE 40 2 AABB 0 1234
```
(a dummy write)

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Command header	USERI2CWRITE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	DeviceAddress	The 7 bit address of the I2C device. Valid values 0 through 127. For ASCII and Abbreviated commands, this field is a hexadecimal string of two digits. There is no 0x prefix and spaces are not allowed in the string.	Uchar	1[1]	H
3	RegisterAddressLen	The length of the register address that follows. Valid values are 0 through 4.	Ulong	4	H+4
4	RegisterAddress	The actual address of the register to be written. The number of bytes here must match the RegisterAddressLen. In particular, when RegisterAddressLen is 0, this field is empty (even for a binary command) For ASCII and Abbreviated commands, this field is a hexadecimal string of two digits for each byte in the register address. There is no 0x prefix and spaces are not allowed in the string.	Uchar Array	X[2]	H+8
5	WriteDataLength	The length of data to be written in bytes. Valid values are 0 through 256.	Ulong	4	H+12[3]
6	WriteData	The data to be written. The number of bytes in this data block must match the WriteDataLength. In particular, when WriteDataLength is 0, this field is empty. For ASCII and Abbreviated commands, this field is a hexadecimal string of two digits for each byte in the data block. There is no 0x prefix and spaces are not allowed in the string. Data is streamed to the device as a series of bytes in the order provided.	Uchar Array	Y[4]	H+16[5]

1. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.
2. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.
3. H+8 if X=0
4. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.
5. H+12 if X=0

Field	Field type	Description	Format	Binary bytes	Binary offset
7	TransactionID	An optional user provided ID for this transaction. Default = 0. This transaction ID will be copied to the **USERI2CRESPONSE** log (see page 1016) created for this write operation.	Ulong	4	H+16+4*INT ((Y+3)/4)[1]

1. H+12+4*INT((Y+3)/4) if X=0

2.220 UTMZONE

Sets UTM parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This command sets the UTM persistence, zone number or meridian. Refer to https://en.wikipedia.org/wiki/Universal_Transverse_Mercator_coordinate_system.

1. The latitude limits of the UTM System are 80°S to 84°N, so if your position is outside this range, the **BESTUTM** log (see page 539) outputs a northing, easting and height of 0.0, along with a zone letter of "*" and a zone number of 0, so that it is obvious that the data in the log is dummy data.
2. If the latitude band is X, then the Zone number should not be set to 32, 34 or 36. These zones were incorporated into other zone numbers and do not exist.

Message ID: 749

Abbreviated ASCII syntax:

```
UTMZONE command [parameter]
```

Factory default:

```
UTMZONE auto 0
```

ASCII example 1:

```
UTMZONE SET 10
```

ASCII example 2:

```
UTMZONE CURRENT
```

The UTM grid system is displayed on all National Topographic Series (NTS) of Canada maps and United States Geological Survey (USGS) maps. On USGS 7.5-minute quadrangle maps (1:24,000 scale), 15-minute quadrangle maps (1:50,000, 1:62,500, and standard-edition 1:63,360 scales) and Canadian 1:50,000 maps the UTM grid lines are drawn at intervals of 1,000 metres and are shown either with blue ticks at the edge of the map or by full blue grid lines. On USGS maps at 1:100,000 and 1:250,000 scale and Canadian 1:250,000 scale maps a full UTM grid is shown at intervals of 10,000 metres.

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	UTMZONE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	command	See *Table 90: UTM Zone commands* on the next page			Enum	4	H
3	parameter	See *Table 90: UTM Zone commands* on the next page			Long	4	H+4

Table 90: UTM Zone commands

Binary	ASCII	Description
0	AUTO	UTM zone default that automatically sets the central meridian and does not switch zones until it overlaps by the set persistence. This a spherical approximation to the earth unless you are at the equator (default = 0) (m)
1	CURRENT	Same as UTMZONE AUTO with infinite persistence of the current zone. The parameter field is not used
2	SET	Sets the central meridian based on the specified UTM zone. A zone includes its western boundary, but not its eastern boundary, Meridian. For example, zone 12 includes (108°W, 114°W) where 108° < longitude < 114°
3	MERIDIAN	Sets the central meridian as specified in the parameter field. In the **BESTUTM** log (see page 539), the zone number is output as 61 to indicate the manual setting (zones are set by pre-defined central meridians not user-set ones)

2.221 WIFIALIGNAUTOMATION

Configure the ALIGN plug-and-play feature over Wi-Fi

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to simplify the configuration of a pair of receivers; one acting as an ALIGN Base and the other acting as an ALIGN Rover.

Similar to the **ALIGNAUTOMATION** command (see page 70) the ALIGN Rover, acting as a Wi-Fi Client, connects to the specified Wi-Fi Access Point and configures it as an ALIGN Base.

The IP address of the ALIGN Rover and ALIGN Base must be different. Since all NovAtel receivers are delivered with the same default IP address, it is highly recommended to use the WIFIAPIPCONFIG command (see page 480) to change the IP address of the ALIGN Rover to a non-default value such as 192.168.20.1 prior to entering the WIFIALIGNAUTOMATION command. Failure to do so may result in loss of wireless communication to the ALIGN Rover.

Message ID: 2214

Abbreviated ASCII syntax:

```
WIFIALIGNAUTOMATION option [base_networkid] [corrections_port] [datarate]
[headingextboption] [interfacemode]
```

Factory default:

```
WIFIALIGNAUTOMATION DISABLE
```

Example:

```
WIFIALIGNAUTOMATION enable 1 icom1 10 on novatelx
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFIALIGN AUTOMATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	option	ENABLE	1	Enable or disable the plug-and-play feature.	Enum	4	H
		DISABLE	0				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	base_network	1-4		Network id of Align Base Access Point as defined in the **WIFINETCONFIG** command (see page 486).	Ulong	4	H+4
4	corrections_port	ICOM1	23	Name of ICOM port to be used by Rover and Base. **The Base ICOM port must be configured with factory default settings.** (default=ICOM1)	Enum	4	H+8
		ICOM2	24				
		ICOM3	25				
		ICOM4	29				
		ICOM5	46				
		ICOM6	47				
		ICOM7	48				
5	datarate	1, 2, 4, 5, 10 or 20		Rate (in Hz) at which heading output is required (default = ICOM1)	Ulong	4	H+12
6	headingextboption	OFF	0	Enable or disable sending HEADINGEXTB / HEADINGEXT2B back to Base (default=ON)	Enum	4	H+16
		ON	1				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
7	interfacemode	See *2.69 INTERFACEMODE* on page 217		Interfacemode for corrections (default = NONE) If this parameter is not specified, the ALIGN Base is not configured to generate any corrections. The assumption is that the Base has been separately configured. Refer to ALIGN Over Wi-Fi Overview in the PwrPak7 Installation and Operation User Manual or SMART7 Installation and Operation User Manual for details on ALIGN.	Enum	4	H+20

2.222 WIFIAPCHANNEL

Set the channel for the Wi-Fi access point

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to set the operating channel for the Wi-Fi module when operating as an access point. The new channel will be used the next time the **WIFIMODE AP** or **WIFIMODE CONCURRENT** command is received.

Message ID: 2091

Abbreviated ASCII syntax:

```
WIFIAPCHANNEL channel
```

Factory default:

```
WIFIAPCHANNEL 11
```

Example:

```
WIFIAPCHANNEL 6
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFIAPCHANNEL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	channel	1-14		802.11 channel	Long	4	H

For best performance, choose one of the non-overlapping channels: 1, 6, or 11.

2.223 WIFIAPIPCONFIG

Set the IP address and netmask for the Wi-Fi access point

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to set the Wi-Fi IP address and netmask for Wi-Fi module when operating as an access point. The new network configuration takes effect the next time the **WIFIMODE AP** or **WIFIMODE CONCURRENT** command is received.

Message ID: 2096

Abbreviated ASCII syntax:

```
WIFIAPIPCONFIG ip_address ip_netmask
```

Factory default:

```
WIFIAPIPCONFIG 192.168.19.1 255.255.255.0
```

Example:

```
WIFIAPIPCONFIG 192.162.55.20 255.255.0.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFIAPIPCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	ip_address	Null-terminated ASCII string		IP address, dot decimal format	String [16]	Variable	H
3	ip_netmask	Null-terminated ASCII string		IP netmask, dot decimal format (optional) Default =255.255.255.0	String [16]	Variable	Variable

2.224 WIFIAPPASSKEY

Set Wi-Fi access point passkey

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to set the WPA2 PSK ASCII passkey for the Wi-Fi module when the receiver is operating as an Access Point.

The default passkey is printed on the receiver label. The default passkey can be labelled **WIFI Password** or **Password**.

The new passkey takes effect the next time the **WIFIMODE AP** or **WIFIMODE CONCURRENT** command is received.

The term passkey and password are the same.

Message ID: 2090

Abbreviated ASCII syntax:

```
WIFIAPPASSKEY passkey
```

Factory default:

The default passkey/password is printed on the receiver label. The default passkey can be labelled **WIFI Password** or **Password**.

Example:

```
WIFIAPPASSKEY "bysP3zE6SZmFQeyd"
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFIAPPASSKEY header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	passkey	Null-terminated ASCII string, 8 to 64 characters		WPA2 PSK ASCII passkey The passkey can contain upper case letters, lower case letters, numbers, punctuation and some symbols. Specifically, any 7-bit ASCII character from SPACE (decimal 32, hex 0x20) to TILDE (decimal 126, hex 0x7E) except QUOTE (decimal 34, hex 0x22). If the new passkey does not meet the above criteria, the receiver will output the response `New password is unacceptable`. This message response does not enforce a minimum number of characters, or comment on password complexity. If the passkey contains a SPACE (decimal 32, hex 0x20) or COMMA (decimal 44, hex 0x2C), the passkey must be enclosed in QUOTE characters (decimal 34, hex 0x22) when entered in ASCII or Abbreviated ASCII. The passkey cannot be blank.	String [65]	Variable	H

2.225 WIFIAPSSID

Set the SSID for the Wi-Fi access point

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to explicitly set the SSID of the Access Point when the receiver is configured to operate in either AP or CONCURRENT mode (refer to the **WIFIMODE** command on the next page for details regarding the Wi-Fi configuration modes).

Message ID: 2206

Abbreviated ASCII syntax:

```
WIFIAPSSID ssid
```

Factory default:

```
<platform-dependent prefix>-<Enclosure PSN>
```

Example:

```
PwrPak7-NMND17190003B
SM7i-NMPX17500010L
```

Example:

```
WIFIAPSSID SomeSSIDName
WIFIAPSSID "SSID with spaces"
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFIAPSSID header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	SSID	Null-terminated ASCII string		SSID to be broadcast by access point	String [33]	Variable	H

2.226 WIFIMODE

Configure the receiver Wi-Fi mode

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to enable, disable or set the operating mode of Wi-Fi on the receiver. This command is also applies any Wi-Fi configuration changes specified by other Wi-Fi commands such as **WIFIAPCHANNEL**.

Message ID: 2144

Abbreviated ASCII syntax:

```
WIFIMODE mode
```

Factory default:

```
WIFIMODE AP
```

Example:

```
WIFIMODE CLIENT
WIFIMODE OFF
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFIMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	mode	OFF	0	Power off the Wi-Fi module	Enum	4	H
		AP	1	Configure the Wi-Fi module as an Access Point (AP)			
		CLIENT	2	Configure the Wi-Fi module as a Client/Station			
		ON	3	Supply power to the Wi-Fi module, but do not configure it.			
		CONCURRENT	4	Configure the Wi-Fi module as both an access point and Client/Station simultaneously. When configured in this mode it is possible to connect the receiver to an access point and for Clients/Stations to connect to the receiver simultaneously.			

2.227 WIFINETCONFIG

Set the connection parameters of Wi-Fi to which the Wi-Fi client can connect

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this command to specify Access Points (AP) to which the Client/Station will automatically connect when the receiver's Wi-Fi Client/Station functionality is enabled (refer to the **WIFIMODE** command (see page 484) for details regarding the Wi-Fi configuration modes).

If the Wi-Fi Client/Station is already connected to an access point (defined using this command), the connection remains in effect even when a more preferred access point comes into range (preferred as indicated by network_id).

If Wi-Fi ALIGN automation is enabled, the Client only connects to the Access Point specified in the **WIFIALIGNAUTOMATION** command (see page 476).

The term passkey and password are the same.

Message ID: 2213

Abbreviated ASCII syntax:

```
WIFINETCONFIG network_id switch [ssid [passkey [address_mode [IP_address
]netmask [gateway [dns]]]]]]]
```

Factory default:

```
WIFINETCONFIG 1 DISABLE
WIFINETCONFIG 2 DISABLE
WIFINETCONFIG 3 DISABLE
WIFINETCONFIG 4 DISABLE
```

Example:

```
WIFINETCONFIG 1 ENABLE SomeSSID 12345678
WIFINETCONFIG 2 ENABLE AnotherSSID 1A2b3C4d STATIC 192.168.19.1
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	WIFINETCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	network_id	1, 2, 3, 4		The Network identifier value is used to prioritize network connections when more than one network is in range of the client. The access point with the lowest network_id is chosen.	Ulong	4	H
3	switch	DISABLE	0	When set to Disable, the client will not connect to an access point with this SSID.	Enum	4	H+4
		ENABLE	1	When set to Enable, the client connects to an access point with this SSID if there are no other APs with a lower network_id in range.			
4	ssid	Null-terminated ASCII string		Access Points with non-ASCII SSIDs are not supported. Required if switch is set to ENABLE.	String [33]	Variable	
5	passkey	Null-terminated ASCII string, 8 to 64 characters		Passkey required to connect to access point identified by “ssid” parameter.(default = “”)	String [65]	Variable	
6	address_ mode	DHCP	1	Use dynamic IP address (default = DHCP)	Enum	4	
		STATIC	2	Use static IP address			
7	ip_address	ddd.ddd.ddd.ddd		IP Address - decimal dot notation The IP address is mandatory when the address mode is STATIC.	String [16]	Variable	
8	netmask	ddd.ddd.ddd.ddd		Netmask – decimal dot notation (default = 255.255.255.0)	String [16]	Variable	
9	gateway	ddd.ddd.ddd.ddd		Gateway – decimal dot notation (default = 0.0.0.0)	String [16]	Variable	

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
10	dns	ddd.ddd.ddd.ddd		DNS server – decimal dot notation (default = 0.0.0.0)	String [16]	Variable	

Chapter 3 Logs

Logs are the mechanism used to extract information from the receiver.

3.1 Log types

See the **LOG** command on page 249, for details about requesting logs.

The receiver is capable of generating three type of logs: synchronous, asynchronous and polled. The data for synchronous logs is generated on a regular schedule. In order to output the most current data as soon as it is available, asynchronous data is generated at irregular intervals. The data in polled logs is generated on demand. The following table outlines the log types and the valid triggers to use:

Table 91: Log type triggers

Type	Recommended trigger	Illegal trigger
Synch	ONTIME	ONNEW, ONCHANGED
Asynch	ONCHANGED or ONCE	-
Polled	ONCE or ONTIME [1]	ONNEW, ONCHANGED

See *Message time stamps* on page 57 for information about how the message time stamp is set for each type of log.

1. The maximum number of logs the OEM7 family of receivers can handle at a time is 128 logs for firmware versions 7.10.xx and 7.09.xx or 80 logs for firmware versions prior to 7.09.00. If an attempt is made to log more than the maximum number of logs at a time, the receiver responds with an Insufficient Resources error. Note that **RXSTATUSEVENTA** logs are requested on most ports by default and these logs count against the maximum.
2. Asynchronous logs, such as MATCHEDPOS, should only be logged ONCHANGED. Otherwise, the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may result in inaccurate time tags.
3. Use the ONNEW trigger with the MARKxTIME or MARKxPOS logs.
4. Before the output of fields for logs, there is a header. See *ASCII* on page 35, *Abbreviated ASCII* on page 37 and *Binary* on page 39.

3.1.1 Log type examples

For polled logs, the receiver only supports an offset that is:

- smaller than the logging period
- integer values that are a multiple of the minimum logging period defined by the receiver model. For more information see the **LOG** command on page 249.

The following are valid examples for a polled log:

```
log portstats ontime 4 2
```

1. Polled log types do not allow fractional offsets and cannot do ontime rates faster than 1 Hz.

```
log version once
```

For polled logs, the following examples are invalid:

```
log serialconfig ontime 1 2      [offset is larger than the logging period]
log serialconfig ontime 4 1.5    [offset is not an integer]
```

For synchronous and asynchronous logs, the receiver supports any offset that is both:

- smaller than the logging period
- a multiple of the minimum logging period

For example, if the receiver supports 20 Hz logging, the minimum logging period is 1/20 Hz or 0.05 s. The following are valid examples for a synchronous or asynchronous log, on a receiver that can log at rates up to 20 Hz:

```
log bestpos ontime 1         [1 Hz]
log bestpos ontime 1 0.1
log bestpos ontime 1 0.90
log avepos ontime 1 0.95
log avepos ontime 2          [0.5 Hz]
log avepos ontime 2 1.35
log avepos ontime 2 1.75
```

For synchronous and asynchronous logs, the following examples are invalid:

```
log bestpos ontime 1 0.08    [offset is not a multiple of the minimum logging period]
log bestpos ontime 1 1.05    [offset is larger than the logging period]
```

3.2 ALIGNBSLNENU

ENU baselines using ALIGN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log outputs the RTK quality ENU baselines from ALIGN. The XYZ baselines (output in the **ALIGNBSLNXYZ** log on page 493) are rotated relative to base receiver position (output in MASTERPOS) to compute ENU baselines.



On dual antenna receivers with an ALIGN Relative Positioning Y-model, the baseline vector from the primary to the secondary antenna is provided. Additionally, the baseline vector from an external base station to the primary antenna is also available. The baseline vector from an external base station to the secondary antenna is not available with the ALIGN feature.

Message ID: 1315

Log type: Asynch

Recommended input:

```
log alignbslnenua onnew
```

ASCII example:

```
#ALIGNBSLNENUA,COM1,0,29.0,FINESTEERING,1629,259250.000,02040000,100b,39448;
SOL_COMPUTED,NARROW_INT,4.1586,-1.9197,-0.0037,0.0047,0.0050,0.0062,"0092",
"AAAA",22,16,16,16,0,01,0,33*e037a27d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ALIGNBSLNENU header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol stat	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	East	East Baseline (relative to base position) in metres	Double	8	H+8
5	North	North Baseline (relative to base position) in metres	Double	8	H+16
6	Up	Up Baseline (relative to base position) in metres	Double	8	H+24
7	East σ	East Baseline standard deviation in metres	Float	4	H+32
8	North σ	North Baseline standard deviation in metres	Float	4	H+36
9	Up σ	Up Baseline standard deviation in metres	Float	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
10	Rover id	Rover Receiver ID Set using the **SETROVERID** command (see page 403) on the Rover e.g., setroverid RRRR	Char[4]	4	H+44
11	Base id	Base Receiver ID Set using the **DGPSTXID** command (see page 138) on the Base Default: AAAA	Char[4]	4	H+48
12	#SVs	Number of satellites tracked	Uchar	1	H+52
13	#solnSVs	Number of satellites used in solution	Uchar	1	H+53
14	#obs	Number of satellites above elevation mask angle	Uchar	1	H+54
15	#multi	Number of satellites with multi-frequency signals above the mask angle	Uchar	1	H+55
16	Reserved		Hex	1	H+56
17	ext sol stat	Extended solution status, see *Table 99: Extended solution status* on page 534	Hex	1	H+57
18	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+58
19	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+59
20	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+60
21	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

3.3 ALIGNBSLNXYZ

XYZ baselines using ALIGN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log outputs the RTK quality XYZ baselines from ALIGN.



On dual antenna receivers with an ALIGN Relative Positioning Y-model, the baseline vector from the primary to the secondary antenna is provided. Additionally, the baseline vector from an external base station to the primary antenna is also available. The baseline vector from an external base station to the secondary antenna is not available with the ALIGN feature.

Message ID: 1314

Log type: Asynch

Recommended input:

```
log alignbslnxyza onnew
```

ASCII example:

```
#ALIGNBSLNXYZA,COM1,0,29.0,FINESTEERING,1629,259250.000,02040000,9d28,39448;
SOL_COMPUTED,NARROW_INT,3.1901,-3.0566,1.2079,0.0050,0.0054,0.0056,"0092",
"AAAA",22,16,16,16,0,01,0,33*9e8a2b71
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ALIGNBSLNXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol stat	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	dX	X Baseline in metres	Double	8	H+8
5	dY	Y Baseline in metres	Double	8	H+16
6	dZ	Z Baseline in metres	Double	8	H+24
7	dX σ	X Baseline standard deviation in metres	Float	4	H+32
8	dY σ	Y Baseline standard deviation in metres	Float	4	H+36
9	dZ σ	Z Baseline standard deviation in metres	Float	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
10	Rover id	Rover Receiver ID Set using **SETROVERID** command (see page 403) on the Rover e.g. SETROVERID RRRR	Uchar[4]	4	H+44
11	Base id	Base Receiver Id Set using the **DGPSTXID** command (see page 138) on the Base Default: AAAA	Uchar[4]	4	H+48
12	#SVs	Number of satellites tracked	Uchar	1	H+52
13	#solnSVs	Number of satellites used in solution	Uchar	1	H+53
14	#obs	Number of satellites above elevation mask angle	Uchar	1	H+54
15	#multi	Number of satellites with multi-frequency signals above the mask angle	Uchar	1	H+55
16	Reserved		Hex	1	H+56
17	ext sol stat	Extended solution status, see *Table 99: Extended solution status* on page 534	Hex	1	H+57
18	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+58
19	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+59
20	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+60
21	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

3.4 ALIGNDOP

Calculated DOP values

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log outputs the DOP computed using the satellites used in the heading solution. This log comes out at a default 1 Hz rate. Additional logs may be output not on the even second if the DOP changes and ALIGN is operating at greater than 1 Hz.

Message ID: 1332

Log type: Asynch

Recommended input:

```
log aligndopa onnew
```

ASCII example:

```
#ALIGNDOPA,COM1,0,22.5,FINESTEERING,1629,259250.000,02040000,de2d,39448;1.6160,
1.2400,0.6900,0.9920,0.7130,10.0,16,4,32,23,10,7,20,13,30,16,47,43,46,53,54,44,
45*1c953d05
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ALIGNDOP header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	GDOP	Geometric DOP	Float	4	H
3	PDOP	Position DOP	Float	4	H+4
4	HDOP	Horizontal DOP	Float	4	H+8
5	HTDOP	Horizontal and time DOP	Float	4	H+12
6	TDOP	GPS time DOP	Float	4	H+16
7	Elev mask	Elevation mask angle	Float	4	H+20
8	#sats	Number of satellites to follow	Ulong	4	H+24
9	sats	Satellites in use at time of calculation	Ulong	4	H+28
10	Next sat offset = H+28+(#sats * 4)				
11	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+28+(#sats * 4)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.5 ALMANAC

Decoded GPS L1 C/A almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the decoded GPS almanac parameters from L1 C/A subframes four and five, as received from the satellite, with the parity information removed and appropriate scaling applied. For more information about almanac data, refer to the GPS SPS Signal Specification.

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

Message ID: 73

Log type: Asynch

Recommended input:

```
log almanaca onchanged
```

ASCII example:

```
#ALMANACA,USB1,0,65.5,SATTIME,2209,494970.000,02000020,06de,16809;
31,
1,2210,61440.0,1.189947e-02,-7.49745516e-09,2.7464570e+00,9.04911221e-01,
5.43628036e-01,3.62396240e-04,-7.27595761e-12,1.45857660e-04,2.6559901e+07,
4.54861256e-02,3,0,0,TRUE,
2,2210,61440.0,2.042484e-02,-7.79461039e-09,2.6553604e+00,-1.4191382e+00,
6.98451114e-01,-6.53266907e-04,0.00000000,1.45858448e-04,2.6559805e+07,
2.35789625e-02,1,0,0,TRUE,
3,2210,61440.0,4.142284e-03,-7.64603277e-09,-2.5031848e+00,9.52756366e-01,
-5.65670396e-01,-2.45094299e-04,-1.45519152e-11,1.45862179e-04,2.6559352e+07,
3.12788270e-02,3,0,0,TRUE,
...
30,2210,61440.0,5.815029e-03,-7.89747182e-09,-3.91536612e-01,-2.6938085e+00,
-1.35149100e-01,-5.28335571e-04,0.00000000,1.45850074e-04,2.6560822e+07,
-6.21981273e-03,3,0,0,TRUE,
31,2210,61440.0,1.043320e-02,-7.71460706e-09,-3.84896228e-01,3.90039333e-01,
-5.91707997e-01,-1.77383423e-04,0.00000000,1.45852520e-04,2.6560525e+07,
1.28291128e-02,2,0,0,TRUE,
32,2210,61440.0,5.961895e-03,-8.08033658e-09,-1.4636431e+00,-2.2868654e+00,
-2.8675969e+00,-1.27792358e-04,-7.27595761e-12,1.45866076e-04,2.6558879e+07,
1.52259577e-02,3,0,0,TRUE*0eadcab6
```



The speed at which the receiver locates and locks onto new satellites is improved if the receiver has approximate time and position (**SETAPPROXTIME** and **SETAPPROXPOS**), as well as an almanac. This allows the receiver to compute the elevation of each satellite so it can tell which satellites are visible and their Doppler offsets, improving Time to First Fix (TTFF).

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#messages	The number of satellite PRN almanac messages to follow. Set to zero until almanac data is available	Long	4	H
3	PRN	Satellite PRN number for current message (dimensionless)	Ulong	4	H+4
4	week	Almanac reference week (GPS reference week number)	Ulong	4	H+8
5	seconds	Almanac reference time (seconds into the week)	Double	8	H+12
6	ecc	Eccentricity (dimensionless)	Double	8	H+20
7	ώ	Rate of right ascension (radians/second)	Double	8	H+28
8	ω_o	Right ascension (radians)	Double	8	H+36
9	ω	Argument of perigee (radians)	Double	8	H+44
10	M_o	Mean anomaly of reference time (radians)	Double	8	H+52
11	a_{fo}	Clock aging parameter (seconds)	Double	8	H+60
12	a_{f1}	Clock aging parameter (seconds/second)	Double	8	H+68
13	N_0	Computed mean motion (radians/second)	Double	8	H+76
14	A	Semi-major axis (metres)	Double	8	H+84
15	incl-angle	Angle of inclination relative to 0.3 π (radians)	Double	8	H+92
16	SV config	Satellite configuration	Ulong	4	H+100
17	health-prn	SV health from Page 25 of subframe 4 or 5 (6 bits)	Ulong	4	H+104
18	health-alm	SV health from almanac (8 bits)	Ulong	4	H+108
19	antispoof	Anti-spoofing on? 0 = FALSE 1 = TRUE	Bool	4	H+112
20...	Next PRN offset = H + 4 + (#messages x 112)				
21	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H + 4 +(112 x #messages)
22	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.6 AUTHCODES

List of authorization codes

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **AUTHCODES** log lists all auth-codes installed on the receiver and their status.

A signature auth-code is one that has been installed with the **AUTH** command (see page 85). An embedded auth-code is included as part of the firmware image. Only those auth-codes with Valid = TRUE can be used as the selected permanent model. The auth-code string is the same up to 7 part string used in the **AUTH** command (see page 85) with the same format. The model name appears after the 5th comma in the string. If a model has an expiry date, the expiry date follows the model.

See the **VERSION** log on page 1023 for which model is currently active and which is the selected permanent model.



See the **DISPATCHSCHEDULE** log on page 571 or **VERSION** log on page 1023 for which model is currently active and which is the selected permanent model.



The following situations will cause an authorization code to be marked invalid:

- Authorization Code is for a different receiver
- Authorization Code has expired
- Authorization Code was entered incorrectly

If you require new authorization codes, contact NovAtel Customer Service.

The **AUTHCODES** log also reports on the validity of the main firmware digital signature. This signature ensures only uncorrupted NovAtel firmware is installed and run on the receiver.



For descriptions of auth-codes, software models and interaction with dispatch messages, see Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, or SMART2 Installation and Operation User Manual.

Message ID: 1348

Log type: Polled

Recommended input:

```
log authcodesa once
```

Abbreviated ASCII example:

```
AUTHCODES COM1 0 66.5 FINESTEERING 2345 157213.000 02000000 2ad2 17375
   VALID 1
         SIGNATURE TRUE "W4PJRF,48GDMN,FPB3H3,5ZB5M2,BZ8B9G,FFNLYNTMNP1"
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	AUTHCODES header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	AUTHCODES firmware signature status	Status of the digital signature check on the main firmware. 1 = NONE 2 = INVALID 3 = VALID 5 = HIGH_SPEED	Enum	4	H
3	Number of Auth-Codes	# of Auth-Codes to follow (max is 24)	Ulong	4	H+4
4	Auth-code type	2=SIGNATURE: Installed with AUTH command. 3=EMBEDDED: Included in the main firmware image.	Enum	4	H+8
5	Valid	TRUE if the Auth-Code has been verified. This model can be used only if TRUE. May be FALSE if expired, incorrect receiver or incorrectly entered.	Bool	4	H+12
6	Auth-Code String	ASCII String of the Auth Code	String [max 80]	variable[1]	H+16
7...	Next Auth-Code = H+8+ (#AuthCodes*variable)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+8+ (#AuthCodes* variable)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

3.7 AVEPOS

Position averaging

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

When position averaging is underway, the various fields in the AVEPOS log contain the parameters being used in the position averaging process. *Table 92: Position averaging status* on the next page shows the possible position averaging status values seen in field #8 of the AVEPOS log table.

See the description of the **POSAVE** command on page 293 or **AUTOSURVEY** command on page 89. For general positioning information, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

Asynchronous logs should only be logged ONCHANGED. Otherwise, the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

Message ID: 172

Log type: Asynch

Recommended input:

```
log aveposa onchanged
```

ASCII example:

```
#AVEPOSA,USB1,0,72.5,FINESTEERING,2210,147873.000,02100020,e3b4,16809;
51.15043181793,-114.03067226763,1097.6045,1.9300,1.9294,1.9392,COMPLETE,5,6
*83bdc6a3
```

When a GNSS position is computed, there are four unknowns being solved: latitude, longitude, height and receiver clock offset (often just called time). The solutions for each of the four unknowns are correlated to satellite positions in a complex way. Since satellites are above the antenna (none are below) there is a geometric bias. Therefore, geometric biases are present in the solutions and affect the computation of height. These biases are called DOPs (Dilution Of Precision). Smaller biases are indicated by low DOP values. VDOP (Vertical DOP) pertains to height. Most of the time, VDOP is higher than HDOP (Horizontal DOP) and TDOP (Time DOP). Therefore, of the four unknowns, height is the most difficult to solve. Many GNSS receivers output the Standard Deviations (SD) of the latitude, longitude and height. Height often has a larger value than the other two.

Accuracy is based on statistics and reliability is measured in percent. When a receiver states it can measure height to one metre, this is an accuracy. Usually this is a one sigma value (one SD). A one sigma value for height has a reliability of 68%. In other words, the error is less than one metre 68% of the time. For a more realistic accuracy, double the one sigma value (one metre) and the result is 95% reliability (error is less than two metres 95% of the time). Generally, GNSS heights are 1.5 times poorer than horizontal positions. See also **GPGST** log on page 648 for CEP and RMS definitions.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	AVEPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	lat	Average WGS84 latitude (degrees)	Double	8	H
3	lon	Average WGS84 longitude (degrees)	Double	8	H+8
4	hgt	Average height above sea level (m)	Double	8	H+16
5	lat σ	Estimated average standard deviation of latitude solution element (m)	Float	4	H+24
6	lon σ	Estimated average standard deviation of longitude solution element (m)	Float	4	H+28
7	hgt σ	Estimated average standard deviation of height solution element (m)	Float	4	H+32
8	posave	Position averaging status (see *Table 92: Position averaging status* below)	Enum	4	H+36
9	ave time	Elapsed time of averaging (s)	Ulong	4	H+40
10	#samples	Number of samples in the average	Ulong	4	H+44
11	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+48
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 92: Position averaging status

Binary	ASCII	Description
0	OFF	Receiver is not averaging
1	INPROGRESS	Averaging is in progress
2	COMPLETE	Averaging is complete

3.8 BDSALMANAC

Decoded BDS almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the decoded BeiDou B1I almanac parameters, with the parity information removed and appropriate scaling applied. Multiple messages are transmitted, one for each SV almanac collected. For more information about almanac data, refer to the BDS Signal Specification.

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

Message ID: 1584

Log type: Asynch

Recommended input:

```
log bdsalmanaca onchanged
```

ASCII example:

```
#BDSALMANACA,USB1,58,66.0,SATTIME,2209,495392.000,02000020,24ad,16809;1,853,
233472,6493.366211,3.9148330688e-04,2.140348862,1.199588705,-2.642467663,
6.62884755e-10,1.3200623733e-02,1.783371e-04,4.36557e-11,0*47ce1f59

#BDSALMANACA,USB1,57,66.0,SATTIME,2209,495422.000,02000020,24ad,16809;2,853,
233472,6493.407715,1.2860298157e-03,-1.063963232,-3.106212600,-2.469847262,
2.85726187e-10,3.2794831454e-02,4.005432e-05,-4.00178e-11,0*8a6f2da6

#BDSALMANACA,USB1,56,66.0,SATTIME,2209,495452.000,02000020,24ad,16809;3,853,
233472,6493.317871,8.8787078857e-04,0.016723986,2.822887922,-2.736275307,
4.11445710e-10,3.2818799903e-02,-5.550385e-04,7.27596e-12,0*d002a7ff

...

#BDSALMANACA,USB1,2,66.0,SATTIME,2209,494348.000,02000020,24ad,16809;60,853,
233472,6493.458496,4.3869018555e-04,1.681354547,2.010414773,2.163612865,
2.25152236e-09,3.6605814973e-02,-9.536743e-07,0.00000,58*0b0eeddc

#BDSALMANACA,USB1,1,66.0,SATTIME,2209,494378.000,02000020,24ad,16809;61,853,
233472,6493.341309,5.9413909912e-04,-0.385926122,-0.842142719,1.330163202,
2.12580283e-09,2.6886608575e-02,0.000000,0.00000,58*0db11f92

#BDSALMANACA,USB1,0,66.0,SATTIME,2209,474248.000,02000020,24ad,16809;62,853,
417792,6553.599609,1.2499809265e-02,-1.256637361,-1.256637361,1.256636987,
5.99202102e-07,1.5707723583e-01,7.810593e-04,-1.49157e-09,100*5633ace5
```

The speed at which the receiver locates and locks onto new satellites is improved if the receiver has approximate time and position (**SETAPPROXTIME** and **SETAPPROXPOS**), as well as an almanac. This allows the receiver to compute the elevation of each satellite so it can tell which satellites are visible and their Doppler offsets, improving Time to First Fix (TTFF).

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	satellite ID	Satellite ID/ranging code	Ulong	4	H
3	week	Week number in BeiDou time (BDT) since the BeiDou system time start epoch (January 1, 2006)	Ulong	4	H+4
4	toa	Time of almanac (s)	Ulong	4	H+8
5	RootA	Square root of semi-major axis (sqrt(m))	Double	8	H+12
6	ecc	Eccentricity (dimensionless)	Double	8	H+20
7	ω	Argument of perigee (radians)	Double	8	H+28
8	M_0	Mean anomaly at reference time (radians)	Double	8	H+36
9	Ω	Longitude of ascending node of orbital of plane computed according to reference time (radians)	Double	8	H+44
10	$\dot{\Omega}$	Rate of right ascension (radians/s)	Double	8	H+52
11	δ_i	Correction of orbit reference inclination at reference time (radians)	Double	8	H+60
12	a_0	Constant term of clock correction polynomial (s)	Double	8	H+68
13	a_1	Linear term of clock correction polynomial (s/s)	Double	8	H+76
14	health	Satellite health information	Ulong	4	H+84
15	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+88
16	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.9 BDSBCNAV1EPHEMERIS

Decoded BeiDou B-CNAV1 ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the decoded BeiDou B-CNAV1 ephemeris for the BeiDou B1C signal.

Message ID: 2371

Log type: Asynch

Recommended input:

```
log bdsbcnav1ephemerisa onall
```

Example log:

```
#BDSBCNAV1EPHEMERISA,USB1,6,59.0,SATTIME,2209,496436.000,02000020,27d6,16809;
25,853,00000000,25,493200,3,83.013672,-0.003732,3.9006981940e-09,
1.9335870986e-14,0.477429585,4.3404346798e-04,0.447233249,1.0544811238e-01,
9.4935254055e-01,-6.84742808e-09,3.476930542e-10,5.401670933e-08,
-3.539025784e-08,128.6171875,146.8867188,1.032091677e-05,6.321817636e-06,
25,493200,-7.37199793e-04,5.41433565e-12,0.00000000,1.920852810e-09,
-1.711305231e-08,-2.328306437e-10,0*eb1ad752

#BDSBCNAV1EPHEMERISA,USB1,5,59.0,SATTIME,2209,496436.000,02000020,27d6,16809;
24,853,00000000,25,493200,3,19.027344,0.006292,3.9494502247e-09,
-6.8209628314e-14,1.247259053,4.9585988745e-04,0.517626996,1.3024422419e-01,
9.4798221860e-01,-6.90885921e-09,3.485859486e-10,2.421438694e-08,
-5.587935448e-09,115.0976563,154.5429688,9.900890291e-06,5.632638931e-06,
25,493200,-9.63939528e-04,-4.78550533e-12,0.00000000,1.175794750e-08,
-1.484295353e-08,2.910383046e-10,0*273a26ab

...

#BDSBCNAV1EPHEMERISA,USB1,1,59.0,SATTIME,2209,496436.000,02000020,27d6,16809;
39,853,00000000,25,493200,2,5263.894531,-0.062899,7.7092496926e-10,
1.9584381616e-13,-2.140521199,2.2453696001e-03,-2.871042649,-9.3801678773e-01,
9.6155928554e-01,-1.86489911e-09,-1.102724504e-09,-4.284083843e-08,
4.004687071e-08,-83.8671875,-507.8242188,2.449937165e-05,-3.319233656e-06,
25,493200,3.49998591e-05,3.10862447e-14,0.00000000,7.799826562e-09,
-1.426087692e-08,-3.492459655e-10,0*890d2cfd

#BDSBCNAV1EPHEMERISA,USB1,0,59.0,SATTIME,2209,496436.000,02000020,27d6,16809;
44,853,00000000,25,493200,3,65.369141,-0.011349,3.8406956947e-09,
1.0343710014e-13,-0.198007475,8.3381979493e-04,0.582406796,2.199813208e+00,
9.5949562234e-01,-6.96636161e-09,-4.343038048e-10,-5.215406418e-08,
-4.190951586e-08,-118.6484375,212.3242188,7.395632565e-06,-5.853362381e-06,
25,493200,6.58427074e-04,1.22231114e-11,0.00000000,-2.153683454e-09,
-1.199077815e-08,-2.910383046e-10,0*aaff1aac
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV1EPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Satellite ID	ID/ranging code	Ulong	4	H
3	WN	Week number in BeiDou time (BDT). This will be offset from GPS time by 1356 weeks.	Ulong	4	H+4
4	Satellite Status	Satellite Status Information: Bits 0 to 1: Health Status (HS) Bit 2: Data Integrity Flag (DIF) Bit 3: Signal Integrity Flag (SIF) Bit 4: Accuracy Integrity Flag (AIF) Bits 5 to 8: Signal In Space Monitoring Accuracy Index (SISMAI)	Hex Ulong	4	H+8
5	IODE	Issue of data, ephemeris	Ulong	4	H+12
6	toe	Reference time of ephemeris parameters in BeiDou time (BDT). (s) This will be offset from GPS time.	Ulong	4	H+16
7	Satellite Type	2 bit orbit type: 01 indicates GEO, 10 indicates IGSO, 11 indicates MEO	Ulong	4	H+20
8	DeltaA	Semi-major axis difference at reference time (m)	Double	8	H+24
9	ADot	Change rate in Semi-major axis (m/s)	Double	8	H+32
10	DeltaN	Mean motion difference from computed value (radians/s)	Double	8	H+40
11	NDot	Rate of Mean motion difference from computed value (radians/s^2)	Double	8	H+48
12	M_0	Mean anomaly at reference time (radians)	Double	8	H+56
13	e	Eccentricity (unitless)	Double	8	H+64
14	Omega	Argument of perigee (radians)	Double	8	H+72
15	$Omega_0$	Longitude of ascending node of orbital of plane at weekly epoch (radians)	Double	8	H+80
16	i_0	Inclination angle at reference time (radians)	Double	8	H+88
17	OmegaDot	Rate of right ascension (radians/s)	Double	8	H+96

Field	Field type	Description	Format	Binary bytes	Binary offset
18	i_0Dot	Rate of inclination angle (radians/s)	Double	8	H+104
19	C_{is}	Amplitude of sine harmonic correction term to the angle of inclination (radians)	Double	8	H+112
20	C_{ic}	Amplitude of cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+120
21	C_{rs}	Amplitude of sine harmonic correction term to the orbit radius (m)	Double	8	H+128
22	C_{rc}	Amplitude of cosine harmonic correction term to the orbit radius (m)	Double	8	H+136
23	C_{us}	Amplitude of sine harmonic correction term to the argument of latitude (radians)	Double	8	H+144
24	C_{uc}	Amplitude of cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+152
25	IODC	Issue of data, clock	Ulong	4	H+160
26	toc	Reference time of clock parameters in BeiDou time (BDT). This will be offset from GPS time by 14 seconds. (s)	Ulong	4	H+164
27	a_0	Constant term of clock correction polynomial (s)	Double	8	H+168
28	a_1	Linear term of clock correction polynomial (s/s)	Double	8	H+176
29	a_2	Quadratic term of clock correction polynomial (s/s^2)	Double	8	H+184
30	TGDB1Cp	Group delay differential between the B1C pilot component and the B3I signal (s)	Double	8	H+192
31	TGDB2Ap	Group delay differential between the B2a pilot component and the B3I signal (s)	Double	8	H+200
32	ISCB1Cd	Group delay differential between the B1C data and pilot components (s)	Double	8	H+208
33	Reserved		Ulong	4	H+216
34	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+220
35	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.10 BDSBCNAV1RAWMESSAGE

Framed BeiDou B-CNAV1 raw navigation message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the framed BeiDou B-CNAV1 navigation message for the BeiDou B1C signals in raw bit format.

Message ID: 2373

Log type: Asynch

Recommended input:

```
log bdsbcnav1rawmessagea onnew
```

Example log:

```
#BDSBCNAV1RAWMESSAGEA,USB1,0,44.0,SATTIME,2209,496508.000,02000020,661c,16809;6
5,35,25,8edc,1aac4832339b3ffd8f4800492456a4fff4b8388a7301006a93d00a12254256670b
18c4e66ba28ecf15da87ffcc009ffddd84032e24041b5fe422cd847641001322800781ffeffd00,
67130e81da82fbb1ce82698141147b890a5ad77d74230493bfcc363b79e2*556d1498
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV1RAWMESSAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Signal Channel	Signal Channel Number	Ulong	4	H
3	Satellite ID	Satellite ID / PRN	Ulong	4	H+4
4	Page ID	Page ID for Subframe 3	Ulong	4	H+8
5	Raw Subframe 1 Data	Framed raw navigation bits for Subframe 1	Hex[2]	2	H+12
6	Raw Subframe 2 Data	Framed raw navigation bits for Subframe 2 (CRC check bits removed)	Hex[72]	72	H+14
7	Raw Subframe 3 Data	Framed raw navigation bits for Subframe 3 (CRC check bits removed)	Hex[30]	30	H+86
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+116
9	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.11 BDSBCNAV2EPHEMERIS

Decoded BDS B-CNAV2 ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the Decoded BDS B-CNAV2 ephemeris for the BeiDou B2a signals.

Message ID: 2372

Log type: Asynch

Recommended input:

```
log bdsbcnav2ephemerisa onall
```

Example log:

```
#BDSBCNAV2EPHEMERISA,COM1,10,39.5,SATTIME,2425,147254.000,02040020,21df,32768;
13,1069,00000020,12,144000,3,245.486328,-0.005758,3.8365883807e-09,
3.4791488268e-14,-0.606482817,3.2121624099e-04,1.301921964,4.4824821849e-01,
9.5077332001e-01,-6.72635161e-09,1.557207721e-10,2.328306437e-08,
5.587935448e-09,157.6054688,222.8164063,6.654299796e-06,7.775612175e-06,12,
144000,-9.32638417e-04,-5.68078917e-12,0.00000000,1.164153218e-09,
-1.327134669e-08,-2.619344741e-09,0*79f2477c

#BDSBCNAV2EPHEMERISA,COM1,9,39.5,SATTIME,2425,147254.000,02040020,21df,32768;
23,1069,00000020,12,144000,3,144.994141,-0.000225,4.5016160818e-09,
6.5397534338e-17,-2.857598867,3.7373561645e-04,-0.973876433,-1.644278945e+00,
9.4335000846e-01,-6.99243412e-09,4.643050545e-11,1.862645149e-08,
4.097819328e-08,6.0937500,263.8632813,4.424713552e-06,2.598389983e-07,12,144000,
-4.54849971e-04,7.54063478e-13,0.00000000,2.299202606e-08,-2.270098776e-09,
-2.735760063e-09,0*2fdccb9d

#BDSBCNAV2EPHEMERISA,COM1,8,39.5,SATTIME,2425,147254.000,02040020,21df,32768;
38,1069,000001e0,12,144000,3,436.820313,0.003819,4.0237390335e-09,
-4.8306978697e-14,-0.006553348,5.5731734028e-04,1.111275921,4.0564822908e-01,
9.4102172021e-01,-6.79617595e-09,1.160762636e-10,1.303851604e-08,
-9.313225746e-10,143.4101563,206.5351563,7.203780115e-06,7.104128599e-06,12,
144000,1.41350145e-04,7.56728014e-13,0.00000000,-9.313225746e-10,
-4.714820534e-09,-2.619344741e-09,0*df1d313e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV2EPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Satellite ID	ID/ranging code	Ulong	4	H
3	WN	Week number in BeiDou time (BDT). This will be offset from GPS time by 1356 weeks.	Ulong	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	Satellite Status	Satellite Status Information: Bits 0 to 1: Health Status (HS) Bit 2: Data Integrity Flag (DIF) – B2a Bit 3: Signal Integrity Flag (SIF) – B2a Bit 4: Accuracy Integrity Flag (AIF) – B2a Bits 5 to 8: Signal In Space Monitoring Accuracy Index (SISMAI) Bit 9: Data Integrity Flag (DIF) – B1C Bit 10: Signal Integrity Flag (SIF) – B1C Bit 11: Accuracy Integrity Flag (AIF) – B1C	Hex Ulong	4	H+8
5	IODE	Issue of data, ephemeris	Ulong	4	H+12
6	toe	Reference time of ephemeris parameters in BeiDou time (BDT). This will be offset from GPS time. (s)	Ulong	4	H+16
7	Satellite Type	2 bit orbit type: 01 indicates GEO, 10 indicates IGSO, 11 indicates MEO	Ulong	4	H+20
8	DeltaA	Semi-major axis difference at reference time (m)	Double	8	H+24
9	ADot	Change rate in Semi-major axis (m/s)	Double	8	H+32
10	DeltaN	Mean motion difference from computed value (radians/s)	Double	8	H+40
11	NDot	Rate of mean motion difference from computed value (radians/s^2)	Double	8	H+48
12	M_0	Mean anomaly at reference time (radians)	Double	8	H+56
13	e	Eccentricity (unitless)	Double	8	H+64
14	Omega	Argument of perigee (radians)	Double	8	H+72
15	$Omega_0$	Longitude of ascending node of orbital of plane at weekly epoch (radians)	Double	8	H+80
16	i_0	Inclination angle at reference time (radians)	Double	8	H+88
17	OmegaDot	Rate of right ascension (radians/s)	Double	8	H+96
18	i_0Dot	Rate of inclination angle (radians/s)	Double	8	H+104
19	C_{is}	Amplitude of sine harmonic correction term to the angle of inclination (radians)	Double	8	H+112

Field	Field type	Description	Format	Binary bytes	Binary offset
20	C_{ic}	Amplitude of cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+120
21	C_{rs}	Amplitude of sine harmonic correction term to the orbit radius (m)	Double	8	H+128
22	C_{rc}	Amplitude of cosine harmonic correction term to the orbit radius (m)	Double	8	H+136
23	C_{us}	Amplitude of sine harmonic correction term to the argument of latitude (radians)	Double	8	H+144
24	C_{uc}	Amplitude of cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+152
25	IODC	Issue of data, clock	Ulong	4	H+160
26	toc	Reference time of clock parameters in BeiDou time (BDT). (s) This will be offset from GPS time by 14 seconds.	Ulong	4	H+164
27	a_0	Constant term of clock correction polynomial (s)	Double	8	H+168
28	a_1	Linear term of clock correction polynomial (s/s)	Double	8	H+176
29	a_2	Quadratic term of clock correction polynomial (s/s^2)	Double	8	H+184
30	TGDB1Cp	Group delay differential between the B1C pilot component and the B3I signal (s)	Double	8	H+192
31	TGDB2Ap	Group delay differential between the B2a pilot component and the B3I signal (s)	Double	8	H+200
32	ISCB2ad	Group delay differential between the B2a data and pilot components (s)	Double	8	H+208
33	Reserved		Ulong	4	H+216
34	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+220
35	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.12 BDSBCNAV2RAWMESSAGE

Framed BeiDou B-CNAV2 raw navigation message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the framed BeiDou B-CNAV2 raw navigation message for the BeiDou B2a signals in raw bit format.

Message ID: 2374

Log type: Asynch

Recommended input:

```
log bdsbcnav2rawmessagea onnew
```

Example log:

```
#BDSBCNAV2RAWMESSAGEA,USB1,0,44.0,SATTIME,2209,496625.000,02000020,fb5d,16809;
144,26,11,e24de868ba1a841e01147a2024d5d4871ed564210bff7bff7c019e8002218005a6001
57a*1985a1bd
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV2RAWMESSAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Signal Channel	Signal channel number	Ulong	4	H
3	Satellite ID	Satellite ID / PRN	Ulong	4	H+4
4	Message Type	Message type contained in the data	Ulong	4	H+8
5	Raw Message Data	Framed raw navigation data, 288 bits (CRC removed)	Hex[36]	36	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+48
7	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.13 BDSBCNAV3EPHEMERIS

Decoded BDS B-CNAV3 ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the decoded parameters from words 10 and 30 of the BeiDou B2b signals. The data includes orbital parameters, group delay, health, and other status information.

Message ID: 2412

Log type: Asynch

Recommended input:

```
log bdsbcnav3ephemerisa onall
```

Example log:

```
#BDSBCNAV3EPHEMERISA,USB1,6,50.5,SATTIME,2209,496718.000,02000020,070d,16809;
26,853,00000000,493200,3,107.203125,-0.005850,3.7798003010e-09,
4.1571032661e-14,2.051998724,7.3472585063e-04,0.436791966,1.0602762178e-01,
9.4940386191e-01,-6.82564146e-09,3.775157250e-10,-3.166496754e-08,
-3.073364496e-08,103.6250000,136.3750000,1.077353954e-05,5.120411515e-06,
493200,7.38367089e-04,-5.27311528e-12,0.00000000,-1.565786079e-08,0*25ddf0a6

#BDSBCNAV3EPHEMERISA,USB1,5,50.5,SATTIME,2209,496718.000,02000020,070d,16809;
35,853,00000000,493200,3,-78.089844,0.004464,3.9608792722e-09,
-3.1478013195e-14,0.693860220,8.1312097609e-04,0.494353216,2.199361578e+00,
9.6212843381e-01,-6.96993318e-09,-4.284107022e-10,-1.210719347e-08,
3.632158041e-08,-136.6210938,203.5351563,7.832422853e-06,-6.644055247e-06,
493200,2.72334553e-04,1.74029680e-11,0.00000000,-1.315493137e-08,0*152a37f1

...

#BDSBCNAV3EPHEMERISA,USB1,1,50.5,SATTIME,2209,496719.000,02000020,070d,16809;
39,853,00000000,493200,2,5263.894531,-0.062899,7.7092496926e-10,
1.9584381616e-13,-2.140521199,2.2453696001e-03,-2.871042649,-9.3801678773e-01,
9.6155928554e-01,-1.86489911e-09,-1.102724504e-09,-4.284083843e-08,
4.004687071e-08,-83.8671875,-507.8242188,2.449937165e-05,-3.319233656e-06,
493200,3.49998591e-05,3.10862447e-14,0.00000000,-1.268927008e-08,0*d3f6f534

#BDSBCNAV3EPHEMERISA,USB1,0,50.5,SATTIME,2209,496718.000,02000020,070d,16809;
44,853,00000000,493200,3,65.369141,-0.011349,3.8406956947e-09,1.0343710014e-13,
-0.198007475,8.3381979493e-04,0.582406796,2.199813208e+00,9.5949562234e-01,
-6.96636161e-09,-4.343038048e-10,-5.215406418e-08,-4.190951586e-08,
-118.6484375,212.3242188,7.395632565e-06,-5.853362381e-06,493200,
6.58427074e-04,1.22231114e-11,0.00000000,-1.204898581e-08,0*0c179456
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV3EPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	Satellite ID	ID/ranging code	Ulong	4	H
3	WN	Week number in BeiDou time (BDT). This will be offset from GPS time by 1356 weeks.	Ulong	4	H+4
4	Satellite Status	Satellite Status Information: Bits 0 to 1: Health Status (HS) Bit 2: Data Integrity Flag (DIF) Bit 3: Signal Integrity Flag (SIF) Bit 4: Accuracy Integrity Flag (AIF) Bits 5 to 8: Signal In Space Monitoring Accuracy Index (SISMAI)	Hex Ulong	4	H+8
5	toe	Reference time of ephemeris parameters in BeiDou time (BDT). This will be offset from GPS time. (s)	Ulong	4	H+12
6	Satellite Type	2 bit orbit type: 01 indicates GEO, 10 indicates IGSO, 11 indicates MEO	Ulong	4	H+16
7	DeltaA	Semi-major axis difference at reference time (m)	Double	8	H+20
8	ADot	Change rate in Semi-major axis (m/s)	Double	8	H+28
9	DeltaN	Mean motion difference from computed value (radians/s)	Double	8	H+36
10	NDot	Rate of mean motion difference from computed value (radians/s^2)	Double	8	H+44
11	M_0	Mean anomaly at reference time (radians)	Double	8	H+52
12	e	Eccentricity (unitless)	Double	8	H+60
13	Omega	Argument of perigee (radians)	Double	8	H+68
14	$Omega_0$	Longitude of ascending node of orbital of plane at weekly epoch (radians)	Double	8	H+76
15	i_0	Inclination angle at reference time (radians)	Double	8	H+84
16	OmegaDot	Rate of right ascension (radians/s)	Double	8	H+92
17	i_0Dot	Rate of inclination angle (radians/s)	Double	8	H+100
18	C_{is}	Amplitude of sine harmonic correction term to the angle of inclination (radians)	Double	8	H+108
19	C_{ic}	Amplitude of cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+116

Field	Field type	Description	Format	Binary bytes	Binary offset
20	C_{rs}	Amplitude of sine harmonic correction term to the orbit radius (m)	Double	8	H+124
21	C_{rc}	Amplitude of cosine harmonic correction term to the orbit radius (m)	Double	8	H+132
22	C_{us}	Amplitude of sine harmonic correction term to the argument of latitude (radians)	Double	8	H+140
23	C_{uc}	Amplitude of cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+148
24	toc	Reference time of clock parameters in BeiDou time (BDT). (s) This will be offset from GPS time by 14 seconds.	Ulong	4	H+156
25	a_0	Constant term of clock correction polynomial (s)	Double	8	H+160
26	a_1	Linear term of clock correction polynomial (s/s)	Double	8	H+168
27	a_2	Quadratic term of clock correction polynomial (s/s^2)	Double	8	H+176
28	TGDB2Bi	Group delay differential between the B2bI and the B3I signal (s)	Double	8	H+184
29	Reserved		Ulong	4	H+192
30	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+196
31	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.14 BDSBCNAV3RAWMESSAGE

Framed BDS B-CNAV3 raw navigation message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the framed BeiDou B-CNAV3 navigation message for the BeiDou B2b signals in raw bit format.

Message ID: 2411

Log type: Asynch

Recommended input:

```
log bdsbcnav3rawmessagea onnew
```

Example log:

```
<BDSBCNAV3RAWMESSAGE COM1 0 71.5 SATTIME 2302 337744.000 02000020 5050 32768
<     307 35 10 eb908d02949d0a62e600231e0011864a013ffced86044167600e96610114331
bd40b6a5f2c9beba1f7db86ff12fffe800f80353f8044f400b5d002cf4040 0 0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV3RAWMESSAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Signal channel	Signal channel number	Ulong	4	H
3	Satellite ID	Satellite ID / PRN	Ulong	4	H+4
4	Message type	Message type contained in the data	Ulong	4	H+8
5	Raw message data	Framed raw navigation data, 490 bits (CRC removed)	Hex[62]	62	H+12
6	Reserved		Char	1	H+74
7	Reserved		Char	1	H+75
8	xxxx	32-bit CRC	Hex	4	H+76
9	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.15 BDSBCNAV3RAWMESSAGE2

Framed BDS B-CNAV3 raw navigation message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the framed BeiDou B-CNAV3 navigation message for the BeiDou B2b signals in raw bit format. This message includes the BeiDou B-CNAV3 navigation message CRC.

Message ID: 2520

Log type: Asynch

Recommended input:

```
log bdsbcnav3rawmessage2a onnew
```

Example log:

```
<BDSBCNAV3RAWMESSAGE2 COM1 0 71.0 SATTIME 2302 337750.000 02000020 264b 32768
<     307 35 10 eb908d02949d2262e600231e0011864a013ffced86044167600e96610114331
bd40b6a5f2c9beba1f7db86ff12fffe800f80353f8044f400b5d002cf4047afba80 0 0 0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSBCNAV3RAWMESSAGE2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Signal channel	Signal channel number	Ulong	4	H
3	Satellite ID	Satellite ID / PRN	Ulong	4	H+4
4	Message type	Message type contained in the data	Ulong	4	H+8
5	Raw message data	Framed raw navigation data (490 bits), 24-bit CRC, and tail bits (sequence of zeros).	Hex[65]	65	H+12
6	Reserved		Char	1	H+77
7	Reserved		Char	1	H+78
8	Reserved		Char	1	H+79
9	xxxx	32-bit CRC	Hex	4	H+80
10	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

3.16 BDSCLOCK

BeiDou time parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains time parameters transmitted by the BeiDou B1I signals. These parameters can be used to calculated the offset between BeiDou time (BDT) and other time frames.

Message ID: 1607

Log type: Asynch

Recommended input:

```
log bdsclocka onchanged
```

ASCII example:

```
#BDSCLOCKA,USB1,0,61.5,SATTIME,2209,496388.000,02000020,3b16,16809;
-9.313225746154785e-10,-9.769962616701378e-15,4,61,6,4,
0.000000000000000e+00,0.000000000000000e+00,0.000000000000000e+00,
0.000000000000000e+00,0.000000000000000e+00,0.000000000000000e+00*ce955bde
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSCLOCK header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	A_{0UTC}	BDT clock bias relative to UTC (s)	Double	8	H
3	A_{1UTC}	BDT clock rate relative to UTC (s/s)	Double	8	H+8
4	ΔT_{LS}	Delta time due to leap seconds before the new leap second is effective (s)	Short	2	H+16
5	WN_{LSF}	Week number of the new leap second (8-bit week in BeiDou time (BDT))	Ushort	2	H+18
6	DN	Day number of week of the new leap second	Ushort	2	H+20
7	ΔT_{LSF}	Delta time due to leap seconds after the new leap second effective	Short	2	H+22
8	A_{0GPS}	BDT clock bias relative to GPS time (s)	Double	8	H+24
9	A_{1GPS}	BDT clock rate relative to GPS time (s/s)	Double	8	H+32
10	A_{0Gal}	BDT clock bias relative to Galileo time (s)	Double	8	H+40
11	A_{1Gal}	BDT clock rate relative to Galileo time (s/s)	Double	8	H+48
12	A_{0GLO}	BDT clock bias relative to GLONASS time (s)	Double	8	H+56
13	A_{1GLO}	BDT clock rate relative to GLONASS time (s/s)	Double	8	H+64

Field	Field type	Description	Format	Binary bytes	Binary offset
14	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+72
15	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.17 BDSEPHEMERIS

Decoded BDS ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains a single set of BDS B1I ephemeris parameters with appropriate scaling applied. Multiple messages are transmitted, one for each SV ephemeris collected.

Message ID: 1696

Log type: Asynch

Recommended input:

```
log bdsephemerisa onall
```

ASCII example:

```
#BDSEPHEMERISA,USB1,37,62.0,SATTIME,2209,496784.000,02000020,2626,16809;6,853,
2.00,0,8.30e-09,-1.60e-09,0,493200,-2.22835224e-05,7.54090124e-11,0.00000000,
1,493200,6493.813231,2.7420885162e-03,-2.990457924,7.3681640565e-10,
-2.306284799,-8.5916965356e-01,-1.83364781e-09,9.4558331017e-01,
-1.049329423e-09,-5.817040801e-06,2.914015204e-05,-660.2187500,-168.3906250,
1.862645149e-08,-1.862645149e-09*7a36ae90

#BDSEPHEMERISA,USB1,36,62.0,SATTIME,2209,446414.000,02000020,2626,16809;7,853,
2.00,0,1.42e-08,7.00e-10,0,446400,-1.59412972e-04,-4.91571228e-11,0.00000000,
1,446400,6493.661501,2.0398380002e-03,3.127789902,2.1922341725e-09,
-1.234405677,1.121228087e+00,-3.13084470e-09,8.7727285371e-01,1.428630937e-11,
4.341825843e-06,-1.132534817e-05,564.6718750,139.0781250,5.261972547e-08,
-2.561137080e-08*f39a85dd

...

#BDSEPHEMERISA,USB1,1,62.0,SATTIME,2209,475214.000,02000020,2626,16809;46,853,
2.00,0,-2.41e-08,-2.41e-08,1,475200,-3.22318403e-04,-2.03899120e-11,0.00000000,
1,475200,5282.635483,6.9640530273e-04,-0.109104372,3.9308780226e-09,
2.513097275,1.3085507441e-01,-6.78742558e-09,9.5335228732e-01,3.782300405e-10,
5.458947271e-06,1.009693369e-05,153.7500000,108.2187500,-8.568167686e-08,
-1.001171768e-07*8c90e4b5

#BDSEPHEMERISA,USB1,0,62.0,SATTIME,2208,422804.000,02000020,2626,16809;58,852,
2.00,1,-9.00e-09,0.00,28,295200,2.80906679e-05,3.90798505e-13,0.00000000,
29,295200,5282.617880,4.8023159616e-04,0.041959073,3.3054948300e-09,
0.355899976,-2.126947333e+00,-6.67813531e-09,9.7631596256e-01,2.464388366e-11,
-9.997747838e-07,9.569805115e-06,175.8125000,-20.7031250,-1.164153218e-08,
-9.778887033e-09*2efb9c0a
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	satellite ID	ID/ranging code	Ulong	4	H
3	Week	Week number in BeiDou time (BDT) since the BeiDou system time start epoch (January 1, 2006)	Ulong	4	H+4
4	URA	User range accuracy (m). This is the evaluated URAI/URA lookup-table value.	Double	8	H+8
5	health 1	Autonomous satellite health flag. 0 means broadcasting satellite is good and 1 means not.	Ulong	4	H+16
6	tgd1	Equipment group delay differential for the B1 signal (s)	Double	8	H+20
7	tgd2	Equipment group delay differential for the B2 signal (s)	Double	8	H+28
8	AODC	Age of data, clock	Ulong	4	H+36
9	toc	Reference time of clock parameters (s)	Ulong	4	H+40
10	a_0	Constant term of clock correction polynomial (s)	Double	8	H+44
11	a_1	Linear term of clock correction polynomial (s/s)	Double	8	H+52
12	a_2	Quadratic term of clock correction polynomial (s/s^2)	Double	8	H+60
13	AODE	Age of data, ephemeris	Ulong	4	H+68
14	toe	Reference time of ephemeris parameters (s)	Ulong	4	H+72
15	RootA	Square root of semi-major axis (sqrt(m))	Double	8	H+76
16	ecc	Eccentricity (dimensionless)	Double	8	H+84
17	ω	Argument of perigee (radians)	Double	8	H+92
18	ΔN	Mean motion difference from computed value (radians/s)	Double	8	H+100
19	M_0	Mean anomaly at reference time (radians)	Double	8	H+108
20	Ω_0	Longitude of ascending node of orbital of plane computed according to reference time (radians)	Double	8	H+116
21	$\dot{\Omega}$	Rate of right ascension (radians/s)	Double	8	H+124
22	i_0	Inclination angle at reference time (radians)	Double	8	H+132
23	IDOT	Rate of inclination angle (radians/second)	Double	8	H+140
24	c_{uc}	Amplitude of cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+148
25	c_{us}	Amplitude of sine harmonic correction term to the argument of latitude (radians)	Double	8	H+156
26	c_{rc}	Amplitude of cosine harmonic correction term to the orbit radius (m)	Double	8	H+164

Field	Field type	Description	Format	Binary bytes	Binary offset
27	c_{rs}	Amplitude of sine harmonic correction term to the orbit radius (m)	Double	8	H+172
28	c_{ic}	Amplitude of cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+180
29	c_{is}	Amplitude of sine harmonic correction term to the angle of inclination (radians)	Double	8	H+188
30	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+196
31	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.18 BDSIONO

BeiDou Klobuchar ionosphere delay model

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the Klobuchar ionosphere model parameters transmitted by the BeiDou B1I signals.

Message ID: 1590

Log type: Asynch

Recommended input:

```
log bdsionoa onchanged
```

ASCII example:

```
#BDSIONOA,USB1,9,61.0,SATTIME,2209,496844.000,02000020,1956,16809;35,
2.700835466384888e-08,1.937150955200195e-07,-1.668930053710938e-06,
2.503395080566406e-06,157696.0,-884736.0,5373952.0,-3932160.0*c84eb5f1
...
#BDSIONOA,USB1,0,61.0,SATTIME,2209,496844.000,02000020,1956,16809;6,
2.700835466384888e-08,1.937150955200195e-07,-1.668930053710938e-06,
2.503395080566406e-06,157696.0,-884736.0,5373952.0,-3932160.0*1f0a025a
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSIONO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	ID	Transmitting satellite ID	Ulong	4	H
3	α0	Alpha parameter constant term	Double	8	H+4
4	α1	Alpha parameter 1st order term	Double	8	H+12
5	α2	Alpha parameter 2nd order term	Double	8	H+20
6	α3	Alpha parameter 3rd order term	Double	8	H+28
7	β0	Beta parameter constant term	Double	8	H+36
8	β1	Beta parameter 1st order term	Double	8	H+44
9	β2	Beta parameter 2nd order term	Double	8	H+52
10	β3	Beta parameter 3rd order term	Double	8	H+60
11	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+68
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.19 BDSRAWNAVSUBFRAME

Raw BeiDou subframe data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw BeiDou subframe data for the BeiDou B1I signals with parity bits removed. Only subframes that have passed the parity check are output.

Message ID: 1695

Log type: Asynch

Recommended input:

```
log bdsrawnavsubframea onchanged
```

ASCII example:

```
#BDSRAWNAVSUBFRAMEA,USB1,0,61.5,SATTIME,2209,496898.000,02000020,88f3,16809;142
,26,B1D1,5,e2415e53d00e945264012f45b271a033e077c1cff684b81b23204963*36497110
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BDSRAWNAVSUBFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	signal channel	Signal channel number	Ulong	4	H
3	satellite ID	Satellite ID	Ulong	4	H+4
4	data source	Source of data (refer to *Table 93: Data source* below)	Enum	4	H+8
5	subframe ID	Subframe identifier	Ulong	4	H+12
6	raw subframe data	Framed raw navigation bits	Hex[28]	28	H+16
7	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+44
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 93: Data source

ASCII	Binary	Description
B1D1	0	Data is from a B1I/D1 signal
B1D2	1	Data is from a B1I/D2 signal

3.20 BESTDATUMINFO

Datum information for best position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution in the **BESTPOS** log (see page 527). For differential solutions, such as RTK or PSRDIFF, where the base station datum is not known, “UNKNOWN” is reported with an ESPG code of 0. Single-point and SBAS report “ECEF” and code 0.

Message ID: 2305

Log type: Asynch

Recommended input:

```
log bestdatuminfoa onchanged
```

ASCII example:

```
#BESTDATUMINFOA,USB1,0,62.5,FINESTEERING,2209,501000.000,02000020,0c2b,16809;
"ITRF2014",1165,2022.364,GOOD*ee0ebd8b
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of the position being output by the **BESTPOS** log.	Char[32]	variable	H
3	epsg_ code	EPSG code of the datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year). Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation status. See *Table 94: Transformation status* below.	Enum	4	variable
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 94: Transformation status

Binary	ASCII	Description
0	GOOD	An exact transformation was found and used.

Binary	ASCII	Description
1	ECEF_EQUIVALENCY	An exact transformation could not be found, but a similar transformation involving another Earth-fixed transformation was found and used.
2	SERVICE_DETAILS_ UNKNOWN	The datum of the input solution was not known and therefore a transformation could not take place.
3	REQUESTED_ TRANSFORMATION_ UNAVAILABLE	No transformation could be found to transform the solution into the requested datum.

3.21 BESTGNSSDATUMINFO

Datum information for BESTGNSS position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution in the **BESTGNSSPOS** log (see page 1098). For differential solutions, such as RTK or PSRDIFF, where the base station datum is not known, “UNKNOWN” is reported with an ESPG code of 0. Single-point and SBAS report “ECEF” and code 0.

Message ID: 2302

Log type: Asynch

Recommended input:

```
log bestgnssdatuminfoa onchanged
```

ASCII example:

```
#BESTGNSSDATUMINFOA,USB1,0,62.0,FINESTEERING,2209,501000.000,02000020,1790,
16809;"ITRF2014",1165,2022.364,GOOD*c889c041
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTGNSSDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of position being output by the **BESTGNSSPOS** log.	Char[32]	variable	
3	epsg_ code	EPSG code of the datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year). Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation Status. See *Table 94: Transformation status* on page 524.	Enum	4	variable
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.22 BESTPOS

Best position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

When positioning with GNSS, there are four parameters being solved for: latitude, longitude, height and receiver clock offset from GPS time. The quality of the solution for all four parameters depends on the geometry of where the satellites are with respect to the antenna (and receiver). The strength of the positioning geometry is indicated by Dilution of Precision (DOP) values, with lower DOP numbers indicating better geometry. Because all the GNSS satellites are above terrestrial receivers, the VDOP (vertical DOP) is the largest DOP value. This is why the reported standard deviation for height is usually larger than for latitude or longitude.

Accuracy is based on statistics and reliability is measured in percentages. When a receiver states it can measure height to one metre, this is an accuracy measure. Usually this is a one sigma value (one SD). A one sigma value for height has a reliability of 68%. In other words, the error is less than one metre 68% of the time. For a more realistic accuracy, double the one sigma value (one metre) and the result is 95% reliability (error is less than two metres 95% of the time). Generally, GNSS heights are 1.5 times poorer than horizontal positions. See also the note in the **GPGST** log on page 648 for CEP and RMS definitions.

This log contains the best position computed by the receiver. In addition, it reports several status indicators, including differential age, which is useful in predicting anomalous behaviour brought about by outages in differential corrections. A differential age of 0 indicates that no differential correction was used.



SPAN systems

On systems with SPAN enabled, this log contains the best available combined GNSS and Inertial Navigation System (INS - if available) position computed by the receiver.

With the system operating in an RTK mode, BESTPOS reflects the latest low-latency solution for up to 60 seconds after reception of the last base station observation. After this 60 second period, the position reverts to the best solution available and the degradation in accuracy is reflected in the standard deviation fields. If the system is not operating in RTK mode, pseudorange differential solutions continue for the time specified in the **PSRDIFFTIMEOUT** command (see page 319). If the receiver is SPAN enabled, the GNSS+INS combined solution is also a candidate for BESTPOS output.

The RTK system in the receiver provides two kinds of position solutions. The Matched RTK position is computed with buffered observations, so there is no error due to the extrapolation of base station measurements. This provides the highest accuracy solution possible at the expense of some latency which is affected primarily by the speed of the differential data link. The **MATCHEDPOS** log (see page 728) contains the matched RTK solution and can be generated for each processed set of base station observations.

The Low-Latency RTK position is computed from the latest local observations and extrapolated base station observations. This supplies a valid RTK position with the lowest latency possible at the expense of some accuracy. The degradation in accuracy is reflected in the standard deviation and is summarized in *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss. The amount of time that the base station observations are extrapolated is in the "differential age" field of the position log. The Low-Latency RTK system extrapolates for 60 seconds. The **RTKPOS** log (see page 903) contains the Low-Latency RTK position when valid, and an "invalid" status when a Low-Latency RTK solution could not be computed. The **BESTPOS** log contains either the low-latency RTK, PPP or pseudorange-based position, whichever has the smallest standard deviation.

RTK positioning uses the carrier phase observations from the receiver. The carrier phases are precise but ambiguous: the measurement includes an unknown integer number of cycles known as the “ambiguities”. Determining these ambiguities is the key to unlocking the highest-accuracy GNSS positions. This determination is known as ambiguity resolution. Before the integer ambiguities can be resolved they are first estimated as real-numbered values, “floats” in computing parlance. After some period that depends on RTK baseline length, ionosphere activity, and other observing conditions, the ambiguities can be resolved into integers, making centimetre or even sub-centimetre positioning possible.

Different positioning modes have different maximum logging rates, which are also controlled by model option. The maximum rates are: 100 Hz for RTK, 100 Hz for pseudorange based positioning, 20 Hz for GLIDE (PDP) and 20 Hz for PPP.

On SMART antennas, the position in the **BESTPOS** log may be corrected for antenna height. If so this will be indicated in the Extended Solution Status. See Terrain Compensation in the SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for details.

Message ID: 42

Log type: Synch

Recommended input:

```
log bestposa ontime 1
```

ASCII example:

```
#BESTPOSA,USB1,0,58.5,FINESTEERING,2209,502061.000,02000020,cdba,16809;
SOL_COMPUTED,PPP,51.15043706870,-114.03067882331,1097.3462,-17.0001,WGS84,
0.0154,0.0139,0.0288,"TSTR",11.000,0.000,43,39,39,38,00,00,7f,37*52483ac5
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol stat	Solution status, see *Table 95: Solution status* on the next page	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (metres)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the ellipsoid (m) of the chosen datum When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER For differential solutions such as RTK or PSRDIFF, the datum is reported as WGS84. However, the position solution is in the same datum as the base station, which may be unknown to the user.	Enum	4	H+36
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	lon σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID	Char[4]	4	H+52
13	diff_age	Differential age in seconds	Float	4	H+56
14	sol_age	Solution age in seconds	Float	4	H+60

Field	Field type	Description	Format	Binary bytes	Binary offset
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#solnL1SVs	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	Reserved		Hex	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 95: Solution status

Binary	ASCII	Description
0	SOL_COMPUTED	Solution computed The output solution should be considered valid only when the solution status reports SOL_COMPUTED.
1	INSUFFICIENT_OBS	Insufficient observations
2	NO_CONVERGENCE	No convergence
3	SINGULARITY	Singularity at parameters matrix
4	COV_TRACE	Covariance trace exceeds maximum (trace > 1000 m)
5	TEST_DIST	Test distance exceeded (maximum of 3 rejections if distance >10 km)
6	COLD_START	Not yet converged from cold start
7	V_H_LIMIT	Height or velocity limits exceeded (in accordance with export licensing restrictions)
8	VARIANCE	Variance exceeds limits
9	RESIDUALS	Residuals are too large

Binary	ASCII	Description
10-12	Reserved	
13	INTEGRITY_ WARNING	Large residuals make position unreliable
14-17	Reserved	
18	PENDING	When a **FIX position** command is entered, the receiver determines if the fixed position is valid. During this period, the receiver may report PENDING in the solution status. The use of a PPP seed may also trigger the PENDING solution status while the seed is being verified. PENDING implies there are not enough satellites currently tracked to verify if the FIX POSITION entered into the receiver is valid. Under normal conditions, you should only see PENDING for a few seconds on power up before the GNSS receiver has locked onto its first few satellites. If your antenna is obstructed (or not plugged in) and you have entered a FIX POSITION command, then you may see PENDING indefinitely.
19	INVALID_FIX	The fixed position, entered using the **FIX position** command, is not valid
20	UNAUTHORIZED	Position type is unauthorized
21	Reserved	
22	INVALID_RATE	The selected logging rate is not supported for this solution type.

Table 96: Position or velocity type

Binary	ASCII	Description
0	NONE	No solution
1	FIXEDPOS	Position has been fixed by the **FIX position** command or by position averaging.
2	FIXEDHEIGHT	Position has been fixed by the **FIX height** or **FIX auto** command or by position averaging
3-7	Reserved	
8	DOPPLER_ VELOCITY	Velocity computed using instantaneous Doppler
9-15	Reserved	
16	SINGLE	Solution calculated using only data supplied by the GNSS satellites
17	PSRDIFF	Solution calculated using pseudorange differential (DGPS, DGNSS) corrections
18	WAAS	Solution calculated using corrections from an SBAS satellite

Binary	ASCII	Description
19	PROPAGATED	Propagated by a Kalman filter without new observations
20-31	Reserved	
32	L1_FLOAT	Single-frequency RTK solution with unresolved, float carrier phase ambiguities
33	Reserved	
34	NARROW_ FLOAT	Multi-frequency RTK solution with unresolved, float carrier phase ambiguities
35-47	Reserved	
48	L1_INT	Single-frequency RTK solution with carrier phase ambiguities resolved to integers
49	WIDE_INT	Multi-frequency RTK solution with carrier phase ambiguities resolved to wide-lane integers
50	NARROW_INT	Multi-frequency RTK solution with carrier phase ambiguities resolved to narrow-lane integers
51	Reserved	
52	INS_SBAS	INS position, where the last applied position update used a GNSS solution computed using corrections from an SBAS (WAAS) solution
53	INS_PSRSP	INS position, where the last applied position update used a single point GNSS (SINGLE) solution
54	INS_PSRDIFF	INS position, where the last applied position update used a pseudorange differential GNSS (PSRDIFF) solution
55	INS_RTKFLOAT	INS position, where the last applied position update used a floating ambiguity RTK (L1_FLOAT or NARROW_FLOAT) solution
56	INS_RTKFIXED	INS position, where the last applied position update used a fixed integer ambiguity RTK (L1_INT, WIDE_INT or NARROW_INT) solution
57-66	Reserved	
67	EXT_ CONSTRAINED	INS position, where the last applied position update used an external source (entered using the **EXTERNALPVAS** command (see page 1046))
68	PPP_ CONVERGING	Converging TerraStar-C PRO or TerraStar-X solution
69	PPP	Converged TerraStar-C PRO or TerraStar-X solution
70	OPERATIONAL	Solution accuracy is within UAL operational limit
71	WARNING	Solution accuracy is outside UAL operational limit but within warning limit
72	OUT_OF_ BOUNDS	Solution accuracy is outside UAL limits

Binary	ASCII	Description
73	INS_PPP_ CONVERGING	INS position, where the last applied position update used a converging TerraStar-C PRO or TerraStar-X PPP (PPP_CONVERGING) solution
74	INS_PPP	INS position, where the last applied position update used a converged TerraStar-C PRO or TerraStar-X PPP (PPP) solution
77	PPP_BASIC_ CONVERGING	Converging TerraStar-L solution
78	PPP_BASIC	Converged TerraStar-L solution
79	INS_PPP_BASIC _CONVERGING	INS position, where the last applied position update used a converging TerraStar-L PPP (PPP_BASIC) solution
80	INS_PPP_BASIC	INS position, where the last applied position update used a converged TerraStar-L PPP (PPP_BASIC) solution

PPP requires access to a suitable correction stream, delivered either through L-band or the Internet. For L-band delivered TerraStar or Veripos service, an L-band capable receiver and software model is required, along with a subscription to the desired service. Contact NovAtel for TerraStar and Veripos subscription details.

Table 97: GPS and GLONASS signal-used mask

Bit	Mask	Description
0	0x01	GPS L1 used in Solution
1	0x02	GPS L2 used in Solution
2	0x04	GPS L5 used in Solution
3	0x08	Reserved
4	0x10	GLONASS L1 used in Solution
5	0x20	GLONASS L2 used in Solution
6	0x40	GLONASS L3 used in Solution
7	0x80	Reserved

Table 98: Galileo and BeiDou signal-used mask

Bit	Mask	Description
0	0x01	Galileo E1 used in Solution
1	0x02	Galileo E5a used in Solution
2	0x04	Galileo E5b used in Solution
3	0x08	Galileo ALTBOC used in Solution

Bit	Mask	Description
4	0x10	BeiDou B1 used in Solution (B1I and B1C)
5	0x20	BeiDou B2 used in Solution (B2I, B2a and B2b)
6	0x40	BeiDou B3 used in Solution (B3I)
7	0x80	Galileo E6 used in Solution (E6B and E6C)

Table 99: Extended solution status

Bit	Mask	Description
0	0x01	If an RTK solution: an RTK solution has been verified If a PDP solution: solution is GLIDE Otherwise: Reserved
1-3	0x0E	Pseudorange Iono Correction 0 = Unknown or default Klobuchar model 1 = Klobuchar Broadcast 2 = SBAS Broadcast 3 = Multi-frequency Computed 4 = PSRDiff Correction 5 = NovAtel Blended Iono Value
4	0x10	RTK ASSIST active
5	0x20	0 = No antenna warning 1 = Antenna information is missing See the **RTKANTENNA** command on page 335
6	0x40	Reserved
7	0x80	0 = Terrain Compensation corrections are not used 1 = Position includes Terrain Compensation corrections

Table 100: Supplemental position types and NMEA equivalents

Value	Documented Enum name	NMEA equivalent
68	PPP_CONVERGING	2
69	PPP	5
70	OPERATIONAL	4
71	WARNING	5
72	OUT_OF_BOUNDS	1
77	PPP_BASIC_CONVERGING	1
78	PPP_BASIC	2

3.23 BESTSATS

Satellites used in BESTPOS

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the used and unused satellites for the corresponding BESTPOS solution. It also describes the signals of the used satellites or reasons for exclusions.

Message ID: 1194

Log type: Synch

Recommended input:

```
log bestsatsa ontime 1
```

Abbreviated ASCII example

```
<BESTSATS COM1 0 62.5 FINESTEERING 2220 503251.000 02000000 be05 16807
<     36
<          GPS 18 GOOD 00000007
<          GPS 16 GOOD 00000003
<          GPS 5 GOOD 00000003
<          GPS 27 GOOD 00000007
<          GPS 29 GOOD 00000003
<          GPS 10 GOOD 00000007
<          GPS 23 GOOD 00000007
<          GPS 13 GOOD 00000003
<          GPS 15 GOOD 00000003
<          GPS 26 GOOD 00000007
<          QZSS 194 GOOD 00000007
<          GLONASS 18-3 GOOD 00000003
<          GLONASS 2-4 GOOD 00000003
<          GLONASS 15 SUPPLEMENTARY 00000003
<          GLONASS 1+1 GOOD 00000003
<          GLONASS 24+2 GOOD 00000003
<          GLONASS 23+3 GOOD 00000001
<          GLONASS 17+4 GOOD 00000003
<          GLONASS 8+6 GOOD 00000003
<          GALILEO 15 GOOD 0000000f
<          GALILEO 27 GOOD 0000000f
<          GALILEO 3 GOOD 0000000f
<          GALILEO 36 GOOD 0000000f
<          GALILEO 5 GOOD 0000000f
<          GALILEO 21 GOOD 0000000f
<          GALILEO 30 SUPPLEMENTARY 0000000f
<          GALILEO 9 GOOD 0000000f
<          BEIDOU 28 GOOD 0000001d
<          BEIDOU 33 GOOD 0000001d
<          BEIDOU 42 GOOD 0000001d
<          BEIDOU 27 GOOD 0000001d
<          BEIDOU 43 GOOD 0000001d
<          BEIDOU 41 GOOD 0000001d
<          BEIDOU 40 GOOD 0000001d
<          BEIDOU 11 GOOD 00000007
<          BEIDOU 14 GOOD 00000007
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	System	See *Table 145: Satellite system* on page 676	Enum	4	H+4
4	Satellite ID	In binary logs, the satellite ID field is 4 bytes. The 2 lowest-order bytes, interpreted as a USHORT, are the system identifier: for instance, the PRN for GPS, Galileo, BeiDou, NavIC and QZSS, or the slot for GLONASS. The 2 highest-order bytes are the frequency channel for GLONASS, interpreted as a SHORT and zero for all other systems. In ASCII and abbreviated ASCII logs, the satellite ID field is the system identifier. If the system is GLONASS and the frequency channel is not zero, then the signed channel is appended to the system identifier. For example, slot 13, frequency channel -2 is output as 13-2.	Ulong	4	H+8
5	Status	Satellite status. See *Table 101: Observation statuses* below	Enum	4	H+12
6	Signal mask	See *Table 102: GPS signal mask* on the next page, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *Table 106: QZSS signal mask* on page 538 and *Table 107: NavIC signal mask* on page 538	Hex	4	H+16
7	Next satellite offset = H + 4 + (#entries x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4 (#entries x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 101: Observation statuses

Value	Name	Description
0	GOOD	Observation is good
1	BADHEALTH	Satellite is flagged as bad health in ephemeris or almanac
2	OLDEPHEMERIS	Ephemeris >3 hours old
6	ELEVATIONERROR	Satellite was below the elevation cutoff
7	MISCLOSURE	Observation was too far from predicted value

Value	Name	Description
8	NODIFFCORR	No differential correction available
9	NOEPHEMERIS	No ephemeris available
10	INVALIDIODE	IODE used is invalid
11	LOCKEDOUT	Satellite has been locked out
12	LOWPOWER	Satellite has low signal power
13	OBSL2	An L2 observation not directly used in the solution
15	UNKNOWN	Observation was not used because it was of an unknown type
16	NOIONOCORR	No ionosphere delay correction was available
17	NOTUSED	Observation was not used in the solution
18	OBSL1	An L1 observation not directly used in the solution
19	OBSE1	An E1 observation not directly used in the solution
20	OBSL5	An L5 observation not directly used in the solution
21	OBSE5	An E5 observation not directly used in the solution
22	OBSB2	A B2 observation not directly used in the solution
23	OBSB1	A B1 observation not directly used in the solution
24	OBSB3	A B3 observation not directly used in the solution
25	NOSIGNALMATCH	Signal type does not match
26	SUPPLEMENTARY	Observation contributes supplemental information to the solution
27	OBSE6	An E6 observation not directly used in the solution
28	OBSL6	An L6 observation not directly used in the solution
99	NA	No observation available
100	BAD_INTEGRITY	Observation was an outlier and was eliminated from the solution
101	LOSSOFLOCK	Lock was broken on this signal
102	NOAMBIGUITY	No RTK ambiguity type resolved

Table 102: GPS signal mask

Bit	Mask	Description
0	0x01	GPS L1 used in the solution
1	0x02	GPS L2 used in the solution
2	0x04	GPS L5 used in the solution

Table 103: GLONASS signal mask

Bit	Mask	Description
0	0x01	GLONASS L1 used in the solution
1	0x02	GLONASS L2 used in the solution
2	0x04	GLONASS L3 used in the solution

Table 104: Galileo signal mask

Bit	Mask	Description
0	0x01	Galileo E1 used in the solution
1	0x02	Galileo E5A used in the solution
2	0x04	Galileo E5B used in the solution
3	0x08	Galileo ALTBOC used in the solution
4	0x10	Galileo E6 used in the solution

Table 105: BeiDou signal mask

Bit	Mask	Description
0	0x01	BeiDou B1I used in the solution
1	0x02	BeiDou B2I used in the solution
2	0X04	BeiDou B3 used in the solution
3	0x08	BeiDou B1C used in the solution
4	0x10	BeiDou B2a used in the solution
5	0x20	BeiDou B2b used in the solution

Table 106: QZSS signal mask

Bit	Mask	Description
0	0x01	QZSS L1 used in the solution
1	0x02	QZSS L2 used in the solution
2	0x04	QZSS L5 used in the solution
4	0x08	QZSS L6 used in the solution

Table 107: NavIC signal mask

Bit	Mask	Description
2	0x04	NavIC L5 used in the solution

3.24 BESTUTM

Best available UTM data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the best available position computed by the receiver in UTM coordinates.

See also the **UTMZONE** command on page 474 and the **BESTPOS** log on page 527.

The latitude limits of the UTM System are 80°S to 84°N. If your position is outside this range, the BESTUTM log outputs a northing, easting and height of 0.0, along with a zone letter of '*'and a zone number of 0, to indicate that the data in the log is unusable.

Message ID: 726

Log type: Synch

Recommended input:

```
log bestutma ontime 1
```

ASCII example:

```
#BESTUTMA,USB1,0,59.0,FINESTEERING,2209,502191.000,02000020,a40a,16809;
SOL_COMPUTED,PPP,11,U,5670746.6432,707661.8351,1097.3653,-17.0001,WGS84,0.0152,
0.0132,0.0286,"TSTR",11.000,0.000,44,39,39,38,0,00,7f,37*5e568127
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTUTM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	z#	Longitudinal zone number	Ulong	4	H+8
5	zletter	Latitudinal zone letter	Ulong	4	H+12
6	northing	Northing (m) where the origin is defined as the equator in the northern hemisphere and as a point 10,000,000 metres south of the equator in the southern hemisphere (that is, a 'false northing' of 10,000,000 m)	Double	8	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
7	easting	Easting (m) where the origin is 500,000 m west of the central meridian of each longitudinal zone (that is, a 'false easting' of 500,000 m)	Double	8	H+24
8	hgt	Height above mean sea level (m)	Double	8	H+32
9	undulation	Undulation - the relationship between the geoid and the ellipsoid (m) of the chosen datum When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+40
10	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+44
11	N σ	Northing standard deviation (m)	Float	4	H+48
12	E σ	Easting standard deviation (m)	Float	4	H+52
13	hgt σ	Height standard deviation (m)	Float	4	H+56
14	stn id	Base station ID	Char[4]	4	H+60
15	diff_age	Differential age in seconds	Float	4	H+64
16	sol_age	Solution age in seconds	Float	4	H+68
17	#SVs	Number of satellites tracked	Uchar	1	H+72
18	#solnSVs	Number of satellites used in solution	Uchar	1	H+73
19	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+74
20	#solnMultiSV	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+75
21	Reserved		Uchar	1	H+76
22	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+77
23	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+78
24	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+79

Field	Field type	Description	Format	Binary bytes	Binary offset
25	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+80
26	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.25 BESTVEL

Best available velocity data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the best available velocity information computed by the receiver. In addition, it reports a velocity status indicator, which is needed to determine whether or not the corresponding data is valid. The velocities calculated by the receiver can have a latency associated with them. When present, the velocity time of validity is the time tag in the log minus the latency value.

The velocity is typically from the same source used in the BESTPOS solution. For example, if the BESTPOS is from the pseudorange filter, then the BESTVEL velocity type is the same as for PSRVEL. However, a specific velocity source can be chosen. See the **BESTVELTYPE** command on page 109.

In a BESTVEL log, the actual speed and direction of the receiver antenna over ground is provided. The receiver does not determine the direction a vessel, craft or vehicle is pointed (heading) but rather the direction of motion of the GNSS antenna relative to ground.

The RTK, PDP and PPP velocities are computed from the average change in position over the time interval between consecutive solutions. As such, they are an average velocity based on the time difference between successive position computations and not an instantaneous velocity at the BESTVEL time tag. The velocity latency to be subtracted from the time tag is normally half the time between filter updates. Under default operation, the positioning filters are updated at a rate of 2 Hz. *This average velocity translates into a velocity latency of 0.25 seconds*. To reduce the latency, increase the update rate of the positioning filter being used by requesting the BESTVEL or BESTPOS messages at a rate higher than 2 Hz. For example, a logging rate of 10 Hz would reduce the velocity latency to 0.05 seconds.

The instantaneous Doppler derived velocity (DOPPLER_VELOCITY) has low latency and is not position change dependent. Under typically seen dynamics with minimal jerk, the velocity latency is negligible. Under extreme, high-jerk dynamics, the latency cannot be well represented and there may be errors in the reported velocity. Such dynamics are typically only seen in simulated or launch trajectories.

If the BESTPOS solution is SINGLE or WAAS or PSRDIFF, and PDP is not enabled with the **PDPFILTER** command (see page 286), then **BESTVEL** is always DOPPLER_VELOCITY. This is the case regardless of the **BESTVELTYPE** configuration.

Message ID: 99

Log type: Synch

Recommended input:

```
log bestvela ontime 1
```

ASCII example:

```
#BESTVELA,USB1,0,57.5,FINESTEERING,2209,502223.000,02000020,10a2,16809;
SOL_COMPUTED,PPP,0.250,13.000,0.0025,28.358727,0.0021,0*e9418656
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTVEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	vel type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results (s)	Float	4	H+8
5	age	Differential age in seconds	Float	4	H+12
6	hor spd	Horizontal speed over ground, in metres per second	Double	8	H+16
7	trk gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees	Double	8	H+24
8	vert spd	Vertical speed, in metres per second, where positive values indicate increasing altitude (up) and negative values indicate decreasing altitude (down)	Double	8	H+32
9	Reserved		Float	4	H+40
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+44
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Velocity (speed and direction) calculations are computed from either Doppler or carrier phase measurements rather than from pseudorange measurements. Typical speed accuracies are around 0.03 m/s (0.07 mph, 0.06 knots).

Direction accuracy is derived as a function of the vehicle speed. A simple approach would be to assume a worst case 0.03 m/s cross-track velocity that would yield a direction error function something like:

$$d\,(\text{speed}) = \tan^{-1}(0.03/\text{speed})$$

For example, if you are flying in an airplane at a speed of 120 knots or 62 m/s, the approximate directional error will be:

$$\tan^{-1}(0.03/62) = 0.03 \text{ degrees}$$

Consider another example applicable to hiking at an average walking speed of 3 knots or 1.5 m/s. Using the same error function yields a direction error of about 1.15 degrees.

You can see from both examples that a faster vehicle speed allows for a more accurate heading indication. As the vehicle slows down, the velocity information becomes less and less accurate. If the vehicle is stopped, a GNSS receiver still outputs some kind of movement at speeds between 0 and 0.5 m/s in random and changing directions. This represents the noise and error of the static position.

In a navigation capacity, the velocity information provided by your GNSS receiver is as, or more, accurate than that indicated by conventional instruments as long as the vehicle is moving at a reasonable rate of speed. It is important to set the GNSS measurement rate fast enough to keep up with all major changes of the vehicle's speed and direction. It is important to keep in mind that although the velocity vector is quite accurate in terms of heading and speed, the actual track of the vehicle might be skewed or offset from the true track by plus or minus 0 to 1.8 metres as per the standard positional errors.

3.26 BESTXYZ

Best available Cartesian position and velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the receiver's best available position and velocity in ECEF coordinates. The position and velocity status fields indicate whether or not the corresponding data is valid. See *Figure 13: WGS84 ECEF coordinate system* on page 547, for a definition of the ECEF coordinates.

See also the **BESTPOS** log on page 527 and **BESTVEL** log on page 542.



The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command (see page 284).

Message ID: 241

Log type: Synch

Recommended input:

```
log bestxyza ontime 1
```

ASCII example:

```
#BESTXYZA,USB1,0,59.0,FINESTEERING,2209,502264.000,02000020,44cf,16809;
SOL_COMPUTED,PPP,-1632848.2165,-3662158.6200,4944901.2721,0.0134,0.0197,0.0259,
SOL_COMPUTED,PPP,0.0007,0.0011,0.0009,0.0055,0.0069,0.0103,"TSTR",0.250,14.000,
0.000,44,40,40,39,0,00,7f,37*868939b6
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	P-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	P-X	Position X-coordinate (m)	Double	8	H+8
5	P-Y	Position Y-coordinate (m)	Double	8	H+16
6	P-Z	Position Z-coordinate (m)	Double	8	H+24
7	P-X σ	Standard deviation of P-X (m)	Float	4	H+32
8	P-Y σ	Standard deviation of P-Y (m)	Float	4	H+36
9	P-Z σ	Standard deviation of P-Z (m)	Float	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
10	V-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H+44
11	vel type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+48
12	V-X	Velocity vector along X-axis (m/s)	Double	8	H+52
13	V-Y	Velocity vector along Y-axis (m/s)	Double	8	H+60
14	V-Z	Velocity vector along Z-axis (m/s)	Double	8	H+68
15	V-X σ	Standard deviation of V-X (m/s)	Float	4	H+76
16	V-Y σ	Standard deviation of V-Y (m/s)	Float	4	H+80
17	V-Z σ	Standard deviation of V-Z (m/s)	Float	4	H+84
18	stn ID	Base station identification	Char[4]	4	H+88
19	V-latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results	Float	4	H+92
20	diff_age	Differential age in seconds	Float	4	H+96
21	sol_age	Solution age in seconds	Float	4	H+100
22	#SVs	Number of satellites tracked	Uchar	1	H+104
23	#solnSVs	Number of satellites used in solution	Uchar	1	H+105
24	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+106
25	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+107
26	Reserved		Char	1	H+108
27	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+109
28	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+110
29	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+111
30	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+112
31	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Figure 13: WGS84 ECEF coordinate system




Table 108: Definitions

Origin =	Earth's center of mass
Z-Axis =	Parallel to the direction of the Conventional Terrestrial Pole (CTP) for polar motion, as defined by the Bureau International de l'Heure (BIH) on the basis of the coordinates adopted for the BIH stations.
X-Axis =	Intersection of the WGS 84 Reference Meridian Plane and the plane of the CTP's Equator, the Reference Meridian being parallel to the Zero Meridian defined by the BIH on the basis of the coordinates adopted for the BIH stations.
Y-Axis =	Completes a right-handed, earth-centred, earth-fixed (ECEF) orthogonal coordinate system, measured in the plane of the CTP Equator, 90° East of the X-Axis.

These definitions are analogous to the BIH Defined Conventional Terrestrial System (CTS), or BTS, 1984.0.

3.27 BSLNXYZ

RTK XYZ baseline

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the receiver's RTK baseline in ECEF coordinates. The position status field indicates whether or not the corresponding data is valid. See *Figure 13: WGS84 ECEF coordinate system* on the previous page for a definition of the ECEF coordinates.

The BSLNXYZ log comes from time-matched base and rover observations such as in the **MATCHEDXYZ** log on page 733.



Asynchronous logs, such as BSLNXYZ, should only be logged ONCHANGED. Otherwise, the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

Message ID: 686

Log type: Asynch

Recommended input:

```
log bslnxyza onchanged
```

ASCII example:

```
#BSLNXYZA,USB1,0,66.0,FINESTEERING,2211,232444.000,02000020,6877,16809;
SOL_COMPUTED,NARROW_INT,2.9912,3.1779,3.3197,0.0070,0.0074,0.0105,"K250",
35,16,16,15,0,01,00,33*6c019b18
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BSLNXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	bsln type	Baseline type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	B-X	X Baseline (m)	Double	8	H+8
5	B-Y	Y Baseline (m)	Double	8	H+16
6	B-Z	Z Baseline (m)	Double	8	H+24
7	B-X σ	Standard deviation of B-X (m)	Float	4	H+32
8	B-Y σ	Standard deviation of B-Y (m)	Float	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
9	B-Z σ	Standard deviation of B-Z (m)	Float	4	H+40
10	stn ID	Base station identification	Char[4]	4	H+44
11	#SVs	Number of satellites tracked	Uchar	1	H+48
12	#solnSVs	Number of satellites used in solution	Uchar	1	H+49
13	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+50
14	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+51
15	Reserved		Uchar	1	H+52
16	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+53
17	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+54
18	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+55
19	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+56
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.28 CHANCONFIGLIST

Channel configuration list

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the channel configuration list including the number of channels and signal types. If more than one channel configuration is available, then it can be switched using the **SELECTCHANCONFIG command (see page 375)**.

Message ID: 1148

Log type: Polled

Recommended input:

```
log chanconfiglist once
```

Abbreviated ASCII example:

```
<CHANCONFIGLIST USB1 0 65.0 FINESTEERING 2209 502508.560 02000020 d1c0 16809
<     3 9
<          7
<          16 GPSL1L2PL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1
<          14 GLOL1L2
<          16 GALE1E5B
<          30 BEIDOUB1B2B2B
<          5 LBAND
<          7
<          16 GPSL1L2
<          4 QZSSL1CAL2C
<          4 SBASL1
<          14 GLOL1L2
<          16 GALE1E5B
<          30 BEIDOUB1B2B
<          5 LBAND
<          7
<          16 GPSL1L2PL2CL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1
<          14 GLOL1L2PL2C
<          16 GALE1E5AE5BALTBOC
<          30 BEIDOUB1B2B2B
<          5 LBAND
<          8
<          16 GPSL1L2PL2CL5
<          4 QZSSL1CAL2CL5
<          4 SBASL1L5
<          14 GLOL1L2PL2C
<          16 GALE1E5AE5BALTBOC
<          20 BEIDOUB1B1CB2B2BB3
<          8 NAVICL5
<          5 LBAND
<          8
<          16 GPSL1L2PL2CL5L1C
```

```
<           4 QZSSL1CAL2CL5L1CL6
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           11 GALE1E5AE5BALTBOCE6
<           16 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           6 QZSSL1CAL2CL5
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           9 GALE1E5AE5BALTBOCE6
<           24 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           4 QZSSL1CAL2CL5
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           16 GALE1E5AE5BALTBOCE6
<           16 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5
<           4 QZSSL1CAL2CL5L1CL6
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           11 GALE1E5AE5BALTBOCE6
<           20 BEIDOUB1B1CB2B2BB3
<           8 NAVICL5
<           5 LBAND
<           8
<           16 GPSL1L2PL2CL5L1C
<           4 QZSSL1CAL2CL5L1C
<           4 SBASL1L5
<           14 GLOL1L2PL2CL3
<           16 GALE1E5AE5BALTBOC
<           20 BEIDOUB1B1CB2B2B
<           8 NAVICL5
<           5 LBAND
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CHANCONFIGLIST header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	SetInUse	Current channel configuration being used. For example, if SetInUse is 2 then the second channel configuration listed in this log is the current channel configuration	Ulong	4	H
3	#chanconfigs	Number of channel configurations to follow	Ulong	4	H+4
4	#signaltypes	Total number of signal types in this channel configuration	Ulong	4	H+8
5	NumChans	Number of channels for individual signal type	Ulong	4	H+12
6	SignalType	See *Table 109: CHANCONFIGLIST signal type* below	Ulong	4	H+16
7	Next chanconfig offset = H + 8+ (#chanconfigs * (4 + (#signaltypes * 8)))				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 109: CHANCONFIGLIST signal type

Value	Name	Description
0	GPSL1	GPS L1 C/A
1	GPSL1L2	GPS L1 C/A and L2 P(Y)
4	SBASL1	SBAS L1 C/A
5	GPSL5	GPS L5
6	GPSL1L2C	GPS L1 C/A and L2C
7	GPSL1L2AUTO	GPS L1 C/A and L2 P(Y) or L2C
8	GLOL1L2	GLONASS L1 C/A and L2 P
9	LBAND	L-band
10	GLOL1	GLONASS L1 C/A
11	GALE1	Galileo E1
12	GALE5A	Galileo E5a
13	GALE5B	Galileo E5b
14	GALALTBOC	Galileo E5 AltBOC
15	BEIDOUB1	BeiDou B1I
16	GPSL1L2PL2C	GPS L1 C/A, L2 P(Y) and L2C
17	GPSL1L5	GPS L1 C/A and L5

Value	Name	Description
18	SBASL1L5	SBAS L1 C/A and L5
19	GPSL1L2PL2CL5	GPS L1 C/A, L2 P(Y), L2C and L5
20	GPSL1L2PL5	GPS L1 C/A, L2 P(Y) and L5
21	GALE1E5AE5B	Galileo E1, E5a and E5b
22	GALE1E5AE5BALTBOC	Galileo E1, E5a, E5b and E5 AltBOC
23	GALE1E5A	Galileo E1 and E5a
24	GLOL1L2C	GLONASS L1 C/A and L2 C/A
25	GLOL1L2PL2C	GLONASS L1 C/A, L2 P and L2 C/A
26	QZSSL1CA	QZSS L1 C/A / L1 C/B
27	QZSSL1CAL2C	QZSS L1 C/A / L1 C/B and L2C
28	QZSSL1CAL2CL5	QZSS L1 C/A / L1 C/B, L2C and L5
29	QZSSL1CAL5	QZSS L1 C/A / L1 C/B and L5
31	GALE1E5B	Galileo E1 and E5b
32	BEIDOUB1B3	BeiDou B1I and B3I
33	BEIDOUB3	BeiDou B3I
35	GALE1E5AE5BALTBOCE6	Galileo E1, E5a, E5b, E5 AltBOC and E6
36	GPSL1L2PL2CL5L1C	GPS L1 C/A, L2 P(Y), L2C, L5 and L1C
37	QZSSL1CAL2CL5L1C	QZSS L1 C/A / L1 C/B, L2C, L5 and L1C
38	QZSSL1CAL2CL5L1CL6	QZSS L1 C/A / L1 C/B, L2C, L5, L1C and L6
39	GLOL1L3	GLONASS L1 C/A and L3
40	GLOL3	GLONASS L3
41	GLOL1L2PL2CL3	GLONASS L1 C/A, L2 P, L2 C/A and L3
42	GPSL1L2PL2CL1C	GPS L1 C/A, L2 P(Y), L2C and L1C
43	QZSSL1CAL2CL1C	QZSS L1 C/A / L1 C/B, L2C and L1C
44	NAVICL5	NavIC L5
45	BEIDOUB1C	BeiDou B1C
46	BEIDOUB1B1C	BeiDou B1I and B1C
49	BEIDOUB1B2IB2B	BeiDou B1I, B2I, and B2b
50	BEIDOUB1B2B	BeiDou B1I, and B2b
51	BEIDOUB1B1CB2IB2B	BeiDou B1I, B1C, B2I and B2b

Value	Name	Description
52	BEIDOUB1B1CB2IB2BB3	BeiDou B1I, B1C, B2I, B2b and B3
53	BEIDOUB1B1CB2B	BeiDou B1I, B1C and B2b
54	BEIDOUB1B2IB2BB3	BeiDou B1I, B2I, B2b and B3
55	BEIDOUB1B2B2B	BeiDou B1I, B2I/B2a and B2b
56	BEIDOUB1B1CB2B2B	BeiDou B1I, B1C, B2I/B2a and B2b
57	BEIDOUB1B1CB2B2BB3	BeiDou B1I, B1C, B2I/B2a, B2b and B3
58	BEIDOUB1B2B2BB3	BeiDou B1I, B2I/B2a, B2b and B3

Configurations with **B2I** will track the B2I signal provided by BeiDou Phase II satellites. Configurations with **B2** will track either the B2I or B2a signal corresponding to BeiDou Phase II and Phase III satellites respectively, if the frequency is enabled by the model.

FW 7.10

Firmware **7.10.02** and greater.
Starting with firmware release 7.10.02, configurations with QZSSL1CA will track either the L1C/A or L1C/B signal corresponding to the QZSS broadcasting satellite configuration.

3.29 CLOCKMODEL

Current clock model status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The CLOCKMODEL log contains a filtered representation of the receiver's clock bias relative to GPS system time.

Message ID: 16

Log type: Synch

Recommended input:

```
log clockmodela ontime 1
```

ASCII example:

```
#CLOCKMODELA,USB1,0,65.0,FINESTEERING,2209,502563.000,02000020,98f9,16809;
VALID,0,502563.000,502563.000,1.645927507e-01,-3.828977102e-02,0.000000000,
3.705045540e-02,8.770260153e-04,0.000000000,8.770260153e-04,3.242199713e-03,
0.000000000,0.000000000,0.000000000,0.000000000,0.227,-4.714598090e-02,FALSE
*6572f493
```

The CLOCKMODEL log can be used to monitor the clock drift of an internal oscillator once the CLOCKADJUST mode has been disabled. Watch the CLOCKMODEL log to see the drift rate and adjust the oscillator until the drift stops.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CLOCKMODEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	status	Clock model status. See *Table 110: Clock model status* on the next page	Enum	4	H
3	reject_count	Number of rejected instantaneous clock errors	Ulong	4	H+4
4	propagation_ time	Time of last propagation	GPSec	4	H+8
5	update_time	Time of last update	GPSec	4	H+12
6	bias	Receiver clock bias (m)	Double	8	H+16
7	rate	Receiver clock bias rate (m/s)	Double	8	H+24
8	Reserved		Double	8	H+32
9	bias_variance	Receiver clock bias variance (m^2)	Double	8	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
10	covariance	Receiver clock bias/bias rate covariance (m^2/s)	Double	8	H+48
11	Reserved		Double	8	H+56
12	Reserved		Double	8	H+64
13	rate_variance	Receiver clock bias rate variance (m^2/s^2)	Double	8	H+72
14	Reserved		Double	8	H+80
15	Reserved		Double	8	H+88
16	Reserved		Double	8	H+96
17	Reserved		Double	8	H+104
18	instantaneous_bias	Last instantaneous receiver clock bias (m)	Double	8	H+112
19	instantaneous_rate	Last instantaneous receiver clock bias rate (m/s)	Double	8	H+120
20	Reserved		Bool	4	H+128
21	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+132
22	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 110: Clock model status

Binary	ASCII	Description
0	VALID	The clock model is valid
1	CONVERGING	The clock model is near validity
2	ITERATING	The clock model is iterating towards validity
3	INVALID	The clock model is not valid

3.30 CLOCKSTEERING

Clock steering status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The CLOCKSTEERING log is used to monitor the current state of the clock steering process. All oscillators have some inherent drift. By default the receiver attempts to steer the receiver clock to accurately match GPS reference time. If for some reason this is not desired, this behaviour can be disabled using the **CLOCKADJUST** command (see page 117).

If the **CLOCKADJUST** command (see page 117) is ENABLED and the receiver is configured to use an external reference frequency (set in the **EXTERNALCLOCK** command (see page 168)), then the clock steering process takes over the VARF output pins and may conflict with a previously entered **EVENTOUTCONTROL** command (see page 164).

Message ID: 26

Log type: Asynch

Recommended input:

```
log clocksteeringa onchanged
```

ASCII example:

```
#CLOCKSTEERINGA,USB1,0,64.0,FINESTEERING,2209,502647.507,02000020,0f61,16809;
INTERNAL,SECOND_ORDER,11000,6888.960937500,0.029999999,0.621999979,0.357,-0.027
*5368cd23
```

To configure the receiver to use an external reference oscillator, see the **EXTERNALCLOCK** command on page 168.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CLOCKSTEERING header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	source	Clock source, see *Table 111: Clock source* on the next page	Enum	4	H
3	steering state	Steering state, see *Table 112: Steering state* on the next page	Enum	4	H+4
4	period	Period of the pulse width modulated signal used to control the oscillator. This value is set using the **CLOCKCALIBRATE** command (see page 119).	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	pulse width	Current pulse width of the pulse width modulated signal used to control the oscillator. The starting point for this value is set using the **CLOCKCALIBRATE** command (see page 119). The clock steering loop continuously adjusts this value in an attempt to drive the receiver clock offset and drift terms to zero.	Double	8	H+12
6	bandwidth	The current band width of the clock steering tracking loop in Hz. This value is set using the **CLOCKCALIBRATE** command (see page 119).	Double	8	H+20
7	slope	The current clock drift change in m/s/bit for a 1 LSB pulse width. This value is set using the **CLOCKCALIBRATE** command (see page 119).	Float	4	H+28
8	offset	The last valid receiver clock offset computed (m). It is the same as Field # 18 of the **CLOCKMODEL** log (see page 555).	Double	8	H+32
9	drift rate	The last valid receiver clock drift rate received (m/s). It is the same as Field # 19 of the **CLOCKMODEL** log (see page 555).	Double	8	H+40
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+48
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 111: Clock source

Binary	ASCII	Description
0	INTERNAL	The receiver is currently steering its internal VCTCXO using an internal VARF signal
1	EXTERNAL	The receiver is currently steering an external oscillator using the external VARF signal

Table 112: Steering state

Binary	ASCII	Description
0	FIRST_ ORDER	Upon start-up, the clock steering task adjusts the VARF pulse width to reduce the receiver clock drift rate to below 1 ms using a 1st order control loop. This is the normal start-up state of the clock steering loop.
1	SECOND_ ORDER	Once the receiver has reduced the clock drift to below 1 m/s, it enters a second order control loop and attempts to reduce the receiver clock offset to zero. This is the normal runtime state of the clock steering process.

Binary	ASCII	Description
2	CALIBRATE_HIGH	This state corresponds to when the calibration process is measuring at the "High" pulse width setting. The CALIBRATE_HIGH state is only seen if you force the receiver to do a clock steering calibration using the **CLOCKCALIBRATE** command (see page 119). With the **CLOCKCALIBRATE** command (see page 119), you can force the receiver to calibrate the slope and centre pulse width of the currently selected oscillator, to steer. The receiver measures the drift rate at several "High" and "Low" pulse width settings.
3	CALIBRATE_LOW	This state corresponds to when the calibration process is measuring at the "Low" pulse width setting. The CALIBRATE_LOW state is only seen if you force the receiver to do a clock steering calibration using the **CLOCKCALIBRATE** command (see page 119). With the **CLOCKCALIBRATE** command (see page 119), you can force the receiver to calibrate the slope and centre pulse width of the currently selected oscillator, to steer. The receiver measures the drift rate at several "High" and "Low" pulse width settings.
4	CALIBRATE_CENTER	This state corresponds to the "Centre" calibration process. Once the centre has been found, the modulus pulse width, centre pulse width, loop bandwidth and measured slope values are saved in NVM and are used from now on for the currently selected oscillator (INTERNAL or EXTERNAL). After the receiver has measured the "High" and "Low" pulse width setting, the calibration process enters a "Centre calibration" process where it attempts to find the pulse width required to zero the clock drift rate.

3.31 CYBERSECEVENTS

Cyber-security events

This sequenced log provides a list of the cyber-security events logged by the receiver.

Message ID: 2608

Log type: Polled

Recommended input:

```
LOG CYBERSECEVENTS
```

ASCII example:

```
#CYBERSECEVENTSA,COM1,0,67.0,FINESTEERING,2371,246719.000,02000020,dbd9,32768;
9,9,9,WIFI_AP_PASSKEY_CHANGED,TRUE,2025,6,17,0,12,6,
ADMIN_PASSWORD_REINITIALIZED,TRUE,2025,6,17,0,12,24,BRUTE_FORCE_ATTACK_DETECTED,
TRUE,2025,6,17,0,16,1,ADMIN_PASSWORD_CHANGE_SAVED,TRUE,2025,6,17,0,16,12,
ADMIN_PASSWORD_CHANGE_SAVED,TRUE,2025,6,17,0,16,13,WIFI_AP_PASSKEY_CHANGED,
TRUE,2025,6,17,0,16,14,WIFI_AP_PASSKEY_CHANGED,TRUE,2025,6,17,0,16,14,
WIFI_AP_PASSKEY_SAVED,TRUE,2025,6,17,0,16,14,WIFI_AP_PASSKEY_REINITIALIZED,TRUE,
2025,6,17,0,16,14*206b00f3
```

Abbreviated ASCII example:

```
<CYBERSECEVENTS COM1 0 65.5 FINESTEERING 2371 245958.000 02000020 dbd9 32768
<     9 9 9
<          WIFI_AP_PASSKEY_CHANGED TRUE 2025 6 17 0 12 6
<          ADMIN_PASSWORD_REINITIALIZED TRUE 2025 6 17 0 12 24
<          BRUTE_FORCE_ATTACK_DETECTED TRUE 2025 6 17 0 16 1
<          ADMIN_PASSWORD_CHANGE_SAVED TRUE 2025 6 17 0 16 12
<          ADMIN_PASSWORD_CHANGE_SAVED TRUE 2025 6 17 0 16 13
<          WIFI_AP_PASSKEY_CHANGED TRUE 2025 6 17 0 16 14
<          WIFI_AP_PASSKEY_CHANGED TRUE 2025 6 17 0 16 14
<          WIFI_AP_PASSKEY_SAVED TRUE 2025 6 17 0 16 14
<          WIFI_AP_PASSKEY_REINITIALIZED TRUE 2025 6 17 0 16 14
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CYBERSECEVENTS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	total_ number_of_ events	Total number of cyber-security events in non-volatile storage	Ulong	4	H
3	number_of_ events_ logged	Number of cyber-security events logged in this log sequence.	Ulong	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	number_of_ cybersec_ events	Number of cyber-security events to follow (0 to 30). Each record consists of the following 8 fields (fields 5 through 12).	Ulong	4	H+8
5	event	Type of cyber-security event. See *Table 113: Cyber-Security event type* below.	Enum	4	H+12+ (N*16)
6	timestamp_ status	If TRUE, the following timestamp is an accurate representation of the UTC time at which the event occurred. If FALSE, the following timestamp is an estimate of the earliest possible UTC time at which the event occurred. The actual time could be any time prior to the next accurate time in the log or the time at which the log was captured.	Bool	4	H+16+ (N*16)
7	timestamp_ year	UTC year at which the event occurred.	Ushort	2	H+20+ (N*16)
8	timestamp_ month	UTC month at which the event occurred.	Uchar	1	H+22+ (N*16)
9	timestamp_ day	UTC day at which the event occurred.	Uchar	1	H+23+ (N*16)
10	timestamp_ hour	UTC hour at which the event occurred.	Uchar	1	H+24+ (N*16)
11	timestamp_ minute	UTC minute at which the event occurred.	Uchar	1	H+25+ (N*16)
12	timestamp_ second	UTC second at which the event occurred.	Ushort	2	H+26+ (N*16)
13	*	Delimiter separating log information from the CRC (ASCII only)	–	–	–
14	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+28+ (N * 16)
15	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 113: Cyber-Security event type

ASCII event name	Hex event value	Decimal event value	Description
INVALID	00	0	Uninitialized value
ADMIN_PASSWORD_ CHANGE_SAVED	0a	10	Admin password was changed to a different value and saved to NVM

ASCII event name	Hex event value	Decimal event value	Description
ADMIN_PASSWORD_ REINITIALIZED	0d	13	Admin password was reset to default value and saved to NVM
WIFI_AP_PASSKEY_ CHANGED	15	21	Wi-Fi AP passkey was changed to a different value
WIFI_AP_PASSKEY_SAVED	16	22	Different Wi-Fi AP passkey was saved to NVM
WIFI_AP_PASSKEY_ REINITIALIZED	17	23	Wi-Fi AP passkey was reset to default value
BRUTE_FORCE_ATTACK_ DETECTED	64	100	Threshold of consecutive invalid admin password entries reached

3.32 DATUMTRANSFORMATIONS

Available datum transformations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum transformations known to the receiver. This includes the default transformations included in the firmware, plus user-defined transformations entered using the **DATUMTRANSFORMATION** command (see page 135).

The entry “USER” to “WGS84” transformation in this log is the datum transformation set by the **USERDATUM** command (see page 463) or the **USEREXPDATUM** command (see page 465). The parameters in this entry will differ from those entered via the user datum commands due to differences in units and convention.

Message ID: 2298

Log type: Asynch

Recommended input:

```
log datumtransformations
```

Abbreviated ASCII example:

```
<DATUMTRANSFORMATIONS USB2 0 67.5 FINESTEERING 2390 245239.090 02000020 f957
32768
<     25
<          "ITRF2014" "ITRF2000" 2010.000 0.0007 0.0012 -0.0261 0.0000 0.0000
0.0000 2.120 0.0001 0.0001 -0.0019 0.0000 0.0000 0.0000 0.110
<          "ITRF2014" "ITRF2005" 2010.000 0.0026 0.0010 -0.0023 0.0000 0.0000
0.0000 0.920 0.0003 0.0000 -0.0001 0.0000 0.0000 0.0000 0.030
<          "ITRF2014" "ITRF2008" 2010.000 0.0016 0.0019 0.0024 0.0000 0.0000
0.0000 -0.020 0.0000 0.0000 -0.0001 0.0000 0.0000 0.0000 0.030
<          "ITRF2014" "ETRF2000" 2010.000 0.0547 0.0522 -0.0741 1.7010 10.2900 -
16.6320 2.120 0.0001 0.0001 -0.0019 0.0810 0.4900 -0.7920 0.110
<          "ITRF2014" "ETRF2005" 1989.000 0.0523 0.0490 -0.0372 0.0000 0.0000
0.0000 0.290 0.0003 0.0000 -0.0001 0.0540 0.5180 -0.7810 0.030
<          "ITRF2014" "ETRF2014" 2010.000 0.0000 0.0000 0.0000 1.7850 11.1510 -
16.1700 0.000 0.0000 0.0000 0.0000 0.0850 0.5310 -0.7700 -0.000
<          "ITRF2014" "NAD83(NSRS2011)" 1997.000 0.9950 -1.9014 -0.5228 -25.9147
-9.4264 -11.5993 1.305 0.0008 -0.0006 -0.0014 -0.0667 0.7574 0.0513 -0.072
<          "ITRF2014" "NAD83(CSRS)" 1997.000 0.9950 -1.9014 -0.5228 -25.9147 -
9.4264 -11.5993 1.305 0.0008 -0.0006 -0.0014 -0.0667 0.7574 0.0513 -0.072
<          "ITRF2014" "NAD83(PA11)" 1997.000 0.9096 -2.0142 -0.5616 -27.7410 -
13.4690 -2.7120 0.690 0.0001 0.0001 -0.0019 0.3840 -1.0070 2.1860 0.110
<          "ITRF2014" "NAD83(MA11)" 1997.000 0.9096 -2.0142 -0.5616 -28.9710 -
10.4200 -8.9280 0.690 0.0001 0.0001 -0.0019 0.0200 -0.1050 0.3470 0.110
<          "ITRF2014" "GDA94" 1994.000 -0.0831 -0.0175 0.0360 0.4254 -2.2578 -
2.4015 9.210 0.0014 0.0013 0.0008 -1.5461 -1.1820 -1.1551 0.139
<          "ITRF2014" "GDA2020" 2020.000 0.0000 0.0000 0.0000 0.0000 0.0000
0.0000 0.000 0.0000 0.0000 0.0000 -1.5038 -1.1835 -1.2072 0.000
<          "ITRF2020" "ITRF2014" 2015.000 -0.0014 -0.0009 0.0014 0.0000 0.0000
0.0000 -0.420 0.0000 -0.0001 0.0002 0.0000 0.0000 0.0000 0.000
<          "ITRF2020" "ITRF2000" 2015.000 -0.0002 0.0008 -0.0342 0.0000 0.0000
0.0000 2.250 0.0001 0.0000 -0.0017 0.0000 0.0000 0.0000 0.110
```

```
<          "ITRF2020" "ITRF2005" 2015.000 0.0027 0.0001 -0.0014 0.0000 0.0000
0.0000 0.650 0.0003 -0.0001 0.0001 0.0000 0.0000 0.0000 0.030
<          "ITRF2020" "ITRF2008" 2015.000 0.0002 0.0010 0.0033 0.0000 0.0000
0.0000 -0.290 0.0000 -0.0001 0.0001 0.0000 0.0000 0.0000 0.030
<          "ITRF2020" "ETRF2000" 2010.000 0.0533 0.0518 -0.0737 1.7010 10.2900 -
16.6320 1.700 0.0001 0.0000 -0.0017 0.0810 0.4900 -0.7920 0.110
<          "ITRF2020" "ETRF2005" 1989.000 0.0509 0.0507 -0.0410 0.0000 0.0000
0.0000 -0.130 0.0003 -0.0001 0.0001 0.0540 0.5180 -0.7810 0.030
<          "ITRF2020" "ETRF2014" 2010.000 -0.0014 -0.0004 0.0004 1.7850 11.1510
-16.1700 -0.420 0.0000 -0.0001 0.0002 0.0850 0.5310 -0.7700 0.000
<          "ITRF2020" "NAD83(NSRS2011)" 1997.000 0.9936 -1.9005 -0.5250 -25.9147
-9.4264 -11.5993 0.885 0.0008 -0.0007 -0.0012 -0.0667 0.7574 0.0513 -0.072
<          "ITRF2020" "NAD83(CSRS)" 1997.000 0.9936 -1.9005 -0.5250 -25.9147 -
9.4264 -11.5993 0.885 0.0008 -0.0007 -0.0012 -0.0667 0.7574 0.0513 -0.072
<          "ITRF2020" "NAD83(PA11)" 1997.000 0.9082 -2.0133 -0.5638 -27.7410 -
13.4690 -2.7120 0.270 0.0001 0.0000 -0.0017 0.3840 -1.0070 2.1860 0.110
<          "ITRF2020" "NAD83(MA11)" 1997.000 0.9082 -2.0133 -0.5638 -28.9710 -
10.4200 -8.9280 0.270 0.0001 0.0000 -0.0017 0.0200 -0.1050 0.3470 0.110
<          "ITRF2020" "GDA94" 1994.000 -0.0845 -0.0163 0.0332 0.4254 -2.2578 -
2.4015 8.790 0.0014 0.0012 0.0010 -1.5461 -1.1820 -1.1551 0.139
<          "ITRF2020" "GDA2020" 2020.000 -0.0014 -0.0014 0.0024 0.0000 0.0000
0.0000 -0.420 0.0000 -0.0001 0.0002 -1.5038 -1.1835 -1.2072 0.000
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	DATUMTRANSFORMATIONS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	# transformations	Number of transformations to follow	Ulong	4	H
3	from	Name of from datum	Char[32]	variable	H+4
4	to	Name of to datum	Char[32]	variable	variable
5	epoch	Reference epoch of parameters (decimal year) Examples: 2011.00 = Jan 1, 2011, 2011.19 = Mar 11, 2011	Double	8	variable
6	tx	Translations at reference epoch (metres)	Float	4	variable
7	ty		Float	4	variable
8	tz		Float	4	variable
9	rx	Rotations at reference epoch (milliarcseconds)	Float	4	variable
10	ry		Float	4	variable
11	rz		Float	4	variable
12	scale	Scale difference at reference epoch (parts per billion)	Float	4	variable

Field	Field type	Description	Format	Binary bytes	Binary offset
13	tx_vel	Translation rates (metres/year)	Float	4	variable
14	ty_vel		Float	4	variable
15	tz_vel		Float	4	variable
16	rx_vel	Rotation rates (milliarcseconds/year)	Float	4	variable
17	ry_vel		Float	4	variable
18	rz_vel		Float	4	variable
19	scale_vel	Scale difference rate (parts per billion/year)	Float	4	variable
21…	Next transformation offset = variable				
variable	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	variable
variable	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.33 DISPATCHMESSAGES

List of dispatch messages saved on receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Dispatch messages carry authorization and subscription information to the receiver. The **DISPATCHMESSAGES** log lists each of the dispatch messages currently saved on the receiver. These messages are in the form of an Offline Dispatch String along with information about its reception and status. If a Dispatch Type is not currently present, the message string will be empty.

The message string begins with the OEM7 Card PSN for identification purposes. See the **DISPATCHSCHEDULE** log on page 571 and **VALIDMODELS** log (see page 1018) for this information displayed in a readable format.

DISPATCHMESSAGES is a collection log; a separate log instance is sent for each dispatch type. The log header sequence number (not the dispatch sequence number) indicates how many logs remain, with 0 indicating the last log. When logged onnew, onchanged, or onall and a new dispatch message is received, only that type is reported.

For information about dispatch messages, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2559

Log type: Asynch

Recommended input:

```
log dispatchmessagesa onchanged
```

ASCII example:

```
#DISPATCHMESSAGESA,COM1,2,54.0,FINESTEERING,2209,513610.000,020000020,a867,
16809;DICTIONARY,110,2024/Mar/15,LBAND,0,19,"DICTIONARY=EbNYWJjZGVmZ2hpamtsbW5v
cHFy_c3R1dnd4eXpBQkNEhpamtsbW5vcHFyc3R1dnd4eXpBQkNEhpamtsbW5vcHFyc3R1dnd4eXpBQk
NE"

#DISPATCHMESSAGESA,COM1,1,54,0,FINESTEERING,2209,513610.000,020000020,a867,
16809;SPLIT,5,2024/Jul/22,LBAND,0,2,"BMHR17090005=Ymlwb3dlaHRvYm5hb3dlbnBhYjtsY
XNka2plb2ppYXdlZGZuamJuZQ=="

#DISPATCHMESSAGESA,COM1,0,54.0,FINESTEERING,2209,513610.000,020000020,a867,
16809;MODEL,3,2024/Jun/11,COMMAND,0,0,"BMHR17090005=cTk0LThocWFlYm4zODlh-O2J2bm
FwZW9pLXp4"
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	DISPATCHMESSAGES header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	dispatch type	The dispatch message type. The log exists if a message of this type has been received at some point in the past. See *Table 114: Dispatch message type* on the next page.	Enum	4	H
3	message sequence number	The maximum sequence number ever received for this message type, even if the message has been deleted. Range is 1 to 65535. 0 =This message type has never been received.	Ulong	4	H+4
4	install date	Date the dispatch of this type, with the given sequence number, was installed and saved. If the time was unknown when installed, this field will report “UNKNOWN”. 0 = This message is not currently installed.	Char[12]	12	H+8
5	delivery	The method for delivering this message to the receiver. See *Table 115: Dispatch delivery method* on the next page.	Enum	4	H+20
6	errors	The number of dispatch messages of this message type with a higher sequence number and correct signature parsed but discarded due to errors or unknown message content since power on. If this field indicates errors, ensure the firmware version is up to date.	Ulong	4	H+24
7	received	The number of dispatch messages of this message type addressed to this receiver that have been received over L-band or NTRIP since power on. This number includes repeats and rejected messages. Includes number also includes broadcast messages.	Ulong	4	H+28
8	message	The dispatch message in Offline Dispatch String format. This carries one or more secure authorization messages for receiver services and features. The string can be up to 2047 characters.	String	Variable	H+32
9	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	Variable

Field	Field type	Description	Format	Binary bytes	Binary offset
10	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 114: Dispatch message type

Binary value	ASCII value	Description
0	DICTIONARY	Dictionary message contains configuration common to all receivers.
1	SPLIT	Split Service Dispatch describes service periods for this receiver, compact.
2	MERGED	Merged Service Dispatch describes service periods for this receiver, extended. Only one of SPLIT or MERGED will be current.
3	MODEL	Model Dispatch describes permanent model upgrades as shown in the **VALIDMODELS** log (see page 1018).
4-15	RESERVED	Reserved.

Table 115: Dispatch delivery method

Binary value	ASCII value	Description
0	None	This message type has not been delivered.
1	COMMAND	This message type was installed with the **DISPATCHSET** command (see page 141).
2	STREAM	The message type was received through L-band satellite or NTRIP.

3.34 DISPATCHRECEIPT

Lists the dispatch messages installed

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **DISPATCHRECEIPT** log provides a digitally signed token that indicates which dispatch messages have been installed on the receiver, including those for Service Periods and for Permanent Models. The receipt string (which includes the PSN) can be provided to the NovAtel commerce system as proof of message reception and to confirm that the receiver has the latest subscription information. If a newer dispatch is available, the system will provide it. The values in the receipt are also expanded in the log for each type.

For information about dispatch messages, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2558

Log type: Asynch

Recommended input:

```
log dispatchreceipt once
```

ASCII Example:

```
<DISPATCHRECEIPT
<     3
<          DICTIONARY 6 0 1 0
<          SPLIT 12 0 1 0
<          MODEL 0 0 0 0
<     "BMHR17090005E=B7qAobpe72na03OdqM5MEwjFqoX7=”
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	DISPATCHRECEIPT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	# entries	Number of message type records to follow. Range is 0 to 15.	Ulong	4	H
3	dispatch type	Message type for this entry. See *Table 114: Dispatch message type* on the previous page. Only one of SPLIT or MERGED type is given – whichever is present. They share the same sequence number.	Enum	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	sequence number	Maximum message sequence number of this type ever received. 0 = This message type has never been received.	Ushort	2	H+8
5	maximum revision	Maximum supported dispatch revision for this type. Messages with higher revisions will be ignored.	Uchar	1	H+10
6	present	1 = This message is currently saved on the receiver 0 = This message is not currently present	Uchar	1	H+11
7	reserved	Reserved field filled with zero. Ignore on reception.	Ulong	4	H+12
9	Next message type = H + 16 + (#entries x 12)				
8	receipt	A digitally signed message indicating which dispatch messages are currently installed in the receiver. This message is in Offline Dispatch format, which begins with the card PSN. This message is 15 to 256 characters and contains only URL safe ASCII characters.	String	256	H+16+ (#entries x 12)
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+272+ (#entries x 12)
11	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.35 DISPATCHSCHEDULE

Scheduled sequence of authorized services

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **DISPATCHSCHEDULE** log describes the scheduled sequence of authorized services – corrections services and receiver features – for this receiver. All subscribed products appear along with the time period(s) subscribed including those current, future and recent past. Authorized services start on the first power on or reset after midnight local time at the start date of the service period. The service period ends at midnight local time at the end of the end date, but the receiver features continue until the next reset, at which point the next service period (if any) becomes active. If a contiguous service period also has corrections services, corrections continue until the reset so there is no gap between services, otherwise the corrections (only) are discontinued at midnight.

The log has three parts, describing what is currently authorized and active, the schedule of periods past, current and future, and the authorized configuration that applies outside of the scheduled service periods.

The **Active Parameters** section indicates the currently applied receiver features, GNSS channel configuration and services (by name). These may be due to a service period or the permanent receiver features. If a service period begins or ends during operation, the status will change from CURRENT to EXPIRED or EXPIRED_STOP, indicating that service will change on the next reboot and whether corrections have stopped.

The **Service Period** array describes a sequence of periods of time which do not overlap (but may not be contiguous). Each service period record includes the receiver features and service products authorized for that period and whether the period is future, current or past. When a new start date occurs, that period becomes PENDING and will take effect on the next reset. When an end date occurs, that period becomes EXPIRED and while the receiver features continue until the next reset, any PPP corrections continue only if a now PENDING period also has a corrections service enabled. Otherwise, any PPP position will gracefully degrade after the end date.

The **Outside Periods** section indicates what receiver features and channel configuration will be applied when no service periods are active – before, between or after all service periods. The receiver features are the selected permanent software model as delivered and selected by the dispatch message (see the **DISPATCHSET** command on page 141), auth code (see the **AUTH** command on page 85) and/or model (see the **MODEL** command on page 265).

See also the **LBANDBEAMTABLE** log on page 707 and **LBANDTRACKSTAT** log on page 709 to ensure PPP corrections can be delivered from the satellites.



For information about dispatch messages, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2556

Log Type: Synch

Recommended input:

```
log dispatchschedule once
```

ASCII Examples:

Example 1 – Normal case with an active period with 2 services.

```
CURRENT "FFNRYNTMNP1" PERIOD 7 GEOGATED 0 2
     "TerraStar-X"
     "ALIGN"
3
     2023 04 1 2024 04 20 PAST "FFNPNNTMNP1" PERIOD SERVICE NONE 0 "TerraStar-C
PRO" "" "" "" "" "" ""
     2024 04 21 2024 04 27 CURRENT "FFNRYNTMNP1" PERIOD SERVICE GEOGATED 0
"TerraStar-X" "ALIGN" "" "" "" "" ""
     2024 04 28 2025 04 20 FUTURE "DDNLNNTMNP1" PERMANENT DEFAULT GEOGATED 0
"TerraStar-L" "" "" "" "" "" ""
BASELINE "DDNLNNTMN" 1 0
```

Example 2 - During a time when no service periods are authorized.

```
CURRENT "DDNLNNTMN" PERMANENT 1 GEOGATED 0 0
0
NONE "DDNLNNTMN" 1 0
```

Example 3 – During a time in-between authorized service periods. In this example, the current date is 2024-04-11.

```
CURRENT "DDNLNNTMN" PERMANENT 1 GEOGATED 0 0
3
     2023 04 1 2024 04 10 PAST "FFNPNNTMNP1" PERIOD SERVICE NONE 0 "TerraStar-C
PRO" "" "" "" "" "" ""
     2024 04 21 2024 04 27 FUTURE "FFNRYNTMNP1" PERIOD SERVICE GEOGATED 0
"TerraStar-X" "ALIGN" "" "" "" "" ""
     2024 04 28 2025 04 20 FUTURE "DDNLNNTMNP1" PERMANENT DEFAULT GEOGATED 0
"TerraStar-L" "" "" "" "" "" ""
BASELINE "DDNLNNTMN" 1 0
```

Example 4 – When one service period has expired and the following is pending (service will change on reset). In this example, the current date is 2024-04-28:

```
EXPIRED "FFNRYNTMNP1" PERIOD 7 GEOGATED 0 2
     "TerraStar-X"
     "ALIGN"
3
     2023 04 1 2024 04 10 PAST "FFNPNNTMNP1" PERIOD SERVICE NONE 0 "TerraStar-C
PRO" "" "" "" "" "" ""
     2024 04 21 2024 04 27 EXPIRED "FFNRYNTMNP1" PERIOD SERVICE GEOGATED 0
"TerraStar-X" "ALIGN" "" "" "" "" ""
     2024 04 28 2025 04 20 PENDING "DDNLNNTMNP1" PERMANENT DEFAULT GEOGATED 0
"TerraStar-L" "" "" "" "" "" ""
BASELINE "DDNLNNTMN" 1 0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	DISPATCHSCHEDULE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
Active parameters					
2	active status	Are the active authorized services current or will they change (start or end a service period) on the next reset. See *Table 116: Active status* on page 576.	Enum	4	H
3	active receiver features	Software model currently applied. This indicates what functions are authorized for use. See the **MODELFEATURES** log on page 735 for details.	Char[16]	16	H+4
4	active receiver features source	How the active receiver features were determined. See *Table 117: Receiver features source* on page 577.	Enum	4	H+20
5	active channel configuration	GNSS channel configuration currently applied. This determines which satellites and signals are tracked. See the **SELECTCHANCONFIG** command on page 375 for details.	Ulong	4	H+24
6	active region restriction	For region restricted services, the type of region restriction currently applied. Receiver features are not region restricted. See *Table 118: Region restrictions* on page 577.	Enum	4	H+28
7	reserved		Ulong	4	H+32
8	# active services	Number of active service records to follow.	Ulong	4	H+36
9	active service name	Names of the active service product(s).	Char[16]	16	H+40+ (#services x 16)
Service periods					
10	# service periods	Number of service period records to follow.	Ulong	4	H+40+ (#services x 16) +16

Field	Field type	Description	Format	Binary bytes	Binary offset
11	service period start year	The year in which the service period begins.	Ushort	2	H+44+ (#services x 16) +16+ (#periods x 156)
12	service period start month	The month in which the service period begins.	Uchar	1	H+46+ (#services x 16) +16 + (#periods x 156)
13	service period start day	Service period begins at midnight local time of this day.	Uchar	1	H+47+ (#services x 16) +16 + (#periods x 156)
14	service period end year	The year in which the service period ends. 0 = No end date – service persists indefinitely.	Ushort	2	H+48+ (#services x 16) +16 + (#periods x 156)
15	service period end month	The month in which the service period ends. 0 = No end date – service persists indefinitely.	Uchar	1	H+50+ (#services x 16) +16 + (#periods x 156)
16	service period end day	Service period ends at midnight local time of this day. 0 = No end date – service persists indefinitely.	Uchar	1	H+51+ (#services x 16) +16 + (#periods x 156)
17	service period status	Indicates if this service period is current, past or future and whether it will change on a reboot. See *Table 119: Service period status* on page 577.	Enum	4	H+52+ (#services x 16) +16 + (#periods x 156)
18	service period receiver features	Software model applied during the service period. Indicates what functions are authorized for use. See the **MODELFEATURES** log on page 735 for details.	Char[16]	16	H+56+ (#services x 16) +16 + (#periods x 156)
19	service period receiver features source	Indicates whether the service period specifies a specific model. See *Table 117: Receiver features source* on page 577.	Enum	4	H+72+ (#services x 16) +16 + (#periods x 156)

Field	Field type	Description	Format	Binary bytes	Binary offset
20	service period channel configuration	Indicates whether GNSS channel configuration optimization is specified. See *Table 120: Channel configuration optimization* on page 578.	Enum	4	H+76+ (#services x 16) +16 + (#periods x 156)
21	service period region restriction	For region restricted services, the type of region restriction applied for this period. Receiver features are not region restricted. See *Table 118: Region restrictions* on page 577.	Enum	4	H+80+ (#services x 16) +16 + (#periods x 156)
22	reserved		Ulong	4	H+84+ (#services x 16) +16 + (#periods x 156)
23	Name1	Name of the service product authorized for this service period. If multiple products are authorized for this service period, the addition products are listed in the following fields.	Char[16]	16	H+88+ (#services x 16) +16 + (#periods x 156)
24	Name2	Name of the second service product authorized (if present). Blank if a second service is not authorized.	Char[16]	16	H+104+ (#services x 16) +16 + (#periods x 156)
25	Name3	Name of the third service product authorized (if present). Blank if a third service is not authorized.	Char[16]	16	H+120+ (#services x 16) +16 + (#periods x 156)
26	Name4	Name of the fourth service product authorized (if present). Blank if a fourth service is not authorized.	Char[16]	16	H+136+ (#services x 16) +16 + (#periods x 156)
27	Name5	Name of the fifth service product authorized (if present). Blank if a fifth service is not authorized.	Char[16]	16	H+152+ (#services x 16) +16 + (#periods x 156)
28	Name6	Name of the sixth service product authorized (if present). Blank if a sixth service is not authorized.	Char[16]	16	H+168+ (#services x 16) +16 + (#periods x 156)

Field	Field type	Description	Format	Binary bytes	Binary offset
29	Name7	Name of the seventh service product authorized (if present). Blank if a seventh service is not authorized.	Char[16]	16	H+184+ (#services x 16) +16 + (#periods x 156)
Outside of service periods					
30	baseline present	Indicates that the baseline subscription type will ensure the final service period does not expire. See *Table 121: Baseline present* on page 578.	Enum	4	H+200+ (#services x 16) +16 + (#periods x 156)
31	selected permanent model	These receiver features will take effect when no service period is scheduled. See the **MODEL** command on page 265.	Char[16]	16	H+204+ (#services x 16) +16 + (#periods x 156)
32	selected channel configuration	This channel configuration will take effect when no service period is scheduled. See the **SELECTCHANCONFIG** command on page 375 for details.	Ulong	4	H+220+ (#services x 16) +16 + (#periods x 156)
33	reserved		Ulong	4	H+224+ (#services x 16) +16 + (#periods x 156)
34	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+228+ (#services x 16) +16 + (#periods x 156)
35	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 116: Active status

Binary value	ASCII value	Description
0	UNKNOWN	GNSS time is not available yet, so it is not known whether the current period has expired or a new one started. The active receiver features and service continue to be authorized.
1	CURRENT	The active receiver features and services continue to be authorized and will continue through the next reset. This includes when no service period is active and the permanent model is applied.
2	EXPIRED	The service period has ended or a period of no service has ended and a different configuration will start with the next reset. Receiver features and any PPP corrections continue until reset.

Binary value	ASCII value	Description
3	EXPIRED_STOP	The service period has ended and a different configuration will start with the next reset. Receiver features continue until reset, but PPP corrections have been disabled (because the following time has no corrections).

Table 117: Receiver features source

Binary value	ASCII value	Description
0	PERIOD	The service period specified a model to use.
1	PERMANENT	The service period does not specify a model to use, so the selected permanent model is in use.
2	OVERRIDE	The service period model has been overridden using the **MODEL** command on page 265.

Table 118: Region restrictions

Binary value	ASCII value	Description
0	NONE	Corrections operation has no region restrictions.
1	GEOGATED	Corrections operation is limited to on-land. GEOGATED is also the default value reported if there is no subscription.
3	NEARSHORE	Corrections operation is limited to on land and near shore (coastal) regions.

Table 119: Service period status

Binary value	ASCII value	Description
0	FUTURE	The start date has not yet occurred.
1	PENDING	The current date is between the start and end date so the service will begin on the next reset.
2	CURRENT	The current date is between the start and end date and the service is being offered. It will continue on the next reset.
3	EXPIRED	The end date has passed while the service was being offered. Receiver features continue, but unless the next period has corrections services, corrections have stopped. The next period will take effect on the next reset.
4	PAST	The end date has passed and the service is not active.
5	PENDING_DICTIONARY	A service dispatch is installed for which a dictionary reference is not yet resolved. No service period will become current until a matching dictionary dispatch is received. The dictionary is transmitted over L-band and NTRIP approximately once per hour. A reset will not change this state. May also occur if a service is purchased that requires a newer firmware version. Update to the latest firmware.

Table 120: Channel configuration optimization

Binary value	ASCII value	Description
0	DEFAULT	The default channel configuration, or the channel configuration selected using the **SELECTCHANCONFIG** command (see page 375) will be used.
1	SERVICE	The GNSS channel configuration will be optimized for the given service if **TERRASTARAUTOCHANCONFIG** is set to ENABLE.

Table 121: Baseline present

Binary value	ASCII value	Description
0	NONE	No baseline subscription is present.
1	BASELINE	A baseline subscription type is present and will automatically extend the end date to ensure the service does not expire.

3.36 DUALANTENNAHEADING

Synchronous heading information for dual antenna product

Platform: OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2, CPT7

The heading is the angle from True North of the primary antenna to secondary antenna vector in a clockwise direction.

You must have an ALIGN capable, dual antenna receiver to use this log.

Message ID: 2042

Log type: Synch

Recommended input:

```
log dualantennaheadinga ontime 1
```

ASCII example:

```
#DUALANTENNAHEADINGA,UNKNOWN,0,66.5,FINESTEERING,1949,575614.000,02000000,d426,
32768;SOL_COMPUTED,NARROW_INT,-1.000000000,255.538528442,0.006041416,0.0,
0.043859947,0.052394450,"J56X",24,18,18,17,04,01,00,33*1f082ec5
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	DUALANTENNAHEADING header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	sol stat	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	length	Baseline length in metres For ALIGN Heading models, this field is -1. For ALIGN Relative Positioning models with a fixed position, this field is -1. For ALIGN Relative Positioning models, this field is the baseline length in metres, unless the position is fixed.	Float	4	H+8
5	heading	Heading in degrees (0° to 359.999°)	Float	4	H+12
6	pitch	Pitch (±90 degrees)	Float	4	H+16
7	Reserved		Float	4	H+20
8	hdg std dev	Heading standard deviation in degrees	Float	4	H+24

Field	Field type	Description	Format	Binary bytes	Binary offset
9	ptch std dev	Pitch standard deviation in degrees	Float	4	H+28
10	stn ID	Station ID string	Char[4]	4	H+32
11	#SVs	Number of satellites tracked	Uchar	1	H+36
12	#solnSVs	Number of satellites used in solution	Uchar	1	H+37
13	#obs	Number of satellites above the elevation mask angle	Uchar	1	H+38
14	#multi	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+39
15	sol source	Solution source (see *Table 144: Solution Source* on page 670)	Hex	1	H+40
16	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+41
17	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+42
18	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+43
19	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+44
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.37 ETHSTATUS

Current Ethernet status

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This log provides the current status of the Ethernet ports.

Message ID: 1288

Log type: Polled

Recommended input:

```
log ethstatusa once
```

ASCII example:

```
#ETHSTATUSA,USB1,0,65.0,FINESTEERING,2209,502756.000,02000020,e89d,16809;
1,ETHA,"00-21-66-04-18-FE",NOTCONNECT*9699791a
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ETHSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# of interfaces	Number of records to follow	Ulong	4	H
3	interface	Name of the Ethernet interface (e.g., ETHA)	Enum	4	H+4
4	MAC address	An identifier assigned to the network adapters or network interface card	String [18]	variable[1]	H+8
5	interface configuration	Current connectivity, speed and duplex settings of the Ethernet interface	Enum	4	H+26
6...	Next interface = H+4+(# of interfaces * 26)				
7	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+(# of interfaces * 26)
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Refer to the **ETHCONFIG** command (see page 160) for enum values.

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

3.38 FILELIST

Display the storage media contents

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this log.

Use this log to display the root directory of the active media. A log is produced for each file and directory in the root directory.

The active media is set with the **FILEMEDIACONFIG** command on page 176.

Message ID: 2100

Log type: Asynch

Recommended input:

```
log filelista
```

ASCII example:

```
#FILELISTA,USB1,16,65.5,FINESTEERING,2209,502825.000,02000020,50e7,16809;
INTERNAL_FLASH,FILE,419859,20200409,221434,
"NMNE17200009B_2020-04-09_22-14-34.LOG"*2ea4d1bf

#FILELISTA,USB1,15,65.5,FINESTEERING,2209,502825.000,02000020,50e7,16809;
INTERNAL_FLASH,FILE,14370264,20200409,223412,
"NMNE17200009B_2020-04-09_22-34-11.LOG"*36c44730

#FILELISTA,USB1,0,65.5,FINESTEERING,2209,502825.000,02000020,50e7,16809;
INTERNAL_FLASH,DIR,0,20200306,162238,"System Volume Information"*4cf7cae9
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	FILELIST header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	MassStorageDevice	Mass Storage Device See *Table 123: Mass storage device* on page 585	Enum	4	H
3	FileType	The type of entry for this log. See *Table 122: File type* on the next page	Enum	4	H+4
4	FileSize	File Size (in Bytes)	Ulong	4	H+8
5	ChangeDate	Date of the last change	Ulong	4	H+12
6	ChangeTime	Time of last change	Ulong	4	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
7	FileName	Name of the file or directory File Name STRING Variable H + 20	String	Variable	H+20
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	Variable
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 122: File type

Binary	ASCII	Description
0	NONE	Indicates there are no entries in the selected media
1	FILE	File
2	DIR	Directory

When there no files or directories on the specified media, a single **FILELIST** log is output with **FileType** set to *NONE* and file information set to *0* and empty strings.

3.39 FILESTATUS

Displays the state of the data log file

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this log.

Use this log to display the current state of the data log file. Typically the **FILESTATUS** log is used to determine if the log file is open for writing or closed. However, it also shows any error that has occurred.

Message ID: 2127

Log type: Asynch

Recommended input:

```
log filestatusa
```

ASCII example

```
#FILESTATUSA,USB1,0,65.5,FINESTEERING,2209,502895.032,02000020,4dbd,16809;
INTERNAL_FLASH,CLOSED,"",0,15726822,15754462,""*791f9a6e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	FILESTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	MassStorageDevice	The type of recording device See *Table 123: Mass storage device* on the next page.	Enum	4	H
3	FileStatus	File status See *Table 124: File status* on the next page.	Enum	4	H+4
4	FileName	Filename of the log file	Fixed Uchar Array	MAX_ FILENAME_ LENGTH (MFL)	H+8
5	FileSize	File Size (bytes)	Ulong	4	H+MFL+8
6	MediaRemainingCapacity	Remaining capacity on the storage media (kb)	Ulong	4	H+MFL+12
7	MediaTotalCapacity	Total capacity of the storage media (kb)	Ulong	4	H+MFL+16

Field	Field type	Description	Format	Binary bytes	Binary offset
8	ErrorMsg	Error Message	String	Variable	H+MFL+20
9	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	Variable
10	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 123: Mass storage device

Binary	ASCII	Description
1	USBSTICK	USB mass storage device
3	NO_STORAGE	No mass storage
4	INTERNAL_FLASH	Internal eMMC flash

Table 124: File status

Binary	ASCII	Description
1	OPEN	Log file is open
2	CLOSED	Log file is closed
3	BUSY	Media device is busy
4	ERROR	An error has occurred
5	COPY	Media is copying
6	PENDING	Waiting for the system to complete an operation. The file can not be opened until the operation is complete.

3.40 FILESYSTEMCAPACITY

Displays storage capacity available

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this log.

Use this log to check the amount of storage capacity available in both the internal and external storage.

Message ID: 2137

Log type: Polled

Recommended input:

```
log filesystemcapacity
```

Abbreviated ASCII example:

```
<FILESYSTEMCAPACITY USB1 0 66.0 FINESTEERING 2209 503457.025 02000020 fded 16809
<     2
<          USBSTICK 30984437760 27656192
<          INTERNAL_FLASH 15754461184 27639808
```

ASCII Example:

```
#FILESYSTEMCAPACITYA,USB1,0,65.0,FINESTEERING,2209,503492.024,02000020,fded,
16809;2,USBSTICK,30984437760,27656192,INTERNAL_FLASH,15754461184,27639808
*63cab762
```

The INTERNAL_FLASH is only present on the PwrPak7, CPT7 and CPT7700.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	FILESYSTEMCAPACITY header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	#Dev	Number of device with data to follow	Ulong	4	H
3	MassStorageDevice	File system type (recording device) See *Table 123: Mass storage device* on the previous page	Enum	4	H+4
4	TotalStorage	Total storage on device in bytes	Ulong	8	H+8
5	UsedStorage	Amount of storage used on the device in bytes	Ulong	8	H+16
6	Next device offset = H+4+(#Dev x 20)				

Field	Field type	Description	Format	Binary bytes	Binary offset
7	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#Dev x 20)
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.41 FILESYSTEMSTATUS

Display state of recording media

Platform: OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

PwrPak7M variants and Legacy CPT7 receivers (PN 80023560) do not support this log.

This log displays the current state of the recording media. It can be used to determine the state of the file system, such as any mounting errors.

When logging the FILESYSTEMSTATUS log, use the ONNEW or ONCHANGED log trigger.

Message ID: 2104

Log type: Asynch

Recommended input:

```
log filesystemstatusa onchanged
```

Abbreviated ASCII example:

```
<FILESYSTEMSTATUS USB1 1 65.5 FINESTEERING 2210 166466.301 02000020 143c 16809
<     USBSTICK MOUNTED 30984440 ""

<FILESYSTEMSTATUS USB1 0 65.5 UNKNOWN 0 15.440 02000020 143c 16809
<     INTERNAL_FLASH MOUNTED 15754462 ""
```

ASCII example:

```
#FILESYSTEMSTATUSA,USB1,1,65.5,FINESTEERING,2210,166466.301,02000020,143c,
16809;USBSTICK,MOUNTED,30984440,""*30c0e28c

#FILESYSTEMSTATUSA,USB1,0,65.5,UNKNOWN,0,15.440,02000020,143c,16809;
INTERNAL_FLASH,MOUNTED,15754462,""*2e6f66ef
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	FILESYSTEMSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	MassStorageDevice	Recording device See *Table 123: Mass storage device* on page 585	Enum	4	H
3	MassStorageStatus	Media status See *Table 125: Mass storage status* on the next page	Enum	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	TotalCapacity	Media total capacity (in kB)	Ulong	4	H+8
5	ErrorMsg	Error message	String	Variable	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	Variable
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 125: Mass storage status

Binary	ASCII	Description
0	UNMOUNTED	Mass storage unmounted
1	MOUNTED	Mass storage mounted
2	BUSY	Mass storage busy. i.e. formatting
3	ERROR	Mounting error
4	MOUNTING	Mass storage is being mounted
5	UNMOUNTING	Mass storage is being unmounted

3.42 FILETRANSFERSTATUS

Display the current state of a file transfer

Platform: PwrPak7

PwrPak7M variants do not support this log.

This log contains the current state of a file transfer from the internal memory to a USB stick. This logs also indicates any file transfer errors that may have occurred.

Message ID: 2101

Log type: Asynch

Recommended input:

```
log filetransferstatusa onchanged
```

ASCII example:

```
#FILETRANSFERSTATUSA,USB1,0,27.0,FINESTEERING,2209,503218.978,02000020,ce81,
16809;TRANSFERRING,0,27444,"NMNE17200009B_2020-04-09_22-14-34.LOG",""*4fa2a7a3
#FILETRANSFERSTATUSA,USB1,0,55.5,FINESTEERING,2209,503236.640,02000020,ce81,
16809;FINISHED,27444,27444,"NMNE17200009B_2022-05-05_23-03-19.LOG",""*2d48645b
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	FILETRANSFERSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	File Transfer Status	The status of the file transfer. See *Table 126: File transfer status* on the next page.	Enum	4	H
3	Total Transferred	Total amount of data transferred. (kbytes)	Ulong	4	H+4
4	Total Transfer Size	Total size of the data to transfer. (kbytes)	Ulong	4	H+8
5	Filename	Name of the file that is currently transferring.	String	Variable	H+12
6	Error Msg	Error message (if an error occurred)	String	Variable	Variable
7	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	Variable
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 126: File transfer status

Binary	ASCII	Description
1	NONE	There is no file transfer in progress
2	TRANSFERRING	There is an active file transfer
3	FINISHED	The transfer has been successfully completed
4	ERROR	An error occurred during the transfer
5	CANCELLED	A user cancelled the active file transfer

3.43 GALALMANAC

Decoded Galileo almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the decoded Galileo almanac parameters from Galileo navigation messages. Multiple messages are transmitted, one for each satellite ID with data. The Galileo almanac can come from any of the E1, E5a or E5b signals.

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

Message ID: 1120

Log type: Asynch

Recommended input:

```
log galalmanaca onchanged
```

ASCII example:

```
#GALALMANACA,USB1,22,65.5,SATTIME,2209,503250.000,02000020,131f,16809;
2,TRUE,TRUE,0,0,0,0,5,1185,502200.000,3.052e-04,-5.852e-09,6.4734e-01,
3.4994e-01,2.017e+00,2.9945e-04,3.638e-12,1.367e-02,-3.260e-03*d4dcde5e

#GALALMANACA,USB1,21,65.5,SATTIME,2209,503250.000,02000020,131f,16809;
3,TRUE,TRUE,0,0,0,0,5,1185,502200.000,3.052e-04,-5.852e-09,-1.452e+00,
-4.6096e-01,-1.392e+00,-5.5885e-04,-3.638e-12,2.344e-02,-2.148e-02*8b956b99

...

#GALALMANACA,USB1,1,65.5,SATTIME,2209,502900.000,02000020,131f,16809;
34,TRUE,TRUE,0,0,0,0,4,1185,501600.000,2.899e-04,-5.120e-09,2.728e+00,
1.629e+00,-1.433e+00,-5.1689e-04,-3.638e-12,2.344e-02,2.052e-02*6235e5c8

#GALALMANACA,USB1,0,65.5,SATTIME,2209,502950.000,02000020,131f,16809;
36,TRUE,TRUE,0,0,0,0,4,1185,501600.000,2.594e-04,-5.120e-09,2.730e+00,
2.2166e-01,7.6191e-01,-3.7384e-04,-7.276e-12,2.539e-02,2.052e-02*7aa7acd3
```

The speed at which the receiver locates and locks onto new satellites is improved if the receiver has approximate time and position (**SETAPPROXTIME** and **SETAPPROXPOS**), as well as an almanac. This allows the receiver to compute the elevation of each satellite so it can tell which satellites are visible and their Doppler offsets, improving Time to First Fix (TTFF).

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	SatId	Satellite ID	Ulong	4	H
3	FNAVReceived	Indicates F/NAV almanac data received	Bool	4	H+4
4	INAVReceived	Indicates I/NAV almanac data received	Bool	4	H+8
5	E1BHealth	E1B health status bits (only valid if INAVReceived is TRUE)	Uchar	1	H+12
6	E5aHealth	E5a health status bits (only valid if FNAVReceived is TRUE)	Uchar	1	H+13
7	E5bHealth	E5b health status bits (only valid if INAVReceived is TRUE)	Uchar	1	H+14
8	Reserved		Uchar	1	H+15
9	IODa	Almanac issue of data	Ulong	4	H+16
10	Weeks	Almanac reference week since the Galileo system time start epoch (August 22nd 1999)	Ulong	4	H+20
11	Seconds	Almanac reference time of week (s for ASCII, ms for binary)	GPSec	4	H+24
12	Ecc	Eccentricity (dimensionless)	Double	8	H+28
13	OmegaDot	Rate of right ascension (radians/s)	Double	8	H+36
14	Omega0	Right ascension (radians)	Double	8	H+44
15	Omega	Argument of perigee (radians)	Double	8	H+52
16	M0	Mean anomaly at ref time (radians)	Double	8	H+60
17	Af0	Satellite clock correction bias (s)	Double	8	H+68
18	Af1	Satellite clock correction linear (s/s)	Double	8	H+76
19	DeltaRootA	Difference with respect to the square root of the nominal semi-major axis (sqrt(m)) Nominal value is 29,600,000 m.	Double	8	H+84
20	DeltaI	Difference with respect to the nominal inclination at reference time (radians) Nominal value is 56 degrees.	Double	8	H+92
21	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+100
22	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.44 GALCLOCK

Galileo clock information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the Galileo time information.

This log is populated from both the I/NAV and F/NAV messages from any of the E1, E5a or E5b signals. Depending on the data source, it is possible that the time in the header of the log is earlier than the time in a previous log. This is expected behaviour.

Message ID: 1121

Log type: Asynch

Recommended input:

```
log galclocka onchanged
```

ASCII example:

```
#GALCLOCKA,USB1,0,66.5,SATTIME,2209,503614.000,02000020,c6cf,16809;
9.313225746e-10,0.0000000,18,432000,161,137,7,18,2.5902e-09,1.199e-14,518400,33
*802b6b93
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALCLOCK header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	A0	Constant term of polynomial (s)	Double	8	H
3	A1	1st order term of polynomial (s/s)	Double	8	H+8
4	DeltaTls	Leap second count before leap second adjustment	Long	4	H+16
5	Tot	UTC data reference time of week (s)	Ulong	4	H+20
6	WNt	UTC data reference week number (0 – 255)	Ulong	4	H+24
7	WNlsf	Week number of leap second adjustment (0 – 255)	Ulong	4	H+28
8	DN	Day number at the end of which a leap second adjustment becomes effective	Ulong	4	H+32
9	DeltaTlsf	Leap second count after leap second adjustment	Long	4	H+36
10	A0g	Constant term of the polynomial describing the difference between Galileo and GPS time (s)	Double	8	H+40
11	A1g	Rate of change of offset the offset between Galileo and GPS time (s/s)	Double	8	H+48

Field	Field type	Description	Format	Binary bytes	Binary offset
12	T0g	Reference time for GGTO data (s)	Ulong	4	H+56
13	WN0g	Week number of GGTO reference (0 – 63)	Ulong	4	H+60
14	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+64
15	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.45 GALCNAVRAWPAGE

Galileo raw CNAV page

Platform: OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7

This log provides Galileo raw C/NAV page data from Galileo E6 signals.

The **GALCNAVRAWPAGE** log is not output by default. To receive this log, data decoding for E6B/E6C must be enabled using the **DATADECODESIGNAL** command (see page 129) the specific signal.

Message ID: 2239

Log type: Asynch

Recommended input:

```
log galcnavrawpagea onnew
```

ASCII example:

```
#GALCNAVRAWPAGEA,COM1,0,61.0,SATTIME,2227,252250.000,02000120,ec4c,32768;
214,30,7,185,fffc13c6e6243942790079d6c8a83e7c1ee5dbcefe2b05e637d7b161a643559c44
a7e148041d9a4511720d7ead579003d92588c7ec76880035e6*cf1b4560
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALCNAVRAWPAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Signal Channel	Signal channel providing the bits	Ulong	4	H
3	PRN	Satellite PRN number	Ulong	4	H+4
4	Message ID	ID of the message	Ushort	2	H+8
5	Page ID	ID of the transmitted page of the encoded message	Ushort	2	H+10
6	Data	Raw C/NAV page data (464 bits). Does not include CRC or Tail bits. The first 14 bits are the Reserved bits of the C/NAV page. The next 448 bits contain the HAS page. The final 2 bits are included due to the HEX byte format and should be ignored.	HEX[58]	58	H+12
7	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	h+70
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.46 GALFNAVEPHEMERIS

Decoded Galileo FNAV ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GALFNAVEPHEMERIS log contains the Galileo F/NAV ephemeris information. Multiple messages are transmitted, one for each satellite ID. The F/NAV messages are only transmitted on E5a.

Message ID: 1310

Log type: Asynch

Recommended input:

```
log galfnavephemerisa onall
```

ASCII example:

```
#GALFNAVEPHEMERISA,USB1,21,35.5,SATTIME,2209,504150.000,02000020,02cd,16809;
2,0,0,0,0,68,107,0,501600,501600,1.94195529e+00,3.0676e-09,3.055053530e-04,
5.44060316e+03,9.740321573e-01,5.6931e-10,6.473214246e-01,3.503504077e-01,
-5.8141708e-09,7.6238e-06,4.7404e-06,2.409e+02,1.610e+02,-5.0291e-08,2.9802e-08
,2.989536151e-04,2.359002e-12,0.0,-6.985e-10*e65b02c5

#GALFNAVEPHEMERISA,USB1,20,35.5,SATTIME,2209,492700.000,02000020,02cd,16809;
3,0,0,0,0,52,107,0,492000,492000,-2.64850798e+00,3.4862e-09,3.018563148e-04,
5.44061768e+03,9.558740377e-01,-4.0323e-10,-1.45198786e+00,-4.689335290e-01,
-5.9263183e-09,-3.3025e-06,5.0087e-06,2.308e+02,-7.150e+01,1.8626e-09,
3.5390e-08,-5.578687415e-04,-3.907985e-12,0.0,3.260e-09*b13e7513

...

#GALFNAVEPHEMERISA,USB1,1,35.5,SATTIME,2209,504150.000,02000020,02cd,16809;
34,0,0,0,0,69,107,0,502200,502200,-1.35918661e+00,2.4115e-09,2.855090424e-04,
5.44061144e+03,9.978304990e-01,-5.8931e-11,2.72810277e+00,1.63000994e+00,
-5.1241420e-09,-4.7926e-06,1.3456e-05,6.991e+01,-1.037e+02,-3.9116e-08,
-3.5390e-08,-5.168793723e-04,-1.961098e-12,0.0,4.657e-09*3e6bf310

#GALFNAVEPHEMERISA,USB1,0,35.5,SATTIME,2209,504150.000,02000020,02cd,16809;
36,0,0,0,0,70,107,0,502800,502800,9.062661404e-01,2.4169e-09,2.578824060e-04,
5.44061532e+03,9.979634387e-01,-6.7860e-12,2.72986363e+00,2.260476454e-01,
-5.1745013e-09,-4.6510e-06,1.4180e-05,5.316e+01,-1.043e+02,8.0094e-08,
3.1665e-08,-3.731751349e-04,-5.456968e-12,0.0,6.286e-09*cfd6ad68
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALFNAVEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	SatId	Satellite identifier	Ulong	4	H
3	E5aHealth	E5a health status bits	Uchar	1	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	E5aDVS	E5a data validity status	Uchar	1	H+5
5	Reserved		Uchar	1	H+6
6	Reserved		Uchar	1	H+7
7	IODnav	Issue of data ephemeris	Ushort	2	H+8
8	SISA Index	Signal in space accuracy (unitless)	Uchar	1	H+10
9	Reserved		Uchar	1	H+11
10	T0e	Ephemeris reference time (s)	Ulong	4	H+12
11	T0c	Clock correction data reference time of week from the F/NAV message (s)	Ulong	4	H+16
12	M0	Mean anomaly at ref time (radians)	Double	8	H+20
13	DeltaN	Mean motion difference (radians/s)	Double	8	H+28
14	Ecc	Eccentricity (unitless)	Double	8	H+36
15	RootA	Square root of semi-major axis	Double	8	H+44
16	I0	Inclination angle at ref time (radians)	Double	8	H+52
17	IDot	Rate of inclination angle (radians/s)	Double	8	H+60
18	Omega0	Longitude of ascending node of orbital plane at weekly epoch (radians)	Double	8	H+68
19	Omega	Argument of perigee (radians)	Double	8	H+76
20	OmegaDot	Rate of right ascension (radians/s)	Double	8	H+84
21	Cuc	Amplitude of the cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+92
22	Cus	Amplitude of the sine harmonic correction term to the argument of latitude (radians)	Double	8	H+100
23	Crc	Amplitude of the cosine harmonic correction term to the orbit radius (m)	Double	8	H+108
24	Crs	Amplitude of the sine harmonic correction term to the orbit radius (m)	Double	8	H+116
25	Cic	Amplitude of the cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+124
26	Cis	Amplitude of the sine harmonic correction term to the angle of inclination (radians)	Double	8	H+132
27	Af0	SV clock bias correction coefficient from the F/NAV message (s)	Double	8	H+140

Field	Field type	Description	Format	Binary bytes	Binary offset
28	Af1	SV clock drift correction coefficient from the F/NAV message (s/s)	Double	8	H+148
29	Af2	SV clock drift rate correction coefficient from the F/NAV message (s/s^2)	Double	8	H+156
30	E1E5aBGD	E1, E5a broadcast group delay	Double	8	H+164
31	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+172
32	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.47 GALFNAVRAWALMANAC

Galileo FNAV raw almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GALFNAVRAWALMANAC log contains the Galileo F/NAV raw almanac information. This log contains the raw bits from page types 5 and 6. The F/NAV messages are only transmitted on E5a.

Message ID: 1123

Log type: Asynch

Recommended input:

```
log galfnavrawalmanaca onchanged
```

ASCII example:

```
#GALFNAVRAWALMANACA,USB1,22,54.5,SATTIME,2209,503250.000,02000020,5a64,16809;5,
1,502200,0800e050390bf78d307f0522b009d00080000000*7f669413
#GALFNAVRAWALMANACA,USB1,21,54.5,SATTIME,2209,503250.000,02000020,5a64,16809;5,
1,502200,0c018053b4e3c8626bff0c749fedbfff80000000*68aedae2
...
#GALFNAVRAWALMANACA,USB1,1,54.5,SATTIME,2209,503700.000,02000020,5a64,16809;6,1
,502800,8801804d09cc35b793ff2cb9efef1fff80000000*cceb28d7
#GALFNAVRAWALMANACA,USB1,0,54.5,SATTIME,2209,503750.000,02000020,5a64,16809;6,1
,502800,9001c04424d835b79d7f224edff3cfff00000000*84d3670a
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALFNAVRAWALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	IODa	Almanac issue of data	Ulong	4	H
3	WNa	Almanac reference Week Number	Ulong	4	H+4
4	T0a	Almanac reference time	Ulong	4	H+8
5	Raw Data	F/NAV raw almanac data	Hex[20]	20	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+32
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.48 GALFNAVRAWEPHEMERIS

Galileo FNAV raw ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GALFNAVEPHEMERIS log contains the Galileo F/NAV raw ephemeris information. This log contains raw ephemeris data from page type 1 to page type 4. The F/NAV messages are only transmitted on E5a.

Message ID: 1124

Log type: Asynch

Recommended input:

```
log galfnavrawephemerisa onall
```

ASCII example:

```
#GALFNAVRAWEPHEMERISA,USB1,21,31.0,SATTIME,2209,504350.000,02000020,4c19,16809;
2,2209,504350.080,4,0421120a8009cbce0000a601ace083204e41fe8942f643caaaaaa9,0,08
444f1f5411ffc06900280b0faa04d3431a5fceb018e9285ec8a0,0,0c4427af86200e46498d218d
0ffd09f11e1e141f82a1285ec8c955,0,1044ffe500100000000010000001278a189e252000b2037
0bd91e2b,0*29c25908

#GALFNAVRAWEPHEMERISA,USB1,20,31.0,SATTIME,2209,492700.000,02000020,4c19,16809;
3,2209,492700.093,4,0430d2008fedb8421ffeed01ace083204e40070942f0938aaaaaaa,0,08
3494170f49ffbf2f0027909eaa04f100c4d7379fee5d285e1298,0,0c3426f220bcece4d88b2621
f9130a811cdaf7108021285e12c155,0,1034000100130000000010000001278a189e252000b2037
0bc25d28,0*582c6a94

#GALFNAVRAWEPHEMERISA,USB1,19,31.0,SATTIME,2209,474100.000,02000020,4c19,16809;
4,2209,474100.093,4,044055ed2fde5928dffdb801ace083204e41f98942e77e8aaaaaab,0,08
15bd2316e5ffbf80002e7ae8aa04f353c4d94c9cf26d285ceffb,0,0c1526f2a4fdc6630b882658
f8610b291c45f62c7b49285cf02155,0,1015ffe800070000000010000001278a189e24f0004e027
0b9e092a,0*e2d0c13d

...

#GALFNAVRAWEPHEMERISA,USB1,2,31.0,SATTIME,2209,489700.000,02000020,4c19,16809;3
3,2209,489700.095,4,0610bdfd6ff1092960001c01ace083204e41fa8942ef1c8aaaaaa9,0,08
2f44c396a3ffc8190021253caa04fd856f39e443fe01285de3b9,0,0c2f28a90fba03eb32641844
f6001fd60415f2f27f59285de3e154,0,102ffff200190000000010000001278a189e252000b2037
0bbc8129,0*8294e367

#GALFNAVRAWEPHEMERISA,USB1,1,31.0,SATTIME,2209,504350.000,02000020,4c19,16809;3
4,2209,504350.081,4,0621160b2fef101a1fff7601ace083204e400a0942f643caaaaaa8,0,08
45c89f2b5dffc7f500256c18aa04e43b6f2724e3fd6d285ec8a3,0,0c4528a7bfe842699ecf1a60
f5f31c3808bdf30982c9285ec8c954,0,1045ffebffed00000001000000001278a189e252000b2037
0bd91e2a,0*d478a330

#GALFNAVRAWEPHEMERISA,USB1,0,31.0,SATTIME,2209,504350.000,02000020,4c19,16809;3
6,2209,504350.079,4,06411a0bcff3c5949ffe8001ace083204e400d8942f643caaaaaa8,0,08
4624ecb2e0ffc7680021cd19aa04ec2f6f3982b0ffb5285ec8a0,0,0c4628a922e10935c3311a6f
f63f1dbd06a5f2f882f1285ec8c954,0,1046002b00110000000010000001278a189e252000b2037
0bd91e2b,0*3dd4e753
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALFNAVRAWEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	satID	Satellite ID	Ulong	4	H
3	weeks	GPS reference week, in weeks	Ulong	4	H+4
4	time	GPS reference time (ms)	GPSec	4	H+8
5	#recs	Number of records to follow	Ulong	4	H+12
6	Raw Data	F/NAV raw ephemeris data	Hex[27]	27	H+16
7	Reserved		UChar	1	H+43
8	Next record offset = H + 12 + (#recs x 28)				
9	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+12+ (#recs x 28)
10	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.49 GALFNAVRAWPAGE

Raw Galileo FNAV page data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw Galileo F/NAV page data. The F/NAV messages are only transmitted on E5a.

Message ID: 1413

Log type: Asynch

Recommended input:

```
log galfnavrawpagea onchanged
```

ASCII example:

```
#GALFNAVRAWPAGEA,USB1,0,53.5,SATTIME,2209,504490.000,02000020,d4fb,16809;323,11
,19eaaaaaaaaaaaaaaab780240648d73f08d36ff0234efef6ffc0a*71133086
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALFNAVRAWPAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	signal channel	Signal channel providing the data	Ulong	4	H
3	SVID	SVID of transmitting satellite	Ulong	4	H+4
4	raw frame data	Raw F/NAV page (214 bits). Does not include CRC or Tail bits.	Hex[27]	27	H+8
5	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+35
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.50 GALHASRAWMT

Assembled HAS MT1 message

Platform: **OEM719, OEM729, OEM7700, PwrPak7, CPT7700**

Firmware: **This log is available only on 7.10.xx firmware.**

The **GALHASRAWMT** log contains a fully assembled raw High Accuracy Service (HAS) MT1 message. This log has fields for the HAS status, message type, message ID, message size, and the whole message data which has a maximum 1696 bytes.

The log time will be the start time of the first source page in GST, with 1024 added to the week to account for the difference between GPS time and GST at GST(t_0).

When logged as a binary message up to 3 bytes may be inserted after the message data to maintain 4-byte alignment.

Message ID: 2564

Log Type: Asnch

Recommended input:

```
LOG GALHASRAWMT ONNEW
```

Abbreviated ASCII example:

```
<GALHASRAWMT USB2 0 80.5 SATTIME 2151 417613.000 02000000 4442 32768
<     TEST MT1 1 106 106 709101934207300080080080082e7fffffeffe001415161718191
a1b1c1d1e1f202122232425262728292a2b2c2d2e2f303132333435363738393a3b3c3d3e3f4041
424344454647484 94a4b4c4d4e4f505152535455565758595a5b5c5d5e5f606162636465666768 69
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALHASRAWMT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	HAS status	HAS Status See *Table 127: HAS status* on the next page	Enum	4	H
3	Message type	Message type See *Table 128: HAS message type* on the next page.	Enum	4	H+4
4	Message ID	Message ID	Ushort	2	H+8
5	Reserved		Ushort	2	H+10
6	Message length	Number of bytes in the message data.	Ulong	4	H+12
7	Message data	MT message data. Maximum size: 1696 (32 pages * 53 bytes)	HEX [1696]	Variable	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
8	xxxx	32-bit CRC	Hex	4	Variable
9	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 127: HAS status

Binary value	ASCII value	Description
0	TEST	Test mode. HAS data is transmitted and can be used without any guarantee.
1	OPERATIONAL	HAS data is transmitted normally.
2	Reserved	Reserved
3	DO_NOT_USE	Do Not Use HAS. Stop using HAS from all satellites and discard any previously received messages.

Table 128: HAS message type

Binary value	ASCII value	Description
1	MT1	The MT1 message contains satellite corrections. It may also include masks, orbit corrections, clock corrections, code biases, carrier phase biases, user range accuracy indicators, or combinations of them.

3.51 GALINAVEPHEMERIS

Decoded Galileo INAV ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GALINAVEPHEMERIS log contains the Galileo I/NAV ephemeris information. Multiple messages are transmitted, one for each SVID with date. The I/NAV messages are only transmitted on E1 and E5b.

Message ID: 1309

Log type: Asynch

Recommended input:

```
log galinavephemerisa onall
```

ASCII example:

```
#GALINAVEPHEMERISA,USB1,21,54.0,SATTIME,2209,504514.000,02000020,dbe9,16809;
2,0,0,0,0,0,0,0,0,68,107,3,501600,501600,1.94195529e+00,3.0676e-09,
3.055053530e-04,5.44060316e+03,9.740321573e-01,5.6931e-10,6.473214246e-01,
3.503504077e-01,-5.8141708e-09,7.6238e-06,4.7404e-06,2.409e+02,1.610e+02,
-5.0291e-08,2.9802e-08,2.989528002e-04,2.359002e-12,0.0,-6.985e-10,-1.630e-09
*96bd12ad

#GALINAVEPHEMERISA,USB1,20,54.0,SATTIME,2209,492664.000,02000020,dbe9,16809;
3,0,0,0,0,0,0,0,0,52,107,3,492000,492000,-2.64850798e+00,3.4862e-09,
3.018563148e-04,5.44061768e+03,9.558740377e-01,-4.0323e-10,-1.45198786e+00,
-4.689335290e-01,-5.9263183e-09,-3.3025e-06,5.0087e-06,2.308e+02,-7.150e+01,
1.8626e-09,3.5390e-08,-5.578683922e-04,-3.907985e-12,0.0,3.260e-09,3.725e-09
*b4c17a47

...

#GALINAVEPHEMERISA,USB1,1,54.0,SATTIME,2209,504514.000,02000020,dbe9,16809;
34,0,0,0,0,0,0,0,0,69,107,3,502200,502200,-1.35918661e+00,2.4115e-09,
2.855090424e-04,5.44061144e+03,9.978304990e-01,-5.8931e-11,2.72810277e+00,
1.63000994e+00,-5.1241420e-09,-4.7926e-06,1.3456e-05,6.991e+01,-1.037e+02,
-3.9116e-08,-3.5390e-08,-5.168783828e-04,-1.961098e-12,0.0,4.657e-09,5.588e-09
*3526c71f

#GALINAVEPHEMERISA,USB1,0,54.0,SATTIME,2209,504514.000,02000020,dbe9,16809;
36,0,0,0,0,0,0,0,0,70,107,3,502800,502800,9.062661404e-01,2.4169e-09,
2.578824060e-04,5.44061532e+03,9.979634387e-01,-6.7860e-12,2.72986363e+00,
2.260476454e-01,-5.1745013e-09,-4.6510e-06,1.4180e-05,5.316e+01,-1.043e+02,
8.0094e-08,3.1665e-08,-3.731743782e-04,-5.456968e-12,0.0,6.286e-09,7.218e-09
*3ad372dc
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALINAVEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	SatId	Satellite identifier	Ulong	4	H
3	E5bHealth	E5b health status bits	Uchar	1	H+4
4	E5bDVS	E5b data validity status	Uchar	1	H+5
5	Reserved		Uchar	1	H+6
6	Reserved		Uchar	1	H+7
7	E1bHealth	E1b health status bits	Uchar	1	H+8
8	E1bDVS	E1b data validity status	Uchar	1	H+9
9	Reserved		Uchar	1	H+10
10	Reserved		Uchar	1	H+11
11	IODnav	Issue of data ephemeris	Ushort	2	H+12
12	SISA Index	Signal in space accuracy (unitless)	Uchar	1	H+14
13	INAV Source	Identifies the source signal: 0 = Unknown 1 = E1b 2 = E5b 3 = E1b and E5b	Uchar	1	H+15
14	T0e	Ephemeris reference time (s)	Ulong	4	H+16
15	T0c	Clock correction data reference time of week from the I/NAV message (s)	Ulong	4	H+20
16	M0	Mean anomaly at ref time (radians)	Double	8	H+24
17	DeltaN	Mean motion difference (radians/s)	Double	8	H+32
18	Ecc	Eccentricity (unitless)	Double	8	H+40
19	RootA	Square root of semi-major axis	Double	8	H+48
20	I0	Inclination angle at ref time (radians)	Double	8	H+56
21	IDot	Rate of inclination angle (radians/s)	Double	8	H+64
22	Omega0	Longitude of ascending node of orbital plane at weekly epoch (radians)	Double	8	H+72
23	Omega	Argument of perigee (radians)	Double	8	H+80

Field	Field type	Description	Format	Binary bytes	Binary offset
24	OmegaDot	Rate of right ascension (radians/s)	Double	8	H+88
25	Cuc	Amplitude of the cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+96
26	Cus	Amplitude of the sine harmonic correction term to the argument of latitude (radians)	Double	8	H+104
27	Crc	Amplitude of the cosine harmonic correction term to the orbit radius (m)	Double	8	H+112
28	Crs	Amplitude of the sine harmonic correction term to the orbit radius (m)	Double	8	H+120
29	Cic	Amplitude of the cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+128
30	Cis	Amplitude of the sine harmonic correction term to the angle of inclination (radians)	Double	8	H+136
31	Af0	SV clock bias correction coefficient from the I/NAV message (s)	Double	8	H+144
32	Af1	SV clock drift correction coefficient from the I/NAV message (s/s)	Double	8	H+152
33	Af2	SV clock drift rate correction coefficient from the I/NAV message (s/s^2)	Double	8	H+160
34	E1E5aBGD	E1, E5a broadcast group delay	Double	8	H+168
35	E1E5bBGD	E1, E5b broadcast group delay	Double	8	H+176
36	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+184
37	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.52 GALINAVRAWALMANAC

Galileo INAV raw almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GALINAVRAWALMANAC log contains the Galileo I/NAV raw almanac information. This log contains the I/NAV raw data from word types of 7 to 10. The I/NAV messages are only transmitted on E1 and E5b.

Message ID: 1125

Log type: Asynch

Recommended input:

```
log galinavrawalmanaca onchanged
```

ASCII example:

```
#GALINAVRAWALMANACA,USB1,22,53.0,SATTIME,2209,504399.000,02000020,53f2,16809;6,
1,502800,0800e05038fff78d307f05537009d00080000000*89e6eee3

#GALINAVRAWALMANACA,USB1,21,53.0,SATTIME,2209,504401.000,02000020,53f2,16809;6,
1,502800,0c018053b4efc8626bff0ca4ffedbfff80000000*069e52d2

#GALINAVRAWALMANACA,USB1,20,53.0,SATTIME,2209,504431.000,02000020,53f2,16809;6,
1,502800,1001a05f199fc8626bff051a1fde5fff00000000*7b988d8c

...

#GALINAVRAWALMANACA,USB1,2,53.0,SATTIME,2209,504640.000,02000020,53f2,16809;7,1
,503400,840240440e4035b79cff28ddbff1100000000000*57fdc359

#GALINAVRAWALMANACA,USB1,1,53.0,SATTIME,2209,504311.000,02000020,53f2,16809;6,1
,502800,8801804d09cc35b793ff2cb9efef1fff80000000*bd7dfce2

#GALINAVRAWALMANACA,USB1,0,53.0,SATTIME,2209,504341.000,02000020,53f2,16809;6,1
,502800,9001c04424d835b79d7f224edff3cfff00000000*f545b33f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALINAVRAWALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	IODa	Almanac issue of data	Ulong	4	H
3	WNa	Almanac reference week number	Ulong	4	H+4
4	T0a	Almanac reference time	Ulong	4	H+8
5	Raw Data	I/NAV raw almanac data	Hex[20]	20	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+32
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.53 GALINAVRAWDATA

Full even and odd pages of Galileo INAV word data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Firmware: **This log is available only on 7.10.02 firmware and greater.**

This log contains the full 240 bits of Galileo I/NAV word data (excluding the preamble word) from both even and odd pages. The I/NAV messages are only transmitted on E1 and E5b.

Message ID: 2623

Log Type: Asynch

Recommended input:

```
log galinavrawdataa onchanged
```

ASCII Example:

```
GALINAVRAWDATAA,USB1,0,81.0,FINESTEERING,2389,485977.013,02000020,e8bb,32768;24
1,8,GALE5B,05477f2fff607dbf500aaaed4aca80,aaaa80000000002aaaaaa23981ff40*e2aad2
aa
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALINAVRAWDATA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Signal channel	Signal channel providing data	Ulong	4	H
3	SVID	Space Vehicle ID (SVID) of transmitting satellite	Ulong	4	H+4
4	Signal type	Signal Type as defined in *Table 129: Signal type* below.	Enum	4	H+8
5	Even raw frame data	Raw I/NAV word from even page (120 bits)	Hex[15]	15	H+12
6	Odd raw frame data	Raw I/NAV word from odd page (120 bits)	Hex[15]	15	H+27
7	xxxx	32-bit CRC (ASCII and binary only)	Hex	4	H+42
8	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 129: Signal type

Binary	ASCII	Description
10433	GALE1	Galileo E1
10499	GALE5B	Galileo E5B

3.54 GALINAVRAWEPHEMERIS

Galileo INAV raw ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GALINAVEPHEMERIS log contains the Galileo I/NAV raw ephemeris information. This log contains the ephemeris raw data from word types of 1 to 6. The I/NAV messages are only transmitted on E1 and E5b.

Message ID: 1126

Log type: Asynch

Recommended input:

```
log galinavrawephemerisa onall
```

ASCII example:

```
#GALINAVRAWEPHEMERISA,USB1,21,46.5,SATTIME,2209,504780.000,02000020,bdd7,16809;
2,2209,504780.081,6,044482a13c7d504400a02c3ea8134d0f,08441a5fceb027af86200e4649
8d18e9,0c44ffc069218d0ffd09f11e1e141f6b,10440bff9400420a8009cbcc4000a601,14e083
204e41feff20250bd9e82aaaaa,180000000400000049e28627893d9e8a*7c51efc8
...
#GALINAVRAWEPHEMERISA,USB1,0,46.5,SATTIME,2209,504780.000,02000020,bdd7,16809;3
6,2209,504780.079,6,044682f093b2cb8000873466a813b0bf,08466f3982b028a922e10935c3
31ffb5,0c46ffc7681a6ff63f1dbd06a5f2f86b,10469000ac00460bcff3c5963ffe8001,14e083
204e400d83e0250bd9e82aaaaa,180000000400000049e28627893d9e8a*a5fcb10e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALINAVRAWEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	satID	Satellite ID	Ulong	4	H
3	weeks	GPS reference week, in weeks	Ulong	4	H+4
4	time	GPS reference time (ms)	GPSec	4	H+8
5	#recs	Number of records to follow	Ulong	4	H+12
6	Raw Data	I/NAV raw ephemeris data	Hex[16]	16	H+16
7	Next record offset = H + 12 + (#recs x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+12+ (#recs x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.55 GALINAVRAWWORD

Raw Galileo INAV word data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw Galileo I/NAV word data. The I/NAV messages are only transmitted on E1 and E5b.

Message ID: 1414

Log type: Asynch

Recommended input:

```
log galinavrawworda onchanged
```

ASCII example:

```
#GALINAVRAWWORDA,USB1,0,52.5,SATTIME,2209,504850.000,02000020,884b,16809;
256,25,GALE5B,025555555555555555555554a17b412*e0b32217
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALINAVRAWWORD header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	signal channel	Signal channel providing data	Ulong	4	H
3	SVID	Space Vehicle ID (SVID) of transmitting satellite	Ulong	4	H+4
4	signal type	Signal Type as defined in *Table 130: Signal type* below	Enum	4	H+8
5	raw frame data	Raw I/NAV word (128 bits)	Hex[16]	16	H+12
6	xxxx	32-bit CRC (ASCII and binary only)	Hex	4	H+28
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 130: Signal type

Binary	ASCII	Description
10433	GALE1	Galileo E1
10499	GALE5B	Galileo E5B

3.56 GALIONO

Decoded Galileo ionospheric corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the decoded Galileo ionospheric corrections.

Message ID: 1127

Log type: Asynch

Recommended input:

```
log galionoa onchanged
```

ASCII example:

```
#GALIONOA,USB1,0,53.5,SATTIME,2209,504850.000,02000020,d22e,16809;
1.12e+02,1.953e-01,9.5520e-03,0,0,0,0,0*38bfa05e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GALIONO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Ai0	Effective ionization level 1st order parameter (sfu)	Double	8	H
3	Ai1	Effective ionization level 2st order parameter (sfu/degree)	Double	8	H+8
4	Ai2	Effective ionization level 3st order parameter (sfu/degree^2)	Double	8	H+16
5	SF1	Ionospheric disturbance flag for region 1	Uchar	1	H+24
6	SF2	Ionospheric disturbance flag for region 2	Uchar	1	H+25
7	SF3	Ionospheric disturbance flag for region 3	Uchar	1	H+26
8	SF4	Ionospheric disturbance for flag region 4	Uchar	1	H+27
9	SF5	Ionospheric disturbance for flag region 5	Uchar	1	H+28
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+29
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.57 GEODETICDATUMS

Available datums

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log shows a list of available datums. User-defined datums can be added using the **GEODETICDATUM** command (see page 203).

The "USER" entry in the this log is the datum set by the **USERDATUM** command (see page 463) or the **USEREXPDATUM** command (see page 465).

Message ID: 2296

Log type: Asynch

Recommended input:

```
log geodeticdatums
```

Abbreviated ASCII example:

```
<GEODETICDATUMS COM1 0 37.0 UNKNOWN 0 0.375 02040020 e7f2 32768
<     15
<          "WGS84" 6326 EARTH_FIXED 6378137.00 298.2572235630
<          "ITRF2000" 6656 EARTH_FIXED 6378137.00 298.2572221010
<          "ITRF2005" 6896 EARTH_FIXED 6378137.00 298.2572221010
<          "ITRF2008" 1061 EARTH_FIXED 6378137.00 298.2572221010
<          "ITRF2014" 1165 EARTH_FIXED 6378137.00 298.2572221010
<          "ITRF2020" 1322 EARTH_FIXED 6378137.00 298.2572221010
<          "ETRF2000" 1186 PLATE_FIXED 6378137.00 298.2572221010
<          "ETRF2005" 1204 PLATE_FIXED 6378137.00 298.2572221010
<          "ETRF2014" 1206 PLATE_FIXED 6378137.00 298.2572221010
<          "NAD83(NSRS2011)" 1116 PLATE_FIXED 6378137.00 298.2572221010
<          "NAD83(CSRS)" 6140 PLATE_FIXED 6378137.00 298.2572221010
<          "NAD83(PA11)" 1117 PLATE_FIXED 6378137.00 298.2572221010
<          "NAD83(MA11)" 1118 PLATE_FIXED 6378137.00 298.2572221010
<          "GDA94" 6283 PLATE_FIXED 6378137.00 298.2572221010
<          "GDA2020" 1168 PLATE_FIXED 6378137.00 298.2572221010
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GEODETICDATUMS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	# datums	Number of datums to follow	Ulong	4	H
3	name	Name of datum	Char[32]	variable	H+4
4	epsg_code	EPSG code of datum	Ulong	4	variable
5	anchor	The datum's anchor. See *Table 44: Datum anchors* on page 204.	Enum	4	variable

Field	Field type	Description	Format	Binary bytes	Binary offset
6	semimajor_axis	Semi-major axis of datum’s ellipsoid (m)	Double	8	variable
7	flattening	Inverse flattening of datum’s ellipsoid (unitless)	Double	8	variable
8…	Next datum offset = variable				
variable	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	variable
variable	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.58 GLMLA

NMEA GLONASS L1 C/A almanac data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log outputs L1 C/A almanac data for GLONASS satellites. Multiple sentences are transmitted, one for each satellite.

The following relationships enable translation between the NMEA GLONASS satellite IDs, the NovAtel GLONASS PRN IDs, and the GLONASS slot numbers:

NMEA GLONASS satellite ID	= GLONASS slot number + 64
NovAtel GLONASS PRN ID	= GLONASS slot number + 37 = NMEA GLONASS satellite ID - 27

Message ID: 859

Log type: Asynch

Recommended input:

```
log glmla onchanged
```

ASCII example:

```
$GLMLA,23,01,65,0864,81,01f4,1e,96d9,0000,34bf42,129a60,0c37e8,001e0d,000,202*60
$GLMLA,23,02,66,0864,9c,0890,24,d8e6,0000,34c033,019183,16aac8,00285e,000,288*6E
$GLMLA,23,03,67,0864,85,0868,24,d5c3,0000,34c034,040255,188fa3,0024a2,000,20f*33
$GLMLA,23,04,68,0864,86,04e1,21,c31c,0000,34c047,066866,1a5cae,002bbc,000,225*30
$GLMLA,23,05,69,0864,81,02e0,22,d6dc,0000,34c05d,08cdb4,1c2bda,002c12,000,218*6F
$GLMLA,23,06,70,0864,9c,0175,20,7033,0000,34c01b,0b9ef4,1e7b43,001dac,000,00d*6F
$GLMLA,23,07,71,0864,85,074e,20,d48f,0000,34c021,0e0302,0fd5ff,0024ce,000,209*35
$GLMLA,23,08,72,0864,86,092c,1e,c79b,0000,34c03b,1051a4,0e14e5,0024f8,000,011*61
$GLMLA,23,09,73,0864,9e,06bf,56,f118,0000,34bfb2,120342,18a752,001077,000,20e*39
$GLMLA,23,10,74,0864,99,0675,57,077a,0000,34c013,0077c3,04b7a2,002068,000,016*36
$GLMLA,23,11,75,0864,80,01c7,56,d960,0000,34c012,02ffd6,02ca03,002685,000,20a*35
$GLMLA,23,12,76,0864,9f,03ec,55,ae43,0000,34bfb3,059c9f,00da9f,00216d,000,205*69
$GLMLA,23,13,77,0864,9e,023b,55,3cdc,0000,34c021,07f162,10f94a,002037,000,006*3E
$GLMLA,23,14,78,0864,99,020b,55,dc08,0000,34bfba,0a9208,12ef43,001ae9,000,207*65
$GLMLA,23,15,79,0864,80,02b6,56,c127,0000,34bfbf,0d03c1,14c440,001fcd,000,219*62
$GLMLA,23,16,81,0864,84,02b6,41,fbc5,0000,34bfb5,112438,02cf59,003ad4,000,28a*64
$GLMLA,23,17,82,0864,9d,0523,41,89a7,0000,34bfcc,137a8d,011221,0040c1,000,21f*62
$GLMLA,23,18,83,0864,83,00f3,48,3129,0000,34c009,01dd22,0e9ada,004642,000,031*67
$GLMLA,23,19,84,0864,82,0430,46,8255,0000,34bfc7,04b2bb,0c7533,004691,000,012*36
$GLMLA,23,20,85,0864,84,01da,43,6b28,0000,34bf81,0773a7,0a3509,003f61,000,04f*33
$GLMLA,23,21,86,0864,9d,095f,43,0cbb,0000,34bff6,09b474,0889a2,0043a5,000,030*37
$GLMLA,23,22,87,0864,83,021f,43,30bb,0000,34c0f6,0c8f05,065ccf,004357,000,00b*37
$GLMLA,23,23,88,0864,82,019d,43,cfaf,0000,34bfd2,0eb0d3,04bb13,002bc3,000,218*36
```

Refer to the GLONASS section of *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

Field	Structure	Description	Symbol	Example
1	$GLMLA	Log header		$GLMLA
2	#alm	Number of NMEA almanac messages in the set	x.x	16
3	alm#	Current message number	x.x	13
4	slot	Slot number for satellite (65-96) The NMEA GLONASS PRN numbers are 64 plus the GLONASS slot number. Current slot numbers are 1 to 24 which give the range 65 to 88. PRN numbers 89 to 96 are available if slot numbers above 24 are allocated to on-orbit spares.	xx	85
5	N	Calendar day count within the four year period from the last leap year	x.x	1176
6	hlth & freq	Health and frequency for satellite Health and carrier frequency numbers are represented in this 2-character Hex field as: hh = [8][7][6][5][4][3][2][1] (LSB) carrier frequency number of satellite spare bits health of satellite	hh	88
7	ecc	Eccentricity [1]	hhhh	01a6
8	ΔTdot	Rate of change of orbital period (s/orbital period^2) [1]	hh	0d
9	w	Argument of perigee (PZ-90.02) (radians)[1]	hhhh	9dc9
10	t_{16MSB}	Clock offset, in seconds (s)[1]	hhhh	8000
11	ΔT	Correction to the mean value of the Draconian period (s/orbital period) [1]	hhhhhh	34bff8
12	tπ	GLONASS Time of ascending node equator crossing (s)[1]	hhhhhhh	031887
13	l	Longitude of ascending node equator crossing (PZ-90.02) (radians)[1]	hhhhhhh	02da1e
14	Δi	Correction to nominal inclination (radians)[1]	hhhhhhh	002838
15	t_{12LSB}	Clock offset (s)[1]	hhh	099
16	t	Coarse value of the time scale shift [1]	hhh	242
17	xxxx	32-bit CRC (ASCII and Binary only)	Hex	*6D
18	[CR][LF]	Sentence terminator (ASCII only)	-	[CR][LF]

1. The LSB of the Hex data field corresponds to the LSB of the word indicated in the Table 4.3 of the GLONASS Interface Control Document, 1995. If the number of available bits in the Hex field is greater than the word, the MSB (upper bits) are unused and filled with zeroes.

3.59 GLOALMANAC

Decoded GLONASS L1 C/A almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GLONASS L1 C/A almanac reference time and week are in GPS reference time coordinates. GLONASS ephemeris information is available through the **GLOEPHEMERIS** log (see page 622).

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

The speed at which the receiver locates and locks onto new satellites is improved if the receiver has approximate time and position (**SETAPPROXTIME** and **SETAPPROXPOS**), as well as an almanac. This allows the receiver to compute the elevation of each satellite so it can tell which satellites are visible and their Doppler offsets, improving Time to First Fix (TTFF).

Message ID: 718

Log type: Asynch

Recommended input:

```
log gloalmanaca onchanged
```

ASCII example:

```
#GLOALMANACA,USB1,0,53.0,SATTIME,2209,504978.000,02000020,ba83,16809;
24,
2209,459317.000,1,1,1,0,38099.000000000,2.399074047,0.023048661,0.000476837,
-0.560765852,-2655.628906250,0.001831055,-0.000007629,
2209,424430.093,2,-4,1,0,3212.093750000,-1.309084823,0.030961245,0.002090454,
-2.181895923,-2656.099609375,0.002197266,-0.000518799,
...
2209,446938.156,23,3,1,0,25720.156250000,1.249280545,0.051649013,0.000517845,
1.196025646,-2656.480468750,-0.000183105,0.000041962,
2209,451304.593,24,2,1,0,30086.593750000,0.928882292,0.033564818,0.000393867,
-1.955729631,-2655.910156250,-0.000183105,-0.000091553*87b68608
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLOALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#recs	The number of GLONASS almanac records to follow. Set to zero until almanac data is available	Long	4	H
3	week	GPS reference week, in weeks	Ulong	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	time	GPS reference time, in milliseconds (binary data) or seconds (ASCII data) **Note**: The week and time are based on the GPS scale and are computed using the N_4, N^A, and $t_{\lambda n}{}^A$ values.	GPSec	4	H+8
5	slot	Slot number for satellite, ordinal	Uchar	1	H+12
6	frequency	Frequency for satellite, ordinal (frequency channels are in the range -7 to +6)	Char	1	H+13
7	sat type	Satellite type where 0 = GLO_SAT 1 = GLO_SAT_M (M type) 2 = GLO_SAT_K (K type) 3 = GLO_SAT_K2 (K2 type)[1]	Uchar	1	H+14
8	health	Satellite status where 0 = OPERATIONAL 1 = MALFUNCTION	Uchar	1	H+15
9	TlambdaN	GLONASS Time of ascending node equator crossing (s)	Double	8	H+16
10	lambdaN	Longitude of ascending node equator crossing (PZ-90.02) (radians)	Double	8	H+24
11	deltaI	Correction to nominal inclination (radians)[2]	Double	8	H+32
12	ecc	Eccentricity	Double	8	H+40
13	ArgPerig	Argument of perigee (PZ-90.02) (radians)	Double	8	H+48
14	deltaT	Correction to the mean value of the Draconian period (s/orbital period)[3]	Double	8	H+56
15	deltaTD	Rate of change of orbital period (s/orbital period^3)	Double	8	H+64
16	tau	Clock offset (s)	Double	8	H+72
17	Next message offset = H + 4 + (#recs x 76)				
18	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (76 x #recs)
19	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. Not documented in the GLONASS ICD.

2. The nominal inclination is 63 degrees.

3. The nominal mean value is 43200.

3.60 GLOCLOCK

GLONASS L1 C/A clock information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the time difference information between GPS and GLONASS time as well as status flags. The status flags are used to indicate the type of time processing used in the least squares adjustment. GPS and GLONASS time are both based on the Universal Time Coordinated (UTC) time scale with some adjustments. GPS reference time is continuous and does not include any of the leap second adjustments to UTC applied since 1980. The result is that GPS reference time currently leads UTC time by 15 seconds.

GLONASS time applies leap seconds but is also three hours ahead to represent Moscow time. The nominal offset between GPS and GLONASS time is therefore due to the three hour offset minus the leap second offset. As well as the nominal offset, there is a residual offset on the order of nanoseconds which must be estimated in the least squares adjustment. The GLONASS-M satellites broadcasts this difference in the navigation message.

This log also contains information from the GLONASS navigation data relating GLONASS time to UTC.

Message ID: 719

Log type: Asynch

Recommended input:

```
log gloclocka onchanged
```

ASCII example:

```
#GLOCLOCKA,USB1,0,53.0,SATTIME,2209,504978.000,02000020,1d44,16809;
0,0.000000000,0.000000000,1,7,4.749745131e-08,864,4.656612873e-10,
-0.095703125,-0.000656128,0*668057a7
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLOCLOCK header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Reserved		Ulong	4	H
3			Double	8	H+4
4			Double	8	H+12
5	sat type	Satellite type where 0 = GLO_SAT 1 = GLO_SAT_M (M type) 2 = GLO_SAT_K (K type) 3 = GLO_SAT_K2 (K2 type)[1]	Uchar	1	H+20

1. Not documented in the GLONASS ICD.

Field	Field type	Description	Format	Binary bytes	Binary offset
6	N^4	Four-year interval number starting from 1996	Uchar	1 [1]	H+21
7	τ_{GPS}	Correction to GPS time relative to GLONASS time	Double	8	H+24
8	N^A	GLONASS calendar day number within a four year period beginning since the leap year, in days	Ushort	2 [2]	H+32
9	τ_C	GLONASS time scale correction to UTC(SU) given at beginning of day N4 (s)	Double	8	H+36
10	b1	Beta parameter 1st order term	Double	8	H+44
11	b2	Beta parameter 2nd order term	Double	8	H+52
12	Kp	Kp provides notification of the next expected leap second. For more information, see *Table 131: Kp UTC leap second descriptions* below	Uchar	1	H+60
13	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+61
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 131: Kp UTC leap second descriptions

Kp	Information on UTC leap second[2]
00	No UTC update for this quarter
01	UTC update of plus 1 second at the end of current quarter
11	UTC update of minus 1 second at end of current quarter

1. In the binary log case, additional bytes of padding are added to maintain 4-byte alignment.

2. Based on GLONASS ICD version 5.1, 2008.

3.61 GLOEPHEMERIS

Decoded GLONASS L1 C/A ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains GLONASS L1 C/A ephemeris information. GLONASS ephemerides are referenced to the PZ90.02 geodetic datum. No adjustment between the GPS and GLONASS reference frames are made for positioning. Multiple messages are transmitted, one for each SVID with data.

Message ID: 723

Log type: Asynch

Recommended input:

```
log gloephemerisa onall
```

Example:

```
#GLOEPHEMERISA,USB1,11,54.0,SATTIME,2209,505128.000,02000020,8d29,16809;
51,0,1,1,2209,504918000,10782,864,0,0,93,0,-7.557760253906250e+06,
-2.396222558593750e+07,-4.337567871093750e+06,1.013183593750000e+02,
6.021127700805664e+02,-3.495733261108398e+03,-3.725290298461914e-06,
-0.00000000000000000,1.862645149230957e-06,-2.572460833454132e-05,
5.587935448e-09,-0.00000000000000000,83910,3,2,0,28*50758dd7

#GLOEPHEMERISA,USB1,10,54.0,SATTIME,2209,498978.000,02000020,8d29,16809;
43,3,1,255,2209,499518000,10782,864,0,0,87,0,-7.561826660156250e+06,
1.514665722656250e+07,1.906908251953125e+07,-2.206126213073730e+03,
1.400692939758301e+03,-1.988567352294922e+03,1.862645149230957e-06,
-0.00000000000000000,-2.793967723846436e-06,4.823785275220871e-05,
2.793967724e-09,-1.818989403545856e-12,77760,3,3,0,28*a8ca7563

...

#GLOEPHEMERISA,USB1,1,54.0,SATTIME,2209,502428.000,02000020,8d29,16809;
44,12,1,255,2209,503118000,10782,864,0,0,91,0,1.842177734375000e+05,
1.396222558593750e+07,2.137998535156250e+07,-2.050176620483398e+03,
2.076422691345215e+03,-1.345032691955566e+03,9.313225746154785e-07,
-0.00000000000000000,-2.793967723846436e-06,-3.505311906337738e-05,
1.862645149e-09,9.094947017729282e-13,81210,3,1,0,12*30d2e4f1

#GLOEPHEMERISA,USB1,0,54.0,SATTIME,2209,505128.000,02000020,8d29,16809;
45,13,1,1,2209,504918000,10782,864,0,0,93,0,9.639804687500000e+06,
5.433780761718750e+06,2.304545214843750e+07,-1.955772399902344e+03,
2.454154968261719e+03,2.380151748657227e+02,9.313225746154785e-07,
0.00000000000000000,-2.793967723846436e-06,6.508920341730118e-05,
-3.725290298e-09,0.00000000000000000,83910,3,2,0,28*9489ad94
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLOEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sloto	Slot information offset - PRN identification (Slot + 37). This is also called SLOTO in Connect	Ushort	2	H
3	freqo	Frequency channel offset for satellite in the range 0 to 20	Ushort	2	H+2
4	sat type	Satellite type where 0 = GLO_SAT 1 = GLO_SAT_M (M type) 2 = GLO_SAT_K (K type) 3 = GLO_SAT_K2 (K2 type)[1]	Uchar	1	H+4
5	Reserved			1	H+5
6	e week	Reference week of ephemeris (GPS reference time)	Ushort	2	H+6
7	e time	Reference time of ephemeris (GPS reference time) (ms)	Ulong	4	H+8
8	t offset	Integer seconds between GPS and GLONASS time. A positive value implies GLONASS is ahead of GPS reference time.	Ulong	4	H+12
9	Nt	Calendar number of day within 4 year interval starting at Jan 1 of a leap year	Ushort	2	H+16
10	Reserved			1	H+18
11				1	H+19
12	issue	15 minute interval number corresponding to ephemeris reference time	Ulong	4	H+20
13	health[2]	Ephemeris health where 0-3 = GOOD 4-15 = BAD	Ulong	4	H+24
14	pos x	X coordinate for satellite at reference time (PZ-90.02) (m)	Double	8	H+28
15	pos y	Y coordinate for satellite at reference time (PZ-90.02) (m)	Double	8	H+36
16	pos z	Z coordinate for satellite at reference time (PZ-90.02) (m)	Double	8	H+44

1. Not documented in the GLONASS ICD.

2. The last four bits of this field are used to describe the health.
Bit 0-2: Bn
Bit 3: In
All other bits are reserved and set to 0.

Field	Field type	Description	Format	Binary bytes	Binary offset
17	vel x	X coordinate for satellite velocity at reference time (PZ-90.02) (m/s)	Double	8	H+52
18	vel y	Y coordinate for satellite velocity at reference time (PZ-90.02) (m/s)	Double	8	H+60
19	vel z	Z coordinate for satellite velocity at reference time (PZ-90.02), (m/s)	Double	8	H+68
20	LS acc x	X coordinate for lunisolar acceleration at reference time (PZ-90.02), (m/s/s)	Double	8	H+76
21	LS acc y	Y coordinate for lunisolar acceleration at reference time (PZ-90.02) (m/s/s)	Double	8	H+84
22	LS acc z	Z coordinate for lunisolar acceleration at reference time (PZ-90.02) (m/s/s)	Double	8	H+92
23	tau_n	Correction to the nth satellite time t_n relative to GLONASS time t_c (s)	Double	8	H+100
24	delta_ tau_n	Time difference between navigation RF signal transmitted in L2 sub-band and navigation RF signal transmitted in L1 sub-band by nth satellite (s)	Double	8	H+108
25	gamma	Frequency correction (s/s)	Double	8	H+116
26	Tk	Time of frame start (since start of GLONASS day) (s)	Ulong	4	H+124
27	P	Technological parameter	Ulong	4	H+128
28	Ft	User range	Ulong	4	H+132
29	age	Age of data (days)	Ulong	4	H+136
30	Flags	Information flags, see *Table 132: GLONASS ephemeris flags coding* on the next page	Ulong	4	H+140
31	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+144
32	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 132: GLONASS ephemeris flags coding

Nibble number	Bit	Description	Range values	Hex value
N0	0	P1 Flag - Time interval between adjacent values of (tb) parameter in minutes	See *Table 133: P1 flag range values* below	00000001
	1			00000002
	2	P2 Flag - Flag of oddness or evenness of the value of (tb) (for intervals of 30 or 60 minutes)	0 = even 1 = odd	00000004
	3	P3 Flag - Number of satellites with almanac information within current subframe	0 = four 1 = five	00000008
N1	4	P4 Flag - Flag to show that ephemeris parameters are present. "1" indicates that updated ephemeris or frequency/time parameters have been uploaded by the control	0 = no updated ephemeris 1 = updated ephemeris present	00000010
	5 ... 7	Reserved		
N2 through N7	8 ... 31	Reserved		

Table 133: P1 flag range values

State	Description
00	0 minutes
01	30 minutes
10	45 minutes
11	60 minutes

3.62 GLORAWALM

Raw GLONASS L1 C/A almanac data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw L1 C/A almanac subframes as received from the GLONASS satellite.

Message ID: 720

Log type: Asynch

Recommended input:

```
log glorawalma onchanged
```

Example:

```
#GLORAWALMA,USB1,0,54.0,SATTIME,2209,505128.000,02000020,77bb,16809;
2209,505128.066,54,
056c00000000238000663a,0,06a180986fd00f0681f413,0,0796d994d30697e847824f,0,
08a2a22d5590142f089043,0,09d8e60c8c1e98066938c3,0,0aa383f11f4612510868b3,0,
0bd5c32012ae9806890ad7,0,0ca48974b95c15de04e1c8,0,0dc31c3343369808e84c87,0,
0ea5863857b4160902e010,0,0fd6dc466da6980ba882b9,0,056c00000000238000663a,0,
06a6037cf6860ed60175e7,0,0770335cf7a6980368387b,0,08a7825fabfe1267074eb7,0,
09d48f7018169804280a92,0,0aa8045c29ca127c092c13,0,0bc79b828d269807678caf,0,
0ca983b14ea4083b86bfbd,0,0df118901a1697f655bca0,0,0eaa05896f441034067531,0,
0f077a03be1e980275f2a5,0,056c00000000238000663a,0,06ab82859406134281c7fe,0,
07d96017feb69802558034,0,08ac8141b53e10b683ec0b,0,09ae432ce4fe97f6757e56,0,
0aad01a1f294101b823be3,0,0b3cdc3f8b169804357c99,0,0cae81e5de860d74820b2c,0,
0ddc0854904697f75572fd,0,0eaf866988800fe682b6b0,0,0fc127681e0e97f7f58012,0,
056c00000000238000663a,0,0630002df3360b8e0c2628,0,070b067dcf9697ea95be30,0,
08b1a2859eb21d6a02b624,0,09fbc58921c697f6b0482d,0,0ab287c22442206085237d,0,
0b89a79bd46e97f9907a1c,0,0cb30c5d35b4232100f3ce,0,0d31290ee91698013206a7,0,
0eb40498ea662348843025,0,0f82552595de97f8f184e8,0,056c00000000238000663a,0,
06b513d46a121fb081da5d,0,076b283b9d3e97f030c88f,0,08b60c11134421d2895f81,0,
090cbb4da3a697fed0fac8,0,0ab702ccb99e21ab821f75,0,0b30bb64782e981ed0c62b,0,
0cb88609762615e1819ddc,0,0dcfaf75869e97fa50c4ac,0,0e8c51592b47c979637118,0
*21202c84
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLORAWALM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	week	GPS reference week, in weeks	Ulong	4	H
3	time	GPS reference time, in milliseconds (binary data) or seconds (ASCII data)	GPSec	4	H+4
4	#recs	Number of records to follow	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	string	GLONASS data string	String [11]	11	H+12
6	Reserved		Uchar	1	H+23
7	Next record offset = H+8+(#recs x 12)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+12+ (#recsx12)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.63 GLORAWEPHEM

Raw GLONASS L1 C/A ephemeris data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw L1 C/A ephemeris frame data as received from the GLONASS satellite.

Message ID: 792

Log type: Asynch

Recommended input:

```
log glorawephema onall
```

Example:

```
#GLORAWEPHEMA,USB1,11,52.0,SATTIME,2209,505278.000,02000020,332d,16809;
51,0,273,2209,504918.000,4,010baa019f00a4ec2e1503,0,021ba009a24186ecd1cefe,0,
03c006b7ee8614878c8b27,0,0481af94c0000245b03989,0*67abf4ec

#GLORAWEPHEMA,USB1,10,52.0,SATTIME,2209,498978.000,02000020,332d,16809;
43,3,282,2209,499518.000,4,010ac8a34c4b14ec4e9db9,0,021ae016693d81d9554278,0,
03c0269fd12c9a53e8a941,0,0403294c60000265b0195a,0*3fa54da7

#GLORAWEPHEMA,USB1,9,52.0,SATTIME,2209,505278.000,02000020,332d,16809;
55,4,289,2209,504918.000,4,010baa17f2b8a697036183,0,021ba0072c4d9d092b7cc2,0,
03801632860c8160b6df21,0,0487a65cc0000245b049c7,0*c970c8c9

...

#GLORAWEPHEMA,USB1,2,52.0,SATTIME,2209,505278.000,02000020,332d,16809;
54,11,32,2209,504918.000,4,010baa2f8f579ccd09da20,0,021ba00859ba8d5aca447f,0,
0380361254fb92b0184451,0,04a2751800000065b04531,0*91a30fc5

#GLORAWEPHEMA,USB1,1,52.0,SATTIME,2209,502428.000,02000020,332d,16809;
44,12,297,2209,503118.000,4,010b43a0cd860805c1be0b,0,021b6021390781b451ced7,0,
0380169585419a9c1fe299,0,04824c1840000025b01dad,0*79a48a72

#GLORAWEPHEMA,USB1,0,52.0,SATTIME,2209,505278.000,02000020,332d,16809;
45,13,40,2209,504918.000,4,010baa9f4ad8092d3e708f,0,021ba027443800a9ce3fea,0,
03800603cee99ad02b9e73,0,0404440680000245b021bb,0*ba344f1d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLORAWEPHEM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sloto	Slot information offset - PRN identification (Slot + 37). Ephemeris relates to this slot and is also called SLOTO in NovAtel Connect	Ushort	2	H
3	freqo	Frequency channel offset in the range 0 to 20	Ushort	2	H+2
4	sigchan	Signal channel number	Ulong	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
5	week	GPS reference week, in weeks	Ulong	4	H+8
6	time	GPS reference time, in milliseconds (binary data) or seconds (ASCII data)	GPSec	4	H+12
7	#recs	Number of records to follow	Ulong	4	H+16
8	string	GLONASS data string	String [11]	11	H+20
9	Reserved		Uchar	1	H+31
10	Next record offset = H+20+(#recs x 12)				
11	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+20+ (#recsx12)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.64 GLORAWFRAME

Raw GLONASS L1 C/A frame data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw GLONASS L1 C/A frame data as received from the GLONASS satellite. Multiple messages are transmitted, one for each SVID with data.

Message ID: 721

Log type: Asynch

Recommended input:

```
log glorawframea onchanged
```

Example:

```
#GLORAWFRAMEA,USB1,0,54.0,SATTIME,2209,505308.000,02000020,8792,16809;4,38,8,22
09,505308.075,305,305,15,010bab96ab4e821602d6a7,0,021ba01b6b7e1530c4a7e3,0,0380
0628618591fb3adfd1,0,0480917120000045b0051b,0,056c00000000238000683e,0,0630002d
f3360b8e0c2628,0,070b067dcf9697ea95be30,0,08b1a2459eb21d6a02b627,0,09fbc58921c6
97f6b0482d,0,0ab2878224422060852340,0,0b89a79bd46e97f9907a1c,0,0cb30c5d35b42321
00f3ce,0,0d31290ee91698013206a7,0,0eb40498ea662348843025,0,0f82552595de97f8f184
e8,0*08409ad3
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLORAWFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	frame#	Frame number	Ulong	4	H
3	sloto	Slot information offset - PRN identification (Slot + 37). Ephemeris relates to this slot and is also called SLOTO in NovAtel Connect.	Ushort	2	H+4
4	freqo	Frequency channel offset in the range 0 to 20	Ushort	2	H+6
5	week	GPS Week, in weeks	Ulong	4	H+8
6	time	GPS Time, in milliseconds (binary data) or seconds (ASCII data)	GPSec	4	H+12
7	frame decode	Frame decoder number	Ulong	4	H+16
8	sigchan	Signal channel number	Ulong	4	H+20
9	#recs	Number of records to follow	Ulong	4	H+24
10	string	GLONASS data string	String [11]	11	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
11	Reserved		Uchar	1	H+39
12	Next record offset = H+28+ (#recs x 12)				
13	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H +28+ (#recs x 12)
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.65 GLORAWSTRING

Raw GLONASS L1 C/A string

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw L1 C/A string data as received from the GLONASS satellite.

Message ID: 722

Log type: Asynch

Recommended input:

```
log glorawstringa onchanged
```

Example:

```
#GLORAWSTRINGA,USB1,0,54.0,SATTIME,2209,505410.000,02000020,50ac,16809;
1,1,0770335cf7a6980368387b,0*520359be
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GLORAWSTRING header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	slot	Slot identification	Uchar	1	H
3	freq	Frequency channel (frequency channels are in the range -7 to +13)	Char	1	H+1
4	string	GLONASS data string	Hex[11]	11	H+2
5	Reserved		Uchar	1	H+13
6	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+14
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.66 GPALM

Almanac data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log outputs raw almanac data for each GPS satellite PRN contained in the broadcast message. A separate record is logged for each PRN, up to a maximum of 32 records. GPALM outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. UTC time is then set to VALID. It takes a minimum of 12.5 minutes to collect a complete almanac following receiver boot-up. In the case of a GLONASS capable receiver, the UTC offset can be determined once the GLONASS ephemeris is decoded, which takes about 50 seconds. If an almanac was stored in NVM, the stored values are reported in the GPALM log once time is set on the receiver.



To obtain copies of ICD-GPS-200, refer to https://www.gps.gov/technical/icwg/.

Message ID: 217

Log type: Asynch

Recommended input:

```
log gpalm onchanged
```

Example:

```
$GPALM,30,01,01,2210,00,617b,0f,1da7,fd70,a10d0a,24de91,6fe696,16263f,17c,ffe*7B
$GPALM,30,02,02,2210,00,a752,0f,0f5f,fd56,a10cf7,c62dda,6c306a,1c751c,d53,000*7F
$GPALM,30,03,03,2210,00,21ef,0f,1464,fd63,a10c9d,26d19c,9a02d6,e8f3d8,eff,ffc*20
$GPALM,30,04,04,2210,00,0ed5,0f,0bfc,fd40,a10c67,871978,c614e7,5cff7f,f51,001*26
$GPALM,30,05,05,2210,00,30d6,0f,0bf0,fd56,a10d59,2996db,98511a,8266e6,faa,000*2B
$GPALM,30,06,06,2210,00,150b,0f,1d37,fd6d,a10d81,dd08a4,6f9046,1f9de5,13f,004*79
$GPALM,30,07,07,2210,00,83b7,0f,059e,fd5c,a10cf2,a38e0f,ef9113,faf04e,152,000*7D
$GPALM,30,08,08,2210,00,3d03,0f,0da3,fd22,a10da6,06d382,43d119,6f02ae,fb9,000*76
$GPALM,30,09,09,2210,00,1113,0f,0770,fd39,a10bfc,4c6129,c3e4b9,844e81,e9f,001*7C
$GPALM,30,10,10,2210,00,3e48,0f,1443,fd65,a10d0e,9a5e76,99e60d,c36848,e4c,ffc*2A
...
$GPALM,30,21,22,2210,00,6d60,0f,0c0f,fd41,a10cff,b484ba,c80d8d,69e9f1,110,002*75
$GPALM,30,22,23,2210,00,118d,0f,1111,fd62,a10d46,7a73b2,98de21,f78a52,fe9,fff*20
$GPALM,30,23,24,2210,00,662b,0f,fad0,fd4c,a10d14,212fb6,ec22c7,22a913,0fc,ffe*24
$GPALM,30,24,25,2210,00,5625,0f,0983,fd44,a10d05,28daa2,19bb67,d5b628,155,001*71
$GPALM,30,25,26,2210,00,38d6,0f,fd0b,fd36,a10d99,0fd6f2,17bfe3,ba7af2,0d8,001*7E
$GPALM,30,26,27,2210,00,5671,0f,1355,fd2a,a10cd2,1bbd7f,44a393,70647e,0d5,002*75
$GPALM,30,27,29,2210,00,119e,0f,18e8,fd35,a10d41,5beea1,47bfe9,7518fe,de5,fff*2A
$GPALM,30,28,30,2210,00,2fa3,0f,fbf2,fd4d,a10dc1,923e8f,f00c20,fa7e58,dd6,000*2E
$GPALM,30,29,31,2210,00,5578,0f,085d,fd5d,a10d86,0fe442,f05163,e7e443,f46,000*2F
$GPALM,30,30,32,2210,00,30d7,0f,09ed,fd3d,a10c3f,a2d321,c45da6,8b29e1,f7a,ffe*70
```

See the *The NMEA (National Marine Electronics Association) has defined standards that specify how electronic equipment for marine users communicate. GNSS receivers are part of this standard and the NMEA has defined the format for several GNSS data logs otherwise known as 'sentences'.* on page 636 that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPALM	Log header		$GPALM
2	# msg	Total number of messages logged. Set to zero until almanac data is available	x.x	17
3	msg #	Current message number[1]	x.x	17
4	PRN	Satellite PRN number: GPS = 1 to 32	xx	28
5	GPS wk	GPS reference week number	x.x	653
6	SV hlth	SV health, bits 17-24 of each almanac page[2]	hh	00
7	ecc	e, eccentricity[3]	hhhh	3EAF
8	alm ref time	to a almanac reference time [3]	hh	87
9	incl angle	(sigma)i, inclination angle [3]	hhhh	OD68
10	omegadot	OMEGADOT, rate of right ascension [3]	hhhh	FD30
11	rt axis	$(A)^{1/2}$, root of semi-major axis [3]	hhhhhh	A10CAB
12	omega	omega, argument of perigee [3]	hhhhhh	6EE732
13	long asc node	(OMEGA)°, longitude of ascension node [3]	hhhhhh	525880
14	Mo	Mo, mean anomaly [3]	hhhhhh	6DC5A8
15	af0	af0, clock parameter [3]	hhh	009
16	af1	af1, clock parameter [3]	hhh	005
17	*xx	Check sum	*hh	*37
18	[CR][LF]	Sentence terminator		[CR][LF]

1. Variable length integer, 4-digits maximum from (2) most significant binary bits of Subframe 1, Word 3 reference Table 20-I, IS-GPS-200L, and (8) least significant bits from subframe 5, page 25, word 3 reference Table 20-I.

2. Reference paragraph 20.3.3.5.1.3, Table 20-VII and Table 20-VIII, IS-GPS-200L.

3. Reference Table 20-VI, IS-GPS-200L for scaling factors and units.

3.67 GPGGA

GPS fix data and undulation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains time, position and fix related data of the GNSS receiver. See also *Table 136: Position precision of NMEA logs* on page 641.

The GPGGA log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

The GPGGA log can be customized using the **NMEAFORMAT** command (see page 272).

The position for the **GPGGA** log is reported in the user selected datum. See the **DATUM** command on page 133 for more details.

When the solution type is INS (SPAN models), the DOPs in the **GPGGA** log are calculated at a 1 Hz rate.
To determine if the receiver is providing an INS solution, check the **pos type** field in the **BESTPOS** log (see page 527).

Message ID: 218

Log type: Synch

Recommended input:

```
log gpgga ontime 1
```

Example:

```
$GPGGA,202530.00,5109.0262,N,11401.8407,W,5,40,0.5,1097.36,M,-17.00,M,18,TSTR*61
```

The NMEA (National Marine Electronics Association) has defined standards that specify how electronic equipment for marine users communicate. GNSS receivers are part of this standard and the NMEA has defined the format for several GNSS data logs otherwise known as 'sentences'.

Each NMEA sentence begins with a '$' followed by a two-letter prefix identifying the type of sending device (for example 'GP', 'GL' or 'GN'), followed by a sequence of letters that define the type of information contained in the sentence. Data contained within the sentence is separated by commas and the sentence is terminated with a two digit checksum followed by a carriage return/line feed. Here is an example of a NMEA sentence describing time, position and fix related data:

```
$GPGGA,134658.00,5106.9792,N,11402.3003,W,2,09,1.0,1048.47,M,
-16.27,M,08,AAAA*60
```

The GPGGA sentence shown above and other NMEA logs are output the same no matter what GNSS receiver is used, providing a standard way to communicate and process GNSS information. For more information about NMEA, see the **NMEATALKER** command on page 276.

Field	Structure	Description	Symbol	Example
1	$GPGGA	Log header		$GPGGA
2	utc	UTC time status of position (hours/minutes/seconds/ decimal seconds)	hhmmss.ss	202134.00
3	lat	Latitude (DDmm.mm)	llll.ll	5106.9847
4	lat dir	Latitude direction (N = North, S = South)	a	N
5	lon	Longitude (DDDmm.mm)	yyyyy.yy	11402.2986
6	lon dir	Longitude direction (E = East, W = West)	a	W
7	quality	refer to *Table 134: GPS quality indicators* on the next page	x	1
8	# sats	Number of satellites in use. May be different to the number in view	xx	10
9	hdop	Horizontal dilution of precision	x.x	1.0
10	alt	Antenna altitude above/below mean sea level	x.x	1062.22
11	a-units	Units of antenna altitude (M = metres)	M	M
12	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid	x.x	-16.271
13	u-units	Units of undulation (M = metres)	M	M
14	age	Age of correction data (in seconds) The maximum age reported here is limited to 99 seconds.	xx	(empty when no differential data is present)
15	stn ID	Differential base station ID	xxxx	(empty when no differential data is present)

Field	Structure	Description	Symbol	Example
16	*xx	Check sum	*hh	*48
17	[CR][LF]	Sentence terminator		[CR][LF]

Table 134: GPS quality indicators

Indicator	Description
0	Fix not available or invalid
1	Single point
	Converging PPP (TerraStar-L)
2	Pseudorange differential
	Converged PPP (TerraStar-L)
	Converging PPP (TerraStar-C PRO, TerraStar-X)
4	RTK fixed ambiguity solution
5	RTK floating ambiguity solution
	Converged PPP (TerraStar-C PRO, TerraStar-X)
6	Dead reckoning mode
7	Manual input mode (fixed position)
8	Simulator mode
9	WAAS (SBAS)[1]



Refer to the **BESTPOS** log (see page 527) and *Table 100: Supplemental position types and NMEA equivalents* on page 534.

1. An indicator of 9 has been temporarily set for SBAS (NMEA standard for SBAS not decided yet). This indicator can be customized using the GGAQUALITY command.

3.68 GPGGALONG

Fix data, extra precision and undulation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains, time, position, undulation and fix related data of the GNSS receiver. This is output as a GPGGA log but the GPGGALONG log differs from the normal GPGGA log by its extra precision. See also *Table 136: Position precision of NMEA logs* on page 641.

The GPGGALONG log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

The GPGGALONG log can be customized using the **NMEAFORMAT** command (see page 272).

When the solution type is INS (SPAN models), the DOPs in the **GPGGALONG** log are calculated at a 1 Hz rate.
To determine if the receiver is providing an INS solution, check the **pos type** field in the **BESTPOS** log (see page 527).

Message ID: 521

Log type: Synch

Recommended input:

```
log gpggalong ontime 1
```

Example:

```
$GPGGA,202601.00,5109.0262339,N,11401.8407317,W,5,40,0.5,1097.350,M,-17.00,M,
09,TSTR*5F
```

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPGGALONG	Log header		$GPGGA
2	utc	UTC time status of position (hours/minutes/seconds/ decimal seconds)	hhmmss.ss	202126.00
3	lat	Latitude (DDmm.mm)	llll.ll	5106.9847029
4	lat dir	Latitude direction (N = North, S = South)	a	N
5	lon	Longitude (DDDmm.mm)	yyyyy.yy	11402.2986286

Field	Structure	Description	Symbol	Example
6	lon dir	Longitude direction (E = East, W = West)	a	W
7	GPS qual	Refer to *Table 134: GPS quality indicators* on page 637	x	1
8	# sats	Number of satellites in use (00-12). May be different to the number in view	xx	10
9	hdop	Horizontal dilution of precision	x.x	1.0
10	alt	Antenna altitude above/below msl	x.x	1062.376
11	units	Units of antenna altitude (M = metres)	M	M
12	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid	x.x	-16.271
13	u-units	Units of undulation (M = metres)	M	M
14	age	Age of Differential GPS data (in seconds) The maximum age reported here is limited to 99 seconds.	xx	10 (empty when no differential data is present)
15	stn ID	Differential base station ID, 0000-1023	xxxx	AAAA (empty when no differential data is present)
16	*xx	Check sum	*hh	*48
17	[CR][LF]	Sentence terminator		[CR][LF]

Table 135: Position precision of NMEA logs

NMEA log	Latitude (# of decimal places)	Longitude (# of decimal places)	Altitude (# of decimal places)
GPGGA	4	4	2
GPGGALONG	7	7	3
GPGLL	7	7	N/A
GPRMC	7	7	N/A

Refer to the **BESTPOS** log (see page 527) and *Table 100: Supplemental position types and NMEA equivalents* on page 534.

3.69 GPGLL

Geographic position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains latitude and longitude of present vessel position, time of position fix and status.

Table 136: Position precision of NMEA logs on the next page compares the position precision of selected NMEA logs.

The GPGLL log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems).

The position for the **GPGLL** log is reported in the user selected datum. See the **DATUM** command on page 133 for more details.

Message ID: 219

Log type: Synch

Recommended input:

```
log gpgll ontime 1
```

Example 1 (GPS only):

```
$GPGLL,5109.0262317,N,11401.8407304,W,202725.00,A,D*79
```

Example 2 (Multi-constellation):

```
$GNGLL,5109.0262321,N,11401.8407167,W,174738.00,A,D*6B
```

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Example
1	$GPGLL	Log header	$GPGLL
2	lat	Latitude (DDmm.mm)	5106.7198674
3	lat dir	Latitude direction (N = North, S = South)	N
4	lon	Longitude (DDDmm.mm)	11402.3587526

Field	Structure	Description	Example
5	lon dir	Longitude direction (E = East, W = West)	W
6	utc	UTC time status of position (hours/minutes/seconds/decimal seconds)	220152.50
7	data status	Data status: A = Data valid, V = Data invalid	A
8	mode ind	Positioning system mode indicator, see *Table 137: NMEA positioning system mode indicator* below	A
9	*xx	Check sum	*1B
10	[CR][LF]	Sentence terminator	[CR][LF]

Table 136: Position precision of NMEA logs

NMEA log	Latitude (# of decimal places)	Longitude (# of decimal places)	Altitude (# of decimal places)
GPGGA	4	4	2
GPGGALONG	7	7	3
GPGLL	7	7	N/A
GPRMC	7	7	N/A

Table 137: NMEA positioning system mode indicator

Mode	Indicator
A	Autonomous
D	Differential
E	Estimated (dead reckoning) mode
M	Manual input
N	Data not valid

3.70 GPGRS

GPS range residuals for each satellite

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Range residuals can be computed in two ways, and this log reports those residuals. Under mode 0, residuals output in this log are used to update the position solution output in the GPGGA message. Under mode 1, the residuals are recomputed after the position solution in the GPGGA message is computed. The receiver computes range residuals in mode 1. An integrity process using GPGRS would also require GPGGA (for position fix data), GPGSA (for DOP figures) and GPGSV (for PRN numbers) for comparative purposes.

The GPGRS log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

1. If the range residual exceeds ± 99.9, then the decimal part is dropped. Maximum value for this field is ± 999. The sign of the range residual is determined by the order of parameters used in the calculation as follows:

   range residual = calculated range - measured range

2. If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GB/BD (BDS satellites only), GQ (QZSS satellites only), GI (NavIC satellites only) or GN (combined system satellites).

The position for the **GPRMC** log is reported in the user selected datum. See the **DATUM** command on page 133 for more details.

Message ID: 220

Log type: Synch

Recommended input:

```
log gpgrs ontime 1
```

Example 1 (NMEATALKER set to GP; GPS only):

```
$GPGRS,202812.00,1,0.5,0.1,-0.0,-0.0,-0.2,0.8,0.4,-0.3,-0.6,-0.0,,*4A
```

Example 2 (NMEATALKER set to AUTO; Multi-constellation):

```
$GNGRS,174837.00,1,-0.1,0.7,-0.2,0.1,0.3,0.5,-0.7,-0.5,-0.3,0.3,,*72
$GNGRS,174837.00,1,2.5,-1.3,-0.4,-0.5,2.8,-2.1,-3.3,,,,,*50
$GNGRS,174837.00,1,-0.3,-0.1,-0.3,-0.5,0.8,-0.3,0.4,0.5,,,,*7D
$GNGRS,174837.00,1,0.2,-0.3,0.1,0.1,-1.3,0.1,0.0,0.3,,,,*5F
```

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPGRS	Log header		$GPGRS
2	utc	UTC time status of position (hours/minutes/seconds/decimal seconds)	hhmmss.ss	192911.0
3	mode	Mode 0= residuals were used to calculate the position given in the matching GGA line (apriori) (not used by OEM7 receivers) Mode 1= residuals were recomputed after the GGA position was computed (preferred mode)	x	1
4 - 15	res	Range residuals for satellites used in the navigation solution. Order matches order of PRN numbers in GPGSA	x.x,x.x,.....	-13.8,-1.9,11.4,-33.6,0.9,6.9,-12.6,0.3,0.6, -22.3
16	system ID	GNSS system ID. See *Table 138: System and signal IDs* below. This field is only output if the NMEAVERSION is 4.11 (see the **NMEAVERSION** command on page 278).	h	1
17	signal ID	ID of the ranging signal. See *Table 138: System and signal IDs* below	h	1
18	*xx	Check sum	*hh	*65
19	[CR][LF]	Sentence terminator		[CR][LF]

Table 138: System and signal IDs

GNSS system	System ID	Signal ID	Signal channel
GPS	1 (GP)	0	All signals
		1	L1 C/A
		2	L1 P(Y)
		3	L1 M
		4	L2 P(Y)
		5	L2C-M
		6	L2C-L
		7	L5-I
		8	L5-Q
		9 - F	Reserved

GNSS system	System ID	Signal ID	Signal channel
GLONASS	2 (GL)	0	All signals
		1	L1 C/A
		2	L1 P
		3	L2 C/A
		4	L2 P
		5 -F	Reserved
Galileo	3 (GA)	0	All signals
		1	E5a
		2	E5b
		3	E5a+b
		4	E6-A
		5	E6-BC
		6	L1-A
		7	L1-BC
		8 - F	Reserved
BDS (BeiDou System)	4 (GB/BD)	0	All signals
		1	B1I
		2	B1Q
		3	B1C
		4	B1A
		5	B2-a
		6	B2-b
		7	B2 a+b
		8	B3I
		9	B3Q
		A	B3A
		B	B2I
		C	B2Q
		D - F	Reserved

GNSS system	System ID	Signal ID	Signal channel
QZSS	5 (GQ)	0	All signals
		1	L1 C/A
		2	L1C (D)
		3	L1C (P)
		4	LIS
		5	L2C-M
		6	L2C-L
		7	L5-I
		8	L5-Q
		9	L6D
		A	L6E
		B - F	Reserved
NavIC	6 (GI)	0	All signals
		1	L5-SPS
		2	S-SPS
		3	L5-RS
		4	S-RS
		5	L1-SPS
		6 - F	Reserved
Reserved	7 - F		

3.71 GPGSA

GPS DOP and active satellites

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains GNSS receiver operating mode, satellites used for navigation and DOP values.

The GPGSA log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), or GN (satellites from multiple systems) or GA (Galileo satellites only).

When the solution type is INS (SPAN models), the DOPs in the **GPGGA** log are calculated at a 1 Hz rate.
To determine if the receiver is providing an INS solution, check the **pos type** field in the **BESTPOS** log (see page 527).

Message ID: 221

Log type: Synch

Recommended input:

```
log gpgsa ontime 1
```

Example 1 (GPS only):

```
$GPGSA,M,3,05,02,31,06,19,29,20,12,24,25,,,0.9,0.5,0.7*35
```

Example 2 (Multi-constellation):

```
$GNGSA,M,3,03,14,17,06,12,19,02,01,24,32,,,0.8,0.5,0.6*22
$GNGSA,M,3,66,85,75,67,73,84,83,,,,,,0.8,0.5,0.6*26
$GNGSA,M,3,12,11,33,31,03,24,25,08,,,,,0.8,0.5,0.6*20
$GNGSA,M,3,28,46,36,27,39,23,43,37,,,,,0.8,0.5,0.6*2B
```

The DOPs provide a simple characterization of the user satellite geometry. DOP is related to the volume formed by the intersection points of the user satellite vectors, with the unit sphere centred on the user. Larger volumes give smaller DOPs. Lower DOP values generally represent better position accuracy. The role of DOP in GNSS positioning is often misunderstood. A lower DOP value does not automatically mean a low position error. The quality of a GNSS derived position estimate depends upon both the measurement geometry as represented by DOP values and range errors caused by signal strength, ionospheric effects, multipath and so on.

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPGSA	Log header		$GPGSA
2	mode MA	A = Automatic 2D/3D M = Manual, forced to operate in 2D or 3D	M	M
3	mode 123	Mode: 1 = Fix not available; 2 = 2D; 3 = 3D	x	3
4 - 15	prn	PRN numbers of satellites used in solution (null for unused fields), total of 12 fields GPS = 1 to 32 SBAS = 33 to 64 (add 87 for PRN number) GLO = 65 to 96 [1]	xx,xx,.....	18,03,13, 25,16, 24,12, 20,,,,
16	pdop	Position dilution of precision	x.x	1.5
17	hdop	Horizontal dilution of precision	x.x	0.9
18	vdop	Vertical dilution of precision	x.x	1.2
19	system ID	GNSS system ID. See *Table 138: System and signal IDs* on page 643. This field is only output if the NMEAVERSION is 4.11 (see the **NMEAVERSION** command on page 278).		
20	*xx	Check sum	*hh	*3F
21	[CR][LF]	Sentence terminator		[CR][LF]

1. The NMEA GLONASS PRN numbers are 64 plus the GLONASS slot number. Current slot numbers are 1 to 24 which give the range 65 to 88. PRN numbers 89 to 96 are available if slot numbers above 24 are allocated to on-orbit spares.

3.72 GPGST

Estimated error in position solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains pseudorange measurement noise statistics are translated in the position domain in order to give statistical measures of the quality of the position solution.

This log reflects the accuracy of the solution type used in the **BESTPOS** log (see page 527) and **GPGGA** log (see page 635), except for the RMS field. The RMS field, since it specifically relates to pseudorange inputs, does not represent carrier-phase based positions. Instead, it reflects the accuracy of the pseudorange position which is given in the **PSRPOS** log (see page 800).

The GPGST log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only) or GN (satellites from multiple systems) or GA (Galileo satellites only).

Message ID: 222

Log type: Synch

Recommended input:

```
log gpgst ontime 1
```

Example 1 (GPS only):

```
$GPGST,203017.00,1.25,0.02,0.01,-16.7566,0.02,0.01,0.03*7D
```

Example 2 (Multi-constellation):

```
$GNGST,205246.00,1.19,0.02,0.01,-2.4501,0.02,0.01,0.03*5B
```

1. See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.
2. Accuracy is based on statistics, reliability is measured in percent. When a receiver can measure height to one metre, this is an accuracy. Usually this is a one sigma value (one SD). A one sigma value for height has a reliability of 68%, that is, the error is less than one metre 68% of the time. For a more realistic accuracy, double the one sigma value (1 m) and the result is 95% reliability (error is less than 2 m 95% of the time). Generally, GNSS heights are 1.5 times poorer than horizontal positions.

   As examples of statistics, the GPGST message and NovAtel performance specifications use Root Mean Square (RMS). Specifications may be quoted in CEP:

   - RMS - root mean square (a probability level of 68%)
   - CEP - circular error probable (the radius of a circle such that 50% of a set of events occur inside the boundary)

Field	Structure	Description	Symbol	Example
1	$GPGST	Log header		$GPGST
2	utc	UTC time status of position (hours/minutes/seconds/ decimal seconds)	hhmmss.ss	173653.00
3	rms	RMS value of the standard deviation of the range inputs to the navigation process. Range inputs include pseudoranges and DGPS corrections	x.x	2.73
4	smjr std	Standard deviation of semi-major axis of error ellipse (m)	x.x	2.55
5	smnr std	Standard deviation of semi-minor axis of error ellipse (m)	x.x	1.88
6	orient	Orientation of semi-major axis of error ellipse (degrees from true north)	x.x	15.2525
7	lat std	Standard deviation of latitude error (m)	x.x	2.51
8	lon std	Standard deviation of longitude error (m)	x.x	1.94
9	alt std	Standard deviation of altitude error (m)	x.x	4.30
10	*xx	Check sum	*hh	*6E
11	[CR][LF]	Sentence terminator		[CR][LF]

3.73 GPGSV

GPS satellites in view

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the number of GPS SVs in view, PRN numbers, elevation, azimuth and SNR value. Each message includes up to four satellites. If there are more than four satellites in view, additional messages are transmitted. The total number of messages and the message number are included in each message.

The GPGSV log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

1. Satellite information may require the transmission of multiple messages. The first field specifies the total number of messages, minimum value 1. The second field identifies the order of this message (message number), minimum value 1.
2. If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems). Each system is output in a separate message.
3. The ID setting in the **NMEATALKER** command (see page 276) controls the satellites reported in this log. If the NMEATALKER ID is set to GP, only GPS satellites are reported in this log. If the NMEATALKER ID is set to AUTO, all satellites in view are reported.
4. A variable number of 'PRN-Elevation-Azimuth-SNR' sets are allowed up to a maximum of four sets per message. Null fields are not required for unused sets when less than four sets are transmitted.
5. SBAS satellites are included with the talker set to GP, if SBASCONTROL ENABLE has been issued and an SBAS almanac has been collected.

Message ID: 223

Log type: Synch

Recommended input:

```
log gpgsv ontime 1
```

Example (GPS only):

```
$GPGSV,4,1,16,02,82,150,53,11,78,139,,12,72,191,53,25,50,296,51*77
$GPGSV,4,2,16,06,43,056,49,20,33,149,45,29,20,275,44,19,16,087,46*73
$GPGSV,4,3,16,31,11,329,42,05,10,169,42,24,07,212,44,04,01,033,*7C
$GPGSV,4,4,16,44,32,184,47,51,31,171,48,48,31,194,47,46,30,199,47*7E
```

Example (Multi-constellation):

```
$GLGSV,3,1,10,81,63,034,51,82,53,272,51,80,52,292,,79,38,200,49*6A
$GLGSV,3,2,10,65,24,046,42,66,16,105,47,73,15,334,46,88,14,062,46*61
```

```
$GLGSV,3,3,10,83,11,253,,72,07,001,44*68
$GPGSV,4,1,16,02,80,085,53,11,76,091,,12,61,180,51,25,58,284,52*79
$GPGSV,4,2,16,20,42,142,50,06,33,056,47,29,28,280,47,05,19,166,47*7F
$GPGSV,4,3,16,31,15,321,46,19,08,093,46,04,04,025,,09,03,055,*78
$GPGSV,4,4,16,44,32,184,48,51,31,171,48,48,31,194,47,46,30,199,48*7E
$GAGSV,3,1,09,34,72,231,53,30,65,251,53,36,51,059,51,02,36,170,49*62
$GAGSV,3,2,09,27,25,314,47,15,19,236,47,04,08,037,46,09,04,085,*65
$GAGSV,3,3,09,11,03,057,*50
$GQGSV,1,1,01,02,08,309,37*4D
$BDGSV,5,1,18,34,85,015,53,11,67,274,51,12,55,069,49,43,39,265,50*61
$BDGSV,5,2,18,23,37,289,50,25,36,225,48,44,31,078,49,22,25,064,46*69
$BDGSV,5,3,18,21,20,119,45,16,11,320,42,06,10,325,40,09,10,340,38*6D
$BDGSV,5,4,18,39,08,310,40,37,07,331,45,59,06,288,,19,05,017,*64
$BDGSV,5,5,18,31,03,333,,24,02,179,*68
$GIGSV,1,1,00,,,,*60
```

The GPGSV log can be used to determine which GPS satellites are currently available to the receiver. Comparing the information from this log to that in the GPGSA log shows if the receiver is tracking all available satellites.

See also the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPGSV	Log header		$GPGSV
2	# msgs	Total number of messages (1-9)	x	3
3	msg #	Message number (1-9)	x	1
4	# sats	Total number of satellites in view. May be different than the number of satellites in use (see also the **GPGGA** log on page 635)	xx	09

Field	Structure	Description	Symbol	Example
5	prn	Satellite PRN number GPS = 1 to 32 Galileo = 1 to 36 BeiDou = 1 to 63 NavIC = 1 to 14 QZSS = 1 to 10 SBAS = 33 to 64 (add 87 for PRN#s) GLONASS = 65 to 96 [1]	xx	03
6	elev	Elevation, degrees, 90 maximum	xx	51
7	azimuth	Azimuth, degrees True, 000 to 359	xxx	140
8	SNR	SNR (C/No) 00-99 dB, null when not tracking	xx	42
... ...	... ...	Next satellite PRN number, elev, azimuth, SNR, ... Last satellite PRN number, elev, azimuth, SNR,		
variable	system ID	GNSS system ID. See *Table 138: System and signal IDs* on page 643. This field is only output if the NMEAVERSION is 4.11 (see the **NMEAVERSION** command on page 278).		
variable	*xx	Check sum	*hh	*72
variable	[CR][LF]	Sentence terminator		[CR][LF]

1. The NMEA GLONASS PRN numbers are 64 plus the GLONASS slot number. Current slot numbers are 1 to 24 which give the range 65 to 88. PRN numbers 89 to 96 are available if slot numbers above 24 are allocated to on-orbit spares.

3.74 GPHDT

NMEA heading log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log contains actual vessel heading in degrees True (from True North). See also a description of heading in the **HEADING2** log on page 668. You can also set a standard deviation threshold for this log, see the **HDTOUTTHRESHOLD** command on page 210.

You must have an ALIGN capable receiver to use this log.

The GPHDT log can only be logged using the ONCHANGED trigger. Other triggers, such as ONTIME are not accepted.

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems).

Message ID: 1045

Log type: Asynch

Recommended input:

```
log gphdt onchanged
```

Example 1 (GPS only):

```
$GPHDT,75.5664,T*36
```

Example 2 (Combined GPS and GLONASS):

```
$GNHDT,75.5554,T*45
```

Field	Structure	Description	Symbol	Example
1	$GPHDT	Log header		$GPHDT
2	heading	Heading in degrees	x.x	75.5554
3	True	Degrees True	T	T
4	*xx	Check sum	*hh	*36
5	[CR][LF]	Sentence terminator		[CR][LF]

3.75 GPHDTDUALANTENNA

Synchronous NMEA heading log

Platform: OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2, CPT7

This log contains actual vessel heading in degrees True (from True North). It provides the same information as the **GPHDT** log (see page 653), but with synchronous output.

You must have an ALIGN capable, dual antenna receiver to use this log.

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems).

Message ID: 2045

Log type: Synch

Recommended input:

```
log gphdtdualantenna ontime 1
```

Example 1 (GPS only):

```
$GPHDT,75.5664,T*36
```

Example 2 (combined GPS and GLONASS):

```
$GNHDT,75.5554,T*45
```

Field	Structure	Description	Symbol	Example
1	$GPHDT	Log header		$GPHDT
2	heading	Heading in degrees	x.x	75.5554
3	True	Degrees True	T	T
4	*xx	Check sum	*hh	*36
5	[CR][LF]	Sentence terminator		[CR][LF]

3.76 GPRMB

Navigation information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains navigation data from present position to a destination waypoint. The destination is set active by the receiver **SETNAV** command (see page 401).

The GPRMB log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

Message ID: 224

Log type: Synch

Recommended input:

```
log gprmb ontime 1
```

Example 1 (GPS only):

```
$GPRMB,A,4.32,L,FROM,TO,5109.7578000,N,11409.0960000,W,4.6,279.2,0.0,V,D*4A
```

Example 2 (Multi-constellation):

```
$GNRMB,A,4.32,L,FROM,TO,5109.7578000,N,11409.0960000,W,4.6,279.2,0.0,V,D*54
```



If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems).



See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPRMB	Log header		$GPRMB
2	data status	Data status: A = data valid; V = navigation receiver warning	A	A

Field	Structure	Description	Symbol	Example
3	xtrack	Cross track error Represents the track error from the intended course If the cross track error exceeds 9.99 NM, displays 9.99. One nautical mile (NM) = 1,852 metres.	x.x	5.14
4	dir	Direction to steer to get back on track (L/R) Direction to steer is based on the sign of the crosstrack error, that is, L = xtrack error (+) R = xtrack error (-)	a	L
5	origin ID	Origin waypoint ID	c--c	FROM
6	dest ID	Destination waypoint ID	c--c	TO
7	dest lat	Destination waypoint latitude (DDmm.mm)	llll.ll	5109.7578000
8	lat dir	Latitude direction (N = North, S = South)	a	N
9	dest lon	Destination waypoint longitude (DDDmm.mm)	yyyyy.yy	11409.0960000
10	lon dir	Longitude direction (E = East, W = West)	a	W
11	range	Range to destination, nautical miles If the range to destination exceeds 999.9 NM, displays 999.9.	x.x	5.1
12	bearing	Bearing to destination, degrees True	x.x	303.0
13	vel	Destination closing velocity, knots	x.x	-0.0
14	arr status	Arrival status: A = perpendicular passed V = destination not reached or passed	A	V
15	mode ind	Positioning system mode indicator, see *Table 139: NMEA positioning system mode indicator* on the next page	a	A
16	*xx	Check sum	*hh	*6F
17	[CR][LF]	Sentence terminator		[CR][LF]

The fields *origin ID*, *dest ID*, *dest lat*, *lat dir*, *dest lon* and *lon dir* are tagged from the **SETNAV** command (see page 401).

Table 139: NMEA positioning system mode indicator

Mode	Indicator
A	Autonomous
D	Differential
E	Estimated (dead reckoning) mode
M	Manual input
N	Data not valid

3.77 GPRMC

GPS specific information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains time, date, position, track made good and speed data provided by the GPS navigation receiver. RMC and RMB are the recommended minimum navigation data to be provided by a GNSS receiver.

A comparison of the position precision between this log and other selected NMEA logs can be seen in *Table 136: Position precision of NMEA logs* on page 641.

The GPRMC log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems).

The position for the **GPRMC** log is reported in the user selected datum. See the **DATUM** command on page 133 for more details.

Message ID: 225

Log type: Synch

Recommended input:

```
log gprmc ontime 1
```

Example 1 (GPS):

```
$GPRMC,203522.00,A,5109.0262308,N,11401.8407342,W,0.004,133.4,130522,0.0,E,D*2B
```

Example 2 (Multi-constellation):

```
$GNRMC,204520.00,A,5109.0262239,N,11401.8407338,W,0.004,102.3,130522,0.0,E,D*3B
```

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPRMC	Log header		$GPRMC
2	utc	UTC of position	hhmmss.ss	144326.00
3	pos status	Position status (A = data valid, V = data invalid)	A	A

Field	Structure	Description	Symbol	Example
4	lat	Latitude (DDmm.mm)	llll.ll	5107.0017737
5	lat dir	Latitude direction: (N = North, S = South)	a	N
6	lon	Longitude (DDDmm.mm)	yyyyy.yy	11402.3291611
7	lon dir	Longitude direction: (E = East, W = West)	a	W
8	speed Kn	Speed over ground, knots	x.x	0.080
9	track true	Track made good, degrees True	x.x	323.3
10	date	Date: dd/mm/yy	xxxxxx	210307
11	mag var	Magnetic variation, degrees Note that this field is the actual magnetic variation and will always be positive. The direction of the magnetic variation is always positive.	x.x	0.0
12	var dir	Magnetic variation direction E/W Easterly variation (E) subtracts from True course. Westerly variation (W) adds to True course.	a	E
13	mode ind	Positioning system mode indicator, see *Table 140: NMEA positioning system mode indicator* below	a	A
14	*xx	Check sum	*hh	*20
15	[CR][LF]	Sentence terminator		[CR][LF]

Table 140: NMEA positioning system mode indicator

Mode	Indicator
A	Autonomous
D	Differential
E	Estimated (dead reckoning) mode
M	Manual input
N	Data not valid

3.78 GPSCNAVRAWMESSAGE

GPS CNAV Raw Message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the raw CNAV message from signals which contain the CNAV message (L2C, L5). It also indicates whether the raw message is generated from an L2C signal or L5 signal.

The **GPSCNAVRAWMESSAGE** log is not output by default. To receive this log, data decoding for L2C or L5 must be enabled using the **DATADECODESIGNAL** command (see page 129) for the specific signal.

Message ID: 2262

Log type: Asynch

Recommended input:

```
log gpscnavrawmessagea onnew
```

ASCII example:

```
#GPSCNAVRAWMESSAGEA,USB1,0,46.5,SATTIME,2209,506256.000,02000020,06c3,16809;
269,25,GPSL2C,10,8b64aa4cd1142707f75100a5187ffd0e6341b800a9731a4316f02b1af1c8a3
6c97f854792390*7e700506
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GPSCNAVRAWMESSAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	signal channel	Signal channel providing the bits	Ulong	4	H
3	PRN	Satellite PRN number	Ulong	4	H+4
4	signal type	Signal type (L2C or L5) See *Table 141: Signal type* below	Enum	4	H+8
5	message ID	Message ID	Ulong	4	H+12
6	data	Raw message data	Hex[38]	38	H+16
7	xxxx	32-bit CRC (ASCII and binary only)	Hex	4	H+54
8	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 141: Signal type

Binary	ASCII	Description
69	GPSL2C	GPS L2 C/A-code
103	GPSL5	GPS L5

3.79 GPSEPHEM

Decoded GPS L1 C/A ephemerides

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains a single set of GPS ephemeris parameters.

Message ID: 7

Log type: Asynch

Recommended input:

```
log gpsephema onall
```

ASCII example:

```
#GPSEPHEMA,USB1,30,52.5,SATTIME,2209,496800.000,02000020,1214,16809;
1,496800.0,0,33,33,2209,2209,504000.0,2.656034748e+07,3.711940331e-09,
2.013999822e+00,1.1881368468e-02,9.0331062162e-01,-2.292916179e-06,
1.384504139e-05,1.27000000e+02,-4.17500000e+01,-2.440065145e-07,
-1.601874828e-07,9.8797254649e-01,1.546492989e-10,2.868107379e+00,
-7.51745599e-09,33,504000.0,5.122274160e-09,3.63708e-04,-8.29914e-12,
0.00000,TRUE,1.458576941e-04,4.00000000e+00*b892b91a

#GPSEPHEMA,USB1,29,52.5,SATTIME,2209,506310.000,02000020,1214,16809;
2,506310.0,0,59,59,2209,2209,511200.0,2.656030527e+07,4.114457098e-09,
-3.065876369e+00,2.0427562180e-02,-1.419168291e+00,-3.142282367e-06,
1.297891140e-05,1.24593750e+02,-6.54062500e+01,3.781169653e-07,1.844018698e-07,
9.6608612461e-01,9.000374902e-11,2.777002903e+00,-7.50781273e-09,59,511200.0,
-1.769512892e-08,-6.53255e-04,1.13687e-13,0.00000,TRUE,1.458584443e-04,
4.00000000e+00*613e9e7e

...

#GPSEPHEMA,USB1,1,52.5,SATTIME,2209,506310.000,02000020,1214,16809;
31,506310.0,0,73,73,2209,2209,511200.0,2.656107835e+07,4.222318734e-09,
1.928386048e+00,1.0431749630e-02,3.8970372621e-01,2.447515726e-06,
1.280941069e-05,1.34125000e+02,4.61250000e+01,-1.508742571e-07,2.980232239e-08,
9.5538846447e-01,-2.110802209e-10,-2.6326210009e-01,-7.85925594e-09,
73,511200.0,-1.350417733e-08,-1.77489e-04,-1.59162e-12,0.00000,TRUE,
1.458521844e-04,4.00000000e+00*085ac00a

#GPSEPHEMA,USB1,0,52.5,SATTIME,2209,497010.000,02000020,1214,16809;
32,497010.0,0,49,49,2209,2209,504000.0,2.655950009e+07,4.804485840e-09,
-1.401126814e+00,5.9581462992e-03,-2.285950321e+00,-2.717599273e-06,
6.832182407e-06,2.48281250e+02,-5.08437500e+01,1.899898052e-07,1.490116119e-08,
9.5774991123e-01,-5.596661695e-10,-1.341873629e+00,-8.19927010e-09,49,504000.0,
4.656612873e-10,-1.26368e-04,-8.64020e-12,0.00000,TRUE,1.458657670e-04,
4.00000000e+00*82ba7dc8
```

The GPSEPHEM log can be used to monitor changes in the orbits of GPS satellites.

To obtain copies of IS-GPS-200, refer to the GPS website (https://www.gps.gov/technical/icwg/).

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GPSEPHEM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	Satellite PRN number	Ulong	4	H
3	tow	Time stamp of subframe 1 (s)	Double	8	H+4
4	health	Health status • bits 0-5: 6-bit health code as defined in IS-GPS-200, • bit 6: Alert flag	Ulong	4	H+12
5	IODE1	Issue of ephemeris data 1	Ulong	4	H+16
6	IODE2	Issue of ephemeris data 2	Ulong	4	H+20
7	week	toe week number computed from Z count week (GPS reference week number)	Ulong	4	H+24
8	z week	Z count week number. This is the week number from subframe 1 of the ephemeris. The ‘toe week’ (field #7) is derived from this to account for rollover	Ulong	4	H+28
9	toe	Reference time for ephemeris (s)	Double	8	H+32
10	A	Semi-major axis (m)	Double	8	H+40
11	ΔN	Mean motion difference (radians/s)	Double	8	H+48
12	M_0	Mean anomaly of reference time (radians)	Double	8	H+56
13	ecc	Eccentricity, dimensionless	Double	8	H+64
14	ω	Argument of perigee (radians)	Double	8	H+72
15	cuc	Amplitude of cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+80
16	cus	Amplitude of sine harmonic correction term to the argument of latitude (radians)	Double	8	H+88
17	crc	Amplitude of cosine harmonic correction term to the orbit radius (m)	Double	8	H+96
18	crs	Amplitude of sine harmonic correction term to the orbit radius (m)	Double	8	H+104
19	cic	Amplitude of cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+112

Field	Field type	Description	Format	Binary bytes	Binary offset
20	cis	Amplitude of sine harmonic correction term to the angle of inclination (radians)	Double	8	H+120
21	I_0	Inclination angle at reference time (radians)	Double	8	H+128
22	I^0	Rate of inclination angle (radians/s)	Double	8	H+136
23	Ω_o	Longitude of ascending node of orbit plane (radians)	Double	8	H+144
24	ώ	Rate of right ascension (radians/s)	Double	8	H+152
25	iodc	Issue of data clock	Ulong	4	H+160
26	toc	SV clock correction term (s)	Double	8	H+164
27	tgd	Estimated group delay difference (s)	Double	8	H+172
28	a_{f0}	Clock aging parameter (s)	Double	8	H+180
29	a_{f1}	Clock aging parameter (s/s)	Double	8	H+188
30	a_{f2}	Clock aging parameter (s/s/s)	Double	8	H+196
31	AS	Anti-spoofing on: 0 = FALSE 1 = TRUE	Bool	4	H+204
32	N	Corrected mean motion (radians/s) This field is computed by the receiver.	Double	8	H+208
33	URA	User Range Accuracy variance $(m)^2$ The ICD specifies that the URA index transmitted in the ephemerides can be converted to a nominal standard deviation value using an algorithm listed there. We publish the square of the nominal value (variance). The correspondence between the original URA index and the value output is shown in *Table 142: URA variance* below	Double	8	H+216
34	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+224
35	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 142: URA variance

Index value (m)	A: standard deviations (m)	Variance: A^2 (m^2)
0	2.0	4
1	2.8	7.84
2	4.0	16
3	5.7	32.49

Index value (m)	A: standard deviations (m)	Variance: A^2 (m^2)
4	8	64
5	11.3	127.69
6	16.0	256
7	32.0	1024
8	64.0	4096
9	128.0	16384
10	256.0	65536
11	512.0	262144
12	1024.0	1048576
13	2048.0	4194304
14	4096.0	16777216
15	8192.0	67108864

3.80 GPVTG

Track made good and ground speed

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the track made good and speed relative to the ground.

The GPVTG log outputs these messages without waiting for a valid almanac. Instead, it uses a UTC time, calculated with default parameters. In this case, the UTC time status (see the **TIME** log on page 1000) is set to WARNING since it may not be one hundred percent accurate. When a valid almanac is available, the receiver uses the real parameters. Then the UTC time status is set to VALID.

Message ID: 226

Log type: Synch

Recommended input:

```
log gpvtg ontime 1
```

Example 1 (GPS only):

```
$GPVTG,224.592,T,224.592,M,0.003,N,0.005,K,D*20
```

Example 2 (Multi-constellation):

```
$GNVTG,139.969,T,139.969,M,0.007,N,0.013,K,D*3D
```

If the **NMEATALKER** command (see page 276) is set to AUTO, the talker (the first 2 characters after the $ sign in the log header) is set to GP (GPS satellites only), GL (GLONASS satellites only), GA (Galileo satellites only), GQ (for QZSS satellites only), GB/BD (for BeiDou satellites only) or GN (satellites from multiple systems).

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPVTG	Log header		$GPVTG
2	track true	Track made good, degrees True	x.x	24.168
3	T	True track indicator	T	T
4	track mag	Track made good, degrees Magnetic; Track mag = Track true + (MAGVAR correction) See the **MAGVAR** command on page 259	x.x	24.168
5	M	Magnetic track indicator	M	M
6	speed Kn	Speed over ground, knots	x.x	0.4220347

Field	Structure	Description	Symbol	Example
7	N	Nautical speed indicator (N = Knots)	N	N
8	speed Km	Speed, kilometres/hour	x.x	0.781608
9	K	Speed indicator (K = km/hr)	K	K
10	mode ind	Positioning system mode indicator, see *Table 143: NMEA positioning system mode indicator* below	a	A
11	*xx	Check sum	*hh	*7A
12	[CR][LF]	Sentence terminator		[CR][LF]

Table 143: NMEA positioning system mode indicator

Mode	Indicator
A	Autonomous
D	Differential
E	Estimated (dead reckoning) mode
M	Manual input
N	Data not valid

3.81 GPZDA

UTC time and date

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The GPZDA log outputs the UTC date and time. If no valid almanac is stored in the receiver, a default UTC offset is used to generate the time until a new almanac is downloaded. If the offset is not up-to-date, this initial UTC time may be incorrect until the new almanac is present.

Message ID: 227

Log type: Synch

Recommended input:

```
log gpzda ontime 1
```

Example:

```
$GPZDA,204007.00,13,05,2022,,*62
```

See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.

Field	Structure	Description	Symbol	Example
1	$GPZDA	Log header		$GPZDA
2	utc	UTC time status	hhmmss.ss	220238.00
3	day	Day, 01 to 31	xx	15
4	month	Month, 01 to 12	xx	07
5	year	Year	xxxx	1992
6	null	Local zone description—not available Local time zones are not supported by OEM7 family receivers. Fields 6 and 7 are always null.	xx	(empty when no data is present)
7	null	Local zone minutes description—not available	xx	(empty when no data is present)
8	*xx	Check sum	*hh	*6F
9	[CR][LF]	Sentence terminator		[CR][LF]

3.82 HEADING2

Heading information with multiple rovers

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

The heading is the angle from True North of the base to rover vector in a clockwise direction. This log can be output at both Base and Rover ends.

An ALIGN capable receiver is required to use this log.

Asynchronous logs, such as HEADING2, should only be logged ONCHANGED or ONNEW otherwise the most current data is not available or included in the output. An example of this occurrence is in the ONTIME trigger. If this trigger is used, it may cause inaccurate time tags.

The HEADING2 log is dictated by the output frequency of the base receiver sending out RTCAOBS2, RTCAOBS3 or NOVATELXOBS messages. HEADING2 supports 20 Hz output rate. Ensure sufficient radio bandwidth is available between the ALIGN Base and the ALIGN Rover.

Message ID: 1335

Log type: Asynch

Recommended input:

```
log heading2a onnew
```

ASCII example:

```
#HEADING2A,COM1,0,39.5,FINESTEERING,1622,422892.200,02040000,f9bf,6521;
SOL_COMPUTED,NARROW_INT,0.927607417,178.347869873,-1.3037414550,0,0.261901051,
0.391376048,"R222","AAAA",18,17,17,16,0,01,0,33*8c48d77c
```

Field	Field type	Description	Binary format	Binary bytes	Binary offset
1	Log header	HEADING2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol stat	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4

Field	Field type	Description	Binary format	Binary bytes	Binary offset
4	length	Baseline length in metres For ALIGN Heading models with position access, this field is -1. For ALIGN Heading models without position access, this field is only the decimal portion of the baseline in metres. For ALIGN Relative Positioning models receiving corrections from a base with a fixed position, this field is -1. For ALIGN Relative Positioning models receiving corrections from a base in moving baseline mode, this field is the complete baseline length in metres.	Float	4	H+8
5	heading	Heading in degrees (0° to 359.999°)	Float	4	H+12
6	pitch	Pitch (±90 degrees)	Float	4	H+16
7	Reserved		Float	4	H+20
8	hdg std dev	Heading standard deviation in degrees	Float	4	H+24
9	ptch std dev	Pitch standard deviation in degrees	Float	4	H+28
10	rover stn ID	Rover Receiver ID Set using the **SETROVERID** command (see page 403) on the Rover e.g. setroverid RRRR	Char[4]	4	H+32
11	base stn ID	Base Receiver ID Set using the **DGPSTXID** command (see page 138) on the Base Default: AAAA	Char[4]	4	H+36
12	#SVs	Number of satellites tracked	Uchar	1	H+40
13	#solnSVs	Number of satellites used in solution	Uchar	1	H+41
14	#obs	Number of satellites above the elevation mask angle	Uchar	1	H+42
15	#multi	Number of satellites with multi-frequency signals above the mask angle	Uchar	1	H+43
16	sol source	Solution source (see *Table 144: Solution Source* on the next page)	Hex	1	H+44
17	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Uchar	1	H+45
18	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+46

Field	Field type	Description	Binary format	Binary bytes	Binary offset
19	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+47
20	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+48
21	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 144: Solution Source

Bit	Mask	Description
0-1	0x03	Reserved
2-3	0x0C	Source antenna 0 = Primary antenna 1 = Secondary antenna
4-7	0xF0	Reserved

3.83 HEADINGEXT

Extended heading log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

HEADINGEXT is a proprietary message sent from the rover receiver to the base receiver in an ALIGN or Relative INS configuration. This message provides the position information from the rover receiver that the base receiver requires to produce an ALIGN or Relative INS solution.

Message ID: 1132

Log type: Asynch

Recommended input:

```
log com2 headingextb onnew
```

3.84 HEADINGEXT2

Extended heading log in variable array form

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

HEADINGEXT2 is a proprietary message sent from the rover receiver to the base receiver in an ALIGN or Relative INS configuration. This message provides the position information from the rover receiver that the base receiver requires to produce an ALIGN or Relative INS solution.

Message ID: 1661

Log type: Asynch

Recommended input:

```
log com2 headingext2b onnew
```

3.85 HEADINGRATE

Heading rate information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log provides rate of change for the heading parameters. The heading is the angle from True North of the base to rover vector in a clockwise direction.

You must have an ALIGN capable receiver to use this log.

Message ID: 1698

Log type: Asynch

Recommended input:

```
log headingratea onchanged
```

ASCII example:

```
#HEADINGRATEA,UNKNOWN,0,60.0,FINESTEERING,1873,411044.700,02040008,c53a,32768;
SOL_COMPUTED,NARROW_INT,0.025000000,0.000000000,-0.308837891,0.575313330,
0.000000000,1.264251590,1.663657904,0.0,"748M","725U",00,0,0,0*66f97b96
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	HEADINGRATE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol stat	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results.	Float	4	H+8
5	length rate	Rate of change of the baseline length in m/s. For Z ALIGN rovers, this field outputs the decimal portion of the baseline rate.	Float	4	H+12
6	heading rate	Rate of change of the heading in degrees/s	Float	4	H+16
7	pitch rate	Rate of change of the pitch in degrees/s	Float	4	H+20
8	length rate std dev	Baseline rate standard deviation in m/s	Float	4	H+24

Field	Field type	Description	Format	Binary bytes	Binary offset
9	heading rate std dev	Heading rate standard deviation in degrees/s	Float	4	H+28
10	pitch rate std dev	Pitch rate standard deviation in degrees/s	Float	4	H+32
11	Reserved		Float	4	H+36
12	rover stn ID	Rover Receiver ID Set using the **SETROVERID** command (see page 403) on the Rover receiver. For example, setroverid RRRR.	Uchar	4	H+40
13	base stn ID	Base Receiver ID Set using the **DGPSTXID** command (see page 138) on the Base receiver. Default: AAAA	Uchar	4	H+44
14	sol source	Solution source (see *Table 144: Solution Source* on page 670)	Hex	1	H+48
15	Reserved		Uchar	1	H+49
16	Reserved		Uchar	1	H+50
17	Reserved		Uchar	1	H+51
18	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+52
19	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.86 HEADINGSATS

Satellite used in heading solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log provides information on the satellites that are used in a heading solution.

The HEADINGSATS log can only be used from the ALIGN rover.

Message ID: 1316

Log type: Asynch

Recommended input:

```
log headingsatsa onnew
```

ASCII example:

```
<HEADINGSATS COM1 0 86.5 FINESTEERING 2075 411685.000 02000020 f5b0 32768
<     17
<           GPS 10 GOOD 00000003
<           GPS 24 GOOD 00000003
<           GPS 15 GOOD 00000003
<           GPS 27 GOOD 00000003
<           GPS 20 GOOD 00000003
<           GPS 8 GOOD 00000003
<           GPS 21 GOOD 00000003
<           GPS 16 GOOD 00000003
<           GPS 13 GOOD 00000003
<           GLONASS 14-7 NODIFFCORR 00000000
<           GLONASS 6-4 GOOD 00000001
<           GLONASS 22-3 GOOD 00000003
<           GLONASS 15 GOOD 00000003
<           GLONASS 23+3 GOOD 00000003
<           GLONASS 21+4 GOOD 00000003
<           GLONASS 7+5 GOOD 00000003
<           GLONASS 8+6 GOOD 00000003
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	HEADINGSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	System	Refer to *Table 145: Satellite system* on the next page.	Enum	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	Satellite ID	In binary logs, the satellite ID field is 4 bytes. The 2 lowest-order bytes, interpreted as a USHORT, are the system identifier: for instance, the PRN for GPS, or the slot for GLONASS. The 2 highest-order bytes are the frequency channel for GLONASS, interpreted as a SHORT and zero for all other systems. In ASCII and abbreviated ASCII logs, the satellite ID field is the system identifier. If the system is GLONASS and the frequency channel is not zero, then the signed channel is appended to the system identifier. For example, slot 13, frequency channel -2 is output as 13-2	Ulong	4	H+8
5	Status	See *Table 101: Observation statuses* on page 536	Enum	4	H+12
6	Signal Mask	See *Table 102: GPS signal mask* on page 537, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *QZSS signal mask* on page 538 and *NavIC signal mask* on page 538	Hex	4	H+16
7	Next satellite offset = H + 4 + (#sat x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#satx16)
9	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

Table 145: Satellite system

Binary value	ASCII mode name
0	GPS
1	GLONASS
2	SBAS
5	Galileo
6	BeiDou
7	QZSS
9	NavIC

3.87 HWMONITOR

Monitor hardware levels

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log allows the user to monitor temperature, antenna current and voltages.

Message ID: 963

Log type: Polled

Recommended input:

```
log hwmonitora ontime 10
```

ASCII example:

```
#HWMONITORA,USB1,0,51.5,FINESTEERING,2209,507561.000,02000020,52db,16809;10,
59.218563080,100,0.000122100,200,3.302808285,600,5.165323734,700,1.189255238,
800,3.301587343,f00,1.835775375,1100,5.161416531,1500,1.554945111,1700,
59.218563080,1600*38415eae
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	HWMONITOR header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	# measurements	Number of measurements to follow	Ulong	4	H
3	reading	Temperature, antenna current or voltage reading Units: • Degree Celsius for Temperature • Amps for Antenna Current • Volts for Voltage	Float	4	H+4
4	status	See *Table 146: HWMONITOR Status* on the next page	HexUlong	4	H+8
5...	Next reading offset = H + 4 + (# measurements x 8)				
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+(# measurements x 8)
7	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

Table 146: HWMONITOR Status

Bits	Description	Applicable platforms
0-7	Boundary Limit Status (Hex): 0x00 = Value falls within acceptable bounds 0x01 = Value is under the lower warning limit 0x02 = Value is under the lower error limit 0x03 = Value is over the upper warning limit 0x04 = Value is over the upper error limit	
8-15	Reading Type (Hex):	
	0x00 = Reserved	
	0x01 = Temperature A temperature sensor is located on the receiver and provides the approximate temperature of the PCB surface near critical components (for example, CPU, TCXO) (degrees Celsius)	All
	0x02 = Antenna Current The amount of current being drawn by the active antenna (A)	All except OEM7500, OEM7600, SMART2
	0x06 = Digital Core 3V3 Voltage Internal regulator output voltage supplying a key component on the receivers (Volts) 0x06 = 3.3V Supply Voltage (Volts)	All except OEM7720 OEM7720
	0x07 = Antenna Voltage	All except OEM7500, SMART2
	0x08 = Digital 1V2 Core Voltage Internal regulator output voltage supplying a key component on the receiver (Volts)	All
	0x0F = Regulated Supply Voltage Internal regulator output voltage supplying a key component on the receiver (Volts) 0x0F = Supply Voltage Voltage applied to Pins 1 and 2 of the main connector	All except OEM7720 OEM7720
	0x11 = 1V8	All
	0x15 = 5V Voltage (Volts) 5V voltage output supplying peripherals such as USB and Ethernet	All except OEM7500, OEM7600, SMART2

Bits	Description	Applicable platforms
	0x16 = Secondary Temperature A second temperature sensor is located on the receiver PCB (degrees Celsius)	OEM719, OEM729, OEM7600, OEM7700, PwrPak7, PwrPak7-E1, PwrPak7-E2, CPT7700,SMART7
	0x17 = Peripheral Core Voltage	OEM729, OEM7600, OEM7700, PwrPak7, PwrPak7-E1PwrPak7-E2, CPT7700, SMART7
	0x18 = Secondary Antenna Current	OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2, CPT7
	0x19 = Secondary Antenna Voltage	OEM7720, PwrPak7D, PwrPak7D-E1, PwrPak7D-E2, CPT7
16-23	Reserved	
24-31	Reserved	

3.88 IONUTC

Ionospheric and UTC data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the Ionospheric Model parameters (ION) and the Universal Time Coordinated parameters (UTC).

Message ID: 8

Log type: Asynch

Recommended input:

```
log ionutca onchanged
```

ASCII example:

```
#IONUTCA,USB1,0,52.5,FINESTEERING,2209,507000.090,02000020,ec21,16809;
1.769512891769409e-08,2.235174179077148e-08,-1.192092895507813e-07,
-1.192092895507813e-07,1.167360000000000e+05,1.310720000000000e+05,
-1.310720000000000e+05,-2.621440000000000e+05,2210,61440,
-5.587935447692871e-09,-1.243449788e-14,2185,7,18,18,0*5b90fa00
```

The Receiver-Independent Exchange (RINEX) format is a broadly accepted, receiver independent format for storing GPS data. It features a non-proprietary ASCII file format that can be used to combine or process data generated by receivers made by different manufacturers.

Use the NovAtel's Convert utility to produce RINEX files from NovAtel receiver data files. The Convert utility is available in the NovAtel Application Suite application.

For information about the RINEX format, refer to the U.S. National Geodetic Survey website at: https://www.ngs.noaa.gov/CORS/data.shtml.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	IONUTC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	a0	Alpha parameter constant term	Double	8	H
3	a1	Alpha parameter 1st order term	Double	8	H+8
4	a2	Alpha parameter 2nd order term	Double	8	H+16
5	a3	Alpha parameter 3rd order term	Double	8	H+24
6	b0	Beta parameter constant term	Double	8	H+32
7	b1	Beta parameter 1st order term	Double	8	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
8	b2	Beta parameter 2nd order term	Double	8	H+48
9	b3	Beta parameter 3rd order term	Double	8	H+56
10	utc wn	UTC reference week number	Ulong	4	H+64
11	tot	Reference time of UTC parameters (s)	Ulong	4	H+68
12	A0	UTC constant term of polynomial (s)	Double	8	H+72
13	A1	UTC 1st order term of polynomial (s)	Double	8	H+80
14	wn lsf	Future week number	Ulong	4	H+88
15	dn	Day number (the range is 1 to 7 where Sunday = 1 and Saturday = 7)	Ulong	4	H+92
16	deltat ls	Delta time due to leap seconds	Long	4	H+96
17	deltat lsf	Future delta time due to leap seconds	Long	4	H+100
18	Reserved			4	H+104
19	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+108
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.89 IPSTATS

IP statistics

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This log contains the current IP interface statistics.

Message ID: 1669

Log type: Polled

Recommended input:

```
log ipstatsa
```

ASCII example:

```
#IPSTATSA,USB1,0,52.5,FINESTEERING,2209,507647.000,02000020,0d94,16809;
4,ETHA,0,0,61,WIFI,0,0,0,WIFI_CLIENT,0,0,0,CELL,0,0,0*c139922f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	IPSTATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#Interface	Number of records to follow.	Ulong	4	H
3	Physical Interface	IP Interface Type 1 = ALL 2 = ETHA	Enum	4	H+4
4	Reserved		Ulong	4	H+8
5	Receive Bytes	Total number of bytes received	Ulong	4	H+12
6	Transmit Bytes	Total number of bytes transmitted	Ulong	4	H+16
7	Next reading offset = H+4+(#Interface * 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#Interface * 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.90 IPSTATUS

Current network configuration status

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This log provides the configuration of IP address, netmask, gateway and a list of DNS servers currently in use.

Message ID: 1289

Log type: Polled

Recommended input:

```
log ipstatusa once
```

ASCII example:

```
#IPSTATUSA,USB1,0,52.5,FINESTEERING,2209,507677.000,02000020,7fe2,16809;3,ETHA,
"","","0.0.0.0",WIFI,"192.168.19.1","255.255.255.0","",WIFI_CLIENT,"","","",1,
"0.0.0.0"*661b638f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	IPSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	#IPrec	Number of records to follow	Ulong	4	H
3	interface	Name of the network interface 2 = ETHA	Enum	4	H+4
4	IP address	IP Address-decimal dot notation	String [16]	variable[1]	H+8
5	netmask	Netmask-decimal dot notation	String [16]	variable[1]	H+24
6	gateway	Gateway-decimal dot notation This is the default gateway that is currently in use by the receiver.	String [16]	variable[1]	H+40
7...	Next reading offset = H+4+(#IPrec * 52)				
8	#dnsserver	Number of DNS Servers to follow	Ulong	4	H+4+(#IPrec x 52)

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

Field	Field type	Description	Format	Binary bytes	Binary offset
9	server IP address	IP address-decimal dot notation	String [16]	variable[1]	H+4+(#IPrec x 52)+4
10...	Next reading offset = H+4+(#IPrec * 52)+4+(#dnsserver * 16)				
11	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+(#IPrec x 52)+4+ (#dnsserver x 16)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.91 ITBANDPASSBANK

Allowable band pass filter configurations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ITBANDPASSBANK log provides information on the allowable configurations for each frequency when applying a bandpass filter. The current filters in use can be seen with the **ITFILTTABLE** log on page 690.

For dual antenna receivers, an **ITBANDPASSBANK_1** log can be requested to view the allowable configurations for the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **ITBANDPASSBANKA_1**, and for a binary log enter **ITBANDPASSBANKB_1**.

The ITBANDPASSBANK and ITBANDPASSBANK_1 logs use the same message ID.

Message ID: 2022

Log type: Asynch

Recommended input:

```
log itbandpassbanka once
```

Abbreviated ASCII example:

```
<ITBANDPASSBANK USB1 0 54.0 UNKNOWN 0 2.392 02000020 fb2e 16809
<     9
<          GPSL5 1164.3750 1173.1250 1178.1250 1186.8750 0.05
<          GALILEOE5A 1164.3750 1173.1250 1178.1250 1186.8750 0.05
<          GALILEOE5B 1195.6250 1204.3750 1209.3750 1218.1250 0.05
<          BEIDOUB1 1549.6875 1558.4375 1563.4375 1572.1875 0.05
<          BEIDOUB2 1195.6250 1204.3750 1209.3750 1218.1250 0.05
<          QZSSL5 1164.3750 1173.1250 1178.1250 1186.8750 0.05
<          NAVICL5 1164.3750 1173.1250 1178.1250 1186.8750 0.05
<          BEIDOUB2A 1164.3750 1173.1250 1178.1250 1186.8750 0.05
<          BEIDOUB2B 1195.6250 1204.3750 1209.3750 1218.1250 0.05
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ITBANDPASSBANK header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# of entries	Number of entries to follow	Ulong	4	H
3	frequency	See *Table 56: Frequency types* on page 241	Enum	4	H+4
4	min lower frequency cutoff	The minimum frequency cutoff at the lower end (MHz)	Float	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	max lower frequency cutoff	The maximum frequency cutoff at the lower end (MHz)	Float	4	H+12
6	min upper frequency cutoff	The minimum frequency cutoff at the upper end (MHz)	Float	4	H+16
7	max upper frequency cutoff	The maximum frequency cutoff at the upper end (MHz)	Float	4	H+20
8	frequency step	The minimum cut off frequency resolution (MHz)	Float	4	H+24
9	Next entry offset = H + 4 + (#entries * 24)				
10	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#entries * 24)
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.92 ITDETECTSTATUS

Interference detection status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists all of the detected interferences from all active paths where interference detection is enabled.

This log should be used with the **onchanged** trigger only.

For dual antenna receivers, an **ITDETECTSTATUS_1** log is requested to view the detected interferences from all active paths on the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **ITDETECTSTATUSA_1**, and for a binary log enter **ITDETECTSTATUSB_1**.

The ITDETECTSTATUS and ITDETECTSTATUS_1 logs use the same message ID.

Message ID: 2065

Log type: Asynch

Recommended input:

```
log itdetectstatusa onchanged
```

ASCII example

```
#ITDETECTSTATUSA,USB2,0,74.0,FINESTEERING,1982,430605.267,0200c000,7fdb,32768;3,
L1,STATISTICANALYSIS,-0.718,29.167,0.126,12.797,00000000,00000000,00000000,
L2,SPECTRUMANALYSIS,1249.961,71.191,-56.769,-132.907,00000000,00000000,00000000,
L2,SPECTRUMANALYSIS,1289.512,1.978,-75.967,-138.493,00000000,00000000,00000000
*87381101
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ITDETECTSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# of entries	Number of interferences to follow	Ulong	4	H
3	RF Path	RF path for this entry. 2 = L1 3 = L2 5 = L5	Enum	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	Interference detection type	Interference detection type for this entry. 0 = SPECTRUMANALYSIS 1 = STATISTICALANALYSIS	Enum	4	H+8
5	Parameter 1	The first parameter of the interference. For SPECTRUMANALYSIS type, this is the center frequency in MHz. For STATISTICALANALYSIS type, this is reserved.	Float	4	H+12
6	Parameter 2	The second parameter of the interference. For SPECTRUMANALYSIS type, this is the bandwidth in MHz. For STATISTICALANALYSIS type, this is reserved.	Float	4	H+16
7	Parameter 3	The third parameter of the interference. For SPECTRUMANALYSIS type, this is the estimated power in dBm of the interference. For STATISTICALANALYSIS type, this is reserved.	Float	4	H+20
8	Parameter 4	The fourth parameter of the interference. For SPECTRUMANALYSIS type, this is the highest estimated power spectrum density in dBmHz of the interference. For STATISTICALANALYSIS type this is reserved.	Float	4	H+24
9	Reserved 1	Reserved	Ulong	4	H+28
10	Reserved 2	Reserved	Ulong	4	H+32
11	Reserved 3	Reserved	Ulong	4	H+36
12	Next interference signal offset = H + 4 + (#entries * 36)				
13	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H=4+ (#entries * 36)
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 147: RF paths for OEM7 receivers

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, SMART2	OEM7600
L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1 LBand	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1
L2	GPS L2 GLONASS L2 Galileo E6 BDS B3 QZSS L2/L6	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5
L5	GPS L5 GLONASS L3 Galileo E5 BDS B2 QZSS L5 NavIC L5 SBAS L5			
LBAND	LBand	LBand		LBand

3.93 ITFILTTABLE

Filter configuration for each frequency

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ITFILTTABLE log contains the filter configuration summary for each frequency. It lists which bandpass or notch filters are enabled and how each is configured.

For dual antenna receivers, an **ITFILTTABLE_1** log can be requested to view the filter configuration summary for the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **ITFILTTABLEA_1**, and for a binary log enter **ITFILTTABLEB_1**.

The ITFILTTABLE and ITFILTTABLE_1 logs use the same message ID.

Refer to *3.93 ITFILTTABLE* above for information about location-based warnings, constraints, and best practices to ensure optimal filtering performance. These constraints are based on the position of the filter's cutoff or centre frequency relative to the signal's centre frequency.

Table 148: Filter warnings and constraints

Signal	Bandpass filter	Notch filter width			
		0.15 MHz	0.5 MHz	1.0 MHz	2.5 MHz
Refer to the **ITPROGFILTBANK** and **ITBANDPASSBANK** logs for supported signal configurations.	Warning flag raised for ≤7 MHz single-sided band. Filter not applied for <2.5 MHz single-sided band.	No warning flag raised.		Warning flag raised for ≤7 MHz single-sided band.	Warning flag raised at any location.

Message ID: 1991

Log type: Asynch

Recommended input:

```
log itfilttablea once
```

ASCII example:

```
#ITFILTTABLEA,USB1,0,52.5,FINESTEERING,2209,507953.506,12000020,35d0,16809;
23,
GPSL1,8,CIC3,00000000,DISABLE,0.0000,0.0000,1,ENABLE,PF0,NOTCHFILTER,1569.0000,
1581.0000,0.150,
GPSL2,4,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GLONASSL1,9,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GLONASSL2,5,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GPSL5,0,CIC3,00000000,DISABLE,0.0000,0.0000,0,
```

```
LBAND,11,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GALILEOE1,8,CIC3,00000000,DISABLE,0.0000,0.0000,1,ENABLE,PF0,NOTCHFILTER,1569.0
000,1581.0000,0.150,
GALILEOE5A,0,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GALILEOE5B,1,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GALILEOALTBOC,10,CIC3,00000000,DISABLE,0.0000,0.0000,0,
BEIDOUB1,2,CIC3,00000000,DISABLE,0.0000,0.0000,0,
BEIDOUB2,1,CIC3,00000000,DISABLE,0.0000,0.0000,0,
QZSSL1,8,CIC3,00000000,DISABLE,0.0000,0.0000,1,ENABLE,PF0,NOTCHFILTER,1569.0000
,1581.0000,0.150,
QZSSL2,4,CIC3,00000000,DISABLE,0.0000,0.0000,0,
QZSSL5,0,CIC3,00000000,DISABLE,0.0000,0.0000,0,
QZSSL6,6,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GALILEOE6,6,CIC3,00000000,DISABLE,0.0000,0.0000,0,
BEIDOUB3,7,CIC3,00000000,DISABLE,0.0000,0.0000,0,
GLONASSL3,10,CIC3,00000000,DISABLE,0.0000,0.0000,0,
NAVICL5,0,CIC3,00000000,DISABLE,0.0000,0.0000,0,
BEIDOUB1C,8,CIC3,00000000,DISABLE,0.0000,0.0000,1,ENABLE,PF0,NOTCHFILTER,1569.0
000,1581.0000,0.150,
BEIDOUB2A,0,CIC3,00000000,DISABLE,0.0000,0.0000,0,
BEIDOUB2B,1,CIC3,00000000,DISABLE,0.0000,0.0000,0*cfb2b0d4
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ITFILTTABLE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# entries	Number of records with information to follow	Ulong	4	H
3	frequency	The frequency at which the filter is applied. See *Table 56: Frequency types* on page 241	Enum	4	H+4
4	Encoder ID	ID of the digital path used by this frequency	Ulong	4	H+8
5	DDC filter type	The DDC filter type (see *Table 149: DDC filter type* on the next page)	Enum	4	H+12
6	status word	Filter warning limit status. Raise a warning flag if the filter is placed too close to the centre frequency of the GNSS signal (see *Table 150: ITFILTTable status word* on page 693)	Ulong	4	H+16
7	switch	Filter is enabled or disabled (see *Table 151: Filter switches* on page 694)	Enum	4	H+20
8	lower cut off frequency	Cut off frequency at the lower end (MHz)	Float	4	H+24
9	upper cut off frequency	Cut off frequency at the upper end (MHz)	Float	4	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
10	# prog filters	Number of programmable filters applied	Ulong	4	H+32
11	switch	Filter is enabled or disabled (see *Table 151: Filter switches* on page 694)	Enum	4	H+36
12	prog filter ID	The programmable filter ID (see *Table 53: Programmable filter ID* on page 237)	Enum	4	H+40
13	mode	Programmable filter mode (notch filter or bandpass) (see *Table 54: Programmable filter mode* on page 238)	Enum	4	H+44
14	lower cut off frequency	Cut off frequency at the lower end (MHz)	Float	4	H+48
15	upper cut off frequency	Cut off frequency at the upper end (MHz)	Float	4	H+52
16	notch width	Width of notch filter (MHz)	Float	4	H+56
17	Next programmable filter – variable binary offset				
18	Next frequency – variable binary offset				
19	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	Variable
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 149: DDC filter type

Binary	ASCII
0	PASSTHROUGH
1	CIC1
2	CIC2
3	CIC3
4	HALFBAND

Table 150: ITFILTTable status word

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	First enabled filter	0 = Within acceptable limit 1 = Warning
	1	0x00000002		
	2	0x00000004		
	3	0x00000008		
N1	4	0x00000010		
	5	0x00000020		
	6	0x00000040		
	7	0x00000080		
N2	8	0x00000100	Second enabled filter	0 = Within acceptable limit 1 = Warning
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		
N3	12	0x00001000		
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000	Third enabled filter	0 = Within acceptable limit 1 = Warning
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		

Nibble	Bit	Mask	Description	Range value
N6	24	0x01000000	Fourth enabled filter	0 = Within acceptable limit 1 = Warning
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

Table 151: Filter switches

Binary value	ASCII value	Description
0	DISABLE	Filter disabled
1	ENABLE	Filter enabled

3.94 ITPROGFILTBANK

Allowable filter configurations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ITPROGFILTBANK log provides information on the allowable configurations for the programmable filter for each frequency when applying either a notch filter or bandpass filter. The current filters in use can be seen with the **ITFILTTABLE** log on page 690.



For dual antenna receivers, an **ITPROGFILTBANK_1** log can be requested to view the allowable configurations for the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **ITPROGFILTBANKA_1**, and for a binary log enter **ITPROGFILTBANKB_1**.

The ITPROGFILTBANK and ITPROGFILTBANK_1 logs use the same message ID.

Message ID: 2023

Log type: Asynch

Recommended input:

```
log itprogfiltbanka once
```

Abbreviated ASCII example:

```
<ITPROGFILTBANK USB1 0 53.5 UNKNOWN 0 2.392 12000020 3696 16809
<     21
<          GPSL1 5
<          NOTCHFILTER 1563.0000 1574.0000 1576.0000 1587.0000 0.05 0.15
<          NOTCHFILTER 1563.7500 1573.6000 1576.4000 1586.2500 0.05 0.50
<          NOTCHFILTER 1564.0500 1573.3000 1576.7000 1585.9500 0.05 1.00
<          NOTCHFILTER 1565.7500 1571.7000 1578.3000 1584.2500 0.05 2.50
<          BANDPASSFILTER 1563.7500 1572.5000 1577.5000 1586.2500 0.05 0.00
<          GPSL2 5
<          NOTCHFILTER 1215.5000 1226.5000 1228.5000 1239.5000 0.05 0.15
<          NOTCHFILTER 1216.2500 1226.1000 1228.9000 1238.7500 0.05 0.50
<          NOTCHFILTER 1216.5500 1225.8000 1229.2000 1238.4500 0.05 1.00
<          NOTCHFILTER 1218.2500 1224.2000 1230.8000 1236.7500 0.05 2.50
<          BANDPASSFILTER 1216.2500 1225.0000 1230.0000 1238.7500 0.05 0.00
...
<          BEIDOUB2A 5
<          NOTCHFILTER 1163.6250 1174.6250 1176.6250 1187.6250 0.05 0.15
<          NOTCHFILTER 1164.3750 1174.2250 1177.0250 1186.8750 0.05 0.50
<          NOTCHFILTER 1164.6750 1173.9250 1177.3250 1186.5750 0.05 1.00
<          NOTCHFILTER 1166.3750 1172.3250 1178.9250 1184.8750 0.05 2.50
<          BANDPASSFILTER 1164.3750 1173.1250 1178.1250 1186.8750 0.05 0.00
<          BEIDOUB2B 5
<          NOTCHFILTER 1194.8750 1205.8750 1207.8750 1218.8750 0.05 0.15
<          NOTCHFILTER 1195.6250 1205.4750 1208.2750 1218.1250 0.05 0.50
<          NOTCHFILTER 1195.9250 1205.1750 1208.5750 1217.8250 0.05 1.00
<          NOTCHFILTER 1197.6250 1203.5750 1210.1750 1216.1250 0.05 2.50
<          BANDPASSFILTER 1195.6250 1204.3750 1209.3750 1218.1250 0.05 0.00
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ITPROGFILTBANK header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# entries	Number of entries to follow	Ulong	4	H
3	frequency	See *Table 56: Frequency types* on page 241	Enum	4	H+4
4	# prog filters	Number of programmable filters applied with information to follow	Ulong	4	H+8
5	mode	Programmable filter mode (notch filter or bandpass) (see *Table 54: Programmable filter mode* on page 238)	Enum	4	H+12
6	min lower frequency cutoff	The minimum frequency cutoff at the lower end (MHz)	Float	4	H+16
7	max lower frequency cutoff	The maximum frequency cutoff at the lower end (MHz)	Float	4	H+20
8	min upper frequency cutoff	The minimum frequency cutoff at the upper end (MHz)	Float	4	H+24
9	max upper frequency cutoff	The maximum frequency cutoff at the upper end (MHz)	Float	4	H+28
10	frequency step	The minimum cut off frequency resolution (MHz)	Float	4	H+32
11	notch width	Width of notch filter (MHz)	Float	4	H+36
12	Next programmable filter – variable binary offset				
13	Next frequency – variable binary offset				
14	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	variable
15	[CR][LF]	Sentence terminator (ASCII only)			

3.95 ITPSDDETECT

Power spectral density computed by the interference detection algorithm

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **ITPSDDETECT** log contains the power spectral density samples for the interference detection algorithm for all available RF paths, excluding the L-band path. The log will iterate through all available RF paths. Generally, the **ITPSDDETECT** log is output slightly slower than every 1 second. For dual antenna receivers, only the RF paths from the primary antenna are considered. Note that one log is output for every 1024 expected samples for a maximum of 32 logs and can be grouped together through the sequence number in the log header.



For dual antenna receivers, an **ITPSDDETECT_1** log can be requested to view the power spectral density samples for the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **ITPSDDETECTA_1**, and for a binary log enter **ITPSDDETECTB_1**.

The ITPSDDETECT_1 log is configured using the **ITDETECTCONFIG_1** command.

The ITPSDDETECT and ITPSDDETECT_1 logs use the same message ID.

3.95.1 PSD samples

PSD samples are compressed into 2 byte samples to reduce log sizes. The range of values that can be displayed is -200 dBm to +56 dBm with a 1/256 resolution. The following steps should be performed on the PSD samples in this log to convert them back into dBm units for display purposes:

1. Divide the sample by 256.0
2. Subtract 200

Message ID: 2063

Log type: Asynch

Recommended input:

```
log itpsddetect onnew
```

ASCII example

```
#ITPSDDETECTA,USB1,1,52.5,FINESTEERING,2209,508190.633,12000020,32d1,16809;
04021b22,1531.287,73242.188,1024,23036,20816,21178,20917,21252,21069,21186,
21501,20228,21326,20561,21254,21157,20442,21682,20875,20916,20918,21560,20287,
20694,21350,21409,20872,20725,20847,20715,21251,20716,21121,20794,21088,21757,
21782,21421,20433,19660,21395,21592,21157,20945,21297,20162,21313,20726,21544,
21468,20795,21080,21124,20490,20914,21649,20835,21548,21097,20551,20178,21341,
20793,21013,20290,21337,21242,21183,21769,21520,21416,20519,21761,21211,21026,
21408,21539,21257,20919,20828,20916,21124,20947,21278,20213,21124,21432,21284,
21336,20645,21817,21091,21413,21390,20698,21843,20842,20867,20598,21750,20852,
...
27699,28604,28277,28894,28715,28949,29529,28176,28121,28923,28753,29411,28256,
29559,27903,29107,29586,28285,29234,28915,28149,29504,28818,29505,28672,28325,
28951,27607,28919,28644,27515,28498,28440,29568,28695,28305,28256,27916,29967,
27756,28453,27556,28395,29259,28183,29241,29288,29205,28347,29147,29471,29428,
```

```
28958,28990,29356,29099,28455,29793,28800,28017,28291,28704,27458,29274,29320,
29374,28700,27100,28272,27938,29056,29151,28173,29381,29479,29597,29123,28960,
28689,28853,28614,28530,28571,28328*fd9113f5
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ITPSDDETECT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Status word	Status word containing information about the detection configuration (see *Table 152: Interference detection status word* below)	Ulong	4	H
3	Frequency start	Frequency represented by first data sample in MHz	Float	4	H+4
4	Resolution bandwidth	The resolution bandwidth (RBW) in Hz	Float	4	H+8
5	# of samples	Number of spectral density samples	Ulong	4	H+12
6	Sample array	Array of power spectral density samples	Ushort	2*NumOf Samples	H+16
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+16+ 2*NumOf Samples
8	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 152: Interference detection status word

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Frequency	See *Table 153: RF frequency path* on the next page
	1	0x00000002		
	2	0x00000004		
	3	0x00000008		
N1	4	0x00000010	Data Source	Predecimation
	5	0x00000020		
	6	0x00000040		
	7	0x00000080		

Nibble	Bit	Mask	Description	Range value
N2	8	0x00000100	Reserved	
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		
N3	12	0x00001000	Reserved	
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000	Reserved	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000	Reserved	
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000	Reserved	
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000	Reserved	
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

Table 153: RF frequency path

Binary	ASCII	Description
2	L1	L1 RF Path
3	L2	L2 RF Path
5	L5	L5 RF Path

Table 154: RF paths for OEM7 receivers

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, SMART2	OEM7600
L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1 LBand	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1
L2	GPS L2 GLONASS L2 Galileo E6 BDS B3 QZSS L2/L6	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5
L5	GPS L5 GLONASS L3 Galileo E5 BDS B2 QZSS L5 NavIC L5 SBAS L5			
LBAND	LBand	LBand		LBand

3.96 ITPSDFINAL

Processed power spectral density

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ITPSDFINAL log contains the samples for the spectral analysis. The rate and size is set by the update period and the FFT size respectively when issuing the **ITSPECTRALANALYSIS** command (see page 239).

PSD samples are compressed into 2 byte samples to reduce log sizes. The range of values that can be displayed is -200 dBm to +56 dBm with a 1/256 resolution. The following steps should be performed on the PSD samples in this log to convert them back into dBm units for display purposes:

1. Divide the sample by 256.0
2. Subtract 200

The number of samples are calculated according to the following table. The maximum number of samples in one ITPSDFINAL log is 1024. That means if the number of samples is less than 1024, one log is enough to output them. However, if the number of samples is larger than 1024, more than one ITPSDFINAL log is needed. For example, in postdecimation mode with the FFT size of 8K and subcarrier integration of 5, there is one log with 1024 samples and another log with 614 samples. The output logs can be grouped together through the sequence number of the log header.

Data source	Number of samples
PREDECIMATION	FFTsize/(2*subcarrier_integration)
POSTDECIMATION	FFTsize/subcarrier_integration
POSTFILTER	FFTsize/subcarrier_integration



As the data rate for the ITPSDFINAL log is dictated by the updateperiod parameter in the **ITSPECTRALANALYSIS** command (see page 239), do not use ONTIME or ONCE to log this message. Instead use ONNEW to log ITPSDFINAL.



The pre-decimation spectrum shows the absolute power in dBm which is proportional to the resolution bandwidth (RBW). The post-decimation and post-filter spectrum shows the signal magnitude in relative power (dB).



For dual antenna receivers, an **ITPSDFINAL_1** log can be requested to view the samples for the spectral analysis for the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **ITPSDFINALA_1**, and for a binary log enter **ITPSDFINALB_1**.

The ITPSDFINAL and ITPSDFINAL_1 logs use the same message ID.

Message ID: 1968

Log type: Asynch

Recommended input:

```
log itpsdfinala onnew
```

ASCII example

```
#ITPSDFINALA,USB1,0,52.5,FINESTEERING,2209,507969.564,12000020,b79a,16809;26142
860,1562.561,122070.313,204,29796,29396,29720,29568,30272,29991,30321,29749,294
82,29315,29754,29329,29859,29839,29366,29818,30178,30317,29421,30146,29896,3014
4,30760,30315,29564,30139,30164,30667,30943,29849,30659,30339,30895,30267,30462
,29965,30541,30240,30712,30883,30523,30596,30775,30638,30753,30839,29860,31314,
31508,30487,30353,28644,26580,26452,27765,29511,30887,31557,31096,31549,31135,3
1567,31193,31756,31568,31470,31732,31118,31946,31416,31526,31193,31882,31454,31
379,31558,31555,31972,32125,31970,31384,31204,32437,31611,31551,32050,31730,319
69,31871,31232,31584,32252,31373,32220,32198,32189,33447,32370,33055,33660,3318
2,33203,33523,33306,32746,33764,33909,33424,33019,33953,32423,33388,33055,32483
,33109,32435,32411,32205,32338,32310,32051,32228,31851,32049,31698,31584,31816,
31821,31399,32122,32096,32253,31889,32050,31787,31575,31775,31363,31556,31593,3
1216,30940,31538,31570,31529,31265,31295,31518,31361,29133,27947,25797,26746,29
320,30342,30694,31279,31063,31655,30911,30762,30625,30845,30991,30900,30946,308
47,30441,30702,31092,31097,30364,31093,30439,31202,30641,30051,29842,30629,3067
6,30082,30466,30499,30363,30245,30515,30441,30365,30217,30359,29207,30538,30327
,30162,30518,29656,29978,30273,30084,30297,30136,30172,29755,29455*40f7bd2d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ITPSDFINAL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	status word	Status word containing information about the configuration of the spectral analysis (see *Table 155: Spectral analysis status word* on the next page)	Ulong	4	H
3	frequency start	Frequency represented by first data sample (MHz)	Float	4	H+4
4	resolution bandwidth	The resolution bandwidth (Hz)	Float	4	H+8
5	# samples	Number of spectral density samples	Ulong	4	H+12
6	sample	Power spectral density sample	Ushort	2	H+16
7	Next sample = H+16+(2*#samples)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+16+ (2*#samples)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 155: Spectral analysis status word

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Frequency	0 – 20 See *Table 56: Frequency types* on page 241
	1	0x00000002		
	2	0x00000004		
	3	0x00000008		
N1	4	0x00000010		
	5	0x00000020	Data Source	0 – 3 See *Table 55: Data sources for PSD samples* on page 240
	6	0x00000040		
	7	0x00000080		
N2	8	0x00000100	FFT Size	0 – 6 See *Table 57: FFT sizes* on page 242
	9	0x00000200		
	10	0x00000400		
	11	0x00000800	Integration Window	1 – 1024 samples
N3	12	0x00001000		
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000		
	17	0x00020000	Time Average Window	0 – 100 seconds
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000	Reserved	
	26	0x04000000		
	27	0x08000000		

Nibble	Bit	Mask	Description	Range value
N7	28	0x10000000	Reserved	
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

3.97 J1939STATUS

Status of CAN J1939 Node

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This logs reports the status of J1939 node, specifically J1939 Address Claim function (initiated using the **J1939CONFIG** command (see page 244)).

This log displays the status only for nodes that have been set.

Message ID: 1907

Log type: Asynch

Recommended input:

```
LOG J1939STATUSA ONCHANGED
```

ASCII examples:

```
#J1939STATUSA,USB1,1,53.0,UNKNOWN,0,0.204,12000020,e9ce,16809;NODE1,DISABLED,0,
FE*6980fd0f
```

```
#J1939STATUSA,USB1,0,53.0,UNKNOWN,0,0.204,12000020,e9ce,16809;NODE2,DISABLED,0,
FE*cee67706
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	J1939STATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	node	J1939 Node. The node can be either NODE1 or NODE2.	Enum	4	H
3	status	Node status. See *Table 156: Node status* below	Enum	4	H+4
4	count	Number of attempts that were made to claim address. This will be 1 when the preferred address is used and may be more if the alternate range is used.	Ulong	4	H+8
5	address	Claimed CAN Address. 0xFE (NULL address) if the address could not be negotiated.	Uchar	1	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+13
7	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

Table 156: Node status

Value	ASCII	Description
1	DISABLED	Address claim activity is not taking place. The node does not have J1939 enabled.

Value	ASCII	Description
2	CLAIMING	Address claim procedure is in progress.
3	CLAIMED	Address claimed successfully. Ready for data transfer.
4	FAILED	Address claim was not successful. No further activity is taking place.

3.98 LBANDBEAMTABLE

List of L-band beams

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the L-band satellite channels used to deliver TerraStar, Oceanix and Veripos corrections streams to the receiver. When a subscription service is active, the Access field indicates which beams are authorized for use to provide corrections. See the **LBANDTRACKSTAT** log on page 709 the current status of each beam.

For information about subscription service, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 1718

Log type: Asynch

Recommended input:

```
log lbandbeamtablea onchanged
```

Abbreviated ASCII example:

```
<LBANDBEAMTABLE USB2 0 64.0 FINESTEERING 2320 159671.293 02000020 19b8 17399
<     8
<          "AORE" "A" 1545855000 1200 -15.50 1
<          "AORW" "B" 1545845000 1200 -54.00 1
<          "IOR" "C" 1545865000 1200 83.50 1
<          "POR" "D" 1545905000 1200 178.00 1
<          "25E" "E" 1545825000 1200 25.00 1
<          "143.5E" "F" 1545835000 1200 143.50 1
<          "98W" "G" 1545865000 1200 -98.00 1
<          "SP98W1" "SP98W1" 1545885000 1200 -98.00 1
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	LBANDBEAMTABLE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	Name	Beam/transmitting satellite name	Char[8]	8	H+4
4	Reserved		Char[8]	8	H+12
5	Frequency	Frequency (Hz)	Ulong	4	H+20
6	Baud	Baud rate (bps)	Ulong	4	H+24

Field	Field type	Description	Format	Binary bytes	Binary offset
7	Longitude	Transmitting satellite longitude (degrees)	Float	4	H+28
8	Access	Beam service availability flag 0 = Denied 1 = Granted	Ulong	4	H+32
9	Next beam offset = H + 4 + (#entries * 32)				
10	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#entries * 32)
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.99 LBANDTRACKSTAT

L-band beams status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the L-band tracking and Viterbi decoding status for the tracked L-band beams.

The maximum logging rate for LBANDTRACKSTAT is 2 Hz.

Message ID: 1201

Log type: Synch

Recommended input:

```
log lbandtrackstata ontime 1
```

ASCII example:

```
#LBANDTRACKSTATA,USB1,0,52.5,FINESTEERING,2209,508418.000,12000020,29e3,16809;
5,
"98W",1545865000,1200,974c,00c2,0,-334.215,40.513,3.0445,4338.944,82624,36,35,
10575872,4081,0.0004,
"AORW",1545845000,1200,974c,00c2,0,48.172,44.840,3.8044,4346.541,82752,0,0,
10592256,0,0.0000,
"POR",1545905000,1200,974c,0000,0,-440.550,0.000,0.0000,0.000,0,0,0,0,0,0.0000,
"",0,0,0000,0003,0,0.000,0.000,0.0000,0.000,0,0,0,0,0,0.0000,
"",0,0,0000,0003,0,0.000,0.000,0.0000,0.000,0,0,0,0,0,0.0000*5b097814
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	LBANDTRACKSTAT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	Name	Beam/transmitting satellite name	Char[8]	8	H+4
4	Frequency	Frequency assigned to this L-band beam (Hz)	Ulong	4	H+12
5	Baud rate	Baud rate of assigned beam	Ushort	2	H+16
6	ID	Service ID of the assigned beam	Ushort	2	H+18
7	Status	Tracking status word. See *Table 157: L-Band signal tracking status* on the next page	Ushort	2	H+20
8	Reserved	Reserved	Ushort	2	H+22
9	Doppler	Signal Doppler (Hz)	Float	4	H+24

Field	Field type	Description	Format	Binary bytes	Binary offset
10	C/No	Carrier to noise density ratio (dB-Hz)	Float	4	H+28
11	Phase stability metric	Tracking stability metric. A higher value is better. A loss of lock may occur when this value drops below 1.2.	Float	4	H+32
12	Lock time	Lock time (s)	Float	4	H+36
13	Unique word bits	Total unique word bits	Ulong	4	H+40
14	Bad unique word bits	Bad unique word bits	Ulong	4	H+44
15	Bad unique words	Bad unique words	Ulong	4	H+48
16	Viterbi symbols	Total Viterbi symbols	Ulong	4	H+52
17	Corrected Viterbi	Corrected Viterbi symbols	Ulong	4	H+56
18	Bit error rate	Estimated pre-Viterbi Bit Error Rate (BER)	Float	4	H+60
19	Next entry offset = H + 4 + (#entries x 60)				
20	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#entries x 60)
21	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 157: L-Band signal tracking status

Nibble	Bit	Mask	Description	Range value
N0	0	0x0001	Tracking State	0 = Searching, 1 = Pull-in, 2 = Tracking, 3 = Idle
	1	0x0002		
	2	0x0004	Reserved	
	3	0x0008		

Nibble	Bit	Mask	Description	Range value
N1	4	0x0010		
	5	0x0020		
	6	0x0040	Bit Timing Lock	0 = Not Locked, 1 = Locked
	7	0x0080	Phase Locked	0 = Not Locked, 1 = Locked
N2	8	0x0100	DC Offset Unlocked	0 = Good, 1 = Warning
	9	0x0200	AGC Unlocked	0 = Good, 1 = Warning
	10	0x0400	Reserved	
	11	0x0800		
N3	12	0x1000		
	13	0x2000		
	14	0x4000		
	15	0x8000	Error	0 = Good, 1 = Error

3.100 LOGLIST

List of system logs

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists which messages are currently being logged to each port and when. The following tables show the binary and ASCII output. See also the **RXCONFIG** log on page 913 for a list of current command settings.

Message ID: 5

Log type: Polled

Recommended input:

```
log loglista once
```

Abbreviated ASCII example:

```
<LOGLIST USB1 0 53.0 FINESTEERING 2209 508498.000 12000020 c00c 16809
<     32
<          COM1 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          COM2 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          COM3 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          FILE RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          USB1 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          USB1 ITDETECTSTATUSA ONCHANGED 0.000000 0.000000 NOHOLD
<          USB1_30 RXCONFIGB ONCHANGED 0.000000 0.000000 HOLD
<          USB1_30 SATVIS2B ONCHANGED 0.000000 0.000000 HOLD
<          USB1_30 AVEPOSB ONCHANGED 0.000000 0.000000 HOLD
<          USB1_30 RXSTATUSB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 INTERFACEMODEB ONCHANGED 0.000000 0.000000 HOLD
<          USB1_30 ITDETECTSTATUSB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 FILESTATUSB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 PORTSTATSB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 INSPVAXB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 RXSTATUSEVENTB ONCHANGED 0.000000 0.000000 HOLD
<          USB1_30 TIMEB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 BESTPOSB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 HWMONITORB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 TRACKSTATB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 LBANDTRACKSTATB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 INSPOSXB ONTIME 1.000000 0.000000 HOLD
<          USB1_30 MODELFEATURESB ONCHANGED 0.000000 0.000000 HOLD
<          USB2 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          USB3 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM1 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM2 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM3 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM4 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM5 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM6 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
<          ICOM7 RXSTATUSEVENTA ONNEW 0.000000 0.000000 HOLD
```

Do not use undocumented logs or commands. Doing so may produce errors and void your warranty.

3.100.1 Binary

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	LOGLIST (binary) header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#logs	Number of messages to follow, maximum = 80	Ulong	4	H
3	port	Output port, see *Table 5: Detailed port identifier* on page 42	Enum	4	H+4
4	message	Message ID of the log	Ushort	2	H+8
5	message type	Bits 0-4 = Reserved Bits 5-6 = Format 00 = Binary 01 = ASCII 10 = Abbreviated ASCII, NMEA 11 = Reserved Bit 7 = Response Bit (see *Message responses* on page 52) 0 = Original Message 1 = Response Message	Char	1	H+10
6	Reserved		Char	1	H+11
7	trigger	0 = ONNEW 1 = ONCHANGED 2 = ONTIME 3 = ONNEXT 4 = ONCE 5 = ONMARK 6 = ONALL	Enum	4	H+12
8	period	Log period for ONTIME	Double	8	H+16
9	offset	Offset for period (ONTIME trigger)	Double	8	H+24
10	hold	0 = NOHOLD 1 = HOLD	Enum	4	H+32
11...	Next log offset = H + 4 + (#logs x 32)				
variable	xxxx	32-bit CRC	Hex	4	H+4+ (#logs x 32)

3.100.2 ASCII

Field	Field type	Description	Format
1	Log header	LOGLIST (ASCII) header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	
2	#logs	Number of messages to follow, maximum = 80	Long
3	port	Output port, see *Table 5: Detailed port identifier* on page 42	Enum
4	message	Message name of log with no suffix for abbreviated ASCII, an A suffix for ASCII and a B suffix for binary	Char [ ]
5	trigger	ONNEW ONCHANGED ONTIME ONNEXT ONCE ONMARK ONALL	Enum
6	period	Log period for ONTIME	Double
7	offset	Offset for period (ONTIME trigger)	Double
8	hold	NOHOLD HOLD	Enum
9...	Next log		
variable	xxxx	32-bit CRC	Hex
variable	[CR][LF]	Sentence terminator	-

3.101 LUAFILELIST

List available Lua scripts

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This sequenced log informs the user of the available scripts, obtained from the ISO loaded onto the receiver. The size of the file, last change date in yyyymmdd format, last change time in hhmmss format, and path to the files are printed as well.

Message ID: 2151

Log type: Polled

Recommended input:

```
LOG LUAFILELIST
```

Abbreviated ASCII example:

```
[COM1]<LUAFILELIST COM1 6 89.5 UNKNOWN 0 4.000 02444020 b447 14635
<     0 20180202 151403 "/lua/uppercase.lua"
<LUAFILELIST COM1 5 90.5 UNKNOWN 0 4.000 02444020 b447 14635
<     2706 20180129 152042 "/lua/debugloop.lua"
<LUAFILELIST COM1 4 90.5 UNKNOWN 0 4.000 02444020 b447 14635
<     4692 20180202 110107 "/lua/parsetime.lua"
<LUAFILELIST COM1 3 90.5 UNKNOWN 0 4.000 02444020 b447 14635
<     4764 20180205 105415 "/lua/scom_rx.lua"
<LUAFILELIST COM1 2 90.5 UNKNOWN 0 4.000 02444020 b447 14635
<     3728 20180202 104830 "/lua/scomtunnel.lua"
<LUAFILELIST COM1 1 90.5 UNKNOWN 0 4.000 02444020 b447 14635
<     3044 20180201 144849 "/lua/scriptargs.lua"
<LUAFILELIST COM1 0 90.5 UNKNOWN 0 4.000 02444020 b447 14635
<     2337 20180129 155140 "/lua/sendtocom2.lua"
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	LUAFILELIST header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Size	File size (in Bytes)	Ulong	4	H
3	Date	Last change date When viewed as a string, the date is of the form YYYYMMDD. So, numerically, the date is (Year * 10000) + (Month * 100) + (Day).	Ulong	4	H+4
4	Time	Last change time When viewed as a string, the time is HHMMSS. So, numerically, the time is (Hour * 10000) + (Minute * 100) + (Second).	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	Path	The path to the Lua script The maximum length of this string is 256 bytes.	String	Variable	H+12

3.102 LUAFILESYSTEMSTATUS

Query mount status of Lua scripts

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this log to query the mount status of the ISO image that contains the Lua scripts loaded on to the receiver.

Message ID: 2150

Log type: Asynch

Recommended input:

```
LOG LUAFILESYSTEMSTATUS
```

Abbreviated ASCII example:

```
<LUAFILESYSTEMSTATUS COM1 0 90.0 UNKNOWN 0 0.204 02444020 b8f8 14635
<     MOUNTED ""
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	LUAFILESYSTEMSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Status	The status of the file system. See *Table 158: File system status* below.	Enum	4	H
3	Error	String that indicates the error message if mounting fails The maximum length of this string is 52 bytes.	String	Variable	H+4

Table 158: File system status

Value	Description
1	UNMOUNTED
2	MOUNTED
3	BUSY
4	ERROR
5	UNMOUNTING
6	MOUNTING

3.103 LUAOUTPUT

Output stderr and stdout from the Lua interpreter

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this log to output `stderr` and `stdout` messages from the Lua interpreter.



The **LUAOUTPUT** log uses a short header. See *Description of ASCII and binary logs with short headers* on page 51 for more information.

Message ID: 2240

Log type: Asynch

Recommended input:

```
LOG LUAOUTPUT ONNEW
```

Abbreviated ASCII example:

```
<LUAOUTPUT 0 346044.929
<     1 0 STDOUT "Lua 5.3.4  Copyright (C) 1994-2017 Lua.org, PUC-Rio"
<LUAOUTPUT 0 346044.987
<     2 0 STDOUT "> "
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	LUAOUTPUT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Sequence Number	Running number of each LUAOUTPUT log produced by the system	Ulong	4	H
3	Executor Number	Lua Executor Number that produced the data	Ulong	4	H+4
4	Data Source	See *Table 159: Lua data source* below	Enum	4	H+8
5	Data	NULL-terminated string containing a single line of data from stderr or stdout. This string is not terminated with a carriage return or line feed. This string contains only printable characters. The maximum length of this string is 128 bytes.	String	Variable	H+12

Table 159: Lua data source

Binary	ASCII	Description
0	STDOUT	Data is from stdout
1	STDERR	Data is from stderr

3.104 LUASTATUS

Display status of Lua scripts

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

Use this log to determine which scripts are running on the receiver and whether the scripts have exited or encountered errors.

Message ID: 2181

Log type: Collection

Recommended input:

```
LOG LUASTATUS
```

Abbreviated ASCII example:

```
[COM1]<LUASTATUS COM1 1 84.5 FINESTEERING 1963 402110.866 02400000 2e18 32768
<     0 "icom_rx.lua 127.0.0.1 3001" EXECUTING
<LUASTATUS COM1 0 84.5 FINESTEERING 1963 402110.866 02400000 2e18 32768
<     1 "" NOT_STARTED
```

The example above is for the projected log output for two executors.

Field	Field type	Description	Format	Binary bytes	Binary format
1	Log header	LUASTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Number	Executor number	Ulong	4	H
3	Script	Script and arguments	String [256]	Variable	H+4
4	Status	Script status. See *Table 160: Script status* below.	Enum	4	Variable

Table 160: Script status

Binary	ASCII	Description
0	NOT_STARTED	There is no script running on the executor
1	EXECUTING	The script is running
2	COMPLETED	The script completed successfully
3	SCRIPT_ERROR	The script exited with an error
4	EXECUTOR_ERROR	The script executor encountered an error while attempting to run the script

3.105 MARKPOS, MARK2POS, MARK3POS and MARK4POS

Position at time of mark input event

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART2**

This log contains the estimated position of the antenna when a pulse is detected at a mark input.

- MARKPOS is generated when a pulse occurs on the MK1I (EVENT_IN1) input.
- MARK2POS is generated when a pulse occurs on the MK2I (EVENT_IN2) input.
- MARK3POS is generated when a pulse occurs on the MK3I (EVENT_IN3) input (OEM7600, OEM7700, OEM7720, PwrPak7, CPT7 and CPT7700 only).
- MARK4POS is generated when a pulse occurs on the MK4I (EVENT_IN4) input (OEM7600, OEM7700 and OEM7720 only).

Refer to the *Technical Specifications* appendices in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for mark input pulse specifications and the location of the mark input pins.

The position at the mark input pulse is extrapolated using the last valid position and velocities. The latched time of mark impulse is in GPS reference weeks and seconds into the week. The resolution of the latched time is 10 ns. See also the notes on MARKPOS in the **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** log on page 723.

The position for the **MARKPOS**, **MARK2POS**, **MARK3POS** and **MARK4POS** logs are reported in the user selected datum. See the **DATUM** command on page 133 for more details.

Message ID: **181 (MARKPOS)**
615 (MARK2POS)
1738 (MARK3POS)
1739 (MARK4POS)

Log type: Asynch

Recommended input:


```
log markposa onnew
```

1. Use the ONNEW trigger with the MARKxTIME or MARKxPOS logs.
2. ONMARK only applies to MK1I. Events on MK2I (if available) do not trigger logs when ONMARK is used. Use the ONNEW or ONALL trigger with the MARK1TIME, MARK2TIME, MARKPOS or MARK2POS logs.
3. Once the 1PPS signal has hit a rising edge, for both MARKxPOS and MARKxTIME logs, a resolution of both measurements is 10 ns. As for the ONMARK trigger for other logs that measure latency, for example RANGE and position logs such as BESTPOS, it takes typically 20-30 ms (50 ms maximum) for the logs to output information from the 1PPS signal. Latency is the time between the reception of the 1PPS pulse and the first byte of the associated log. See also the **MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME** log on page 723.

Abbreviated ASCII example:

```
<MARKPOS COM1 0 89.0 FINESTEERING 1670 413138.000 02000020 c223 42770
SOL_COMPUTED SINGLE 51.11289233689 -114.02932170726 1018.9653 1049.4915 BUKIT
1.9372 1.1981 4.0909 "" 0.000 0.000 19 18 18 18 0 06 0 33
```

Consider the case where you have a user point device such as video equipment. Connect the device to the receiver's I/O port using a cable that is compatible to both the receiver and the device. Refer to your device's documentation for information about connectors and cables. The arrow along the cable in the figure below indicates a MARKIN pulse, from the user device on the right to the receiver I/O port.



Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MARKPOS / MARK2POS / MARK3POS / MARK4POS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (see *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (see *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (m)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid (m) When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	lon σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID	Char[4]	4	H+52
13	diff_age	Differential age in seconds	Float	4	H+56
14	sol_age	Solution age in seconds	Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	Reserved		Uchar	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.106 MARK1TIME, MARK2TIME, MARK3TIME and MARK4TIME

Time of mark input event

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART2**

This log contains the time of the leading edge of the detected mark input pulse.

- MARK1TIME is generated when a pulse occurs on a MK1I (EVENT_IN1) input
- MARK2TIME is generated when a pulse occurs on a MK2I (EVENT_IN2) input
- MARK3TIME is generated when a pulse occurs on a MK3I (EVENT_IN3) input (OEM7600, OEM7700, OEM7720, PwrPak7, CPT7 and CPT7700 only)
- MARK4TIME is generated when a pulse occurs on a MK4I (EVENT_IN4) input (OEM7600, OEM7700 and OEM7720 only)

The MARKTIME log (message ID 231) is deprecated. Use the MARK1TIME log as a replacement.

Refer to the *Technical Specifications* appendix in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual CPT7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual for mark input pulse specifications and the location of the mark input pins. The resolution of this measurement is 10 ns.

1. Use the ONNEW trigger with the MARKxTIME or the MARKxPOS logs.
2. Only the MARKxPOS logs, MARKxTIME logs and ‘polled’ log types are generated ‘on the fly’ at the exact time of the mark. Synchronous and asynchronous logs output the most recently available data.
3. ONMARK only applies to MK1I. Events on MK2I (if available) do not trigger logs when ONMARK is used. Use the ONNEW or ONALL trigger with the MARK1TIME, MARK2TIME, MARKPOS or MARK2POS logs.
4. Once the 1PPS signal has hit a rising edge, for both MARKxPOS and MARKxTIME logs, a resolution of both measurements is 10 ns. As for the ONMARK trigger for other logs that measure latency, for example RANGE and POSITION logs such as BESTPOS, it takes typically 20-30 ms (50 ms maximum) for the logs to output information from the 1PPS signal. Latency is the time between the reception of the 1PPS pulse and the first byte of the associated log. See also the **MARKPOS, MARK2POS, MARK3POS and MARK4POS** log on page 720.

Message ID: **1130 (MARK1TIME)**
616 (MARK2TIME)
1075 (MARK3TIME)
1076 (MARK4TIME)

Log type: Asynch

Recommended input:

```
log mark1timea onnew
```

ASCII example:

```
#MARK1TIMEA,COM1,0,77.5,FINESTEERING,1358,422621.000,02000000,292e,2214;1358,
422621.000000500,-1.398163614e-08,7.812745577e-08,-14.000000002,VALID*b8815d3a
```

These logs allow you to measure the time when events are occurring in other devices (such as a video recorder). See also the **MARKCONTROL** command on page 261.

GPS reference time is the receiver's estimate of the true GPS system time. GPS reference time can be found in the header of the log. The relationship between GPS reference time and true GPS system time is:
GPS system time = GPS reference time - offset

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MARK1TIME / MARK2TIME / MARK3TIME / MARK4TIME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	week	GPS reference week number	Long	4	H
3	seconds	Seconds into the week as measured from the receiver clock, coincident with the time of electrical closure on the Mark Input port	Double	8	H+4
4	offset	Receiver clock offset, in seconds. A positive offset implies that the receiver clock is ahead of GPS system time. To derive GPS system time, use the following formula: GPS system time = GPS reference time - (offset) Where GPS reference time can be obtained from the log header	Double	8	H+12
5	offset std	Standard deviation of receiver clock offset (s)	Double	8	H+20
6	utc offset	This field represents the offset of GPS system time from UTC time (s), computed using almanac parameters. UTC time is GPS reference time plus the current UTC offset minus the receiver clock offset. UTC time = GPS reference time - offset + UTC offset 0 indicates that UTC time is unknown because there is no almanac available in order to acquire the UTC offset.	Double	8	H+28
7	status	Clock model status, see *Table 110: Clock model status* on page 556	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.107 MASTERPOS

Base Position using ALIGN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

ALIGN generates distance and bearing information between a Base and Rover receiver. This log outputs the position information of the Base when using the ALIGN feature. This log can be output from both Y and Z ALIGN models and can be output at both Base and Rover ends.

You must have an ALIGN capable receiver to use this log.

1. ALIGN is useful for obtaining the relative directional heading of a vessel/body, separation heading between two vessels/bodies or heading information with moving base and pointing applications.
2. The log can be output at both Y and Z model Rover if it is receiving the RTCAREFEXT or NovAtelXRef message from the Base. The log can be output at any Base if the Base is receiving HEADINGEXTB or HEADINGEXT2B from the Rover.
3. MASTERPOS logging is dictated by the output frequency of the RTCAREFEXT or NovAtelXRef output frequency.

Message ID: 1051

Log type: Asynch

Recommended input:

```
log masterposa onchanged
```

ASCII example:

```
#MASTERPOSA,COM1,0,21.5,FINESTEERING,1544,340322.000,02000008,5009,4655;
SOL_COMPUTED,NARROW_INT,51.11604599076,-114.03855412002,1055.7756,16.9000,
WGS84,0.0090,0.0086,0.0143,"AAAA",0.0,0.0,13,13,13,12,0,0,0,0*b01cd033
```

Asynchronous logs, such as MASTERPOS, should only be logged ONCHANGED or ONNEW, otherwise the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MASTERPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	sol stat	Solution Status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position Type see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	lat	Base WGS84 Latitude in degrees	Double	8	H+8
5	long	Base WGS84 Longitude in degrees	Double	8	H+16
6	hgt	Base MSL Height in metres	Double	8	H+24
7	undulation	Undulation in metres	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER (default = WGS84)	Enum	4	H+36
9	lat σ	Latitude standard deviation in metres	Float	4	H+40
10	long σ	Longitude standard deviation in metres	Float	4	H+44
11	hgt σ	Height standard deviation in metres	Float	4	H+48
12	stn id	Receiver ID can be set using the **DGPSTXID** command (see page 138)	Char[4]	4	H+52
13	Reserved		Float	4	H+56
14			Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#obs	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#multi	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	sol source	Solution source (see *Table 144: Solution Source* on page 670)	Hex	1	H+68
20	Reserved		Uchar	1	H+69
21			Uchar	1	H+70
22			Uchar	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	HEX	1	H+72
24	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

3.108 MATCHEDPOS

Matched RTK position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log represents positions that have been computed from time matched base and rover observations. There is no base extrapolation error on these positions because they are based on buffered measurements, that is, they lag real time by some amount depending on the latency of the data link. If the rover receiver has not been enabled to accept RTK differential data or is not actually receiving data leading to a valid solution, this is shown in fields #2 (*sol status*) and #3 (*pos type*).

This log provides the best accuracy in static operation. For lower latency in kinematic operation, see the **RTKPOS** log (see page 903) or **BESTPOS** log (see page 527). The data in the logs changes only when a base observation (RTCMv3) changes.

A good message trigger for this log is onchanged. Then, only positions related to unique base station messages are produced and the existence of this log indicates a successful link to the base.

Asynchronous logs, such as MATCHEDPOS, should only be logged ONCHANGED otherwise the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

The RTK system in the receiver provides two kinds of position solutions. The Matched RTK position is computed with buffered observations, so there is no error due to the extrapolation of base station measurements. This provides the highest accuracy solution possible at the expense of some latency which is affected primarily by the speed of the differential data link. The **MATCHEDPOS** log contains the matched RTK solution and can be generated for each processed set of base station observations.

The Low-Latency RTK position is computed from the latest local observations and extrapolated base station observations. This supplies a valid RTK position with the lowest latency possible at the expense of some accuracy. The degradation in accuracy is reflected in the standard deviation and is summarized in *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss. The amount of time that the base station observations are extrapolated is in the "differential age" field of the position log. The Low-Latency RTK system extrapolates for 60 seconds. The **RTKPOS** log (see page 903) contains the Low-Latency RTK position when valid, and an "invalid" status when a Low-Latency RTK solution could not be computed. The **BESTPOS** log (see page 527) contains either the low-latency RTK, PPP or pseudorange-based position, whichever has the smallest standard deviation.

Message ID: 96

Log type: Asynch

Recommended input:

```
log matchedposa onchanged
```

ASCII example:

```
#MATCHEDPOSA,USB1,0,66.5,FINESTEERING,2211,232751.000,02000020,8b46,16809;
SOL_COMPUTED,NARROW_INT,51.15043862995,-114.03067350591,1098.9166,-17.0000,
WGS84,0.0070,0.0063,0.0114,"K250",0.000,0.000,37,16,16,15,00,01,00,33*755bb833
```

Measurement precision is different from the position computation precision. Measurement precision is a value that shows how accurately the actual code or carrier phase is measured by the GNSS receiver. Position precision is a value that shows the accuracy of the position computation made from the code and/or carrier phase measurements. The P-code L2 measurement precision is not as good as the C/A measurement precision because the NovAtel GNSS receiver is a civilian grade GPS device and does not have direct access to the decrypted military L2 P(Y) code. This means that NovAtel's semi-codeless P-code L2 measurements are noisier than the civilian band C/A code measurements. Refer to the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual or SMART7 Installation and Operation User Manual for the technical specification of the receiver.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MATCHEDPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (see *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (see *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (m)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid (m) When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+36
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	lon σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID	Char[4]	4	H+52

Field	Field type	Description	Format	Binary bytes	Binary offset
13	Reserved		Float	4	H+56
14			Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	Reserved		Hex	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.109 MATCHEDSATS

Satellites used in MATCHEDPOS solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the used and unused satellites for the corresponding MATCHEDPOS solution. It also describes the signals of the used satellites and reasons for exclusions.

Message ID: 1176

Log type: Asynch

Recommended input:

```
log matchedsatsa onchanged
```

Abbreviated ASCII example:

```
<MATCHEDSATS COM1 0 62.5 FINESTEERING 2220 503122.000 02000000 b555 16807
<     36
<          GPS 18 GOOD 00000007
<          GPS 16 GOOD 00000003
<          GPS 5 GOOD 00000003
<          GPS 27 GOOD 00000007
<          GPS 29 GOOD 00000003
<          GPS 10 GOOD 00000007
<          GPS 23 GOOD 00000007
<          GPS 13 GOOD 00000003
<          GPS 15 GOOD 00000003
<          GPS 26 GOOD 00000007
<          QZSS 194 GOOD 00000007
<          GLONASS 18-3 GOOD 00000003
<          GLONASS 2-4 GOOD 00000003
<          GLONASS 15 GOOD 00000003
<          GLONASS 1+1 GOOD 00000003
<          GLONASS 24+2 GOOD 00000003
<          GLONASS 23+3 GOOD 00000001
<          GLONASS 17+4 GOOD 00000003
<          GLONASS 8+6 GOOD 00000003
<          GALILEO 15 GOOD 0000000f
<          GALILEO 27 GOOD 0000000f
<          GALILEO 3 GOOD 0000000f
<          GALILEO 36 GOOD 0000000f
<          GALILEO 5 GOOD 0000000f
<          GALILEO 21 GOOD 0000000f
<          GALILEO 30 GOOD 0000000f
<          GALILEO 9 GOOD 0000000f
<          BEIDOU 28 GOOD 0000001d
<          BEIDOU 33 GOOD 0000001d
<          BEIDOU 42 GOOD 0000001d
<          BEIDOU 27 GOOD 0000001d
<          BEIDOU 43 GOOD 0000001d
<          BEIDOU 41 GOOD 0000001d
<          BEIDOU 40 GOOD 0000001d
<          BEIDOU 11 GOOD 00000005
<          BEIDOU 14 GOOD 00000005
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MATCHEDSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	system	See *Table 145: Satellite system* on page 676	Enum	4	H+4
4	Satellite ID	Satellite identifier	Ulong	4	H+8
5	Status	Satellite status (*Table 101: Observation statuses* on page 536)	Enum	4	H+12
6	Signal mask	See *Table 102: GPS signal mask* on page 537, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *Table 106: QZSS signal mask* on page 538 and *Table 107: NavIC signal mask* on page 538	Hex	4	H+16
7	Next satellite offset = H + 4 + (#sat x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	1	H+4+ (#sat x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.110 MATCHEDXYZ

Matched RTK Cartesian position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the receiver's matched position in ECEF coordinates. It represents positions that have been computed from time matched base and rover observations. There is no base station extrapolation error on these positions because they are based on buffered measurements, that is, they lag real time, by some amount, depending on the latency of the data link. If the rover receiver has not been enabled to accept RTK differential data or is not actually receiving data leading to a valid solution, this is reflected by the code shown in field #2 (solution status) and #3 (position type). See *Figure 13: WGS84 ECEF coordinate system* on page 547 for a definition of the ECEF coordinates.

This log provides the best accuracy in static operation. For lower latency in kinematic operation, see the **BESTXYZ** log (see page 545) or **RTKXYZ** log (see page 910). The data in the logs changes only when a base observation (RTCMv3) changes.

The time stamp in the header is the time of the matched observations that the computed position is based on and not the current time.



The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command (see page 284).

Message ID: 242

Log type: Asynch

Recommended input:

```
log matchedxyza onchanged
```



Asynchronous logs, such as MATCHEDXYZ, should only be logged ONCHANGED otherwise the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

ASCII example:

```
#MATCHEDXYZA,USB1,0,66.5,FINESTEERING,2211,233514.000,02000020,1d7b,16809;
SOL_COMPUTED,NARROW_INT,-1632848.2280,-3662159.5450,4944902.5909,0.0070,
0.0077,0.0104,"K250",36,16,16,15,0,01,00,33*e2f7457b
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MATCHEDXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	P-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	P-X	Position X-coordinate (m)	Double	8	H+8
5	P-Y	Position Y-coordinate (m)	Double	8	H+16
6	P-Z	Position Z-coordinate (m)	Double	8	H+24
7	P-X σ	Standard deviation of P-X (m)	Float	4	H+32
8	P-Y σ	Standard deviation of P-Y (m)	Float	4	H+36
9	P-Z σ	Standard deviation of P-Z (m)	Float	4	H+40
10	stn ID	Base station ID	Char[4]	4	H+44
11	#SVs	Number of satellites tracked	Uchar	1	H+48
12	#solnSVs	Number of satellites used in solution	Uchar	1	H+49
13	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+50
14	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+51
15	Reserved		Char	1	H+52
16	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+53
17	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+54
18	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+55
19	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+56
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.111 MODELFEATURES

States features available for current loaded model

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **MODELFEATURES** log states the features available for the current active model.



See the **VERSION** log on page 1023 or the **DISPATCHSCHEDULE** log on page 571 for the currently active model.

To see which satellite systems are available for the current model, use the **CHANCONFIGLIST** log (see page 550).

Most features have a boolean state: authorized or unauthorized. However, some have more complex licensed states with varying degrees of capability.



For descriptions of receiver features, software models and subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.



This log is best viewed in Abbreviated ASCII.

Message ID: 1329

Log type: Polled

Recommended input:

```
log modelfeatures once
```

Abbreviated ASCII example:

```
<MODELFEATURES USB1 0 53.5 FINESTEERING 2209 508953.938 12000020 141a 16809
<     26
<          100HZ MAX_MSR_RATE
<          100HZ MAX_POS_RATE
<          SINGLE ANTENNA
<          COMMERCIAL_MEMS IMU
<          STANDARD INS
<          AUTHORIZED MEAS_OUTPUT
<          AUTHORIZED DGPS_TX
<          AUTHORIZED RTK_TX
<          AUTHORIZED RTK_FLOAT
<          AUTHORIZED RTK_FIXED
<          AUTHORIZED PPP
<          AUTHORIZED LOW_END_POSITIONING
<          AUTHORIZED RAIM
<          AUTHORIZED INTERFERENCE_MITIGATION
<          AUTHORIZED NTRIP
```

```
<           AUTHORIZED INS_PLUS_PROFILES
<           AUTHORIZED HEAVE
<           AUTHORIZED DEBUG
<           UNAUTHORIZED ALIGN_HEADING
<           UNAUTHORIZED ALIGN_RELATIVE_POS
<           UNAUTHORIZED API
<           UNAUTHORIZED SPRINKLER
<           UNAUTHORIZED RTKASSIST
<           UNAUTHORIZED SCINTILLATION
<           UNAUTHORIZED GENERIC_IMU
<           UNAUTHORIZED RELATIVE_INS
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MODELFEATURES header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# Feature	Number of features in list	Ulong	4	H
3	Feature Status	Licensing status of feature See *Table 161: Feature status* below	Enum	4	H+4
4	Feature Type	Type of feature See *Table 162: Feature type* on the next page	Enum	4	H+8
5...	Next feature = H+4+(# Feature x 8)				
6	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+(# Feature x 8)
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 161: Feature status

Value	Name	Description
0	AUTHORIZED	The feature is authorized
1	UNAUTHORIZED	The feature is unauthorized
2	0Hz	Disables output of POS logs
6	20Hz	Maximum logging rate for POS or MSR logs is 20 Hz
8	100Hz	Maximum logging rate for POS or MSR logs is 100 Hz
9	RATE_INVALID	Option bits don't correspond to a valid rate
15	STANDARD	SPAN Standard Model
20	COMMERCIAL_MEMS	IMU Grade-Commercial MEMS
21	TACTICAL	IMU Grade-Tactical

Value	Name	Description
22	HIGH_GRADE_TACTICAL	IMU Grade-High Grade Tactical
23	NAVIGATION	IMU Grade-Navigation
25	SINGLE	Single antenna
26	DUAL	Dual antennas
30	LITE	SPAN Lite Model
33	CONSUMER_MEMS	IMU Grade-Consumer MEMS
37	RADIO_TX	External Radio Control
38	GLIDE	GLIDE
39	TILT	Terrain compensation

Table 162: Feature type

Value	Name	Description
0	MAX_MSR_RATE	Maximum measurement logging rate
1	MAX_POS_RATE	Maximum position logging rate
3	MEAS_OUTPUT	Output of raw measurements (phase and pseudorange)
4	DGPS_TX	Transmission of DGPS (non RTK) corrections
5	RTK_TX	Transmission of RTK corrections
6	RTK_FLOAT	RTK float positioning
7	RTK_FIXED	RTK fixed positioning
8	RAIM	Extended RAIM
9	LOW_END_ POSITIONING	GLIDE and TerraStar-L positioning
10	ALIGN_HEADING	Heading
11	ALIGN_RELATIVE_ POS	Heading and Relative Positioning
12	API	Lua Scripted User Interface (formerly User Application API)
15	NTRIP	NTRIP Server/Client
16	HIGH_SPEED	Enables receiver to operate faster than 1000 nautical miles per hour.
19	PPP	TerraStar-C PRO or TerraStar-X positioning
20	SCINTILLATION	Scintillation
22	INS	Inertial (SPAN)
23	IMU	IMU Grade

Value	Name	Description
26	INTERFERENCE_ MITIGATION	Interference Mitigation
28	ANTENNA	Number of antennas enabled on the receiver
29	GENERIC_IMU	SPAN Generic IMU Interface
30	INS_PLUS_PROFILES	SPAN Plus Profiles
31	HEAVE	SPAN Heave Option
32	RELATIVE_INS	SPAN Relative INS
33	PRODUCT_FEATURE	Additional product feature has been authorized. See the **Feature Status** field for details.
34	SPRINKLER	Sprinkler
35	TILT	Terrain compensation
999	MODEL_INVALID	If a bad model is loaded, MODELFEATURES will contain one entry: MODEL_ INVALID STATUS_INVALID

3.112 NAVICALMANAC

Decoded NavIC almanac

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log contains the decoded NavIC almanac parameters from NavIC navigation messages. Multiple messages are transmitted, one for each satellite ID with data.

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

Message ID: 2122

Log type: Asynch

Recommended input:

```
log navicalmanaca onchanged
```

ASCII example:

```
#NAVICALMANACA,COM1,4,69.5,SATTIME,1943,158160.000,02000020,fb6e,32768;919,
0.001982212,86400,0.075264303,8.457495146e-10,6493.383789062,1.327344662,
2.996060720,2.542881375,-0.000580788,7.275957614e-12,6,0,0,5*05cfbc62

#NAVICALMANACA,COM1,3,69.5,SATTIME,1943,156276.000,02000020,fb6e,32768;919,
0.001962662,0,0.509411950,2.742971399e-10,6493.538574219,1.844826864,
3.107479183,-3.001633760,-0.000161171,-5.093170330e-11,4,0,0,7*8fbd9e3a

#NAVICALMANACA,COM1,2,69.5,SATTIME,1943,158148.000,02000020,fb6e,32768;919,
0.001979351,86400,0.499982612,2.400099974e-10,6493.359375000,-1.300198895,
-3.061969089,0.047002130,0.000025749,-3.637978807e-12,5,0,0,5*be12ffa2

#NAVICALMANACA,COM1,1,69.5,SATTIME,1943,157620.000,02000020,fb6e,32768;919,
0.001854897,86400,0.509561753,1.371485699e-10,6493.388671875,1.842267109,
3.032190537,2.385950946,0.000114441,-5.456968211e-11,2,0,0,5*b64cf69c

#NAVICALMANACA,COM1,0,69.5,SATTIME,1943,156804.000,02000020,fb6e,32768;919,
0.000161171,86400,0.076541746,1.142904749e-09,6493.613281250,1.349937548,
0.783248119,0.142653098,0.000204086,-8.003553376e-11,7,0,0,7*495808b9
```

The speed at which the receiver locates and locks onto new satellites is improved if the receiver has approximate time and position (**SETAPPROXTIME** and **SETAPPROXPOS**), as well as an almanac. This allows the receiver to compute the elevation of each satellite so it can tell which satellites are visible and their Doppler offsets, improving Time to First Fix (TTFF).

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	NAVICALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	WNa	Week number for the almanac since the NavIC system time start epoch (August 22nd 1999)	Ulong	4	H
3	Ecc	Eccentricity (dimensionless)	Double	8	H+4
4	Toa	Time of Almanac (s)	Ulong	4	H+12
5	I0	Inclination angle (radians)	Double	8	H+16
6	OmegaDot	Rate of RAAN (radians/s)	Double	8	H+24
7	RootA	Square root of semi-major axis (sqrt(m))	Double	8	H+32
8	Omega0	Longitude of ascending node (radians)	Double	8	H+40
9	Omega	Argument of perigee (radians)	Double	8	H+48
10	M0	Mean Anomaly (radians)	Double	8	H+56
11	Af0	Clock bias A0 (s)	Double	8	H+64
12	Af1	Clock Drift A1 (s/s)	Double	8	H+72
13	AlmSVID	PRN ID for Almanac	Ulong	4	H+80
14	InterSigCorr	Inter Signal Correction (s)	Ulong	4	H+84
15	Spare		Ulong	4	H+88
16	PRN	Transmitting Satellite Identifier	Ulong	4	H+92
17	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+96
18	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.113 NAVICEPHEMERIS

Decoded NavIC ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log contains NavIC ephemeris parameters with the appropriate scaling applied. Multiple messages are transmitted, one for each SV ephemeris collected.

Message ID: 2123

Log type: Asynch

Recommended input:

```
log navicephemerisa onall
```

ASCII example:

```
#NAVICEPHEMERISA,COM1,5,74.0,SATTIME,1943,255984.000,02000020,01fa,32768;2,919,
1.05838757e-04,-5.63886715e-11,0.00000000,0,252000,-1.86e-09,3.2829938927e-09,
11,0,0,0,1.922249794e-06,1.032650471e-05,2.011656761e-07,4.097819328e-08,
-230.9375000,66.1250000,-5.239503961e-10,0,1.900019163,252000,1.8492219970e-03,
6493.385761,1.842761896e+00,3.027013584,-2.94012247e-09,5.0965660552e-01,
0,0,0*d2f4c9a5

#NAVICEPHEMERISA,COM1,4,74.0,SATTIME,1943,255984.000,02000020,01fa,32768;6,919,
-5.79587650e-04,1.02318154e-11,0.00000000,1,252000,-1.86e-09,8.5817860373e-09,
11,0,0,0,-1.282989979e-05,2.417713404e-06,1.974403858e-07,2.644956112e-07,
-83.3125000,-395.3125000,-5.535944880e-10,0,2.050709297,252000,
1.9699299010e-03,6493.408867,1.328589850e+00,2.996532035,-7.66746224e-09,
7.5298187077e-02,0,0,0*50cdb388

...

#NAVICEPHEMERISA,COM1,0,74.0,SATTIME,1943,255984.000,02000020,01fa,32768;7,919,
1.90386083e-04,-8.28777047e-11,0.00000000,1,255024,-1.40e-09,6.3988379659e-09,
252,0,0,0,-8.992850780e-06,-1.732259989e-06,-9.313225746e-08,-2.235174179e-08,
60.1250000,-266.1875000,-3.928735076e-10,0,-0.445949980,255024,
2.4348858278e-04,6493.269802,1.351327715e+00,1.099632488,-5.54308803e-09,
7.6573741924e-02,0,0,0*01bf330e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	NAVICEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	PRN	Satellite Identifier	Ulong	4	H
3	WN	Week number since the NavIC system time start epoch (August 22nd 1999)	Ulong	4	H+4
4	Af0	Clock bias (s)	Double	8	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	Af1	Clock drift (s/s)	Double	8	H+16
6	Af2	Clock drift rate (s/s^2)	Double	8	H+24
7	URA	SV Accuracy	Ulong	4	H+32
8	toc	Reference time for the satellite clock corrections (s)	Ulong	4	H+36
9	TGD	Total group delay (s)	Double	8	H+40
10	DeltaN	Mean motion difference (radian/s)	Double	8	H+48
11	IODEC	Issue of data ephemeris and clock	Ulong	4	H+56
12	Reserved		Ulong	4	H+60
13	L5 Health	Health status of navigation data on L5 SPS signal 0=OK; 1=bad	Ulong	4	H+64
14	S Health	Health status of navigation data on S SPS signal 0=OK; 1=bad	Ulong	4	H+68
15	Cuc	Amplitude of the cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+72
16	Cus	Amplitude of the sine harmonic correction term to the argument of latitude (radians)	Double	8	H+80
17	Cic	Amplitude of the cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+88
18	Cis	Amplitude of the sine harmonic correction term to the angle of inclination (radians)	Double	8	H+96
19	Crc	Amplitude of the cosine harmonic correction term to the orbit radius (m)	Double	8	H+104
20	Crs	Amplitude of the sine harmonic correction term to the orbit radius (m)	Double	8	H+112
21	IDOT	Rate of inclination angle (radians/s)	Double	8	H+120
22	Spare		Ulong	4	H+128
23	M0	Mean anomaly (radians)	Double	8	H+132
24	toe	Time of ephemeris (s)	Ulong	4	H+140
25	Ecc	Eccentricity (dimensionless)	Double	8	H+144
26	RootA	Square root of semi-major axis (sqrt(m))	Double	8	H+152
27	Omega0	Longitude of ascending node (radians)	Double	8	H+160
28	Omega	Argument of perigee (radians)	Double	8	H+168

Field	Field type	Description	Format	Binary bytes	Binary offset
29	OmegaDot	Rate of RAAN (radians/s)	Double	8	H+176
30	I0	Inclination angle (radians)	Double	8	H+184
31	Spare		Ulong	4	H+192
32	Alert flag	The utilization of navigation data shall be at the users' own risk. 1=Alert; 0=OK	Ulong	4	H+196
33	AutoNav flag	When set to 1, satellite is in AutoNav mode. Satellite broadcasts primary navigation parameters from AutoNav data sets with no uplink from ground for maximum of 7 days	Ulong	4	H+200
34	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+204
35	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.114 NAVICIONO

NavIC ionospheric coefficients parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log contains NavIC ionospheric coefficients parameters. Ionospheric error correction for single frequency (L5) users of the NavIC are provided through a set of eight coefficients. The correction coefficients are:

- 4 Alpha Coefficients (αn; n=0,1,2,3)

  These are the coefficients of the cubic polynomial representing the amplitude of the positive cosine curve in the cosine model approximation of ionospheric delay.

- 4 Beta Coefficients (βn; n=0,1,2,3)

  These are the coefficients of the cubic polynomial representing the period of the positive cosine curve in the cosine model approximation of ionospheric delay.

Message ID: 2124

Log type: Asynch

Recommended input:

```
log navicionoa onchanged
```

ASCII example:

```
#NAVICIONOA,COM1,0,92.5,SATTIME,1944,166272.000,02000020,56c0,32768;
5,2.980232238769531e-08,3.874301910400390e-07,-2.562999725341796e-06,
-7.510185241699216e-06,558.0,168.0,-2286.0,2286.0,0*2b250bbd
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	NAVICIONO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	PRN	Satellite Identifier of the transmitting NavIC SV	Ulong	4	H
3	Alpha 0	Alpha parameter constant term	Double	8	H+4
4	Alpha 1	Alpha parameter 1st order term	Double	8	H+12
5	Alpha 2	Alpha parameter 2nd order term	Double	8	H+20
6	Alpha 3	Alpha parameter 3rd order term	Double	8	H+28
7	Beta 0	Beta parameter constant term	Double	8	H+36
8	Beta 1	Beta parameter 1st order term	Double	8	H+44
9	Beta 2	Beta parameter 2nd order term	Double	8	H+52
10	Beta 3	Beta parameter 3rd order term	Double	8	H+60
11	Spare		Ulong	4	H+68

Field	Field type	Description	Format	Binary bytes	Binary offset
12	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.115 NAVICRAWSUBFRAME

Raw NavIC subframe data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log contains the raw NavIC subframe data with parity bits removed. Only subframes that have passed the parity check are output.

Message ID: 2105

Log type: Asynch

Recommended input:

```
log navicrawsubframea onchanged
```

ASCII example:

```
#NAVICRAWSUBFRAMEA,COM1,0,72.5,SATTIME,1943,159168.000,02000020,76af,32768;182,
7,1,8b19e883971a005bf4880009ab3f400eac0af84f7541befff78018e6d7e1dfacd1*88c2ba19

#NAVICRAWSUBFRAMEA,COM1,0,72.5,SATTIME,1943,159168.000,02000020,76af,32768;177,
2,1,8b19e883970e8fc3f8500009ab3f00087f0af8415e4232800f7fd9eb8650b7b630*c7e27e82

#NAVICRAWSUBFRAMEA,COM1,0,72.5,SATTIME,1943,159168.000,02000020,76af,32768;181,
6,1,8b19e88397b3e73401600009ab3f0012370af84f550327c032800ad1d9da339260*0bb7b256

#NAVICRAWSUBFRAMEA,COM1,0,72.5,SATTIME,1943,159168.000,02000020,76af,32768;180,
5,1,8b19e88397036703ff1c0049ab3fc009b10af84fe7e3773ffd7fd6d8f5fddc4181*f42f59ab
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	NAVICRAWSUBFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Signal channel	Signal channel providing the data	Ulong	4	H
3	PRN	Satellite Identifier of transmitting NavIC SV	Ulong	4	H+4
4	Subframe Id	Subframe ID	Ulong	4	H+8
5	Raw subframe data	Raw subframe data (262 bits). Does not include CRC or Tail bits	Hex[33]	33	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+45
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.116 NAVICSYSCLOCK

NavIC clock parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

This log provides the NavIC system time offset with respect to UTC, UTC (NPLI) and other GNSS times such as GPS, GALILEO, GLONASS.

Message ID: 2125

Log type: Asynch

Recommended input:

```
log navicsysclocka onchanged
```

ASCII example:

```
#NAVICSYSCLOCKA,COM1,0,93.0,SATTIME,1944,166320.000,02000020,3dfd,32768;7,
-7.625203579664230e-09,-1.598721155460225e-14,0.000000000000000e+00,18,32508,
920,905,7,18,2,2.149608917534351e-07,-5.151434834260726e-14,
-1.998997755520149e-19,32508,920,0*f6617e67
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	NAVICSYSCLOCK header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	Satellite Identifier of the transmitting NavIC SV	Ulong	4	H
3	$A0_{utc}$	Bias coefficient of the NavIC time scale relative to the UTC time scale (s)	Double	8	H+4
4	$A1_{utc}$	Drift coefficient of the NavIC time scale relative to the UTC time scale (s/s)	Double	8	H+12
5	$A2_{utc}$	Drift rate coefficient of the NavIC time scale relative to the UTC time scale (s/s^2)	Double	8	H+20
6	Δt_{LS}	Current or past leap second count (s)	Long	4	H+28
7	T_{outc}	Time data reference time of week (s)	Ulong	4	H+32
8	WN_{outc}	Time data reference week number (0-1023)	Ulong	4	H+36
9	WN_{LSF}	Leap second reference week number (0-1023)	Ulong	4	H+40
10	DN	Leap second reference day number	Ulong	4	H+44
11	Δt_{LSF}	Current or future leap second count (s)	Long	4	H+48
12	GNSSID	Timescale for the time offsets with respect to NavIC (*Table 163: GNSS time scales* on the next page)	Ulong	4	H+52

Field	Field type	Description	Format	Binary bytes	Binary offset
13	A0	Bias coefficient of the NavIC time scale relative to the GNSS time scale (s)	Double	8	H+56
14	A1	Drift coefficient of the NavIC time scale relative to the GNSS time scale (s/s)	Double	8	H+64
15	A2	Drift rate correction coefficient of the NavIC time scale relative to the GNSS time scale (s/s^2)	Double	8	H+72
16	Tot	Time data reference time of week (s)	Ulong	4	H+80
17	WN_{ot}	Time data reference week number (0-1023)	Ulong	4	H+84
18	Spare		Ulong	4	H+88
19	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+92
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 163: GNSS time scales

GNSS ID	Time scale
0	GPS
1	GALILEO
2	GLONASS
3-6	Reserved
7	UTC (NPLI)

3.117 NAVIGATE

User navigation data


Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the status of the waypoint navigation progress. It is used in conjunction with the **SETNAV** command (see page 401).

See the figure below for an illustration of navigation parameters.

The SETNAV command (see page 401) must be enabled before valid data will be reported from this log.

Figure 14: Navigation parameters



Reference	Description
1	TO lat-lon
2	X-Track perpendicular reference point
3	Current GPS position
4	A-Track perpendicular reference point
5	X-Track (cross track)
6	A-Track (along track)
7	Distance and bearing from 3 to 1

Message ID: 161

Log type: Sync

Recommended input:

```
log navigatea ontime 1
```

ASCII example:

```
#NAVIGATEA,USB1,0,48.0,FINESTEERING,2209,509171.000,12000020,aece,16809;
SOL_COMPUTED,PPP,SOL_COMPUTED,NOVELOCITY,8567.8503,279.156559,-3362.2613,
8005.7921,9999,0.000*1c71003c
```

Use the **NAVIGATE** log in conjunction with the **SETNAV** command (see page 401) to tell you where you currently are with relation to known To and From points. You can find a specific latitude, longitude or height knowing from where you started. For example, a backpacker could use these two commands to program a user supplied graphical display, on a digital GPS compass, to show their progress as they follow a defined route.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	NAVIGATE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	vel status	Velocity status, see *Table 95: Solution status* on page 530	Enum	4	H+8
5	nav type	Navigation data type (see *Table 164: Navigation data type* on the next page)	Enum	4	H+12
6	distance	Straight line horizontal distance from current position to the destination waypoint, in metres (see *Figure 14: Navigation parameters* on the previous page). This value is positive when approaching the waypoint and becomes negative on passing the waypoint.	Double	8	H+16
7	bearing	Direction from the current position to the destination waypoint, in degrees, with respect to True North (or magnetic if corrected for magnetic variation by the **MAGVAR** command on page 259).	Double	8	H+24
8	along track	Horizontal track distance from the current position to the closest point on the waypoint arrival perpendicular; expressed in metres. This value is positive when approaching the waypoint and becomes negative on passing the waypoint.	Double	8	H+32

Field	Field type	Description	Format	Binary bytes	Binary offset
9	xtrack	The horizontal distance (perpendicular track error), from the vessel's present position to the closest point on the great circle line, that joins the FROM and TO waypoints. If a "track offset" has been entered in the **SETNAV** command (see page 401), xtrack is the perpendicular error from the "offset track". Xtrack is expressed in metres. Positive values indicate the current position is right of the Track, while negative offset values indicate left.	Double	8	H+40
10	eta week	Estimated GPS reference week number at time of arrival at the "TO" waypoint, along track arrival perpendicular based on current position and speed, in units of GPS reference weeks. If the receiving antenna is moving at a speed of less than 0.1 m/s, in the direction of the destination, the value in this field is "9999".	Ulong	4	H+48
11	eta secs	Estimated GPS seconds into week at time of arrival at destination waypoint along track arrival perpendicular, based on current position and speed, in units of GPS seconds into the week. If the receiving antenna is moving at a speed of less than 0.1 m/s in the direction of the destination, the value in this field is "0.000".	Double	8	H+52
12	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+60
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 164: Navigation data type

Binary	ASCII	Description
0	GOOD	Navigation is good
1	NOVELOCITY	Navigation has no velocity
2	BADNAV	Navigation calculation failed for an unknown reason
3	FROM_TO_SAME	“From” is too close to “To” for computation
4	TOO_CLOSE_TO_TO	Position is too close to “To” for computation
5	ANTIPODAL_WAYPTS	Waypoints are antipodal on surface

3.118 NMEA standard logs

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains NMEA logs.

GLMLA	**GLONASS Almanac Data**
GPALM	**Almanac Data**
GPGGA	**Global Position System Fix Data and Undulation**
GPGGALONG	**GPS Fix Data, Extra Precision and Undulation**
GPGLL	**Geographic Position**
GPGRS	**GPS Range Residuals for Each Satellite**
GPGSA	**GPS DOP on Active Satellites**
GPGST	**Estimated Error in Position Solution**
GPGSV	**GPS Satellites in View**
GPHDT	**NMEA Heading Log (ALIGN)**
GPRMB	**Navigation Information**
GPRMC	**GPS Specific Information**
GPVTG	**Track Made Good and Ground Speed**
GPZDA	**UTC Time and Date**

The NMEA log structures follow format standards as adopted by the National Marine Electronics Association. The reference document used is "Standard For Interfacing Marine Electronic Devices NMEA 0183 Version 3.01". For further information, refer to www.nmea.org. The following table contains excerpts from Table 6 of the NMEA Standard which defines the variables for the NMEA logs. The actual format for each parameter is indicated after the description.



See the Note in the **GPGGA** log (see page 635) that applies to all NMEA logs.



1. Spaces may only be used in variable text fields.
2. A negative sign "-" (HEX 2D) is the first character in a Field if the value is negative. The sign is omitted if the value is positive.
3. All data fields are delimited by a comma (,).
4. Null fields are indicated by no data between two commas (,,). Null fields indicate invalid data or no data available.
5. The NMEA Standard requires that message length be limited to 82 characters.

Field type	Symbol	Definition
Special format fields		

Field type	Symbol	Definition
Status	A	Single character field: A = Yes, Data Valid, Warning Flag Clear V = No, Data Invalid, Warning Flag Set
Latitude	llll.ll	Fixed/Variable length field: degrees|minutes.decimal - 2 fixed digits of degrees, 2 fixed digits of mins and a *variable* number of digits for decimal-fraction of minutes. Leading zeros always included for degrees and minutes to maintain fixed length. The decimal point and associated decimal-fraction are optional if full resolution is not required
Longitude	yyyyy.yy	Fixed/Variable length field: degrees|minutes.decimal - 3 fixed digits of degrees, 2 fixed digits of minutes and a *variable* number of digits for decimal-fraction of minutes. Leading zeros always included for degrees and minutes to maintain fixed length. The decimal point and associated decimal-fraction are optional if full resolution is not required
Time	hhmmss.ss	Fixed/Variable length field: hours|minutes|seconds.decimal - 2 fixed digits of hours, 2 fixed digits of minutes, 2 fixed digits of seconds and *variable* number of digits for decimal-fraction of seconds. Leading zeros always included for hours, minutes and seconds to maintain fixed length. The decimal point and associated decimal-fraction are optional if full resolution is not required.
Defined field		Some fields are specified to contain predefined constants, most often alpha characters. Such a field is indicated in this standard by the presence of one or more valid characters. Excluded from the list of allowable characters are the following which are used to indicate field types within this standard: "A", "a", "c", "hh", "hhmmss.ss", "llll.ll", "x", "yyyyy.yy"
Numeric value fields		
Variable numbers	x.x	Variable length integer or floating numeric field. Optional leading and trailing zeros. The decimal point and associated decimal-fraction are optional if full resolution is not required (example: 73.10 = 73.1 = 073.1 = 73)
Fixed HEX field	hh___	Fixed length HEX numbers only, MSB on the left
Information fields		
Variable text	c--c	Variable length valid character field
Fixed alpha field	aa___	Fixed length field of uppercase or lowercase alpha characters
Fixed number field	xx___	Fixed length field of numeric characters
Fixed text field	cc___	Fixed length field of valid characters

3.119 NOVATELXOBS

NovAtel proprietary RTK correction

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

NOVATELX is a combined observation and reference station message used to transmit RTK corrections. This is a proprietary message and supports sending data for all systems.

Message ID: 1618

Log type: Synch

Recommended input:

```
log com2 novatelxobs ontime 1
```

To calculate the size of the NOVATELXOBS messages, use the following formula.

Size = 168 + s * (6 + p * (54 + f*33))

where:

s = number of systems (maximum 8)

p = number of PRN per system (maximum 64)

f = number of signals data per PRN – 1 (maximum 10 signals possible)

Example size calculations:

- For 2 systems (GPS and GLONASS), 12 PRN per system, and 2 signals per satellite (L1CA, L2PY)

  Size = 168 + 2 * (6 + 12 * (54 + 33))
  = 2268 bits per second
  = 284 bytes + NovAtelXHeader (8 bytes)

- For 3 systems (GPS, BEIDOU and GLONASS), 12 PRN per system, and 2 signals per satellite (L1CA, L2PY)

  Size = 168 + 3 * (6 + 12 * (54 + 33))
  = 3318 bits per second
  = 415 bytes + NovAtelXHeader (8 bytes)

- For 3 systems (GPS, BEIDOU and GLONASS), 12 PRN per system, and 3 signals per satellite (L1CA, L2PY, L2C)

  Size = 168 + 3 * (6 + 12 * (54 + 2*33))
  = 4506 bits per second
  = 564 bytes + NovAtelXHeader (8 bytes)

3.120 NOVATELXREF

NovAtel proprietary reference station message for use in ALIGN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

NOVATELXREF is a proprietary extended reference station message for use in ALIGN configurations only. This message enables the output of the **MASTERPOS** log (see page 726), **ROVERPOS** log (see page 889) and **ALIGNBSLNENU** log (see page 491) on the rover.

Message ID: 1620

Log type: Synch

Recommended input:

```
log com2 novatelxref ontime 1
```

3.121 OCEANIXINFO

Oceanix subscription information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains details on any currently active Oceanix subscription.



See the **DISPATCHSCHEDULE** log on page 571 for more detailed information about current and upcoming service periods.



For information about subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2159

Log type: Asynch

Recommended input:

```
log oceanixinfoa onchanged
```

Abbreviated ASCII example:

```
<OCEANIXINFO COM1 0 32.5 FINESTEERING 2394 495438.220 02040020 9ce8 32768
<     "TU432:3110:8989" TERM 80000002 332 2025 0 NEARSHORE
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	OCEANIXINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PAC	Product activation code	Char[16]	16	H
3	Type	Subscription type (see *Table 165: Oceanix subscription type* on the next page)	Enum	4	H+16
4	Subscription permissions	Services permitted by the subscription (see *Table 166: Oceanix subscription details mask* on the next page) Bits in the Reserved areas of this field may be set, but the Reserved bits should be ignored.	Hex	4	H+20

Field	Field type	Description	Format	Binary bytes	Binary offset
5	Service End Day	Last day of the year for which service is available. Service expires on midnight local time at the end of this day. For example, if the Service End Year and Day are 2019 and 15, respectively, then the service will expire on January 15, 2019 at 24:00 local time.	Ulong	4	H+24
6	Service End Year	Year that the subscription ends.	Ulong	4	H+28
7	Reserved		Ulong	4	H+32
8	Region restriction	For region restricted subscriptions, the type of region restriction (see *Table 167: Oceanix region restriction* below)	Enum	4	H+36
9	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+40
10	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 165: Oceanix subscription type

ASCII	Binary	Description
UNASSIGNED	0	No Oceanix service is active.
TERM	1	Active service period includes Oceanix service.
MODEL	5	Reserved

Table 166: Oceanix subscription details mask

Bit	Mask	Description
0	0x00000001	Reserved
1	0x00000002	Oceanix H service
2-31	0xFFFFFFFC	Reserved

Table 167: Oceanix region restriction

ASCII	Binary	Description
NONE	0	Oceanix operation has no region restrictions
GEOGATED	1	Oceanix operation is limited to on land regions. GEOGATED is also the default value reported if there is no subscription
NEARSHORE	3	Oceanix operation is limited to on land and near shore (coastal) regions

3.122 OCEANIXSTATUS

Oceanix decoder and subscription status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains status information for the Oceanix decoder and subscription.



See the **DISPATCHSCHEDULE** log on page 571 for more detailed information on current and upcoming service periods.



For information about subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2160

Log type: Asynch

Recommended input:

```
log oceanixstatusa onchanged
```

Abbreviated ASCII example:

```
<OCEANIXSTATUS COM1 0 32.5 FINESTEERING 2394 495438.220 02040020 049a 32768
<     ENABLE LOCKED UNKNOWN
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	OCEANIXSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Access	Access status. ENABLE (1) if the subscription is valid. DISABLE (0) otherwise.	Enum	4	H
3	Sync state	Decoder data synchronization state (see *Table 168: Decoder data synchronization state* on the next page)	Enum	4	H+4
4	Region restriction status	Region restriction status (see *Table 169: Region restriction status* on the next page)	Enum	4	H+8
5	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+12
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 168: Decoder data synchronization state

Binary	ASCII	Description
0	NO_SIGNAL	None of the decoders have received data in the last 30 seconds.
1	SEARCH	At least one decoder is receiving data and is searching for the format.
2	LOCKED	At least one decoder has locked onto the format.

Table 169: Region restriction status

ASCII	Binary	Description
UNKNOWN	0	Region restriction status cannot be determined.
IN_REGION	1	Receiver is within the permitted region.
OUT_OF_REGION	2	Receiver is outside the permitted region.

3.123 PASSCOM, PASSAUX, PASSUSB, PASSICOM, PASSNCOM

Redirects data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The pass-through logging feature enables the receiver to redirect any ASCII or binary data, input at a specified port, to any specified receiver port. It allows the receiver to perform bi-directional communications with other devices such as a modem, terminal or another receiver. See also the **INTERFACEMODE** command on page 217.

There are many pass through logs: PASSCOM1, PASSCOM2, PASSCOM3, PASSCOM4, PASSCOM5, PASSCOM6, PASSAUX, PASSICOM1, PASSICOM2, PASSICOM3, PASSICOM4, PASSICOM5, PASSICOM6, PASSICOM7, PASSNCOM1, PASSNCOM2, PASSNCOM3 allow for redirection of data that is arriving at COM1, COM2, COM3, virtual COM1, virtual COM2 or AUX. PASSCOM4 and PASSCOM5 are only available on OEM7600, OEM7700 and OEM7720 receivers. The AUX port is available on some products. PASSUSB1, PASSUSB2, PASSUSB3 are used to redirect data from USB1, USB2 or USB3.

A pass through log is initiated the same as any other log, that is, log [to-port] [data-type] [trigger]. However, pass-through can be more clearly specified as: log [to-port] [from-port-AB] [onchanged]. Now, the [from-port-AB] field designates the port which accepts data (that is, COM1, COM2, COM3, COM4, COM5, COM6, AUX, USB1, USB2 or USB3) as well as the format in which the data is logged by the [to-port] (A for ASCII or B for Binary).



To pass through data arriving on all ports, use the **PASSTHROUGH** log (see page 764).

When the [from-port-AB] field is suffixed with an [A], all data received by that port is redirected to the [to-port] in ASCII format and logs according to standard NovAtel ASCII format. Therefore, all incoming ASCII data is redirected and output as ASCII data. However, any binary data received is converted to a form of ASCII hexadecimal before it is logged.

When the [from-port-AB] field is suffixed with a [B], all data received by that port is redirected to the [to-port] exactly as it is received. The log header and time tag adhere to standard NovAtel Binary format followed by the pass through data as it was received (ASCII or binary).

Pass through logs are best utilized by setting the [trigger] field as onchanged or onnew.

If the data being injected is ASCII, then the data is grouped together with the following rules:

- blocks of 80 characters
- any block of characters ending in a <CR>
- any block of characters ending in a <LF>
- any block remaining in the receiver code when a timeout occurs (100 ms)

If the data being injected is binary or the port INTERFACEMODE mode is set to GENERIC, then the data is grouped as follows:

- blocks of 80 bytes
- any block remaining in the receiver code when a timeout occurs (100 ms)

If a binary value is encountered in an ASCII output, then the byte is output as a hexadecimal byte preceded by a backslash and an x. For example 0A is output as \x0A. An actual '\' in the data is output as \\. The output counts as one pass through byte although it is four characters.

The first character of each pass-through record is time tagged in GPS reference weeks and seconds.

PASSAUX	**Message ID: 690**
PASSCCOM1	**Message ID: 1893**
PASSCCOM2	**Message ID: 1894**
PASSCCOM3	**Message ID: 1895**
PASSCCOM4	**Message ID: 1930**
PASSCCOM5	**Message ID: 1937**
PASSCCOM6	**Message ID: 1938**
PASSCOM1	**Message ID: 233**
PASSCOM2	**Message ID: 234**
PASSCOM3	**Message ID: 235**
PASSCOM4	**Message ID: 1384**
PASSCOM5	**Message ID: 1576**
PASSCOM6	**Message ID: 1577**
PASSCOM7	**Message ID: 1701**
PASSCOM8	**Message ID: 1702**
PASSCOM9	**Message ID: 1703**
PASSCOM10	**Message ID: 1704**
PASSICOM1	**Message ID: 1250**
PASSICOM2	**Message ID: 1251**
PASSICOM3	**Message ID: 1252**
PASSICOM4	**Message ID: 1385**
PASSICOM5	**Message ID: 2119**
PASSICOM6	**Message ID: 2120**
PASSICOM7	**Message ID: 2121**
PASSNCOM1	**Message ID: 1253**
PASSNCOM2	**Message ID: 1254**
PASSNCOM3	**Message ID: 1255**
PASSUSB1	**Message ID: 607**
PASSUSB2	**Message ID: 608**
PASSUSB3	**Message ID: 609**

Log type: Asynch

Recommended input:

```
log passcom1a onchanged
```



Asynchronous logs should only be logged ONCHANGED or ONNEW, otherwise the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

ASCII example 1:

```
#PASSCOM2A,COM1,0,59.5,FINESTEERING,1337,400920.135,02000000,2b46,1984;80,
#BESTPOSA,COM3,0,80.0,FINESTEERING,1337,400920.000,02000000,4ca6,1899;
SOL_COMPUT*f9dfab46
```


```
#PASSCOM2A,COM1,0,64.0,FINESTEERING,1337,400920.201,02000000,2b46,1984;80,ED,
SINGLE,51.11636326036,-114.03824210485,1062.6015,-16.2713,WGS84,1.8963,
1.0674*807fd3ca
#PASSCOM2A,COM1,0,53.5,FINESTEERING,1337,400920.856,02000000,2b46,1984;49,,
2.2862,"",0.000,0.000,9,9,0,0,0,0,0,0*20b24878\x0d\x0a*3eef4220
#PASSCOM1A,COM1,0,53.5,FINESTEERING,1337,400922.463,02000000,13ff,1984;17,
unlog passcom2a\x0d\x0a*ef8d2508
```

ASCII example 2:

```
#PASSUSB1A,USB1,0,41.5,FINESTEERING,2209,509394.765,12000020,4491,16809;52,\xaa
D\x12\x1c\xb2\x00\x00\xde\x14\x00\x00\x00\x00\x00\x00\x00\x00\x00\x00\x00\x
00\x00\x00\x00\x00\x00\x00\xde\x00\x00\x00\x06\x00\x00\x00Sendhxdt\x00\x00\x00\
x00\x19W\x10Z*69380120
```

For example, you could connect two OEM7 family receivers together via their COM1 ports such as in the *Figure 15: Pass through log data* below (a rover station to base station scenario). If the rover station is logging BESTPOSA data to the base station, it is possible to use the pass through logs to pass through the received BESTPOSA data to a disk file (let's call it diskfile.log) at the base station host PC hard disk.

Figure 15: Pass through log data



Under default conditions, the two receivers "chatter" back and forth with the Invalid Command Option message (due to the command interpreter in each receiver not recognizing the command prompts of the other receiver). The chattering in turn causes the accepting receiver to transmit new pass through logs with the

response data from the other receiver. To avoid the chattering problem, use the **INTERFACEMODE** command (see page 217) on the accepting port to disable error reporting from the receiving port command interpreter.

If the accepting port's error reporting is disabled by INTERFACEMODE, the BESTPOSA data record passes through and creates two records.

The reason that two records are logged from the accepting receiver is the first record was initiated by receipt of the BESTPOSA first terminator <CR>. The second record followed in response to the BESTPOSA second terminator <LF>.

Note the time interval between the first character received and the terminating <LF> can be calculated by differencing the two GPS reference time tags. This pass through feature is useful for time tagging the arrival of external messages. These messages can be any user related data. When using this feature for tagging external events, it is recommended that the rover receiver be disabled from interpreting commands so the receiver does not respond to the messages, using the **INTERFACEMODE** command (see page 217).

If the BESTPOSB binary log data is input to the accepting port (log com2 passcom1a onchanged), the BESTPOSB binary data at the accepting port is converted to a variation of ASCII hexadecimal before it is passed through to com2 port for logging.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PASSCOM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#bytes	Number of bytes to follow	Ulong	4	H
3	data	Message data	Char [80]	80	H+4
4	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#bytes)
5	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.124 PASSTHROUGH

Redirected data from all ports

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log outputs pass through data from all receiver ports. The behaviour is the same as the port specific pass though logs described in *PASSCOM, PASSAUX, PASSUSB, PASSICOM, PASSNCOM* on page 760.

Message ID: 1342

Log type: Asynch

Recommended input:

```
log passthrougha onchanged
```

ASCII example:

```
#PASSTHROUGHA,USB1,0,53.0,FINESTEERING,2209,509529.759,12000020,5fa3,16809;USB1
,52,\xaaD\x12\x1c\xb2\x00\x00\xde\x14\x00\x00\x00\x00\x00\x00\x00\x00\x00\x00\x
00\x00\x00\x00\x00\x00\x00\x00\x00\x00\xde\x00\x00\x00\x06\x00\x00\x00Sendhxdt\x00\
x00\x00\x00\x19W\x10Z*72b6022f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PASSTHROUGH header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Port	See *Table 76: COM port identifiers* on page 384	Enum	4	H
3	#bytes	Number of bytes to follow	Ulong	4	H+4
4	data	Message data	Char[80]	80	H+8
5	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+8+#bytes
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.125 PDPDATUMINFO

Datum information for the PDP position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution in the **PDPPOS** log (see page 770).

The datum message for TerraStar Correction Services is broadcast periodically. Therefore, it can take several hours, from the start of receiving TerraStar corrections, for the **PPPDATUMINFO** log to reflect the correct datum and co-ordinate epoch for the PPP position solution. Once the PPP datum is known, it will persist through a **RESET** or a power cycle. It will not persist through a **FRESET**.

Message ID: 2303

Log type: Asynch

Recommended input:

```
log pdpdatuminfoa onchanged
```

ASCII example:

```
#PDPDATUMINFOA,USB1,0,44.0,FINESTEERING,2209,510156.500,12000020,f611,16809;
"ECEF",0,2022.364,GOOD*e30218ea
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of the position being output by the **PDPPOS** log.	Char[32]	variable	H
3	epsg_code	EPSG code of datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year) Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation Status. See *Table 94: Transformation status* on page 524.	Enum	4	variable
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.126 PDPDOP

DOP values for the satellites in the PDP solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PDPDOP log contains the Dilution Of Precision (DOP) values for the satellites being used in the PDP solution. The PDP DOPs are updated every 60 seconds or whenever the satellites used in the PDP solution changes.

DOP values are a measure of the solution strength. Essentially, the DOPs reflect the geometry of the satellites used in the solution. Solutions with good counts of well-distributed satellites will have low DOPs and should be accurate and reliable. Solutions with fewer or poorly-distributed satellites will have high DOPs and be less accurate and reliable. As a rough guideline, PDOP values less than 4 imply a solution with reasonable geometry.

There can be many reasons for high DOP values. The most common reason is that there are obstructions limiting satellite visibility. Even if satellites are visible and being tracked they might still not be used in the solution if, for example, they are unhealthy or there are not corrections available for them. The **PDPSATS** log (see page 772) will inform which satellites are being tracked and explain why a tracked satellite is not used in the solution.

The DOPs do not consider that different satellites or signals will be weighted differently in the solution. Therefore, they do not completely reflect the solution quality. Ultimately, the standard deviations reported in the **PDPPOS** log (see page 770) are the best reflection of the solution accuracy.

Message ID: 1998

Log type: Asynch

Recommended input:

```
log pdpdopa onchanged
```

ASCII example:

```
#PDPDOPA,USB1,0,52.5,FINESTEERING,2209,510180.000,12000020,3bf3,16809;1.1720,
0.7320,0.4070,0.6100,0.4550,5.0,38,5,2,31,9,18,6,29,20,12,25,56,39,46,40,55,52,
38,54,36,2,30,34,4,27,15,9,25,34,23,22,44,43,42,37,11,12,9,21*1ccc85ba
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPDOP header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	gdop	Geometric dilution of precision - assumes 3D position and receiver clock offset (all 4 parameters) are unknown	Float	4	H
3	pdop	Position dilution of precision - assumes 3D position is unknown and receiver clock offset is known	Float	4	H+4
4	hdop	Horizontal dilution of precision	Float	4	H+8
5	htdop	Horizontal position and time dilution of precision	Float	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
6	tdop	GPS time dilution of precision – assumes 3D position is known and only the GPS receiver clock offset is unknown	Float	4	H+16
7	cutoff	GPS elevation cut-off angle	Float	4	H+20
8	#PRN	Number of satellites PRNs to follow	Long	4	H+24
9	PRN	PRN of a satellite used in the position solution	Ulong	4	H+28
10	Next PRN offset = H+28+(#prn x 4)				
11	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+28+(#prn x 4)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.127 PDPDOP2

DOP values for the satellites used in the PDP solution

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2

The PDPDOP2 log contains the Dilution Of Precision (DOP) values for the satellites being used in the PDP solution. This log is similar to the **PDPDOP** log (see page 766) but contains the per-system TDOPs; see the **PDPDOP** log on page 766 for more information on the DOPs.

Message ID: 1995

Log type: Asynch

Recommended input:

```
log pdpdop2a onchanged
```

ASCII example:

```
#PDPDOP2A,USB1,0,52.5,FINESTEERING,2209,510180.000,12000020,2488,16809;1.1720,
0.7320,0.4070,0.6080,4,GPS,0.4550,GLONASS,0.4650,GALILEO,0.4810,BEIDOU,0.4270
*0a9746dd
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPDOP2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	GDOP	Geometric dilution of precision - assumes 3D position and receiver clock offset (all 4 parameters) are unknown	Float	4	H
3	PDOP	Position dilution of precision - assumes 3D position is unknown and receiver clock offset is known	Float	4	H+4
4	HDOP	Horizontal dilution of precision	Float	4	H+8
5	VDOP	Vertical dilution of precision	Float	4	H+12
6	#systems	Number of systems	Ulong	4	H+16
7	system	See *Table 170: System used for timing* on the next page	Enum	4	H+20
8	TDOP	Time dilution of precision	Float	4	H+24
9	Next system offset = H+20+(#systems x 8)				
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+20+ (#systems x 8)
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 170: System used for timing

Binary	ASCII
0	GPS[1]
1	GLONASS
2	GALILEO
3	BEIDOU
4	NAVIC
99	AUTO[2]

1. GPS setting includes QZSS satellites.

2. AUTO is used only as a backup system (not available for primary system field).

3.128 PDPPOS

PDP filter position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PDPPOS log contains the receiver position computed by the receiver with the PDP filter enabled. See also the **PDPFILTER** command on page 286.

Message ID: 469

Log type: Synch

Recommended input:

```
log pdpposa ontime 1
```

ASCII example:

```
#PDPPOSA,USB1,0,52.5,FINESTEERING,2209,510261.000,12000020,0649,16809;
SOL_COMPUTED,WAAS,51.15043435551,-114.03068191005,1097.5002,-17.0000,WGS84,
0.7923,0.6986,1.3420,"131",7.000,0.000,44,40,0,0,00,86,7f,37*7dd56614
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (refer to *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (refer to *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (m)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid (m) When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	lon σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID	Char[4]	4	H+52
13	diff_age	Differential age in seconds	Float	4	H+56
14	sol_age	Solution age in seconds	Float	4	H+60
15	#sats	Number of satellites tracked	Uchar	1	H+64
16	#sats soln	Number of satellites in the solution	Uchar	1	H+65
17	Reserved		Uchar	1	H+66
18			Uchar	1	H+67
19			Hex	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.129 PDPSATS

Satellites used in PDPPOS solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the used and unused satellites for the corresponding PDPPOS solution. It also describes the signals of the used satellites and reasons for exclusions.

Message ID: 1234

Log type: Synch

Recommended input:

```
log pdpsatsa ontime 1
```

Abbreviated ASCII example:

```
<PDPSATS USB1 0 51.5 FINESTEERING 2209 510295.000 12000020 74d6 16809
<     45
<           GPS 5 GOOD 00000003
<           GPS 2 GOOD 00000003
<           GPS 31 GOOD 00000003
<           GPS 9 GOOD 00000007
<           GPS 18 GOOD 00000007
<           GPS 6 GOOD 00000007
<           GPS 29 GOOD 00000003
<           GPS 20 GOOD 00000003
<           GPS 12 GOOD 00000003
<           GPS 25 GOOD 00000007
<           QZSS 194 SUPPLEMENTARY 00000007
<           SBAS 135 NOTUSED 00000000
<           SBAS 138 NOTUSED 00000000
<           SBAS 131 NOTUSED 00000000
<           SBAS 133 NOTUSED 00000000
<           GLONASS 19+3 GOOD 00000003
<           GLONASS 2-4 GOOD 00000003
<           GLONASS 9-2 GOOD 00000003
<           GLONASS 3+5 GOOD 00000003
<           GLONASS 18-3 GOOD 00000003
<           GLONASS 15 GOOD 00000003
<           GLONASS 1+1 GOOD 00000003
<           GLONASS 17+4 GOOD 00000003
<           GALILEO 36 GOOD 0000000f
<           GALILEO 2 GOOD 0000000f
<           GALILEO 30 GOOD 0000000f
<           GALILEO 34 GOOD 0000000f
<           GALILEO 4 GOOD 0000000f
<           GALILEO 27 GOOD 0000000f
<           GALILEO 15 GOOD 0000000f
<           GALILEO 9 GOOD 0000000f
<           GALILEO 5 SUPPLEMENTARY 0000000f
<           BEIDOU 25 GOOD 0000001d
<           BEIDOU 34 GOOD 0000001d
<           BEIDOU 23 GOOD 0000001d
<           BEIDOU 22 GOOD 0000001d
```

```
<           BEIDOU 44 GOOD 0000001d
<           BEIDOU 43 GOOD 0000001d
<           BEIDOU 42 GOOD 0000001d
<           BEIDOU 28 NOEPHEMERIS 00000000
<           BEIDOU 37 GOOD 0000001d
<           BEIDOU 11 GOOD 00000007
<           BEIDOU 12 GOOD 00000007
<           BEIDOU 9 GOOD 00000007
<           BEIDOU 21 GOOD 0000001d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	system	See *Table 145: Satellite system* on page 676	Enum	4	H+4
4	Satellite ID	Satellite identifier	Ulong	4	H+8
5	Status	Satellite status (see *Table 101: Observation statuses* on page 536)	Enum	4	H+12
6	Status mask	See *Table 102: GPS signal mask* on page 537, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *Table 106: QZSS signal mask* on page 538 and *Table 107: NavIC signal mask* on page 538	Hex	4	H+16
7	Next satellite offset = H+4+(#sat x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#sat x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.130 PDPVEL

PDP filter velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PDPVEL log contains the pseudorange velocity computed by the receiver with the PDP filter enabled. See also the **PDPFILTER** command on page 286.

Message ID: 470

Log type: Synch

Recommended input:

```
log pdpvela ontime 1
```

ASCII example:

```
#PDPVELA,USB1,0,51.5,FINESTEERING,2209,510354.000,12000020,3303,16809;
SOL_COMPUTED,WAAS,0.250,5.000,0.0036,356.812176,-0.0052,0*6e811151
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPVEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (refer to *Table 95: Solution status* on page 530)	Enum	4	H
3	vel type	Velocity type (refer to *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results	Float	4	H+8
5	age	Differential age in seconds	Float	4	H+12
6	hor spd	Horizontal speed over ground, in metres per second	Double	8	H+16
7	trk gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees	Double	8	H+24
8	height	Height in metres where positive values indicate increasing altitude (up) and negative values indicate decreasing altitude (down)	Double	8	H+32
9	Reserved		Float	4	H+40
10	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+44
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.131 PDPXYZ

PDP filter Cartesian position and velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PDPXYZ log contains the Cartesian position in X, Y and Z coordinates as computed by the receiver with the PDP filter enabled. See also the **PDPFILTER** command on page 286.



The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command (see page 284).

Message ID: 471

Log type: Synch

Recommended input:

```
log pdpxyza ontime 1
```

ASCII example:

```
#PDPXYZA,USB1,0,51.5,FINESTEERING,2209,510374.000,12000020,5d37,16809;
SOL_COMPUTED,WAAS,-1632848.5654,-3662158.8160,4944901.1475,0.6048,0.7566,
1.0662,SOL_COMPUTED,WAAS,0.0003,0.0024,0.0011,0.0048,0.0069,0.0085,"131",
0.250,6.000,0.000,45,41,41,41,0,86,7f,37*eafd8f90
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PDPXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	P-sol status	Solution status (refer to *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (refer to *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	P-X	Position X-coordinate (m)	Double	8	H+8
5	P-Y	Position Y-coordinate (m)	Double	8	H+16
6	P-Z	Position Z-coordinate (m)	Double	8	H+24
7	P-X σ	Standard deviation of P-X (m)	Float	4	H+32
8	P-Y σ	Standard deviation of P-Y (m)	Float	4	H+36
9	P-Z σ	Standard deviation of P-Z (m)	Float	4	H+40
10	V-sol status	Solution status (refer to *Table 95: Solution status* on page 530)	Enum	4	H+44

Field	Field type	Description	Format	Binary bytes	Binary offset
11	vel type	Velocity type (refer to *Table 96: Position or velocity type* on page 531)	Enum	4	H+48
12	V-X	Velocity vector along X-axis (m)	Double	8	H+52
13	V-Y	Velocity vector along Y-axis (m)	Double	8	H+60
14	V-Z	Velocity vector along Z-axis (m)	Double	8	H+68
15	V-X σ	Standard deviation of V-X (m)	Float	4	H+76
16	V-Y σ	Standard deviation of V-Y (m)	Float	4	H+80
17	V-Z σ	Standard deviation of V-Z (m)	Float	4	H+84
18	stn ID	Base station ID	Char[4]	4	H+88
19	V-latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results	Float	4	H+92
20	diff_age	Differential age in seconds	Float	4	H+96
21	sol_age	Solution age in seconds	Float	4	H+100
22	#sats	Number of satellite vehicles tracked	Uchar	1	H+104
23	#sats soln	Number of satellite vehicles used in solution	Uchar	1	H+105
24	Reserved		Uchar	1	H+106
25			Uchar	1	H+107
26			Uchar	1	H+108
27	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+109
28	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+110
29	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+111
30	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+112
31	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.132 PORTSTATS

Port statistics

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log conveys various status parameters of the receiver's communication ports. The receiver maintains a running count of a variety of status indicators of the data link. This log outputs a report of those indicators.

Message ID: 72

Log type: Polled

Recommended input:

```
log portstatsa once
```

ASCII example:

```
#PORTSTATSA,USB1,0,50.0,FINESTEERING,2209,510485.000,12000020,a872,16809;26,COM
1,0,957,0,0,142,0,0,0,0,COM2,0,957,0,0,142,0,0,0,0,COM3,0,957,0,0,142,0,0,0,0,F
ILE,0,0,0,0,0,0,0,0,0,USB1,180716,115373935,180716,0,0,0,0,0,0,USB2,0,0,0,0,0,0
,0,0,0,USB3,0,0,0,0,0,0,0,0,0,0,COM4,140,0,140,0,40,0,0,0,0,ICOM1,0,0,0,0,0,0,0,0
,0,ICOM2,0,0,0,0,0,0,0,0,0,0,ICOM3,0,0,0,0,0,0,0,0,0,0,NCOM1,0,0,0,0,0,0,0,0,0,NCOM
2,0,0,0,0,0,0,0,0,0,0,NCOM3,0,0,0,0,0,0,0,0,0,0,ICOM4,0,0,0,0,0,0,0,0,0,0,WCOM1,0,7,0
,0,0,0,0,0,0,0,COM5,0,6,0,0,4,0,0,0,0,CCOM1,0,0,0,0,0,0,0,0,0,0,CCOM2,0,0,0,0,0,0,0
,0,0,CCOM3,0,0,0,0,0,0,0,0,0,0,CCOM4,0,0,0,0,0,0,0,0,0,0,CCOM5,0,0,0,0,0,0,0,0,0,0,CC
OM6,0,0,0,0,0,0,0,0,0,0,ICOM5,0,0,0,0,0,0,0,0,0,0,ICOM6,0,0,0,0,0,0,0,0,0,0,ICOM7,0,0
,0,0,0,0,0,0,0*2739d038
```

Parity and framing errors occur for COM ports if poor transmission lines are encountered or if there is an incompatibility in the data protocol. If errors occur, you may need to confirm the bit rate, number of data bits, number of stop bits and parity of both the transmit and receiving ends. Characters may be dropped when the CPU is overloaded.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PORTSTATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#port	Number of ports with information to follow	Long	4	H
3	port	Refer to *Table 34: Communications port identifiers* on page 153	Enum	4	H+4
4	rx chars	Total number of characters received through this port	Ulong	4	H+8
5	tx chars	Total number of characters transmitted through this port	Ulong	4	H+12
6	acc rx chars	Total number of accepted characters received through this port	Ulong	4	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
7	dropped rx chars	Number of software overruns in receive	Ulong	4	H+20
8	interrupts	Number of interrupts on this port	Ulong	4	H+24
9	breaks	Number of breaks (only for serial ports)	Ulong	4	H+28
10	par err	Number of parity errors (only for serial ports)	Ulong	4	H+32
11	frame err	Number of framing errors (only for serial ports)	Ulong	4	H+36
12	rx overruns	Number of hardware overruns in receive	Ulong	4	H+40
13	Next port offset = H+4+(#port x 40)				
14	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#port x 40)
15	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.133 PPPDATUMINFO

Datum information for the PPP position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution in the **PPPPOS** log (see page 780).

The datum message for TerraStar Correction Services is broadcast periodically. Therefore, it can take several hours, from the start of receiving TerraStar corrections, for the **PPPDATUMINFO** log to reflect the correct datum and co-ordinate epoch for the PPP position solution. Once the PPP datum is known, it will persist through a **RESET** or a power cycle. It will not persist through a **FRESET**.

Message ID: 2293

Log type: Asynch

Recommended input:

```
log pppdatuminfoa onchanged
```

ASCII example:

```
#PPPDATUMINFOA,USB1,0,51.5,FINESTEERING,2209,510600.000,12000020,ea8d,16809;
"ITRF2014",1165,2022.364,GOOD*62e40570
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PPPDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of the position being output by the **PPPPOS** log.	Char[32]	variable	H
3	epsg_code	EPSG code of datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year) Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation Status. See *Table 94: Transformation status* on page 524.	Enum	4	variable
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.134 PPPPOS

PPP filter position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the position solution computed by the PPP filter.

Message ID: 1538

Log type: Synch

Recommended input:

```
log ppppposa ontime 1
```

ASCII example:

```
#PPPPOSA,USB1,0,52.0,FINESTEERING,2209,510777.000,12000020,9078,16809;
SOL_COMPUTED,PPP,51.15043722698,-114.03067878229,1097.3465,-17.0001,WGS84,
0.0167,0.0118,0.0293,"TSTR",17.000,0.000,45,41,41,41,00,00,7f,37*e8b0f4f7
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PPPPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Status	Solution status (see *Table 95: Solution status* on page 530)	Enum	4	H
3	Type	Position type (see *Table 171: Position type* on the next page)	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (m)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid (m)[1]	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+36
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	lon σ	Longitude standard deviation (m)	Float	4	H+44

1. When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.

Field	Field type	Description	Format	Binary bytes	Binary offset
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID TSTL = TerraStar-L service TSTR = TerraStar-C PRO service TSX = TerraStar-X Regional service OCXH = Oceanix service	Char[4]	4	H+52
13	diff_age	Differential age in seconds	Float	4	H+56
14	sol_age	Solution age in seconds	Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	Reserved		Hex	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 171: Position type

Binary	ASCII	Description
0	NONE	No solution
68	PPP_CONVERGING	Converging TerraStar-C PRO, TerraStar-X solution
69	PPP	Converged TerraStar-C PRO, TerraStar-X solution
77	PPP_BASIC_CONVERGING	Converging TerraStar-L solution
78	PPP_BASIC	Converged TerraStar-L solution

3.135 PPPSATS

Satellites used in the PPPPOS solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the used and unused satellites for the corresponding PPPPOS solution. It also describes the signals of the used satellites and reasons for exclusions.

Message ID: 1541

Log type: Synch

Recommended input:

```
log pppsatsa ontime 1
```

Abbreviated ASCII example:

```
<PPPSATS COM1 0 62.0 FINESTEERING 2220 503464.000 02000000 ce3f 16807
<     35
<          GPS 18 GOOD 00000007
<          GPS 16 GOOD 00000003
<          GPS 5 GOOD 00000003
<          GPS 27 GOOD 00000007
<          GPS 29 GOOD 00000003
<          GPS 10 GOOD 00000007
<          GPS 23 GOOD 00000007
<          GPS 13 GOOD 00000003
<          GPS 15 GOOD 00000003
<          GPS 26 GOOD 00000007
<          QZSS 194 SUPPLEMENTARY 00000007
<          GLONASS 18-3 SUPPLEMENTARY 00000003
<          GLONASS 2-4 GOOD 00000003
<          GLONASS 1+1 GOOD 00000003
<          GLONASS 24+2 GOOD 00000003
<          GLONASS 23+3 SUPPLEMENTARY 00000001
<          GLONASS 17+4 GOOD 00000003
<          GLONASS 8+6 GOOD 00000003
<          GALILEO 15 GOOD 0000000f
<          GALILEO 27 GOOD 0000000f
<          GALILEO 3 GOOD 0000000f
<          GALILEO 36 GOOD 0000000f
<          GALILEO 5 GOOD 0000000f
<          GALILEO 21 GOOD 0000000f
<          GALILEO 13 SUPPLEMENTARY 0000000f
<          GALILEO 9 GOOD 0000000f
<          BEIDOU 28 GOOD 0000001d
<          BEIDOU 33 GOOD 0000001d
<          BEIDOU 42 GOOD 0000001d
<          BEIDOU 27 GOOD 0000001d
<          BEIDOU 43 GOOD 0000001d
<          BEIDOU 41 GOOD 0000001d
<          BEIDOU 40 SUPPLEMENTARY 0000001d
<          BEIDOU 11 SUPPLEMENTARY 00000007
<          BEIDOU 14 SUPPLEMENTARY 00000007
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PPPSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	System	Satellite system (see *Table 145: Satellite system* on page 676)	Enum	4	H+4
4	Satellite ID	In binary logs, the satellite ID field is 4 bytes. The 2 lowest-order bytes, interpreted as a USHORT, are the system identifier: for instance, the PRN for GPS, or the slot for GLONASS. The 2 highest-order bytes are the frequency channel for GLONASS, interpreted as a SHORT and zero for all other systems. In ASCII and abbreviated ASCII logs, the satellite ID field is the system identifier. If the system is GLONASS and the frequency channel is not zero, then the signed channel is appended to the system identifier. For example, slot 13, frequency channel -2 is output as 13-2.	Ulong	4	H+8
5	Status	Satellite status (see *Table 101: Observation statuses* on page 536)	Enum	4	H+12
6	Signal Mask	Signals used in the solution (see *Table 102: GPS signal mask* on page 537, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *Table 106: QZSS signal mask* on page 538 and *Table 107: NavIC signal mask* on page 538)	Hex	4	H+16
7	Next satellite offset = H + 4 + (#entries x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#entries x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.136 PPPSEEDAPPLICATIONSTATUS

Progress or outcome of the latest PPP seeding attempt

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log is used to report the progress or outcome of the latest attempt to apply a static PPP seed. For a static seed to shorten the PPP convergence time, the receiver must remain stationary until this log indicates motion is permitted. The receiver may move during **PENDING_MOTION_ALLOWED** and seeding and fast convergence will be successful, but the reported accuracy will be highest if the receiver remains stationary until **APPLIED** status, which normally takes about two minutes longer. Large movements between recording the seed and the end of **PENDING** status will result in the seed being discarded and a full convergence taking place; but movements during this time of less than 10 m may cause an incorrect seed to be applied and an incorrect PPP solution to be reported for a few minutes before this is discovered. This can be avoided by erasing the seed with **PPPSEED CLEAR**. A status of **APPLIED** means that a seed was successfully applied.

The **PPPSEED** command (see page 302) is used to control the application of seeds. Seeds can be manually applied by **PPPSEED SET** or **RESTORE**, or automatically by **PPPSEED AUTO**.

PPPSEEDAPPLICATIONSTATUS does not report the results of the **PPPDYNAMICSEED** command (see page 299).

Message ID 2250

Log type: Asynch

Recommended input

```
log pppseedapplicationstatusa onchanged
```

ASCII example

```
#PPPSEEDAPPLICATIONSTATUSA,USB1,0,50.5,UNKNOWN,0,0.000,12000020,4bd6,16809;
UNAVAILABLE,0.00000000000,0.00000000000,0.0000,0.0000,0.0000,0.0000*d604a4a4
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PPPSEEDAPPLICATIONSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Status	See *Table 172: PPP Seed application status* on the next page.	Enum	4	H
3	Latitude	Latitude Range: ±90 (degrees)	Double	8	H+4
4	Longitude	Longitude Range: ±180 (degrees)	Double	8	H+12
5	Height	Ellipsoidal height Range: > -2000 (m)	Double	8	H+20

Field	Field type	Description	Format	Binary bytes	Binary offset
6	Latitude std. dev.	Latitude standard deviation (m)	Float	4	H+28
7	Longitude std. dev.	Longitude standard deviation (m	Float	4	H+32
8	Height std. dev.	Ellipsoidal height standard deviation (m)	Float	4	H+36
9	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+40
10	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 172: PPP Seed application status

Binary	ASCII	Description
0	UNAVAILABLE	No seed was stored in NVM before the time of seeding or has been set, so a full convergence solution will be provided. Move as desired.
1	AVAILABLE	A seed is stored in NVM but seeding is not enabled, so a full convergence solution will be provided. Either enable seeding or move as desired.
2	PENDING	A seed is stored in NVM or has been set and seeding is enabled and the system is waiting to be able to use the seed for rapid convergence. Remain stationary.
3	APPLIED	The system has used the seed to complete rapid convergence. Move as desired.
4	PENDING_ MOTION_ ALLOWED	The system is currently able to use the seed for rapid convergence. The receiver may move with minor loss of accuracy or remain stationary for a minute or two to improve convergence accuracy.
10	REJECTED_ MOTION_ DETECTED	The seed was rejected because motion was detected or explicitly set via PPPDYNAMICS DYNAMIC (see **PPPDYNAMICS** command on page 298) before the seed could be used. A full convergence solution will be provided. Move as desired.
11	REJECTED_BAD_ POSITION	The seed and seeded solution were discarded because the seed position was found to be incorrect. A full convergence solution will be provided. Move as desired. Note the possibility that an incorrect position may have been reported as accurate before this point.
20	DISCARDED_ RAPID_ CONVERGENCE	A seed was not required for fast convergence of the available solution so it was not used. Move as desired.

3.137 PPPSEEDSTORESTATUS

Status of the NVM-stored PPP seed

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the availability of the PPP seed stored in NVM. When the status is **AVAILABLE**, a seed has been stored in NVM and is available for recall.

Seed storing and recall is controlled by the **PPPSEED** command (see page 302).

Message ID 2251

Log type: Asynch

Recommended input

```
log pppseedstorestatusa onchanged
```

ASCII example

```
#PPPSEEDSTORESTATUSA,USB1,0,48.5,UNKNOWN,0,0.195,12000020,edad,16809;
UNAVAILABLE,0.000*e3794bc7
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PPPSEEDSTORESTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Status	Status of the stored PPP seed: 0 = UNAVAILABLE 1 = AVAILABLE	Enum	4	H
3	Horizontal std. dev.	Horizontal standard deviation (metres)	Float	4	H+4
4	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+8
5	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.138 PPPXYZ

PPP filter Cartesian position and velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PPPXYZ log contains the Cartesian position in X, Y and Z coordinates as computed by the receiver with the PPP filter enabled.

The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command on page 284.

Message ID: 1543

Log type: Synch

Recommended input:

```
log pppxyza ontime 1
```

ASCII example:

```
#PPPXYZA,USB1,0,50.5,FINESTEERING,2209,510993.000,12000020,951f,16809;
SOL_COMPUTED,PPP,-1632848.2151,-3662158.6164,4944901.2646,0.0137,0.0208,0.0239,
SOL_COMPUTED,PPP,-0.0002,0.0021,-0.0039,0.0052,0.0071,0.0092,"TSTR",0.250,
13.000,0.000,47,43,43,42,0,00,7f,37*429a6672
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PPPXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	P-sol status	Position solution status (refer to *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (refer to *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	P-X	Position X-coordinate (m)	Double	8	H+8
5	P-Y	Position Y-coordinate (m)	Double	8	H+16
6	P-Z	Position Z-coordinate (m)	Double	8	H+24
7	P-X σ	Standard deviation of P-X (m)	Float	4	H+32
8	P-Y σ	Standard deviation of P-Y (m)	Float	4	H+36
9	P-Z σ	Standard deviation of P-Z (m)	Float	4	H+40
10	V-sol status	Velocity solution status (refer to *Table 95: Solution status* on page 530)	Enum	4	H+44

Field	Field type	Description	Format	Binary bytes	Binary offset
11	vel type	Velocity type (refer to *Table 96: Position or velocity type* on page 531)	Enum	4	H+48
12	V-X	Velocity vector along X-axis (m)	Double	8	H+52
13	V-Y	Velocity vector along Y-axis (m)	Double	8	H+60
14	V-Z	Velocity vector along Z-axis (m)	Double	8	H+68
15	V-X σ	Standard deviation of V-X (m)	Float	4	H+76
16	V-Y σ	Standard deviation of V-Y (m)	Float	4	H+80
17	V-Z σ	Standard deviation of V-Z (m)	Float	4	H+84
18	stn ID	Base station ID	Char[4]	4	H+88
19	V-latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results.	Float	4	H+92
20	diff_age	Differential age in seconds	Float	4	H+96
21	sol_age	Solution age in seconds	Float	4	H+100
22	#sats	Number of satellite vehicles tracked	Uchar	1	H+104
23	#sats soln	Number of satellite vehicles used in solution	Uchar	1	H+105
24	Reserved		Uchar	1	H+106
25			Uchar	1	H+107
26			Uchar	1	H+108
27	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+109
28	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+110
29	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+111
30	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+112
31	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.139 PROFILEINFO

Profile information in NVM

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log outputs a list of Profiles in the system. Refer also to the **PROFILE** command on page 313.

FW 7.10 A list may consist of a maximum of 128 profiles.

FW 7.09 A list may consist of a maximum of 20 profiles.

Message ID: 1412

Log type: Polled

Recommended input:

```
log profileinfoa onchanged
```

ASCII examples:

```
#PROFILEINFOA,USB1,0,39.5,FINESTEERING,2209,511199.410,12000020,ae3a,16809;
"BASE",0,0*aefd0c3e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PROFILEINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Name	Profile Name	String [Max 20]	variable[1]	H
3	Status Word	Refer to *Table 173: PROFILEINFO Status word – Firmware 7.10.xx* on the next page or *PROFILEINFO Status word – Firmware 7.09.xx* on page 791.	Ulong	4	variable
4	# of Commands	Number of commands assigned to the Profile	Ulong	4	variable
5	Command	Profile command	String [Max 200]	variable[1]	variable

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

Field	Field type	Description	Format	Binary bytes	Binary offset
6	Next command offset = variable				
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	variable
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 173: PROFILEINFO Status word – Firmware 7.10.xx

Bit #	Mask	Description	Bit = 0	Bit = 1
0	0x00000001	Activate Flag	Deactivated (default)	Activated
1	0x00000002	Profile valid flag	All commands valid	At least 1 command invalid (Includes commands greater than 28)
2 – 3	0x00000006	Reserved		
4	0x00000010	Command 1 validation flag	Valid (default)	Invalid
5	0x00000020	Command 2 validation flag	Valid (default)	Invalid
6	0x00000040	Command 3 validation flag	Valid (default)	Invalid
7	0x00000080	Command 4 validation flag	Valid (default)	Invalid
8	0x00000100	Command 5 validation flag	Valid (default)	Invalid
9	0x00000200	Command 6 validation flag	Valid (default)	Invalid
10	0x00000400	Command 7 validation flag	Valid (default)	Invalid
11	0x00000800	Command 8 validation flag	Valid (default)	Invalid
12	0x00001000	Command 9 validation flag	Valid (default)	Invalid
13	0x00002000	Command 10 validation flag	Valid (default)	Invalid
14	0x00004000	Command 11 validation flag	Valid (default)	Invalid
15	0x00008000	Command 12 validation flag	Valid (default)	Invalid
16	0x00010000	Command 13 validation flag	Valid (default)	Invalid
17	0x00020000	Command 14 validation flag	Valid (default)	Invalid
18	0x00040000	Command 15 validation flag	Valid (default)	Invalid
19	0x00080000	Command 16 validation flag	Valid (default)	Invalid
20	0x00100000	Command 17 validation flag	Valid (default)	Invalid
21	0x00200000	Command 18 validation flag	Valid (default)	Invalid
22	0x00400000	Command 19 validation flag	Valid (default)	Invalid
23	0x00800000	Command 20 validation flag	Valid (default)	Invalid

Bit #	Mask	Description	Bit = 0	Bit = 1
24	0x01000000	Command 21 validation flag	Valid (default)	Invalid
25	0x02000000	Command 22 validation flag	Valid (default)	Invalid
26	0x04000000	Command 23 validation flag	Valid (default)	Invalid
27	0x08000000	Command 24 validation flag	Valid (default)	Invalid
28	0x10000000	Command 25 validation flag	Valid (default)	Invalid
29	0x20000000	Command 26 validation flag	Valid (default)	Invalid
30	0x40000000	Command 27 validation flag	Valid (default)	Invalid
31	0x80000000	Command 28 validation flag	Valid (default)	Invalid

Table 174: PROFILEINFO Status word – Firmware 7.09.xx

Bit #	Mask	Description	Bit = 0	Bit = 1
0	0x00000001	Activate Flag	Deactivated (default)	Activated
1 – 3	0x0000000E	Reserved		
4	0x00000010	Command 1 validation flag	Valid (default)	Invalid
5	0x00000020	Command 2 validation flag	Valid (default)	Invalid
6	0x00000040	Command 3 validation flag	Valid (default)	Invalid
7	0x00000080	Command 4 validation flag	Valid (default)	Invalid
8	0x00000100	Command 5 validation flag	Valid (default)	Invalid
9	0x00000200	Command 6 validation flag	Valid (default)	Invalid
10	0x00000400	Command 7 validation flag	Valid (default)	Invalid
11	0x00000800	Command 8 validation flag	Valid (default)	Invalid
12	0x00001000	Command 9 validation flag	Valid (default)	Invalid
13	0x00002000	Command 10 validation flag	Valid (default)	Invalid
14	0x00004000	Command 11 validation flag	Valid (default)	Invalid
15	0x00008000	Command 12 validation flag	Valid (default)	Invalid
16	0x00010000	Command 13 validation flag	Valid (default)	Invalid
17	0x00020000	Command 14 validation flag	Valid (default)	Invalid
18	0x00040000	Command 15 validation flag	Valid (default)	Invalid
19	0x00080000	Command 16 validation flag	Valid (default)	Invalid
20	0x00100000	Command 17 validation flag	Valid (default)	Invalid
21	0x00200000	Command 18 validation flag	Valid (default)	Invalid

Bit #	Mask	Description	Bit = 0	Bit = 1
22	0x00400000	Command 19 validation flag	Valid (default)	Invalid
23	0x00800000	Command 20 validation flag	Valid (default)	Invalid
24 - 31	0xFF000000	Reserved		

3.140 PROFILERESPONSE

Check profile for failed commands

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Firmware: **This log is available only on 7.10.xx firmware.**

Use this log to assist in debugging profiles.

After a profile is Activated, the **PROFILERESPONSE** log can be used to check for any failed commands. One log will be output for each failed command. If all commands succeed, a single log will be output with the OK response.

Message ID: 2528

Log Type: Asynch

Recommended Input:

```
LOG PROFILERESPONSE ONCE
```

ASCII Example:

```
#PROFILERESPONSEA,COM1,0,20.5,UNKNOWN,0,0.920,024c0020,bcce,32768;"TEST",1,"LOG
COM1 TIMEA ONTIME 5 0 NOHLLD",5,"Command failed on receiver"*eebb7d5d
```

Field	Field name	Description	Format	Binary bytes	Binary offset
1	Log header	PROFILEINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	ProfileName	Name of the profile to which the following information pertains.	String	Variable (1) (max 20)	H
3	FailedCmdIndex	The element index corresponding to **PROFILEINFO** for which this information pertains.	Ulong	4	H+ Variable (1)
4	FailedCommand	The profile element that failed.	String	Variable (2) (max 201)	H+4+ Variable (1)
5	ResponseEnum	The response enumeration value. See *Responses* on page 1219.	Ulong	4	H+4+ Variable (1, 2)
6	ResponseString	A description of how the profile element failed, corresponding to the enumeration value.	String	Variable (3) (max 101)	H+8+ Variable (1, 2)

Field	Field name	Description	Format	Binary bytes	Binary offset
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+8+ Variable (1, 2, 3)
8	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.141 PSRDATUMINFO

Datum information for the pseudorange position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution in the **PSRPOS** log (see page 800).

Message ID: 2300

Log type: Asynch

Recommended input:

```
log psrdatuminfoa onchanged
```

ASCII example:

```
#PSRDATUMINFOA,USB1,0,51.5,COARSESTEERING,2209,511539.000,02000020,f85f,16809;
"ECEF",0,2022.364,GOOD*bbfbdb59
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of the position being output by the **PSRPPOS** log.	Char[32]	variable	H
3	epsg_ code	EPSG code of datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year) Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation Status. See *Table 94: Transformation status* on page 524.	Enum	4	variable
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.142 PSRDOP

DOP values for the satellites used in the PSR solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PSRDOP log contains the Dilution Of Precision (DOP) values for the satellites being used in the PSR solution. The PSR DOPs are updated every 60 seconds or whenever the satellites used in the PSR solution changes.

DOP values are a measure of the solution strength. Essentially, the DOPs reflect the geometry of the satellites used in the solution. Solutions with good counts of well-distributed satellites will have low DOPs and should be accurate and reliable. Solutions with fewer or poorly-distributed satellites will have high DOPs and be less accurate and reliable. As a rough guideline, PDOP values less than 4 imply a solution with reasonable geometry.

There can be many reasons for high DOP values. The most common reason is that there are obstructions limiting satellite visibility. Even if satellites are visible and being tracked they might still not be used in the solution if, for example, they are unhealthy or there are not corrections available for them. The **PSRSATS** log (see page 802) will inform which satellites are being tracked and explain why a tracked satellite is not used in the solution.

The DOPs do not consider that different satellites or signals will be weighted differently in the solution. Therefore, they do not completely reflect the solution quality. Ultimately, the standard deviations reported in the **PSRPOS** log (see page 800) are the best reflection of the solution accuracy.

1. If a satellite is locked out using the **LOCKOUTSATELLITE** command (see page 247), it will still show in the prn list but it will be significantly deweighted in the dop calculation.
2. The vertical dilution of precision can be calculated by:
   vdop = $\sqrt{}$ pdop2 - hdop2
3. If the DOP is not yet calculated, a default value of 9999.0 is displayed.

Message ID: 174

Log type: Asynch

Recommended input:

```
log psrdopa onchanged
```

ASCII example:

```
#PSRDOPA,USB1,0,50.0,FINESTEERING,2209,511740.000,02000020,1779,16809;
1.8150,1.6190,0.8940,1.2150,0.8220,5.0,10,26,2,18,12,5,20,29,31,9,25*982c4334
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRDOP header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	gdop	Geometric dilution of precision - assumes 3D position and receiver clock offset (all 4 parameters) are unknown	Float	4	H
3	pdop	Position dilution of precision - assumes 3D position is unknown and receiver clock offset is known	Float	4	H+4
4	hdop	Horizontal dilution of precision.	Float	4	H+8
5	htdop	Horizontal position and time dilution of precision.	Float	4	H+12
6	tdop	GPS time dilution of precision – assumes 3D position is known and only the GPS receiver clock offset is unknown	Float	4	H+16
7	cutoff	GPS elevation cut-off angle	Float	4	H+20
8	#PRN	Number of satellites PRNs to follow	Ulong	4	H+24
9	PRN	PRN of SV PRN tracking, null field until position solution available	Ulong	4	H+28
10...	Next PRN offset = H+28+(#prn x 4)				
11	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+28+(#prn x 4)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.143 PSRDOP2

DOP values for the satellites used in the PSR solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PSRDOP2 log contains the Dilution Of Precision (DOP) values for the satellites being used in the PSR solution. This log is similar to the **PSRDOP** log (see page 796) but contains the per-system TDOPs; see the **PSRDOP** log on page 796 for more information on the DOPs.

Message ID: 1163

Log type: Asynch

Recommended input:

```
log psrdop2a onchanged
```

ASCII example:

```
#PSRDOP2A,USB1,0,18.5,FINESTEERING,2209,511740.000,02000020,0802,16809;
1.8150,1.6190,0.8940,1.3490,1,GPS,0.8220*2a32bc78
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRDOP2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	GDOP	Geometric dilution of precision - assumes 3D position and receiver clock offset (all 4 parameters) are unknown	Float	4	H
3	PDOP	Position dilution of precision - assumes 3D position is unknown and receiver clock offset is known	Float	4	H+4
4	HDOP	Horizontal dilution of precision	Float	4	H+8
5	VDOP	Vertical dilution of precision	Float	4	H+12
6	#systems	Number of systems	Ulong	4	H+16
7	system	See *Table 175: System used for timing* on the next page	Enum	4	H+20
8	TDOP	Time dilution of precision	Float	4	H+24
9	Next satellite offset = H+20+(#systems x 8)				
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+20+(#systems x 8)
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 175: System used for timing

Binary	ASCII
0	GPS[1]
1	GLONASS
2	GALILEO
3	BEIDOU
4	NAVIC
99	AUTO[2]

1. GPS setting includes QZSS satellites.

2. AUTO is used only as a backup system (not available for primary system field).

3.144 PSRPOS

Pseudorange position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the position computed by the receiver, along with three status flags. In addition, it reports other status indicators, including differential age, which is useful in predicting anomalous behaviour brought about by outages in differential corrections.

Message ID: 47

Log type: Synch

Recommended input:

```
log psrposa ontime 1
```

ASCII example:

```
#PSRPOSA,USB1,0,20.0,FINESTEERING,2209,511779.000,02000020,28ff,16809;
SOL_COMPUTED,WAAS,51.15043801969,-114.03066782703,1096.7864,-17.0000,WGS84,
0.9069,0.8826,1.8779,"133",4.000,0.000,45,10,0,0,00,06,00,03*bc4f3b04
```

There are DGPS use cases in which the base receiver is not maintained or controlled by the positioning user. For example, the US Coast Guard operates a differential correction service which broadcasts GPS differential corrections over marine radio beacons. As a user, all you need is a marine beacon receiver and a GNSS receiver to achieve positioning accuracy of less than 1 metre. In this case, the Coast Guard owns and operates the base receiver at known coordinates. Other examples of users appearing to use only one GNSS receiver include FM radio station correction services, privately owned radio transmitters and corrections carried by communication satellites. Some of the radio receivers have built-in GNSS receivers and combined antennas, so they even appear to look as one self-contained unit.

The major factors degrading GPS signals which can be removed or reduced with differential methods are the atmosphere, ionosphere, satellite orbit errors, and satellite clock errors. Some errors which are not removed include receiver noise and multipath.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (see *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (see *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (m)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid (m) [1]	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+36
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	lon σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID	Char[4]	4	H+52
13	diff_age	Differential age in seconds	Float	4	H+56
14	sol_age	Solution age in seconds	Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	Reserved		Uchar	1	H+66
18			Uchar	1	H+67
19			Hex	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.

3.145 PSRSATS

Satellites used in PSRPOS solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the used and unused satellites for the corresponding PSRPOS solution. It also describes the signals of the used satellites and reasons for exclusions.

Message ID: 1162

Log type: Synch

Recommended input:

```
log psrsatsa ontime 1
```

Abbreviated ASCII example:

```
<PSRSATS COM1 0 76.5 FINESTEERING 2220 502666.000 02000008 fea4 16807
<     36
<          GPS 13 GOOD 00000003
<          GPS 29 GOOD 00000003
<          GPS 10 GOOD 00000003
<          GPS 16 GOOD 00000003
<          GPS 18 GOOD 00000003
<          GPS 27 GOOD 00000003
<          GPS 5 GOOD 00000003
<          GPS 15 GOOD 00000003
<          GPS 23 GOOD 00000003
<          GPS 26 GOOD 00000003
<          QZSS 194 GOOD 00000003
<          GLONASS 23+3 NOIONOCORR 00000000
<          GLONASS 24+2 GOOD 00000003
<          GLONASS 15 GOOD 00000003
<          GLONASS 17+4 GOOD 00000003
<          GLONASS 1+1 GOOD 00000003
<          GLONASS 2-4 GOOD 00000003
<          GLONASS 8+6 GOOD 00000003
<          GALILEO 36 GOOD 00000009
<          GALILEO 30 GOOD 00000009
<          GALILEO 15 GOOD 00000009
<          GALILEO 21 GOOD 00000009
<          GALILEO 3 GOOD 00000009
<          GALILEO 9 GOOD 00000009
<          GALILEO 27 GOOD 00000009
<          GALILEO 5 GOOD 00000009
<          BEIDOU 33 GOOD 00000011
<          BEIDOU 40 GOOD 00000011
<          BEIDOU 28 GOOD 00000011
<          BEIDOU 14 NOIONOCORR 00000000
<          BEIDOU 21 GOOD 00000011
<          BEIDOU 41 GOOD 00000011
<          BEIDOU 27 GOOD 00000011
<          BEIDOU 43 GOOD 00000011
<          BEIDOU 42 GOOD 00000011
<          BEIDOU 11 NOIONOCORR 00000000
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	system	See *Table 145: Satellite system* on page 676	Enum	4	H+4
4	Satellite ID	Satellite identifier	Ulong	4	H+8
5	Status	Satellite status (see *Table 101: Observation statuses* on page 536)	Enum	4	H+12
6	Signal mask	See *Table 102: GPS signal mask* on page 537, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *Table 106: QZSS signal mask* on page 538 and *Table 107: NavIC signal mask* on page 538	Hex	4	H+16
7	Next satellite offset = H+4+(#sat x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#sat x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.146 PSRVEL

Pseudorange velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

In the PSRVEL log, the actual speed and direction of the receiver antenna over ground is provided. The velocity measurements sometimes have a latency associated with them. The time of validity is the time tag in the log minus the latency value.



In a PSRVEL log, the actual speed and direction of the receiver antenna over ground is provided. The receiver does not determine the direction a vessel, craft or vehicle is pointed (heading) but rather the direction of motion of the GNSS antenna relative to ground.

The velocity in the PSRVEL log is determined by the pseudorange filter. Velocities from the pseudorange filter are calculated from the Doppler.

The velocity status indicates varying degrees of velocity quality. To ensure healthy velocity, the velocity sol-status must also be checked. If the sol-status is non-zero, the velocity is likely invalid. It should be noted that the receiver does not determine the direction a vessel, craft, or vehicle is pointed (heading), but rather the direction of the motion of the GPS antenna relative to the ground.

The latency of the instantaneous Doppler velocity is always 0.15 seconds. The latency represents an estimate of the delay caused by the tracking loops under acceleration of approximately 1 G. For most users, the latency can be assumed to be zero (instantaneous velocity).

Message ID: 100

Log type: Synch

Recommended input:

```
log psrvela ontime 1
```

ASCII example:

```
#PSRVELA,USB1,0,51.5,FINESTEERING,2209,511827.000,02000020,0dd6,16809;
SOL_COMPUTED,WAAS,0.000,4.000,0.0175,290.743174,0.0309,0*3d24adcc
```



Consider the case where vehicles are leaving a control centre. The control centre's coordinates are known but the vehicles are on the move. Using the control centre's position as a reference, the vehicles are able to report where they are with PSRPOS and their speed and direction with PSRVEL at any time.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRVEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	vel type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results	Float	4	H+8
5	age	Differential age in seconds	Float	4	H+12
6	hor spd	Horizontal speed over ground, in metres per second	Double	8	H+16
7	trk gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees	Double	8	H+24
8	vert spd	Vertical speed, in metres per second, where positive values indicate increasing altitude (up) and negative values indicate decreasing altitude (down)	Double	8	H+32
9	Reserved		Float	4	H+40
10	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+44
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.147 PSRXYZ

Pseudorange Cartesian position and velocity

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2

This log contains the receiver's pseudorange position and velocity in ECEF coordinates. The position and velocity status field's indicate whether or not the corresponding data is valid. See *Figure 13: WGS84 ECEF coordinate system* on page 547 for a definition of the ECEF coordinates.

The velocity status indicates varying degrees of velocity quality. To ensure healthy velocity, the velocity sol-status must also be checked. If the sol-status is non-zero, the velocity is likely invalid. It should be noted that the receiver does not determine the direction a vessel, craft or vehicle is pointed (heading) but rather the direction of the motion of the GNSS antenna relative to the ground.

The latency of the instantaneous Doppler velocity is always 0.15 seconds. The latency represents an estimate of the delay caused by the tracking loops under acceleration of approximately 1 G. For most users, the latency can be assumed to be zero (instantaneous velocity).

The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command (see page 284).

Message ID: 243

Log type: Synch

Recommended input:

```
log psrxyza ontime 1
```

ASCII example:

```
#PSRXYZA,USB1,0,50.5,FINESTEERING,2209,511855.000,02000020,c94c,16809;
SOL_COMPUTED,WAAS,-1632847.3796,-3662158.7826,4944901.0871,1.0126,0.9519,
1.6561,SOL_COMPUTED,WAAS,0.0025,-0.0009,0.0025,0.1210,0.1138,0.1979,"131",
0.000,5.000,0.000,46,10,0,0,0,06,00,03*be512b3f
```

The instantaneous Doppler is the measured Doppler frequency which consists of the satellite's motion relative to the receiver (Satellite Doppler + User Doppler) and the clock (local oscillator) drift.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PSRXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	P-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H

Field	Field type	Description	Format	Binary bytes	Binary offset
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	P-X	Position X-coordinate (m)	Double	8	H+8
5	P-Y	Position Y-coordinate (m)	Double	8	H+16
6	P-Z	Position Z-coordinate (m)	Double	8	H+24
7	P-X σ	Standard deviation of P-X (m)	Float	4	H+32
8	P-Y σ	Standard deviation of P-Y (m)	Float	4	H+36
9	P-Z σ	Standard deviation of P-Z (m)	Float	4	H+40
10	V-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H+44
11	vel type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+48
12	V-X	Velocity vector along X-axis (m/s)	Double	8	H+52
13	V-Y	Velocity vector along Y-axis (m/s)	Double	8	H+60
14	V-Z	Velocity vector along Z-axis (m/s)	Double	8	H+68
15	V-X σ	Standard deviation of V-X (m/s)	Float	4	H+76
16	V-Y σ	Standard deviation of V-Y (m/s)	Float	4	H+80
17	V-Z σ	Standard deviation of V-Z (m/s)	Float	4	H+84
18	stn ID	Base station ID	Char[4]	4	H+88
19	V-latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results	Float	4	H+92
20	diff_age	Differential age in seconds	Float	4	H+96
21	sol_age	Solution age in seconds	Float	4	H+100
22	#SVs	Number of satellites tracked	Uchar	1	H+104
23	#solnSVs	Number of satellites used in solution	Uchar	1	H+105
24	Reserved		Char	1	H+106
25			Char	1	H+107
26			Char	1	H+108
27	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+109

Field	Field type	Description	Format	Binary bytes	Binary offset
28	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+110
29	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+111
30	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+112
31	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.148 PTPDELTATIME

Time difference between local clock and reference clock

Platform: **OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-I, SMART7-SI**

This log provides information regarding the time difference between the receiver's current GPS time as used in log headers and the time provided by the grandmaster clock currently recognized by the receiver.

Message ID: 2465

Log type: Asynchronous

Recommended input:

```
LOG PTPDELTATIMEA
```

ASCII example:

```
#PTPDELTATIMEA,COM1,0,65.5,FINESTEERING,2197,243640.000,02000020,cdba,32768;
PASSIVE,002166FFFE012868,128,128,248,FE,65536,B0D5CCFFFE417085,127,128,248,FE,
65535,TRUE,1538942729.217678,0.2345e-2,-0.2456077e-5,0.123456e-9*3b26afc7
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	PTPDELTATIME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	PTP State	Current PTP state (see *Table 176: PTP states* on the next page)	Enum	4	H
3	Clock Identity	Local clock identity	Hex[8]	8	H+4
4	Priority1	Local clock priority1	Uchar	1	H+12
5	Priority2	Local clock priority2	Uchar	1	H+13
6	Clock Class	Local clock class	Uchar	1	H+14
7	Clock Accuracy	Local clock accuracy	HexByte	1	H+15
8	Offset Scaled Log Variance	Local clock offset scaled log variance	Ushort	2	H+16
9	Reference Clock Identity	Reference clock identity	Hex[8]	8	H+18
10	Reference Clock Priority1	Reference clock priority1	Uchar	1	H+26
11	Reference Clock Priority2	Reference clock priority2	Uchar	1	H+27

Field	Field type	Description	Format	Binary bytes	Binary offset
12	Reference Clock Clock Class	Reference clock class	Uchar	1	H+28
13	Reference Clock Clock Accuracy	Reference clock accuracy	HexByte	1	H+29
14	Reference Clock Offset Scaled Log Variance	Reference clock offset scaled log variance	Ushort	2	H+30
15	Time Offsets Valid	Indication that the offsets fields are valid	Bool	4	H+32
16	Time Offset	Filtered local PTP clock time – grandmaster time (seconds)	Double	8	H+36
17	Time Offset Variance	Filtered time offset variance (seconds$^{2)}$	Double	8	H+44
18	Fractional Frequency Offset	Filtered (Local clock frequency - reference clock frequency) / reference clock frequency	Double	8	H+52
19	Fractional Frequency Offset Variance	Filtered fractional frequency offset variance	Double	8	H+60
20	*	Delimiter separating log info from CRC (ASCII only)	–	–	–
21	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+68
22	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 176: PTP states

Binary	ASCII	Description
1	INITIALIZING	Data sets, hardware and communication facilities are being initialized.
2	FAULTY	A fault has been detected and PTP activity is halted.
3	DISABLED	The port is disabled.
4	LISTENING	Listening for announce messages to determine if a better grand master is active.
5	PRE_MASTER	About to enter MASTER state.
6	MASTER	Acting as a PTP master.
7	PASSIVE	Equivalent to SLAVE state when the clock class < 128.
8	UNCALIBRATED	Preparing to enter SLAVE state.
9	SLAVE	Reporting time difference between the receiver and the selected foreign master.

3.149 QZSSALMANAC

Decoded QZSS almanac parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the decoded L1 C/A almanac parameters as received from the satellite with the parity information removed and appropriate scaling applied.

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

For more information about QZSS almanac data, refer to the Interface Specifications for QZSS at https://qzss.go.jp/en/technical/ps-is-qzss/ps-is-qzss.html.

Message ID: 1346

Log type: Asynch

Recommended input:

```
log qzssalmanaca onchanged
```

ASCII example:

```
#QZSSALMANACA,USB1,0,52.0,SATTIME,2209,435870.000,02000020,67d2,16809;4,
194,2210,86016.0,7.608324e-02,-2.30866759e-09,5.57636471e-01,-1.5856923e+00,
-2.8557607e+00,0.00000000,0.00000000,7.29378066e-05,4.2157755e+07,
7.30630256e-01,0,0,195,2210,86016.0,7.458836e-02,-2.59439378e-09,2.2676078e+00,
-1.5598701e+00,1.6893387e+00,-1.90734863e-06,0.00000000,7.29131785e-05,
4.2167248e+07,7.11593314e-01,0,0,196,2210,86016.0,7.522970e-02,-3.50871758e-09,
-2.2752950e+00,-1.5559876e+00,-9.89514980e-02,1.02043152e-04,3.63797881e-12,
7.29238543e-05,4.2163133e+07,6.00026173e-01,0,0,199,2210,86016.0,2.670288e-04,
9.60039990e-10,-1.6991414e+00,-1.1489437e+00,-1.2297942e+00,0.00000000,
0.00000000,7.29167972e-05,4.2165853e+07,1.21040672e-03,0,0*37178436
```

The speed at which the receiver locates and locks onto new satellites is improved if the receiver has approximate time and position (**SETAPPROXTIME** and **SETAPPROXPOS**), as well as an almanac. This allows the receiver to compute the elevation of each satellite so it can tell which satellites are visible and their Doppler offsets, improving Time to First Fix (TTFF).

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	#messages	Number of satellite PRN almanac messages to follow. Set to zero until almanac data is available	Ulong	4	H
3	PRN	Satellite PRN number for current message (dimensionless)	Ulong	4	H+4
4	week	Almanac reference week (GPS reference week number)	Ulong	4	H+8
5	seconds	Almanac reference time (s)	Double	8	H+12
6	ecc	Eccentricity (dimensionless)	Double	8	H+20
7	ώ	Rate of right ascension (radians/s)	Double	8	H+28
8	ω_0	Right, ascension (radians)	Double	8	H+36
9	ω	Argument of perigee (radians)	Double	8	H+44
10	M_0	Mean anomaly of reference time (radians)	Double	8	H+52
11	a_{f0}	Clock aging parameter (s)	Double	8	H+60
12	a_{f1}	Clock aging parameter (s/s)	Double	8	H+68
13	N	Corrected mean motion (radians/s)	Double	8	H+76
14	A	Semi-major axis (m)	Double	8	H+84
15	inclination angle	Angle of inclination	Double	8	H+92
16	health-prn	SV health from Page 25 of subframe 4 or 5 (6 bits)	Ulong	4	H+100
17	health-alm	SV health from almanac (8 bits)	Ulong	4	H+104
18	Next PRN offset = H+4+(#messages x 104)				
19	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#messages x 104)
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.150 QZSSCNAVRAWMESSAGE

QZSS CNAV raw message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the raw CNAV message from signals which contain the CNAV message (L2C, L5). It also indicates whether the raw message is generated from an L2C signal or L5 signal.

The **QZSSCNAVRAWMESSAGE** log is not output by default. To receive this log, data decoding for L2C or L5 must be enabled using the **DATADECODESIGNAL** command (see page 129)

```
DATADECODESIGNAL QZSSL2C ENABLE
DATADECODESIGNAL QZSSL5 ENABLE
```

Message ID: 2261

Log type: Asynch

Recommended input:

```
log qzsscnavrawmessagea onnew
```

ASCII example:

```
#QZSSCNAVRAWMESSAGEA,USB1,0,45.5,SATTIME,2209,512022.000,02000020,65aa,16809;
173,194,QZSSL5,11,8b08ba6ad35a0dd279c8877112f86741c12c200aa038609c8d40313bdfe35
d0478e809512d50*a22c707e
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSCNAVRAWMESSAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	signal channel	Signal channel providing the bits	Ulong	4	H
3	PRN	Satellite PRN number	Ulong	4	H+4
4	signal type	Signal type (L2C or L5) See *Table 177: Signal type* on the next page	Enum	4	H+8
5	message ID	Message ID	Ulong	4	H+12
6	data	Raw message data	Hex[38]	38	H+16
7	xxxx	32-bit CRC (ASCII and binary only)	Hex	4	H+54
8	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 177: Signal type

Binary	ASCII	Description
14787	QZSSL2C	QZSS L2 C/A-code
14820	QZSSL5	QZSS L5

3.151 QZSSEPHEMERIS

Decoded QZSS parameters

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains a single set of QZSS L1 C/A ephemeris parameters.

Message ID: 1336

Log type: Asynch

Recommended input:

```
log qzssephemerisa onall
```

ASCII example:

```
#QZSSEPHEMERISA,USB1,2,50.5,SATTIME,2209,512010.000,02000020,1e9d,16809;
194,512010.0,0,121,121,2209,2209,514800.0,4.215826861e+07,2.486532145e-09,
-3.127432312e+00,7.6143292477e-02,-1.585891666e+00,3.105588257e-05,
-7.426366210e-06,4.20750000e+02,1.02396875e+03,4.302710295e-07,
-8.195638657e-08,7.3058678204e-01,3.739441477e-10,6.7849504293e-01,
-2.86190492e-09,889,514800.0,9.313225746e-10,-1.13156e-07,-1.13687e-13,0.00000,
FALSE,7.293896144e-05,7.84000000e+00,0,0,0,0*42695181

#QZSSEPHEMERISA,USB1,1,50.5,SATTIME,2209,460800.000,02000020,1e9d,16809;
195,460800.0,0,65,65,2209,2209,464400.0,4.216786739e+07,1.912936824e-09,
-2.252659029e+00,7.4505718076e-02,-1.560284732e+00,-2.508051693e-05,
2.811849117e-05,-7.96906250e+02,-7.62375000e+02,1.281499863e-06,
7.413327694e-07,7.1167492174e-01,-6.507413917e-10,2.388640708e+00,
-2.51189034e-09,833,464400.0,0.000000000,-2.11736e-06,-2.27374e-13,0.00000,
FALSE,7.291348520e-05,7.84000000e+00,0,0,0,0*f8a88fc9

#QZSSEPHEMERISA,USB1,0,50.5,SATTIME,2209,482400.000,02000020,1e9d,16809;
196,482400.0,0,89,89,2209,2209,486000.0,4.216483448e+07,4.154101606e-09,
-2.467916384e+00,7.5259242672e-02,-1.556757964e+00,8.281320333e-06,
-1.931935549e-05,7.30312500e+02,2.36562500e+02,-1.218169928e-06,
-1.806765795e-07,5.9983243978e-01,8.503925651e-10,-2.154062884e+00,
-4.07552690e-09,857,486000.0,-3.725290298e-09,1.01195e-04,2.50111e-12,0.00000,
FALSE,7.292359328e-05,7.84000000e+00,0,0,0,0*fd6bdfea
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSEPHEMERIS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	Satellite PRN number	Ulong	4	H
3	tow	Time stamp of subframe 0 (s)	Double	8	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	health	Health status • bits 0-5: 6-bit health code as defined in QZSS Interface Specification • bit 6: Alert flag	Ulong	4	H+12
5	IODE1	Issue of ephemeris data 1	Ulong	4	H+16
6	IODE2	Issue of ephemeris data 2	Ulong	4	H+20
7	week	GPS reference week number	Ulong	4	H+24
8	z week	Z count week number. This is the week number from subframe 1 of the ephemeris. The ‘toe week’ (field #7) is derived from this to account for rollover	Ulong	4	H+28
9	toe	Reference time for ephemeris (s)	Double	8	H+32
10	A	Semi-major axis (m)	Double	8	H+40
11	ΔN	Mean motion difference (radians/s)	Double	8	H+48
12	M_0	Mean anomaly of reference time (radius)	Double	8	H+56
13	ecc	Eccentricity (dimensionless)	Double	8	H+64
14	ω	Argument of perigee (radians)	Double	8	H+72
15	cuc	Amplitude of cosine harmonic correction term to the argument of latitude (radians)	Double	8	H+80
16	cus	Amplitude of sine harmonic correction term to the argument of latitude (radians)	Double	8	H+88
17	crc	Amplitude of cosine harmonic correction term to the orbit radius (m)	Double	8	H+96
18	crs	Amplitude of sine harmonic correction term to the orbit radius (m)	Double	8	H+104
19	cic	Amplitude of cosine harmonic correction term to the angle of inclination (radians)	Double	8	H+112
20	cis	Amplitude of sine harmonic correction term to the angle of inclination (radians)	Double	8	H+120
21	I_0	Inclination angle at reference time (radians)	Double	8	H+128
22	İ	Rate of inclination angle (radians/s)	Double	8	H+136
23	ω_0	Right ascension (radians)	Double	8	H+144
24	ώ	Rate of right ascension (radians/s)	Double	8	H+152
25	iodc	Issue of data clock	Ulong	4	H+160
26	toc	SV clock correction term (s)	Double	8	H+164

Field	Field type	Description	Format	Binary bytes	Binary offset
27	tgd	Estimated group delay difference (s)	Double	8	H+172
28	a_{fo}	Clock aging parameter (s)	Double	8	H+180
29	a_{f1}	Clock aging parameter (s/s)	Double	8	H+188
30	a_{f2}	Clock aging parameter (s/s/s)	Double	8	H+196
31	AS	Anti-spoofing on: 0= FALSE 1=TRUE	Enum	4	H+204
32	N	Corrected mean motion (radians/s)	Double	8	H+208
33	URA	User Range Accuracy variance, m^2. The ICD specifies that the URA index transmitted in the ephemerides can be converted to a nominal standard deviation value using an algorithm listed there. We publish the square of the nominal value (variance)	Double	8	H+216
34	Fit Interval	Curve fit interval: 0 = Ephemeris data are effective for 2 hours 1 = Ephemeris data are effective for more than 2 hours	Uchar	1	H+224
35	Reserved		Uchar	1	H+225
36	Reserved		Uchar	1	H+226
37	Reserved		Uchar	1	H+227
38	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+228
39	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.152 QZSSIONUTC

QZSS ionospheric and time information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the Ionospheric Model parameters (ION) and the Universal Time Coordinated parameters (UTC) for QZSS.

Message ID: 1347

Log type: Asynch

Recommended input:

```
log qzssionutca onchanged
```

ASCII example:

```
#QZSSIONUTCA,USB1,0,51.5,FINESTEERING,2209,512070.265,02000020,158b,16809;
1.862645149230957e-08,7.450580596923828e-09,-3.576278686523438e-07,
-5.364418029785156e-07,1.290240000000000e+05,1.966080000000000e+05,
-6.553600000000000e+04,-6.553600000000000e+05,2210,94208,
-2.7939677238464355e-09,0.000000000,2185,7,18,18,0*d3e60828
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSIONUTC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	a0	Alpha parameter constant term	Double	8	H
3	a1	Alpha parameter 1st order term	Double	8	H+8
4	a2	Alpha parameter 2nd order term	Double	8	H+16
5	a3	Alpha parameter 3rd order term	Double	8	H+24
6	b0	Beta parameter constant term	Double	8	H+32
7	b1	Beta parameter 1st order term	Double	8	H+40
8	b2	Beta parameter 2nd order term	Double	8	H+48
9	b3	Beta parameter 3rd order term	Double	8	H+56
10	utc wn	UTC reference week number (GPS reference week number)	Ulong	4	H+64
11	tot	Reference time of UTC parameters (s)	Ulong	4	H+68
12	A0	UTC constant term of polynomial (s)	Double	8	H+72
13	A1	UTC 1st order term of polynomial (s/s)	Double	8	H+80
14	wn lsf	Future week number (GPS reference week number)	Ulong	4	H+88

Field	Field type	Description	Format	Binary bytes	Binary offset
15	dn	Day number (the range is 1 to 7 where Sunday=1 and Saturday=7)	Ulong	4	H+92
16	deltat ls	Delta time due to leap seconds	Long	4	H+96
17	deltat lsf	Future delta time due to leap seconds	Long	4	H+100
18	Reserved			4	H+104
19	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+108
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.153 QZSSRAWALMANAC

Raw QZSS almanac data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the undecoded L1 C/A almanac subframes as received from the QZSS satellite.

Message ID: 1345

Log type: Asynch

Recommended input:

```
log qzssrawalmanaca onchanged
```

ASCII example:

```
#QZSSRAWALMANACA,USB1,0,52.0,SATTIME,2209,512070.000,02000020,64c4,16809;
4294967202,86016.000,14,
0,00000000000000000000000000000000000000000000000000000000000000000000,
2,8b02aaa6a195c283c115dc4cff3600cae73416b85cbf64a18ba556000003,
3,8b02aaa6ab96c3778215cfe3ff1d00caed0d5c6402c071f744d471ff0018,
4,8b02aaa6b096c47cc3158728fecd00caea84a34bd0c09a76fbf7e60d002e,
0,00000000000000000000000000000000000000000000000000000000000000000000,
0,00000000000000000000000000000000000000000000000000000000000000000000,
7,8b02aaa6a694c702301500ca005400caec31bac550d13015cde4c8000003,
0,00000000000000000000000000000000000000000000000000000000000000000000,
0,00000000000000000000000000000000000000000000000000000000000000000000,
0,00000000000000000000000000000000000000000000000000000000000000000000,
51,8b02aaa68310f315a2f80000fbe03efbe00000000000000000000000000000,
55,8b02aaa69795f72929616262626f6f626f6f6f0000000000000000000002,
56,8b02aaa68591f81401faf73f0cfff6000000ffffffffd17a2128907120000,
61,8b02aaa68615fd21e506002f4aac61000000ffffffffd17a2128907120002*7fe16ef0
```

The OEM7 family of receivers automatically saves almanacs in their Non-Volatile Memory (NVM), therefore creating an almanac boot file is not necessary.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSRAWALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	ref week	Almanac reference week number	Ulong	4	H
3	ref secs	Almanac reference time, in milliseconds (binary data) or seconds (ASCII data)	GPSec	4	H+4
4	#subframes	Number of subframes to follow	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	svid	SV ID (satellite vehicle ID) SV ID 1 to 10 corresponds to QZSS PRN 193 to 202. Any other values indicate the page ID. Refer to QZSS Interface Specification for more details.	Hex	2	H+12
6	data	Subframe page data	Hex	30	H+14
7	Next subframe offset = H+12+(#subframe x 32)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+12+ (#subframes x 32)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.154 QZSSRAWCNAVMESSAGE

Raw QZSS L2C and L5 CNAV message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides the raw QZSS L2C and L5 CNAV message.

The QZSSRAWCNAVMESSAGE log is not output by default. To receive this log, data decoding for QZSSL2C or QZSSL5 must be enabled using the **DATADECODESIGNAL** command (see page 129) for the specific signal.

Message ID: 1530

Log type: Collection

Recommended input:

```
log qzssrawcnavmessage onnew
```

ASCII example:

```
#QZSSRAWCNAVMESSAGEA,USB1,0,53.0,SATTIME,2209,512148.000,02000020,20f7,16809;
173,194,30,8b09ea6b7b5a740d69fff865ffff080001a0007fbc07c0431401faf73f0cfff6a100
0e2e9710*db33f7fd
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSRAWCNAVMESSAGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	signal channel	Signal channel providing the bits	Ulong	4	H
3	PRN	QZSS satellite PRN number	Ulong	4	H+4
4	message ID	CNAV message ID	Ulong	4	H+8
5	data	CNAV raw message data	Hex[38]	38	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+50
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.155 QZSSRAWEPHEM

QZSS Raw ephemeris information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw binary information for subframes one, two and three from the satellite with the parity information removed. Each subframe is 240 bits long (10 words - 24 bits each) and the log contains a total 720 bits (90 bytes) of information (240 bits x 3 subframes). This information is preceded by the PRN number of the satellite from which it originated. This message is not generated unless all 10 words from all 3 frames have passed parity.

Message ID: 1331

Log type: Asynch

Recommended input:

```
log qzssrawephema onall
```

ASCII example:

```
#QZSSRAWEPHEMA,USB1,2,53.5,SATTIME,2209,512160.000,02000020,2f9e,16809;
194,2209,514800,8b02aaa6b8842861038000000000000000000000002797daf00fffffffc35,8b
02aaa6b90a797fff1b328093b29e412126fc40eef06dcae784ed7daf7f,8b02aaa6b98c00e71ba4
f5c3ffd41dc44beb3498bf628cc6ffe0b379105d*44abb439

#QZSSRAWEPHEMA,USB1,1,53.5,SATTIME,2209,460800.000,02000020,2f9e,16809;
195,2209,464400,8b02aa960084286103800000000000000000000041716100fffeffb8f4,8b
02aa96010a41a0b414eca437e9fecb6726259d0d3af8caed6ea971617e,8b02aa96018c02b06152
6d24018e1cff09e89c63c06da3d1ffe48741e38b*c0feac5d

#QZSSRAWEPHEMA,USB1,0,53.5,SATTIME,2209,482400.000,02000020,2f9e,16809;
196,2209,486000,8b02aa9d088628610380000000000000000000f85976a70000160d438a,8b
02aa9d0908591d922d6f9b72b2c9115e26886124d77ccaeb906376a77f,8b02aa9d098efd72a83c
4f23ff9f18707ab35b4ac0926ce9ffd36d592537*8f7c95d2
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSRAWEPHEM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Satellite PRN number	Ulong	4	H
3	ref week	Ephemeris reference week number	Ulong	4	H+4
4	ref secs	Ephemeris reference time (s)	Ulong	4	H+8
5	subframe1	Subframe 1 data	Hex	30	H+12
6	subframe2	Subframe 2 data	Hex	30	H+42
7	subframe3	Subframe 3 data	Hex	30	H+72
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+102
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.156 QZSSRAWSUBFRAME

Raw QZSS subframe data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw QZSS L1 C/A subframe data.

A raw QZSS L1 C/A subframe is 300 bits in total, 10 words of 30 bits each. This includes the parity 6 bits at the end of each word, for a total of 60 parity bits. Note that in Field #4, the 'data' field below, the 60 parity bits are stripped out and only the raw subframe data remains, for a total of 240 bits. There are two bytes added onto the end of this 30 byte packed binary array to pad out the entire data structure to 32 bytes in order to maintain 4 byte alignment.

Message ID: 1330

Log type: Asynch

Recommended input:

```
log qzssrawsubframea onnew
```

ASCII example:

```
#QZSSRAWSUBFRAMEA,USB1,0,50.5,SATTIME,2209,512202.000,02000020,e56b,16809;
194,3,8b02aaa6bc0f00e71ba4f5c3ffd41dc44beb3498bf628cc6ffe0b379105d,171*f92b64e0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	QZSSRAWSUBFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	Satellite PRN number	Ulong	4	H
3	subframe ID	Subframe ID	Ulong	4	H+4
4	data	Raw subframe data	Hex [30]	32[1]	H+8
5	chan	Signal channel number that the frame was decoded on	Ulong	4	H+40
6	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+44
7	[CR][LF]	Sentence terminator	-	-	-

1. In the binary log case, an additional 2 bytes of padding are added to maintain 4-byte alignment.

3.157 RADARSTATUS

Emulated radar signal information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides information on the velocity and Emulated Radar (ER) signal.

Message ID: 1877

Log type: Synch

Recommended input:

```
log radarstatusa ontime 1
```

ASCII example:

```
#RADARSTATUSA,USB1,0,54.0,FINESTEERING,2209,512323.000,02000020,3a93,16809;
00000000,SOL_COMPUTED,PPP,0.0019,0.0000,0.000000*638616c3
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RADARSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Emulated radar status	Bit field representing current state of radar emulation *Table 178: Emulated radar status* on the next page	Hex	4	H
3	Solution status	Solution status as reported in **BESTVEL** log on page 542	Enum	4	H+4
4	Velocity type	Velocity type as reported in **BESTVEL** log on page 542	Enum	4	H+8
5	Hor speed	Horizontal speed over ground (m/s)	Double	8	H+12
6	Smooth hor speed	Smoother horizontal speed over ground (m/s)	Enum	4	H+20
7	Frequency	Output frequency (Hz)	Double	8	H+28

Table 178: Emulated radar status

Bit	Mask	Description
0	0x01	Feature enabled
1	0x02	Velocity type good
2	0x04	Velocity >1 kph
3-4	0x18	Current response mode being applied will equal the **RADARCONFIG** command on page 326 response mode parameter unless it is 2. If response mode is set to 2 in the **RADARCONFIG** command , this will be either 500 or 1000, depending on speed. Mapped as follows: - 00: Response mode 1 (no smoothing) - 01: Response mode 500 (500 ms smoothing) - 10: Response mode 1000 (1000 ms smoothing) - 11: Response mode 2000 (2000 ms smoothing)
5-31	0xFFFFE700	Reserved

3.158 RAIMSTATUS

RAIM status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides information on Receiver Autonomous Integrity Monitoring (RAIM) status (refer to the **RAIMMODE** command on page 328).

Message ID: 1286

Log type: Synch

Recommended input:

```
log raimstatusa ontime 1
```

ASCII example:

```
#RAIMSTATUSA,USB1,0,54.0,FINESTEERING,2209,512358.000,02000020,bf2d,16809;
DEFAULT,PASS,NOT_AVAILABLE,0.000,NOT_AVAILABLE,0.000,0*3f408598
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAIMSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	RAIM Mode	RAIM mode (refer to *Table 179: RAIM mode types* on the next page)	Enum	4	H
3	Integrity status	Integrity Status (see *Table 180: Integrity status* on the next page)	Enum	4	H+4
4	HPL status	Horizontal protection level status (see *Table 181: Protection level status* on page 829)	Enum	4	H+8
5	HPL	Horizontal protection level (m)	Double	8	H+12
6	VPL status	Vertical protection level status (see *Table 181: Protection level status* on page 829)	Enum	4	H+20
7	VPL	Vertical protection level (m)	Double	8	H+24
8	#SVs	Number of excluded satellites	Ulong	4	H+32
9	System	Satellite system (see *Table 145: Satellite system* on page 676)	Enum	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
10	Satellite ID	In binary logs, the satellite ID field is 4 bytes. The 2 lowest order bytes, interpreted as a USHORT, are the system identifier. For instance, the PRN for GPS or the slot for GLONASS. The 2 highest-order bytes are the frequency channel for GLONASS, interpreted as a SHORT and zero for all other systems. In ASCII and abbreviated ASCII logs, the satellite ID field is the system identifier. If the system is GLONASS and the frequency channel is not zero, then the signed channel is appended to the system identifier. For example, slot 13, frequency channel -2 is output as 13-2.	Ulong	4	H+40
11	Next offset field = H+36+(#SVs * 8)				
12	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+36 + (#SVs * 8)
13	[CR][LF]	Sentence terminator (ASCII only)			

Table 179: RAIM mode types

Binary	ASCII	Description
0	DISABLE	Do not do integrity monitoring of least squares solution
1	USER	User will specify alert limits and probability of false alert
2	DEFAULT	Use NovAtel RAIM (default)
3	APPROACH	Default numbers for non-precision approach navigation modes are used - HAL = 556 m (0.3 nm), VAL = 50 m for LNAV/VNAV
4	TERMINAL	Default numbers for terminal navigation mode are used - HAL = 1 nm, no VAL requirement
5	ENROUTE	Default numbers for enroute navigation mode are used - HAL = 2 nm, no VAL requirement

Table 180: Integrity status

Binary	ASCII	Description
0	NOT_ AVAILABLE	RAIM is unavailable because either there is no solution or because the solution is unique, that is, there is no redundancy
1	PASS	RAIM succeeded. Either there were no bad observations or the bad observations were successfully removed from the solution
2	FAIL	RAIM detected a failure and was unable to isolate the bad observations

Table 181: Protection level status

Binary	ASCII	Description
0	NOT_ AVAILABLE	When RAIM is not available. For example, immediately after issuing a **FRESET** command (see page 192) or when there are not enough satellites tracked to have the required redundant observations.
1	PASS	Current protection levels are below alert limits, meaning positioning accuracy requirements are fulfilled. HPL < HAL VPL < VAL
2	ALERT	Current protection levels are above alert limits, meaning required positioning accuracy cannot be guaranteed by RAIM algorithm. HPL ≥ HAL VPL ≥ VAL

3.159 RANGE

Satellite range information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The RANGE log contains the channel measurements for the currently tracked satellites. When using this log, please keep in mind the constraints noted along with the description.

It is important to ensure that the receiver clock has been set. This can be monitored by the bits in the Receiver Status field of the log header. Large jumps in pseudorange as well as Accumulated Doppler Range (ADR) occur as the clock is being adjusted. If the ADR measurement is being used in precise phase processing, it is important not to use the ADR if the "parity known" flag, in the ch-tr-status field, is not set as there may exist a half (1/2) cycle ambiguity on the measurement. The tracking error estimate of the pseudorange and carrier phase (ADR) is the thermal noise of the receiver tracking loops only. It does not account for possible multipath errors or atmospheric delays.

If multiple signals are being tracked for a given PRN, an entry for each signal, with the same PRN, appears in the RANGE logs. As shown in *Table 182: Channel tracking status* on page 832, these entries can be differentiated by bits 21-25, which indicate the signal type of the observation.



For dual antenna receivers, a **RANGE_1** log can be requested to get RANGE data from the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **RANGEA_1**, and for a binary log enter **RANGEB_1**.

The RANGE and RANGE_1 logs use the same message ID.

Message ID: 43

Log type: Synch

Recommended input:

```
log rangea ontime 1
```

ASCII example:

```
#RANGEA,USB1,0,54.0,FINESTEERING,2209,512449.000,02000020,5103,16809;154,
26,0,24101771.233,0.199,-126655684.482618,0.012,2806.247,44.4,853.017,1810dc04,
26,0,24101778.285,0.063,-98692757.083922,0.012,2186.688,44.3,852.637,11305c0b,
26,0,24101777.807,0.210,-98692761.337851,0.013,2186.688,43.9,852.897,0230dc0b,
26,0,24101777.726,0.048,-94580569.886827,0.007,2095.792,45.5,890.436,01d0dc04,
2,0,22499844.130,0.095,-118237471.207489,0.006,-2253.363,50.8,948.960,0810dc24,
2,0,22499844.354,0.042,-92133093.288779,0.006,-1755.868,47.8,905.245,01305c2b,
18,0,23410900.110,0.140,-123025123.733624,0.009,3172.589,47.4,948.419,0810dc44,
18,0,23410904.748,0.058,-95863754.520894,0.009,2472.151,45.0,905.239,01305c4b,
18,0,23410905.377,0.134,-95863750.778546,0.009,2472.152,47.8,908.359,0230dc4b,
...
11,0,21627872.790,0.045,-87086480.543534,0.004,-456.096,54.2,909.624,0034df64,
11,0,21627872.930,0.029,-91514607.194262,0.005,-479.336,49.8,908.797,0054df64,
14,0,25543595.901,0.066,-133012227.032812,0.013,3483.877,41.7,942.083,08149fc4,
14,0,25543601.865,0.118,-102853526.267150,0.008,2693.828,45.9,909.810,1034dfc4,
14,0,25543600.620,0.077,-108083356.036078,0.012,2830.744,41.4,909.024,0054dfc4,
23,0,24918187.158,0.026,-97784306.543904,0.005,-1719.866,50.8,904.036,0134dfe4,
```

```
23,0,24918183.473,0.056,-105436980.058879,0.008,-1854.495,44.1,908.614,0054dfe4
*b35a6012
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RANGE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	# obs	Number of observations with information to follow [1]	Ulong	4	H
3	PRN/slot	Satellite PRN number of range measurement Refer to *PRN numbers* on page 55	Ushort	2	H+4
4	glofreq	(GLONASS Frequency + 7) (see GLONASS Slot and Frequency Numbers section of this manual) FW 7.10 Firmware versions **7.10.02** and greater. When QZSS L1C/B is tracked, this field will output the L1C/B PRN. The L1C/B PRN differs from the QZSS satellite PRN used for all other signals on the satellite. For all signals except for GLONASS signals and QZSS L1C/B, this field will be zero.	Ushort	2	H+6
5	psr	Pseudorange measurement (m)	Double	8	H+8
6	psr σ	Pseudorange measurement standard deviation (m)	Float	4	H+16
7	adr	Carrier phase, in cycles (accumulated Doppler range)	Double	8	H+20
8	adr σ	Estimated carrier phase standard deviation (cycles)	Float	4	H+28
9	dopp	Instantaneous carrier Doppler frequency (Hz)	Float	4	H+32
10	C/No	Carrier to noise density ratio C/No = 10[log10(S/N_0)] (dB-Hz)	Float	4	H+36
11	locktime	Number of seconds of continuous tracking (no cycle slipping)	Float	4	H+40
12	ch-tr-status	Tracking status (see *Table 182: Channel tracking status* on the next page and the example in *Figure 16: Channel tracking example* on the next page)	Ulong	4	H+44
13...	Next PRN offset = H + 4 + (#obs x 44)				

1. Satellite PRNs may have multiple lines of observations, one for each signal tracked.

Field	Field type	Description	Format	Binary bytes	Binary offset
variable	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#obs x 44)
variable	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Figure 16: Channel tracking example




Table 182: Channel tracking status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Tracking state	0-24 see *Table 183: Tracking state* on page 835
	1	0x00000002		
	2	0x00000004		
	3	0x00000008		

Nibble	Bit	Mask	Description	Range value
N1	4	0x00000010		
	5	0x00000020	SV channel number	(n-1) (0 = first, n = last) n depends on the receiver
	6	0x00000040		
	7	0x00000080		
N2	8	0x00000100		
	9	0x00000200		
	10	0x00000400	Phase lock flag	0 = Not locked, 1 = Locked
	11	0x00000800	Parity known flag	0 = Not known, 1 = Known
N3	12	0x00001000	Code locked flag	0 = Not locked, 1 = Locked
	13	0x00002000	Correlator type	0-7, see *Table 184: Correlator Type* on page 835
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000	Satellite system	0 = GPS 1 = GLONASS 2 = SBAS 3 = Galileo 4 = BeiDou 5 = QZSS 6 = NavIC 7 = Other
	17	0x00020000		
	18	0x00040000		
	19	0x00080000	Reserved	
	20	0x00100000	Grouping	0 = Not grouped, 1 = Grouped

Nibble	Bit	Mask	Description	Range value
N5	21	0x00200000	Signal type (Dependent on satellite system above)	GPS: 0 = L1C/A 5 = L2P 9 = L2P (Y), semi-codeless 14 = L5 (Q) 16 = L1C (P) 17 = L2C (M) GLONASS: 0 = L1C/A 1 = L2C/A 5 = L2P 6 = L3 (Q) BeiDou: 0 = B1 (I) with D1 data 1 = B2 (I) with D1 data 2 = B3 (I) with D1 data 4 = B1 (I) with D2 data 5 = B2 (I) with D2 data 6 = B3 (I) with D2 data 7 = B1C (P) 9 = B2a (P) 11 = B2b (I) Galileo: 2 = E1 (C) 6 = E6B 7 = E6C 12 = E5a (Q) 17 = E5b (Q) 20 = E5AltBOC (Q) QZSS: 0 = L1C/A 14 = L5 (Q) 16 = L1C (P) 17 = L2C (M) 24 = L1C/B (FW 7.10.02) 27 = L6P (FW 7.09.xx) 28 = L6D (FW 7.10.xx) SBAS: 0 = L1C/A 6 = L5 (I) NavIC: 0 = L5 SPS Other: 19 = L-band
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000	Reserved	
	27	0x08000000	Primary L1 channel	0 = Not primary, 1 = Primary
N7	28	0x10000000	Carrier phase measurement [1]	0 = Half Cycle Not Added 1 = Half Cycle Added
	29	0x20000000	Digital filtering on signal	0 = No digital filter 1 = Digital filter
	30	0x40000000	PRN lock flag [2]	0 = PRN Not Locked Out 1 = PRN Locked Out
	31	0x80000000	Channel assignment	0 = Automatic, 1 = Forced

1. This bit is zero until the parity is known and the parity known flag (bit 11) is set to 1.
After a loss of lock, there is a half cycle ambiguity on the ADR (carrier phase) until enough navigation data has been decoded to determine the correct phase of the carrier. At the point this is determined, the "parity known" and "half cycle added" flags will get set. If the half cycle flag is set to 1, it indicates that a half cycle was added to the ADR to correct an inverted phase.

2. A PRN can be locked out using the **LOCKOUT** command.

Table 183: Tracking state

State	Description
0	Idle
1	Sky search
2	Wide frequency band pull-in
3	Narrow frequency band pull-in
4	FW 7.09 Phase lock loop FW 7.10 Tracking
6	Channel steering
7	Frequency lock loop
9	Channel alignment
10	Code search
11	FW 7.09 Aided phase lock loop FW 7.10 Aided tracking
21	Code sweep
23	Side peak detection
24	FFT sky search

When signal is tracking, it can be phased locked / code locked. When phase is locked, code must be locked and the Accumulated Doppler Range (ADR), ADR standard deviation (std), pseudorange (PSR), PSR std all have non 0 values. However, when code is locked, phase is not necessarily locked. In that case the ADR, ADR std and lock time are set to 0 while the PSR, PSR std, and Doppler are still valid.

Table 184: Correlator Type

State	Description
0	N/A
1	Standard correlator: spacing = 1 chip

State	Description
2	Narrow correlator: spacing < 1 chip
3	Reserved
4	Pulse Aperture Correlator (PAC)
5	Narrow PAC
6	FW 7.09 Multipath Estimation and Correction (MEC) FW 7.10 MEC is not available in 7.10.xx.

Table 185: RINEX Mappings

GNSS System	Frequency Band	Frequency	Observation Codes					RINEX Phase Shift
			Signal Type	Pseudo Range	Carrier Phase	Doppler	Signal Strength	
GPS	L1	1575.42	L1CA	C1C	L1C	D1C	S1C	0
			L1C(P)	C1L	L1L	D1L	S1L	0.25
	L2	1227.6	L2C(M)	C2S	L2S	D2S	S2S	-0.25
			L2P	L2P	C2P	D2P	S2P	0
			L2P(Y)	C2W	L2W	D2W	S2W	0
	L5	1176.45	L5(Q)	C5Q	L5Q	D5Q	S5Q	-0.25
GLONASS	G1	1598.0625-1609.3125	L1CA	C1C	L1C	D1C	S1C	0
	G2	1242.9375-1251.6875	L2CA	C2C	L2C	D2C	S2C	0
			L2P	C2P	L2P	D2P	S2P	0.25
	G3	1202.025	L3(Q)	C3Q	L3Q	D3Q	S3Q	0.25

GNSS System	Frequency Band	Frequency	Observation Codes					RINEX Phase Shift
			Signal Type	Pseudo Range	Carrier Phase	Doppler	Signal Strength	
Galileo	E1	1575.42	E1C	C1C	L1C	D1C	S1C	0.5
	E5a	1176.45	E5a(Q)	C5Q	L5Q	D5Q	S5Q	-0.25
	E5b	1207.14	E5b(Q)	C7Q	L7Q	D7Q	S7Q	-0.25
	E5 (E5a+E5b)	1191.795	E5AltBOC (Q)	C8Q	L8Q	D8Q	S8Q	-0.25
	E6	1278.75	E6B	C6B	L6B	D6B	S6B	0
			E6C	C6C	L6C	D6C	S6C	-0.5
SBAS	L1	1575.42	L1CA	C1C	L1C	D1C	S1C	
	L5	1176.45	L5(I)	C5I	L5I	D5I	S5I	
QZSS	L1	1575.42	L1CA	C1C	L1C	D1C	S1C	0
			L1C(P)	C1L	L1L	D1L	S1L	0.25
			L1CB	C1E	L1E	D1E	S1E	0
	L2	1227.6	L2C(M)	C2S	L2S	D2S	S2S	0
	L5	1176.45	L5(Q)	C5Q	L5Q	D5Q	S5Q	-0.25
	L6	1278.75	L6(P) (FW 7.09.xx) L6(D) (FW 7.10.xx)	C6L (FW 7.09.xx) C6S (FW 7.10.xx)	L6L (FW 7.09.xx) L6S (FW 7.10.xx)	D6L (FW 7.09.xx) D6S (FW 7.10.xx)	S6L (FW 7.09.xx) S6S (FW 7.10.xx)	0
BeiDou	B1	1561.098	B1(I)	C2I	L2I	D2I	S2I	0
	B1C	1575.42	B1C(P)	C1P	L1P	D1P	S1P	0.25
	B2	1207.14	B2(I)	C7I	L7I	D7I	S7I	0
	B2a	1176.45	B2a(P)	C5P	L5P	D5P	S5P	0.25
	B2b	1207.14	B2b(I)	C7D	L7D	D7D	S7D	0
	B3	1268.52	B3(I)	C6I	L6I	D6I	S6I	0
NavIC	L5	1176.45	L5SPS	C5A	L5A	D5A	S5A	0

3.160 RANGECMP

Compressed version of the RANGE log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the RANGE data in a compressed format.

For dual antenna receivers, a **RANGECMP_1** log can be requested to get RANGECMP data from the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **RANGECMPA_1**, and for a binary log enter **RANGECMPB_1**.

The RANGECMP and RANGECMP_1 logs use the same message ID.

FW 7.10

- The Phase locked flag and Code locked flag are reported in **RANGECMP**. Those two bits should be used to interpret the validity of ADR or PSR. The ADR is valid when Phase locked flag is set, and the PSR and Doppler are valid when Code locked flag is set.
- In firmware 7.10.xx, the StdDev-ADR field may not be big enough. 7.10.xx firmware will track more noisy signals, which means the ADR standard deviation may be larger than what the log field can accommodate.
- RANGECMP is not recommended for OEM 7.10.xx firmware release. Use the **RANGECMP5** log (see page 863) instead.

Message ID: 140

Log type: Synch

Recommended input:

```
log rangecmpa ontime 10
```

ASCII example:

```
#RANGECMPA,USB1,0,54.5,FINESTEERING,2209,512487.000,02000020,9691,16809;154,
04dc1018c2e70a40d6a37b0b9fb702f5531a616f20030000,
0b5c3011667f08400ea47b0bf32b559f501a546f20030000,
0bdc3002667f08f00aa47b0bb027559f631a5d6fe0020000,
04dcd001dd2408400aa47b0bc1e906de301a0e7440030000,
24dc1008122cf77f198ebc0ab3e387f221025f7bc0030000,
2b5c3001041ff96f1a8ebc0a0e1324812002e87560030000,
44dc1008fa5d0c6073fa260b0a8d9fac32124d7b80030000,
4b5c300100a309f097fa260b0cc9aaca4012e87520030000,
4bdc300200a309309dfa260bcaccaaca32124b7680030000,
44dcd001303c09e0c3fa260b1b378e8710127976e0030000,
449c1042175e0c607efa260b4b7e9fac30127a7680030000,
64dc10180ea8f00f2091680bcb3e8a81420c3e7b40030000,
6b5c3011410bf43f4991680b5b9218a9400c187600030000,
6bdc3002420bf47f4b91680b189518a9430c557640030000,
...
24de15181dcb00b02e50bd1457da6be063c25179e0020000,
649f14086ea6fd7fdfa6500a20df2dc9200b2b7be0030000,
64df3400ca2efe2fe2a6500ad00de6ce100b7476e0030000,
```

```
64df54002e17fe9fe3a6500a0b35518b200b5976c0030000,
849f1408c398f57f19a0dc0b79e06fc7400cef7920030000,
84df3410a5f4f73f29a0dc0bac969887210c6e7680030000,
84df5400f18bf74f28a0dc0bcb6ce1b9300c547640030000,
c49f14081d9a0d101c032b0c6dfa6994500e837ae0020000,
c4df341087840a504a032b0c8a2e24e0420e7a7620030000,
c4df5400900d0bf040032b0c9d7c6b90510e6176c0020000,
e49f1408a208f76f49cfe30b1bbac2c22017117880030000,
e4dff400a9f3f6ff35cfe30ba97395b04217527660030000,
e4df34013c3ef92f51cfe30bf503eeaa1017c175e0030000,
e43f74011a11f91f49cfe30b8bebfa832017547680030000,
e4df5400e2b6f86f34cfe30bbeb814b63017547600030000*5bf4bd0a
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RANGECMP header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#obs	Number of satellite observations with information to follow	Ulong	4	H
3	1st range record	Compressed range log in format of *Table 186: Range record format (RANGECMP only)* below	Hex	24	H+4
4	Next rangecmp offset = H+4 (#obs x 24)				
5	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#obs x 24)
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 186: Range record format (RANGECMP only)

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
Channel Tracking Status	Channel tracking status word	0-31	32	see *Table 182: Channel tracking status* on page 832	-
Doppler Frequency	Instantaneous carrier Doppler frequency	32-59	28	1/256	Hz
Pseudorange (PSR)	Pseudorange measurement	60-95	36	1/128	m

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
ADR	ADR (Accumulated Doppler Range) is calculated as follows: ADR_ROLLS = (RANGECMP_PSR / WAVELENGTH + RANGECMP_ADR) / MAX_VALUE Round to the closest integer IF (ADR_ROLLS ≤ 0) ADR_ROLLS = ADR_ROLLS - 0.5 ELSE ADR_ROLLS = ADR_ROLLS + 0.5 At this point integerise ADR_ROLLS CORRECTED_ADR = RANGECMP_ADR - (MAX_VALUE*ADR_ROLLS) where ADR has units of cycles WAVELENGTH = 0.1902936727984 for GPS L1 WAVELENGTH = 0.2442102134246 for GPS L2 MAX_VALUE = 8388608 GLONASS satellites emit L1 and L2 carrier waves at a satellite-specific frequency, refer to the GLONASS section of *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss	96-127	32	1/256	cycles
StdDev-PSR	Pseudorange measurement standard deviation	128-131	4	See *Table 187: StdDev-PSR values* on the next page	m
StdDev-ADR	ADR measurement standard deviation	132-135	4	(n+1)/512	cycles
PRN/Slot	Refer to *PRN numbers* on page 55	136-143	8	1	-
Lock Time	Number of seconds of continuous tracking (no cycle slipping) This field is constrained to a maximum value of 2,097,151 which represents a lock time of 65535.96875 s (2097151/32).	144-164	21	1/32	s

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
C/No	Carrier to noise density ratio The C/No is constrained to a value between 20-51 dB-Hz. Thus, if it is reported that C/No = 20 dB-Hz, the actual value could be less. Likewise, if it is reported that C/No = 51, the true value could be greater.	165-169	5	(20+n)	dB-Hz
GLONASS Frequency number	GLONASS frequency number When GLONASS is tracked, this field will output the GLONASS frequency plus 7. FW 7.10 Firmware **7.10.02** and greater. When QZSS L1C/B is tracked, this field will output the L1C/B PRN minus 190. The L1C/B PRN differs from the QZSS satellite PRN used for all other signals on the satellite. For all signals except for GLONASS signals and QZSS L1C/B, this field will be zero.	170-175	6	1	
Reserved		176-191	16		

Table 187: StdDev-PSR values

Code	StdDev-PSR (m)
0	0.050
1	0.075
2	0.113
3	0.169
4	0.253
5	0.380
6	0.570
7	0.854
8	1.281
9	2.375
10	4.750
11	9.500

Code	StdDev-PSR (m)
12	19.000
13	38.000
14	76.000
15	152.000

3.161 RANGECMP2

Compressed version of the RANGE log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the RANGE data in a compressed format. RANGECMP2 is more compressed than RANGECMP.

For dual antenna receivers, a **RANGECMP2_1** log can be requested to get RANGECMP2 data from the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **RANGECMP2A_1**, and for a binary log enter **RANGECMP2B_1**.

The RANGECMP2 and RANGECMP2_1 logs use the same message ID.

FW 7.10

- The Phase locked flag and Code locked flag are reported in RANGECM2. Those two bits should be used to interpret the validity of ADR or PSR. The ADR is valid when Phase locked flag is set, and the PSR and Doppler are valid when Code locked flag is set.
- In firmware 7.10.xx, the ADR std field may not be big enough. 7.10.xx firmware will track more noisy signals, which means the ADR std may be larger than what the log field can accommodate.
- In firmware 7.10.xx, the PSR std fields may not be big enough. When a channel is tracking in an FLL mode, the PSR std may be larger than what the log field can accommodate.
- RANGECMP2 is not recommended for OEM 7.10.xx firmware release. Use the **RANGECMP5** log (see page 863) instead.

Message ID: 1273

Log type: Synch

Recommended input:

```
log rangecmp2a ontime 10
```

Example:

```
#RANGECMP2A,USB1,0,55.0,FINESTEERING,2209,512524.000,02000020,1fe3,16809;2256,0
01a00a09fbc856c0540e1ffff6dd8c80c004201d1ffe4ffff4578e87c983d82d1ffe5ffff0dd8c8
75308082d1ffe7ffff0d5a667570f102faff01020010405f8592fb2fe1ffff2dbda41eb81980160
0e4ffff055ce61e08060016000212005421928 52b0650e1ffff2dbc860f50e280ffffe4ffff0579
6655c83a820000e5ffff0dbc865f4800820000e7ffff0d3f62ad3033040900effffff097cc61e009
681fcff030c00ecf8b58551f83fe1ffff6dda06508021800d00e4ffff457948a400aa800c00e5ff
...
5cdfe3fe1ffff291f8417b01900d5ffe3ffff0d7f001b285f00d6ffedffff0d3e041ef86680deff
3c0c600078ef05cafa3fe1ffff29796829181500e5ffe3ffff4d9c6449685f80f5ffedffff0d79c
647307b80f6ff3e0e6018ff1306cc0630e1ffff2977e80f203a011100e3ffff4db80669d069830b
00edffff0d954856b8c88200003f176024e7f2057efb5fe1ffff293d0466980501dffff3ffff0db
be63bf81b02d6fff4ffff0d3f226fd0e380e2fff5ffff031ca45db89d80e9ffedffff0d784636b8
3900eaff*e438ba70
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RANGECMP2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	# bytes	Number of bytes in the compressed binary range data. The maximum is 2880 bytes for 120 channels or 5760 bytes for 240 channels.	Uchar	4	H
3	RangeData	Compressed binary range data in the format of *Table 188: Satellite block of the range record format (RANGECMP2 only)* below and *Table 189: Signal block of the range record format (RANGECMP2 only)* on the next page. The compressed binary range data is organized into satellite blocks, one for each satellite. Each satellite block is followed by a variable number of signal blocks corresponding to the same satellite. For example, a Satellite Block for GPS PRN 17 may be followed by two Signal Blocks for the L1 C/A and L2C signals.	Uchar	#bytes	H+4
4	xxxx	32-bit CRC (ASCII and binary only)	Hex	4	H+4+ (# bytes)
5	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 188: Satellite block of the range record format (RANGECMP2 only)

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
SV Channel Number	Receiver SV channel number	0-7	8	-	-
Satellite Identifier	Satellite identifier specific to the satellite system Refer to *PRN numbers* on page 55	8-15	8	-	-
GLONASS Frequency Identifier	GLONASS frequency channel offset by +7	16-19	4	(7+Ch#)	-
Satellite System Identifier	Defined in *Table 145: Satellite system* on page 676	20-24	5	-	Enum
Reserved		25	1	-	-
Pseudorange Base	Pseudorange base value to be combined with PSR Diff and Phaserange Diff in each following Signal Block	26-54	29	1	m

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
Doppler Base	Doppler base value to be combined with the Scaled Doppler Diff value in each following Signal Block	55-75	21	1	Hz
Number of Signal Blocks	The number of Signal Blocks to follow this Satellite Block. See *Table 189: Signal block of the range record format (RANGECMP2 only)* below for Signal Block definition	76-79	4	-	-

Table 189: Signal block of the range record format (RANGECMP2 only)

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
Signal Type	Defined in *Table 193: Signal type (only in RANGECMP2)* on page 849	0-4	5	-	Enum
Phase Lock	Phase Lock: 0 = Not locked, 1 = Locked	5	1	-	Bool
Parity Known	Parity Known: 0 = Not known, 1 = Known	6	1	-	Bool
Code Lock	Code Lock: 0 = Not locked, 1 = Locked	7	1	-	Bool
Locktime	Time of continuous tracking with no cycle slips. The locktime value saturates at a maximum of 131071 ms	8-24	17	1	ms
Correlator Type	Correlator type: (see *Table 184: Correlator Type* on page 835)	25-28	4	-	Enum
Primary Signal	Primary signal: 0 = Not primary, 1 = Primary	29	1	-	Bool
Carrier Phase Measurement	Carrier phase measurement: 0 = Half cycle not added, 1 = Half cycle added	30	1	-	Bool
Reserved		31	1	-	-
C/No	Carrier to Noise density ratio	32-36	5	(20 + n)	dB-Hz
StdDev PSR	Pseudorange Standard Deviation (defined *Table 190: Std Dev PSR scaling* on the next page)	37-40	4	Bit Field in *Table 190: Std Dev PSR scaling* on the next page	-

Data	Description	Bits first to last	Length (bits)	Scale factor	Units
StdDev ADR	Carrier-Phase Standard Deviation (defined *Table 191: Std Dev ADR scaling* on the next page)	41-44	4	Bit Field in *Table 191: Std Dev ADR scaling* on the next page	-
PSR Diff	Pseudorange Diff to be combined with Pseudorange base i.e., PSR = PSRBase + PSRDiff/128	45-58	14	1/128	m (unsigned)
Phaserange Diff	Phaserange Diff to be combined with Pseudorange Base i.e., ADR = PSRBase + PhaserangeDiff/2048	59-78	20	1/2048	m (unsigned)
Scaled Doppler Diff[1]	Doppler Diff to be combined with Doppler Base. Note that all Doppler values are scaled to the L1/E1 equivalent value. (refer to *Table 192: L1/E1/B1 scaling* on page 848) i.e., Doppler = (DopplerBase + ScaledDopplerDiff/256)/L1ScaleFactor **Note**: The Scaled Doppler Diff field is the only field in the RANGECMP2 log that should be parsed as Two's Complement. The most significant byte (MSB) determines whether the number will be positive (< 0x7) or negative (> 0x7). Two's complement should be applied prior to AND, right bit shift computations.	79-95	17	1/256	Hz (signed)

Table 190: Std Dev PSR scaling

PSR Std Dev bit field value	Represented Std Dev (m)
0	0.020
1	0.030
2	0.045
3	0.066
4	0.099

1. The Scaled Doppler Diff field is the only field in the RANGECMP2 that should be parsed as Two's Complement. The most significant byte (MSB) determines whether the number will be positive (< 0x7) or negative (> 0x7). Two's complement should be applied prior to AND, right bit shift computations.

PSR Std Dev bit field value	Represented Std Dev (m)
5	0.148
6	0.220
7	0.329
8	0.491
9	0.732
10	1.092
11	1.629
12	2.430
13	3.625
14	5.409
15	>5.409

Table 191: Std Dev ADR scaling

ADR Std Dev bit field value	Represented Std Dev (cycles)
0	0.00391
1	0.00521
2	0.00696
3	0.00929
4	0.01239
5	0.01654
6	0.02208
7	0.02947
8	0.03933
9	0.05249
10	0.07006
11	0.09350
12	0.12480
13	0.16656
14	0.22230
15	>0.22230

Table 192: L1/E1/B1 scaling

Satellite system	Signal type	L1/E1/B1 scale factor
GPS	L1CA	1.0
	L2Y	154/120
	L2C	154/120
	L5Q	154/115
GLONASS	L1CA	1.0
	L2CA	9/7
	L2P	9/7
SBAS	L1CA	1.0
	L5I	154/115
Galileo	E1	1.0
	E5A	154/115
	E5B	154/118
	AltBOC	154/116.5
	E6C	154/125
	E6B	154/125
QZSS	L1CA	1.0
	L1CB (FW 7.10.02)	1.0
	L2C	154/120
	L5Q	154/115
	L6D (FW 7.10.xx)	154/125
	L6P (FW 7.09.xx)	154/125
LBAND	LBAND	1.0
BDS	B1	1.0
	B1C	1526/1540
	B2	1526/1180
	B2a	1526/1150
	B2b	1526/1180
	B3	1526/1240
NAVIC	L5SPS	1.0

Table 193: Signal type (only in RANGECMP2)

Satellite system	Signal type	Value
GPS	L1CA	1
	L2Y	4
	L2CM	5
	L5Q	7
	L1C	15
GLONASS	L1CA	1
	L2CA	3
	L2P	4
	L3Q	6
SBAS	L1CA	1
	L5I	2
Galileo	E1C	1
	E5AQ	2
	E5BQ	3
	AltBOCQ	4
	E6C	5
	E6B	12
QZSS	L1CA	1
	L1CB (FW 7.10.02)	2
	L2CM	3
	L5Q	4
	L1C	8
	L6D (FW 7.10.xx)	10
	L6P (FW 7.09.xx)	11
LBAND	LBAND	1

Satellite system	Signal type	Value
BDS	B1D1I	1
	B1D2I	2
	B2D1I	3
	B2D2I	4
	B3D1I	13
	B3D2I	16
	B1CP	19
	B2AP	20
	B2B_I	21
NAVIC	L5SPS	1

3.162 RANGECMP4

Highly compressed version of the RANGE log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the RANGE data in a more heavily compressed format compared to the RANGECMP2 log.

For dual antenna receivers, a **RANGECMP4_1** log can be requested to get RANGECMP4 data from the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **RANGECMP4A_1**, and for a binary log enter **RANGECMP4B_1**.

The RANGECMP4 and RANGECMP4_1 logs use the same message ID.

To match the **RANGE** log sign convention, the constructed phase range (m) and Doppler (m/s) must be multiplied by −1.

1. Channels that have been manually assigned to a PRN with **ASSIGN** or **ASSIGNALL** are not reported in the **RANGECMP4** log.
2. L-band channels are not reported in the **RANGECMP4** log.
3. The **RANGECMP4** log should not be logged with an offset. The RANGECMP4 implementation is dependent on getting measurements at the even second. The allowable triggers are the same as other measurement logs such as **RANGE**, **RANGECMP** and **RANGECMP2**.
4. **RANGECMP4** is a complex log. For more information about decoding the **RANGECMP4** log, refer to *Example of bit parsing a RANGECMP4 log* on page 1228.

FW 7.10

- The Phase locked flag and Code locked flag are not reported in RANGECMP4. However, the flags can be interpreted from the encoded values. When invalid pseudorange values are encoded, code is not locked, and hence Doppler is not valid as well. When invalid phaserange values are encoded, phase is not locked. If phase is not locked, the ADR std and Lock time are set to zero.
- RANGECMP4 is not recommended for OEM 7.10.xx firmware release. Use the **RANGECMP5** log (see page 863) instead.

Message ID: 2050

Log type: Synch

Recommended input:

```
log rangecmp4a ontime 10
```

Example:

```
#RANGECMP4A,USB1,0,54.0,FINESTEERING,2209,512549.000,02000020,fb0e,16809;1843,e
70012090a5300000000b280e3bcf3c77be740d2fb1aa652a93f153ffce7b40f22ddbdcc060018dc
```

```
fe090078834fb2f11b379bb20b008429d3dfbe17915a80ca1b80ff1ffd9ee45e02a02700fd3ffcb
6b712ef93b55da3b7fffc4a12eedb8f09a0c0ece1df0228716fe6370208717f0b20dfbd08d60abc
a5fe1b0298746f1317599ab27898fe574c724cb71f224d01f066bf0310e3de085605fc5cfd0f00c
4bbaf19ebf6fc563064803636d24bdccf6887808923c0fecf785f337202025080fbbf077ec41613
...
f0c0164bc97e1ded4165bc259007451d5d7dccb74b201d9006033e8745f345cffef00019fbf047e
84342030ef010e82b4f710577970a10a5809201a3ec40d2bea90aaedff6be9967ffb3e626603604
700b440107c9235f88f9c019c00edf00114436060ec9f03e4bf87b8d1805701c00a00d8ef43709f
8488d8900520310278010000000000000008d8087b9f65763259740342702309 7a17f38fbab2f165
09ffd030031ee67e67ce09cfe9f09f4b52782e4ff721bc0f90f*4fb4c740
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RANGECMP4 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	# bytes	Number of bytes in the compressed binary Range Data.	Uchar	4	H
3	Range Data	The compressed binary range data is organized into satellite system blocks which break down into measurement blocks for each active signal within each system. Refer to the following tables for more details about this format: *Table 194: Header* on the next page (sent once) *Table 195: Satellite and signal block* on the next page (sent once per satellite system bit set to 1 in the GNSS Field found in *Table 194: Header* on the next page) *Table 196: Measurement block header* on page 854 (sent once for each bit set to 1 in the Satellites Field found in *Table 195: Satellite and signal block* on the next page) *Table 197: Primary reference signal measurement block* on page 855 and *Table 198: Secondary reference signals measurement block* on page 856, or *Table 199: Primary differential signal measurement block* on page 857 and *Table 200: Secondary differential signals measurement block* on page 858, Measurement Block (sent for each bit set to 1 in the Included Signals Field for a given satellite found in *Table 195: Satellite and signal block* on the next page) The byte data is received MSB first so each group of bytes (as defined by the number of needed bits) must be swapped prior to processing.	Uchar	# bytes	H+4
4	xxxx	32-bit CRC (ASCII only)	Hex	4	H+4+(# bytes)
5	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 194: Header

Data name	Description	Bits	Scale factor
GNSS	Indicates which satellite system data is encoded and in what order. When the bit is set the satellite data is included. Data for each system is encoded sequentially: Bit 0 = GPS Bit 1 = GLONASS Bit 2 = SBAS Bit 5 = Galileo Bit 6 = BeiDou Bit 7 = QZSS Bit 9 = NavIC	16	1
	Bit Sum:	16	
	This block is sent once per message		

Table 195: Satellite and signal block

Data name	Range	Description	Bits	Scale factor
Satellites	0… 1.84467E+19	Indicates which satellites are present for this system and their order in the message. Each PRN is represented by a bit. (Bit 0 = PRN 1, Bit 1 = PRN 2, …) **Notes**: • GLONASS Satellite: This value represents the Slot ID of the satellite (range of 1 to 24 where Bit 0 = Slot ID 1). In the event the Slot ID is between 43 and 63, the actual GLONASS Slot ID has not yet been determined and has been replaced with a temporary Slot ID calculated using the GLONASS Frequency Number. See the GLONASS Frequency Number field in *Table 196: Measurement block header* on the next page for more details. • SBAS Satellite PRNs 120 to 158 are offset by 120. (Bit 0 = PRN 120, Bit 1 = 121, …) • SBAS Satellite PRNs 183 to 191 are offset by 130 • QZSS Satellite PRNs are offset by 193	64	1
Signals	0… 65535	Indicates which signals are present for this system and their order in the message. Each signal is represented by a bit as defined in *Table 201: Signal bit mask* on page 860.	16	1

Data name	Range	Description	Bits	Scale factor
Included Signals	0… mxn	A two dimensional field to tell the decoder which signals are present for each of the satellites. **m** = The number of rows equals the number of bits set to 1 found in the Satellites field. (Maximum number of PRNs in the satellite system) **n** = The number of columns equals the number of bits set to 1 found in the Signals field. (Maximum number of Signals in the satellite system)	mxn	
		Bit Sum:	80 + mxn	

This block is sent once for each bit set to 1 in the GNSS field found in *Table 194: Header* on the previous page.

Table 196: Measurement block header

Data name	Range	Description	Bits	Scale factor
Data Format Flag	0… 1	Identifies what type of Measurement Block will be used: 0 = Reference (*Table 197: Primary reference signal measurement block* on the next page and *Table 198: Secondary reference signals measurement block* on page 856) 1 = Differential (*Table 199: Primary differential signal measurement block* on page 857 and *Table 200: Secondary differential signals measurement block* on page 858)	1	1
Ref Data Block ID	0… 7	This ID identifies to which reference data the Differential Data is linked. This value is incremented by 1 each time a new Reference Measurement Block is used.	3	1

Data name	Range	Description	Bits	Scale factor
GLONASS Frequency Number	0… 20 (-7 to +13)	These bits are only present for GLONASS satellites in the Reference Data. This represents the GLONASS Frequency Number which identifies the frequency offset of the carrier frequency. The value will appear as a number between 0 and 20 which directly translates into a frequency offset number between -7 to +13. If the GLONASS Slot ID is unknown, a temporary Slot ID for this satellite will be set between 43 and 63 based on the GLONASS Frequency Number: PRN = 63 – GLONASS Frequency Number The GLONASS Frequency Number used in this calculation is the 0 to 20 value, not the adjusted -7 to +13 value.	5	1
		Bit Sum:	4 (Non-GLONASS) 9 (GLONASS)	
This block is sent once for each bit set to 1 in the Satellites field found in *Table 195: Satellite and signal block* on page 853.				

Table 197: Primary reference signal measurement block

Data name	Range	Description	Bits	Scale factor
Parity Flag	0… 1	0 = Parity Unknown 1 = Parity Known	1	1
½ Cycle Flag	0… 1	0 = Half Cycle Not Added 1 = Half Cycle Added	1	1
C/No	0… 63.95	C/No	11	0.05 dBHz
Lock Time	0… 15	The Lock Time – See *Table 202: Lock time* on page 860	4	1
Pseudorange Std Dev	0… 15	The Pseudorange Standard Deviation (m) – See *Table 204: Pseudorange Std Dev* on page 862	4	
ADR Std Dev	0… 15	The ADR Standard Deviation (cycles) – See *Table 203: ADR Std Dev* on page 861	4	

Data name	Range	Description	Bits	Scale factor
Primary Pseudorange	0… 68719476.74	The Pseudo Range of the 1st signal (Signals field in *Table 195: Satellite and signal block* on page 853). If this value equals (2^{37}-1) = 137438953471, it represents a signal that is not locked.	37	0.0005 m
PhaseRange – Primary Pseudorange	±419.4303	(2's Complement) If this value equals –(2^{23}-1) = -4194304, it represents the signal is not locked.	23	0.0001 m
Primary Doppler	±3355.4431	(2's Complement) If this value equals –(2^{26}-1) = -33554432, it represents an invalid Doppler.	26	0.0001 m/s
		Bit Sum:	111	

This block is sent once for the first bit set to 1 in the Included Signals field found in *Table 195: Satellite and signal block* on page 853.
For any bits set to 1 after the first bit set to 1, refer to *Table 198: Secondary reference signals measurement block* below.

This table is for Reference blocks only, as indicated by the Data Format Flag (see *Table 196: Measurement block header* on page 854).

Table 198: Secondary reference signals measurement block

Data name	Range	Description	Bits	Scale factor
Parity Flag	0… 1	0 = Parity Unknown 1 = Parity Known	1	1
½ Cycle Flag	0… 1	0 = Half Cycle Not Added 1 = Half Cycle Added	1	1
C/No Indicator	0… 63.95	C/No	11	0.05 dBHz
Lock Time	0… 15	The Lock Time – See *Table 202: Lock time* on page 860	4	1
Pseudorange Std Dev	0… 15	The Pseudorange Standard Deviation (m) – See *Table 204: Pseudorange Std Dev* on page 862	4	
ADR Std Dev	0… 15	The ADR Standard Deviation (cycles) – See *Table 203: ADR Std Dev* on page 861	4	

Data name	Range	Description	Bits	Scale factor
Pseudorange – Primary Signal Pseudorange	±262.1435	(2's Complement) If this value equals $-(2^{20}-1) = -524288$, it indicates the signal is not locked.	20	0.0005 m
Phaserange – Pseudorange	±419.4303	(2's Complement) If this value equals $-(2^{23}-1) = -4194304$, it indicates the signal is not locked.	23	0.0001 m
Doppler – Primary Doppler	±0.8191	(2's Complement) If this value equals $-(2^{14}-1) = -8192$, it indicates an invalid Doppler.	14	0.0001 m/s
		Bit Sum:	82	

This block is sent once for each bit set to 1 after the first bit set to 1 in the Included Signals field found in *Table 195: Satellite and signal block* on page 853.

This table is for Reference blocks only, as indicated by the Data Format Flag (see *Table 196: Measurement block header* on page 854).

Table 199: Primary differential signal measurement block

Data name	Range	Description	Bits	Scale factor
Parity Flag	0… 1	0 = Parity Unknown 1 = Parity Known	1	1
½ Cycle Flag	0… 1	0 = Half Cycle Not Added 1 = Half Cycle Added	1	1
C/No	0… 63.95	C/No	11	0.05 dBHz
Lock Time	0… 15	The Lock Time – See *Table 202: Lock time* on page 860	4	1
Pseudorange Std Dev	0… 15	The Pseudorange Standard Deviation (m) – See *Table 204: Pseudorange Std Dev* on page 862	4	
ADR Std Dev	0… 15	The ADR Standard Deviation (cycles) – See *Table 203: ADR Std Dev* on page 861	4	

Data name	Range	Description	Bits	Scale factor
Pseudorange – Predicted Pseudorange	±131.0715	(2's Complement) If this value equals $-(2^{19}-1) = -262144$, it indicates a signal that is not locked. The Predicted Pseudorange = reference pseudorange plus (the reference doppler x time difference between the reference log and the differential log). The Reference log and Differential logs used must contain matching Ref Data Block ID references (*Table 196: Measurement block header* on page 854).	19	0.0005 m
Phaserange – Predicted Phaserange	±3.2767	(2's Complement) If this value equals $-(2^{16}-1) = -32768$, it indicates the signal is not locked. The Predicted Phaserange = reference phaserange plus (the reference doppler x time difference between the reference log and the differential log). The Reference log and Differential logs used must contain matching Ref Data Block ID references (*Table 196: Measurement block header* on page 854).	16	0.0001 m
Doppler – Reference Doppler	±13.1071	(2's Complement) If this value equals $-(2^{18}-1) = -131072$, it indicates an invalid Doppler. The Reference Doppler is the Doppler for that PRN and for that signal from the Reference log. The Reference log and Differential logs used must contain matching Ref Data Block ID references (*Table 196: Measurement block header* on page 854).	18	0.0001 m/s
		Bit Sum:	78	

This block is sent once for each bit set to 1 after the first bit set to 1 in the Included Signals field found in *Table 195: Satellite and signal block* on page 853.
For any bits set to 1 after the first bit set to 1, refer to *Table 200: Secondary differential signals measurement block* below.

This table is for Differential blocks only, as indicated by the Data Format Flag (see *Table 196: Measurement block header* on page 854).

Table 200: Secondary differential signals measurement block

Data name	Range	Description	Bits	Scale factor
Parity Flag	0… 1	0 = Parity Unknown 1 = Parity Known	1	1

Data name	Range	Description	Bits	Scale factor
½ Cycle Flag	0… 1	0 = Half Cycle Not Added 1 = Half Cycle Added	1	1
C/No	0… 63.95	C/No	11	0.05 dBHz
Lock Time	0… 15	The Lock Time – See *Table 202: Lock time* on the next page	4	1
Pseudorange Std Dev	0… 15	The Pseudorange Standard Deviation (m) – See *Table 204: Pseudorange Std Dev* on page 862	4	1
ADR Std Dev	0… 15	The ADR Std Dev (cycles)– See *Table 203: ADR Std Dev* on page 861	4	1
Pseudorange – Predicted Pseudorange	±131.0715	(2's Complement) If this value equals $-(2^{19}-1) = -262144$, it indicates the signal is not locked. The Predicted Pseudorange = reference pseudorange plus (the reference doppler x time difference between the reference log and the differential log). The Reference log and Differential logs used must contain matching Ref Data Block ID references (*Table 196: Measurement block header* on page 854).	19	0.0005 m
Phaserange – Predicted Phaserange	±3.2767	(2's Complement) If this value equals $-(2^{16}-1) = -32768$, it indicates the signal is not locked. The Predicted Phaserange = reference phaserange plus (the reference doppler x time difference between the reference log and the differential log). The Reference log and Differential logs used must contain matching Ref Data Block ID references (*Table 196: Measurement block header* on page 854).	16	0.0001 m
Doppler – Reference Doppler	±13.1071	(2's Complement) If this value equals $-(2^{14}-1) = -8192$, it indicates an invalid Doppler. The Reference Doppler is the Doppler for that PRN and for that signal from the Reference log. The Reference log and Differential logs used must contain matching Ref Data Block ID references (*Table 196: Measurement block header* on page 854).	14	0.0001 m/s
		Bit Sum:	74	

Data name	Range	Description	Bits	Scale factor

This block is sent once for each bit set to 1 after the first bit set to 1 in the Included Signals field found in *Table 195: Satellite and signal block* on page 853.

This table is for Differential blocks only, as indicated by the Data Format Flag (see *Table 196: Measurement block header* on page 854).

Table 201: Signal bit mask

	GPS	GLONASS	SBAS	Galileo	BeiDou	QZSS	NavIC
Bit 1	L1CA	L1CA	L1CA	E1	B1I	L1CA	L5SPS
Bit 2			L5I	E5A	B1GEO	L1CB (FW 7.10.02)	
Bit 3		L2CA		E5B	B2I	L2C	
Bit 4	L2Y	L2P		ALTBOC	B2GEO	L5Q	
Bit 5	L2C			E6C	B3I		
Bit 6	L2P	L3			B3GEO		
Bit 7	L5Q				B1CP		
Bit 8						L1C	
Bit 9					B2AP		
Bit 10						L6D (FW 7.10.xx)	
Bit 11					B2bI	L6P (FW 7.09.xx)	
Bit 12				E6B			
Bit 13							
Bit 14							
Bit 15	L1C						

Table 202: Lock time

Indicator (i)	Minimum lock time (ms)	Range of indicated lock times (t represents the lock time) (ms)
0	0	$0 \le t < 16$
1	16	$16 \le t < 32$
2	32	$32 \le t < 64$

Indicator (i)	Minimum lock time (ms)	Range of indicated lock times (t represents the lock time) (ms)
3	64	64 ≤ t < 128
4	128	128 ≤ t < 256
5	256	256 ≤ t < 512
6	512	512 ≤ t < 1024
7	1024	1024 ≤ t < 2048
8	2048	2048 ≤ t < 4096
9	4096	4096 ≤ t < 8192
10	8192	8192 ≤ t < 16384
11	16384	16384 ≤ t < 32768
12	32768	32768 ≤ t < 65536
13	65536	65536 ≤ t < 131072
14	131072	131072 ≤ t < 262144
15	262144	262144 ≤ t

Table 203: ADR Std Dev

ADR Std Dev (cycles)	
0	≤ 0.0039
1	≤ 0.0052
2	≤ 0.0070
3	≤ 0.0093
4	≤ 0.0124
5	≤ 0.0165
6	≤ 0.0221
7	≤ 0.0295
8	≤ 0.0393
9	≤ 0.0525
10	≤ 0.0701
11	≤ 0.0935
12	≤ 0.1248
13	≤ 0.1666

ADR Std Dev (cycles)	
14	≤ 0.2223
15	> 0.2223

Table 204: Pseudorange Std Dev

Pseudorange Std Dev (m)	
0	≤ 0.020
1	≤ 0.030
2	≤ 0.045
3	≤ 0.066
4	≤ 0.099
5	≤ 0.148
6	≤ 0.220
7	≤ 0.329
8	≤ 0.491
9	≤ 0.732
10	≤ 1.092
11	≤ 1.629
12	≤ 2.430
13	≤ 3.625
14	≤ 5.409
15	> 5.409

3.163 RANGECMP5

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Firmware: **This log is available only on 7.10.xx firmware.**

The RANGECMP5 log offers more compression than RANGECMP and RANGECMP2 while not having the differential aspect and complexity of RANGECMP4. The RANGECMP5 log also has wider parameters for some fields when compared to the rest of the RANGECMP logs. The widened Primary Doppler, Secondary-Primary Doppler, ADR Std Dev and PSR Std Dev provide more information when operating in challenging environments.

For dual antenna receivers, a **RANGECMP5_1** log can be requested to get RANGECMP5 data from the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **RANGECMP5A_1**, and for a binary log enter **RANGECMP5B_1**.

The RANGECMP5 and RANGECMP5_1 logs use the same message ID.

Message ID: 2537

Log type: Synch

Recommended input:

```
LOG RANGECMP5A ONTIME 10
```

ASCII example:

```
#RANGECMP5A,COM1,0,71.5,FINESTEERING,2297,339714.000,1a000000,4f34,32768;1156,
61000270b52000000000b200337f3733ff30f49e20b275e67605693338e1498151f7049d90c0ee
fce0ff1f06df93429d1a44a758ceffef3d5030dabe18b81b20dafe1300400efc41ee0cf82dd339
b96013080582df0f92580276e503008008f843d48bc07aece006a027be000a4250d54480ff87be
f7a4946dc109abf43e40f4db0c34b92705cf07daf0fe0200d1ed8b29ff0160c3ff09006cc31f62
74af912f295312fef8e27f07be10081eb09066f8ff4f7c4fc6eb063cbb1662ffa106fe20fd5b9c
ff09e266e073f7fa65ef0751f2807352c2fe3f84b92f88350e9567d96e0ae8408ea0ad7d412
. . . .
e1f2692dae0c5d04fec5b65fff7e88b217d8d114200194c01fe12f04f67a05e4ff300b5f88b0e8
180815bd1e605e108022f8232cc9c0c5daa0f9bf0ffe08fc27808c2cd0fd87d1f7630039d842ab
d3b8c1a8940c74be272350064a390a4000fbef879827814a6bc2fa3ffcb52f486c221988edf4fd
25c067004ee10b8115bc4da65e7b071290c9df007f08821ee8202980ff4fc11f611306b2990a92
ff70d2bea0be9cf93786ad0a580385ff40f7a5084783078adffd7fc97d2947baf0f8dd4fff8731
f7a46811a4032faebd008a7ce627bb2784870da0c700f6ff37efc9a8c90299574008004cbe1f83
19474e663196fb1f379ea0fdfd10eb1180f1e12fff9f813f82a301f089f863ff01*b4cd8fcd
```

Field	Field name	Description	Format	Binary bytes	Binary offset
1	Log header	RANGECMP5 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	#bytes	Number of bytes in the compressed binary Range data.	Uchar	4	H

Field	Field name	Description	Format	Binary bytes	Binary offset
3	Range data	The compressed binary range data is organized into satellite system blocks which break down into measurement blocks for each active signal within each system. The following tables define this format: • *Table 205: RANGECMP5 header* on the next page (sent once) • *Table 206: Satellite and signal block* on the next page (sent once per satellite system bit set to 1 in the *GNSS field* found in *Table 205: RANGECMP5 header* on the next page) • *Table 207: Measurement block header* on page 866 (sent once for each bit set to 1 in the *Satellites field* found in *Table 206: Satellite and signal block* on the next page) • *Table 208: Primary signal measurement block* on page 867 or *Table 209: Secondary signal measurement block* on page 867 (sent for each bit set to 1 in the Included *Signals field* for a given satellite found in *Table 206: Satellite and signal block* on the next page) The byte data is received MSB first so each group of bytes (as defined by the number of needed bits) must be swapped prior to processing.	Uchar	# bytes	H+4
4	xxxx	32-bit CRC (ASCII only)	Hex	4	H+4+(# bytes)
5	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 205: RANGECMP5 header

Data name	Range	Description	Bits	Scale factor
GNSS field	0… 65535	Indicates which satellite system data is encoded and in what order. When the bit is set, the satellite data is included. Data for each system is encoded sequentially: Bit 0 = GPS Bit 1 = GLONASS Bit 2 = SBAS Bit 5 = Galileo Bit 6 = BeiDou Bit 7 = QZSS Bit 9 = NavIC L-band channels are not reported.	16	1
		Bit sum:	16	

This block is sent once per message.

Table 206: Satellite and signal block

Data name	Range	Description	Bits	Scale factor
Satellites field	0… 1.84467E+19	Indicates which *m* satellites are present for this system and their order in the message. Each PRN is represented by a bit. (Bit 0 = PRN 1, Bit 1 = PRN 2, …) **Notes**: • Manually assigned channels are not reported. • SBAS satellite PRNs 120 to 158 are offset by 120. (Bit 0 = PRN 120, Bit 1 = 121, …) • SBAS satellite PRNs 183 to 187 are offset by 130. • QZSS satellite PRNs are offset by 193.	64	1
Signals field	0… 65535	Indicates which *n* signals are present for this system and their order in the message. Each symbol is represented by a bit as defined in *Table 210: Signal bit mask* on page 868.	16	1

Data name	Range	Description	Bits	Scale factor
Included signals field	0… m x n	A two-dimensional field to tell the decoder which signals are present for each of the satellites. *m* = The number of rows equals the number of bits set to 1 found in the Satellites Field. (Maximum number of PRN's in the satellite system.) *n* = The number of columns equals the number of bits set to 1 found in the Signals Field. (Maximum number of Signals in the satellite system.)	*m* x *n*	
		Bit sum:	80 + m x *n*	



This block is sent once for each bit set to 1 in the *GNSS field* found in *Table 205: RANGECMP5 header* on the previous page.

Table 207: Measurement block header

Data name	Range	Description	Bits	Scale factor
Data format flag	0… 1	Identifies what type of Measurement Block (*Table 208: Primary signal measurement block* on the next page or *Table 209: Secondary signal measurement block* on the next page) will be used: 0 = Reference 1 = Reserved	1	N/A
Reserved	0… 7	Reserved	3	N/A
GLONASS frequency number	0… 20 (-7 to +13)	These bits are only present for GLONASS satellites. This is the GLONASS slot ID. If the Slot ID is unknown, set the PRN between 43 and 63 based on the GLONASS Frequency: (0,20) PRN = 63 – GLONASS Frequency	5	N/A
		Bit sum:	4 (Non-GLONASS) 9 (GLONASS)	



This block is sent once for each bit set to 1 in the *Satellites field* found in *Table 206: Satellite and signal block* on the previous page.

Table 208: Primary signal measurement block

Data name	Range	Description	Bits	Scale factor
Parity flag	0… 1	0 = Parity Unknown 1 = Parity Known	1	N/A
½ Cycle flag	0… 1	0 = Half Cycle Not Added 1 = Half Cycle Added	1	N/A
Quality indicator	0… 63.95	C/No	11	0.05 dB-Hz
Lock time	0… 15	Lock time – see *Table 211: Lock time* on page 869.	4	N/A
Primary pseudorange standard deviation	0… 31	Pseudorange standard deviation – see *Table 213: Pseudorange standard deviation* on page 871***Table 30***.	5	N/A
Primary phaserange standard deviation	0… 31	Phaserange standard deviation – see *Table 212: Phaserange standard deviation* on page 869.	5	N/A
Primary pseudorange	0… 68719476.74	If this value is 2^{n-1}, it represents a signal that is not locked.	37	0.0005 m
Primary phaserange – primary pseudorange	(2's Complement) ±419.4303	If this value equals -2^{n-1}, it represents the signal is not locked.	23	0.0001 m
Primary doppler	(2's Complement) ±13421.773	If this value equals -2^{n-1}, it represents an invalid Doppler.	28	0.0001 m/s
		Bit sum:	115	

This block is sent once for the first bit set to 1 in the Included *Signals field* found in *Table 206: Satellite and signal block* on page 865.

Table 209: Secondary signal measurement block

Data name	Range	Description	Bits	Scale factor
Parity flag	0… 1	0 = Parity Unknown 1 = Parity Known	1	N/A
½ Cycle flag	0… 1	0 = Half Cycle Not Added 1 = Half Cycle Added	1	N/A
Quality indicator	0… 63.95	C/No	11	0.05 dB-Hz

Data name	Range	Description	Bits	Scale factor
Lock time	0… 15	Lock time – see *Table 211: Lock time* on the next page.	4	N/A
Secondary pseudorange standard deviation	0… 31	Pseudorange standard deviation – see *Table 213: Pseudorange standard deviation* on page 871.	5	N/A
Secondary phaserange standard deviation	0… 31	Phaserange standard deviation – see *Table 212: Phaserange standard deviation* on the next page.	5	N/A
Secondary pseudorange – Primary pseudorange	(2's Complement) ±262.1435	If this value is -2^{n-1}, it represents a signal that is not locked.	20	0.0005 m
Secondary phaserange – Secondary pseudorange	(2's Complement) ±419.4303	If this value equals -2^{n-1}, it represents the signal is not locked.	23	0.0001 m
Secondary doppler – Primary doppler	(2's Complement) ±6.554	If this value equals -2^{n-1}, it represents an invalid Doppler.	16	0.0002 m/s
		Bit sum:	86	

This block is sent once for each bit set to 1 after the first bit set to 1 in the Included *Signals field* found in *Table 206: Satellite and signal block* on page 865.

Table 210: Signal bit mask

System bit	GPS	GLONASS	SBAS	Galileo	BeiDou	QZSS	NavIC
Bit 1	L1CA	L1CA	L1CA	E1	B1I	L1CA	L5SPS
Bit 2			L5I	E5A	B1GEO	L1CB	
Bit 3		L2CA		E5B	B2I	L2C	
Bit 4	L2Y	L2P		ALTBOC	B2GEO	L5Q	
Bit 5	L2C			E6C	B3I		
Bit 6	L2P	L3			B3GEO		
Bit 7	L5Q				B1CP		
Bit 8						L1C	
Bit 9					B2AP		
Bit 10							
Bit 11					B2BI	L6P	
Bit 12				E6B			

System bit	GPS	GLONASS	SBAS	Galileo	BeiDou	QZSS	NavIC
Bit 13							
Bit 14							
Bit 15	L1C						

Table 211: Lock time

Indicator (i)	Minimum lock time (ms)	Range of indicated lock times (t represents the lock time) (ms)
0	0	0 ≤ t < 16
1	16	16 ≤ t < 32
2	32	32 ≤ t < 64
3	64	64 ≤ t < 128
4	128	128 ≤ t < 256
5	256	256 ≤ t < 512
6	512	512 ≤ t < 1024
7	1024	1024 ≤ t < 2048
8	2048	2048 ≤ t < 4096
9	4096	4096 ≤ t < 8192
10	8192	8192 ≤ t < 16384
11	16384	16384 ≤ t < 32768
12	32768	32768 ≤ t < 65536
13	65536	65536 ≤ t < 131072
14	131072	131072 ≤ t < 262144
15	262144	262144 ≤ t

Table 212: Phaserange standard deviation

Phaserange standard deviation (cycles) (4 MSBs)		
X	(1/256) *exp(x/(3.65*sqrt(3)) (cycles)	
0	≤	0.00391
1	≤	0.00458
2	≤	0.00536

Phaserange standard deviation (cycles) (4 MSBs)		
3	≤	0.00628
4	≤	0.00735
5	≤	0.00861
6	≤	0.01001
7	≤	0.01182
8	≤	0.01385
9	≤	0.01621
10	≤	0.01900
11	≤	0.02223
12	≤	0.02607
13	≤	0.03054
14	≤	0.03577
15	≤	0.04190
16	≤	0.04908
17	≤	0.05749
18	≤	0.06734
19	≤	0.07889
20	≤	0.09240
21	≤	0.10824
22	≤	0.12679
23	≤	0.14851
24	≤	0.17396
25	≤	0.20378
26	≤	0.23870
27	≤	0.27961
28	≤	0.32753
29	≤	0.38366
30	≤	0.44940
31	>	0.44940

Table 213: Pseudorange standard deviation

Pseudorange Standard Deviation (m) (4 LSBs)		
X	0.020*exp(0.4 x) if x ≤ 14 5.409*exp(0.24(x-14)) if x ≤ 30 (m)	
0	≤	0.020
1	≤	0.030
2	≤	0.045
3	≤	0.066
4	≤	0.099
5	≤	0.148
6	≤	0.220
7	≤	0.329
8	≤	0.491
9	≤	0.732
10	≤	1.092
11	≤	1.629
12	≤	2.430
13	≤	3.625
14	≤	5.409
15	≤	6.876
16	≤	8.741
17	≤	11.111
18	≤	14.125
19	≤	17.957
20	≤	22.828
21	≤	29.020
22	≤	36.891
23	≤	46.898
24	≤	59.619
25	≤	75.791

Pseudorange Standard Deviation (m) (4 LSBs)		
26	≤	96.349
27	≤	122.484
28	≤	155.707
29	≤	197.943
30	≤	251.634
31	>	251.634

3.164 RANGEGPSL1

L1 version of the RANGE log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log is identical to the **RANGE** log (see page 830) except that it only includes GPS L1 C/A observations.

Message ID: 631

Log type: Synch

Recommended input:

```
log rangegpsl1a ontime 30
```

ASCII example:

```
#RANGEGPSL1A,USB1,0,55.0,FINESTEERING,2209,512583.000,02000020,5862,16809;
10,
26,0,24030889.100,0.199,-126283196.274792,0.012,2752.781,44.3,987.017,1810dc04,
2,0,22557616.108,0.123,-118541064.672676,0.007,-2277.646,48.6,1082.960,
0810dc24,
18,0,23330317.018,0.126,-122601657.447823,0.009,3147.617,48.4,1082.419,
0810dc44,
12,0,23997160.481,0.151,-126105903.891743,0.009,-3940.361,46.8,1081.940,
1810dc64,
5,0,20822721.607,0.083,-109424141.788836,0.005,1522.260,52.0,1082.908,1810dc84,
20,0,20953423.978,0.087,-110110984.182224,0.007,-827.676,51.6,1082.829,
0810dca4,
29,0,20734204.928,0.077,-108958983.599878,0.006,1473.416,52.6,1082.708,
1810dcc4,
31,0,24809616.479,0.239,-130375401.308516,0.014,-2112.775,42.8,1082.271,
0810dd04,
9,0,25163112.825,0.207,-132233041.316998,0.013,-1279.863,44.0,1065.218,
1810dd24,
25,0,21543476.977,0.093,-113211728.999577,0.008,-2507.055,50.9,1082.449,
0810ddc4
*51b3705b
```

Since the RANGEGPSL1 log includes only GPS L1 C/A observations, it is smaller in size than the RANGE log which contains entries for multiple systems and signals. Use the RANGEGPSL1 log when data throughput is limited and you are only interested in GPS L1 C/A range data. For GPS L1 only models, RANGE and RANGEGPSL1 logs are identical.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RANGEGPSL1 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	# obs	Number of L1 observations with information to follow	Long	4	H
3	PRN	Satellite PRN number of range measurement (1-32)	Ushort	2	H+4
4	Reserved		Ushort	2	H+6
5	psr	Pseudorange measurement (m)	Double	8	H+8
6	psr std	Pseudorange measurement standard deviation (m)	Float	4	H+16
7	adr	Carrier phase, in cycles (accumulated Doppler range)	Double	8	H+20
8	adr std	Estimated carrier phase standard deviation (cycles)	Float	4	H+28
9	dopp	Instantaneous carrier Doppler frequency (Hz)	Float	4	H+32
10	C/No	Carrier to noise density ratio C/No = $10[\log_{10}(S/N_0)]$ (dB-Hz)	Float	4	H+36
11	locktime	Number of seconds of continuous tracking (no cycle slipping)	Float	4	H+40
12	ch-tr-status	Tracking status (see *Table 182: Channel tracking status* on page 832)	Ulong	4	H+44
13...	Next PRN offset = H + 4 + (#obs x 44)				
14	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#obs x 44)
15	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.165 RAWALM

Raw GPS L1 C/A almanac data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the undecoded GPS L1 C/A almanac subframes as received from the satellite with the parity information removed. For more information about almanac data, refer to *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.

Message ID: 74

Log type: Asynch

Recommended input:

```
log rawalma onchanged
```

ASCII example:

```
#RAWALMA,USB1,0,54.0,SATTIME,2209,512250.000,02000020,cc1b,16809;
2210,61440.000,36,
1,8b0284a683b741617b0f1da7fd7000a10d0a6fe69624de9116263f2fffd1,
2,8b0284a6863442a7520f0f5ffd5600a10cf76c306ac62dda1c751caa000e,
3,8b0284a688b74321ef0f1464fd6300a10c9d9a02d626d19ce8f3d8dfff9d,
4,8b0284a68b36440ed50f0bfcfd4000a10c67c614e78719785cff7fea0026,
5,8b0284a68db74530d60f0bf0fd5600a10d5998511a2996db8266e6f5000b,
6,8b0284a6903646150b0f1d37fd6d00a10d816f9046dd08a41f9de527009f,
7,8b0284a692b44783b70f059efd5c00a10cf2ef9113a38e0ffaf04e2a000a,
8,8b0284a69536483d030f0da3fd2200a10da643d11906d3826f02aef70006,
9,8b0284a697b44911130f0770fd3900a10bfcc3e4b94c6129844e81d3003e,
10,8b0284a69a354a3e480f1443fd6500a10d0e99e60d9a5e76c36848c9ff92,
11,8b0284a69cb44b02f50f0d78fd5bffa10c457199187328c76e423efc003b,
12,8b0284a69f354c46e70f11a3fd4900a10c0d1ce6f23456f0e271e5e3ffda,
13,8b0284a6a1b44d306c0f10d1fd4800a10ce3ca2eb72584145db6b328005d,
14,8b0284a6a4374e0f210f06d6fd3e00a10ce41b91cf7e35bbe16d55f10018,
15,8b0284a6a6b54f73050ff7bffd2100a10daebf79842c82e548176cf80022,
16,8b0284a6a93550685a0f1190fd4600a10cd81da8911daac8963f89beffee,
17,8b0284a6abb7516ea50f1790fd3400a10bff47360bc326976e454250002d,
18,8b0284a6ae345212f30f1319fd6000a10c85702a367b999023da9d16ffab,
19,8b0284a6b0b7534ba10f16cdfd3400a10d3049099c53ddb4cf43e7140037,
20,8b0284a6b3365427670f0074fd4b00a10c2a939b0180ea134062d6430011,
21,8b0284a6b5b755c6f10f0ba5fd5600a10db26c197fd946af759ce6150007,
22,8b0284a6b836566d600f0c0ffd4100a10cffc80d8db484ba69e9f1220040,
23,8b0284a6bab457118d0f1111fd6200a10d4698de217a73b2f78a52fdffe7,
24,8b0284a6bd3658662b0ffad0fd4c00a10d14ec22c7212fb622a9131fffd0,
25,8b0284a685b05956250f0983fd4400a10d0519bb6728daa2d5b6282a0034,
26,8b0284a688315a38d60ffd0bfd3600a10d9917bfe30fd6f2ba7af21b0023,
27,8b0284a68ab35b56710f1355fd2a00a10cd244a3931bbd7f70647e1a0055,
0,00000000000000000000000000000000000000000000000000000000000000,
29,8b0284a692325d119e0f18e8fd3500a10d4147bfe95beea17518febcfff7,
30,8b0284a694b35e2fa30ffbf2fd4d00a10dc1f00c20923e8ffa7e58ba001a,
31,8b0284a697325f55780f085dfd5d00a10d86f051630fe442e7e443e80018,
32,8b0284a699b16030d70f09edfd3d00a10c3fc45da6a2d3218b29e1efffcb,
51,8b0284a6bfb4730fa2000000000000000fc0000000000000000000155557,
55,8b0284a6ab3177444d3039272f4c20394a2d4e503a2e4854384c4f504c03,
56,8b0284a6adb0781303fefe3908fefcfffff2fffffffa0fa2128907120001,
```

```
63,8b0284a6bf327fb9bcababbbca9ca9ac9999cbbbb9abab00000fc0000000*f7f7e59e
```

The OEM7 family of receivers automatically saves almanacs in their Non-Volatile Memory (NVM), therefore creating an almanac boot file is not necessary.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWALM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	ref week	Almanac reference week number	Ulong	4	H
3	ref secs	Almanac reference time (ms)	GPSec	4	H+4
4	#subframes	Number of subframes to follow	Ulong	4	H+8
5	svid	SV ID (satellite vehicle ID) A value between 1 and 32 for the SV ID indicates the PRN of the satellite. Any other values indicate the page ID. See section 20.3.3.5.1.1, Data ID and SV ID, of IS-GPS-200L for more details. To obtain copies of IS-GPS-200, refer to the GPS website (http://www.gps.gov/technical/icwg/).	Ushort	2	H+12
6	data	Subframe page data	Hex	30	H+14
7...	Next subframe offset = H+12+(#subframe x 32)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+12+ (#subframes x 32)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.166 RAWCNAVFRAME

Raw GPS CNAV frame data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides raw frame data from signals which contain the CNAV message (L2C, L5).

The RAWCNAVFRAME log is not output by default. To receive this log, data decoding for L2C or L5 must be enabled using the **DATADECODESIGNAL** command (see page 129) for the specific signal.

Message ID: 1066

Log type: Asynch

Recommended input:

```
log rawcnavframea onnew
```

ASCII example:

```
#RAWCNAVFRAMEA,USB1,0,46.0,SATTIME,2209,512724.000,02000020,ee56,16809;
193,18,30,8b49ea6e7adde57d742cca59ffa72001ee0ffe82cffc7fe01303fefe3908fefca1000
628aca0*40babc24
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWCNAVFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	signal channel	Signal channel providing the bits	Ulong	4	H
3	PRN	Satellite PRN number	Ulong	4	H+4
4	frame ID	frame ID	Ulong	4	H+8
5	data	Raw frame data	Hex[38]	38	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+50
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.167 RAWEPHEM

Raw GPS L1 C/A ephemeris

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw binary information for subframes one, two and three from the GPS satellite L1 C/A signal with the parity information removed. Each subframe is 240 bits long (10 words - 24 bits each) and the log contains a total 720 bits (90 bytes) of information (240 bits x 3 subframes). This information is preceded by the PRN number of the satellite from which it originated. This message is not generated unless all 10 words from all 3 frames have passed parity.

Ephemeris data whose Time of Ephemeris (TOE) is older than six hours is not shown. Multiple logs are output, one for each GPS satellite with collected ephemeris information.

Message ID: 41

Log type: Asynch

Recommended input:

```
log rawephema onall
```

ASCII example:

```
#RAWEPHEMA,USB1,30,54.0,SATTIME,2209,496800.000,02000020,58ba,16809;1,2209,5040
00,8b0284a1b8a52850000724918b913e21a92dc6ee0b217b0c00ffb72fac04,8b0284a1b92b21f
ac82899520ec7b7fb31061550921d09a10d62b87b0c7c,8b0284a1b9adff7d74db71f3ffaa2840e
d6e0fe024cddf1effadc82106c4*0ea3cca1

#RAWEPHEMA,USB1,29,54.0,SATTIME,2209,512730.000,02000020,58ba,16809;2,2209,5184
00,8b0284a6e82728500051d2718b913e21a92dc6eeda427e90000001aa606d,8b0284a6e8aa42f
8f82d56addef337fa840a758d8d1c42a10d56437e907e,8b0284a6e92f00777124a07100c7275ca
76f0e76c62e1e8bffad9c42067f*5581fdb5

#RAWEPHEMA,USB1,28,54.0,SATTIME,2209,496800.000,02000020,58ba,16809;3,2209,5040
00,8b0284a1b8a52850000724918b913e21a92dc6ee04167b0c00ff88e02542,8b0284a1b92b160
57c326224c51f2604ed021ebf6a0db8a10cf92a7b0c7c,8b0284a1b9adffef9ef8203a001627ab6
c56208226d033b4ffa63a160f90*73505674

...

#RAWEPHEMA,USB1,2,54.0,SATTIME,2209,489600.000,02000020,58ba,16809;30,2209,4968
00,8b02849f60a52850000724918b913e21a92dc6ee0847794a00fff3bad3c7,8b02849f612b470
46033f40bb132b0041702f88bd31993a10e34eb794a7d,8b02849f61ad0032f5025ef6004b26264
dc7108e922777edffa6fe47025e*9763ae6b

#RAWEPHEMA,USB1,1,54.0,SATTIME,2209,512730.000,02000020,58ba,16809;31,2209,5184
00,8b0284a6e82728500051d2718b913e21a92dc6eee34b7e9000fff2e8bc16,8b0284a6e6294b0
5352e16795ad6fd044f055757e01ac0a10df3d67e907e,8b0284a6e6afffe1f5457d19ffd026ed0
e00105f0fe105f5ffab7a4bf840*7838d9ba

#RAWEPHEMA,USB1,0,54.0,SATTIME,2209,497010.000,02000020,58ba,16809;32,2209,5040
00,8b0284a1ca242850000724918b913e21a92dc6ee01317b0c00ffb4ef6fcd,8b0284a1c82b31f
9a5348cc6e9b79bfa4d030cf2370e54a10cba597b0c7f,8b0284a1c8ad0066c953c01700082705b
1a61f09a2dcac5bffa65331e786*f299f05c
```

A way to use only one receiver and achieve better than 1 metre accuracy is to use precise orbit and clock files. Three types of GPS ephemeris, clock and earth orientation solutions are compiled by an elaborate network of GNSS receivers around the world all monitoring the satellite characteristics. IGS rapid orbit data is processed to produce files that correct the satellite clock and orbit parameters. Since there is extensive processing involved, these files are available on a delayed schedule from the IGS website: https://igs.org/products-access/#gps-orbits-clocks

Precise ephemeris files are available today to correct GPS data which was collected a few days ago. All you need is one GNSS receiver and a computer to process on. Replace the ephemeris data with the precise ephemeris data and post-process to correct range values.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWEPHEM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	Satellite PRN number	Ulong	4	H
3	ref week	Ephemeris reference week number	Ulong	4	H+4
4	ref secs	Ephemeris reference time (s)	Ulong	4	H+8
5	subframe1	Subframe 1 data	Hex[30]	30	H+12
6	subframe2	Subframe 2 data	Hex[30]	30	H+42
7	subframe3	Subframe 3 data	Hex[30]	30	H+72
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+102
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.168 RAWGPSSUBFRAME

Raw GPS L1 C/A subframe data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw GPS L1 C/A subframe data.

A raw GPS L1 C/A subframe is 300 bits in total. This includes the parity bits which are interspersed with the raw data ten times in six bit chunks, for a total of 60 parity bits. Note Field #5, below, has these 60 parity bits stripped out and only the raw subframe data remains, for a total of 240 bits.

Message ID: 25

Log type: Asynch

Recommended input:

```
log rawgpssubframea onnew
```

ASCII example:

```
#RAWGPSSUBFRAMEA,USB1,0,47.0,SATTIME,2209,512808.000,02000020,0457,16809;2,2,4,
8b0284a6eeb37a4134a0f0469296b5ee80dc7da6ce1ada076697d4296ac6,2*3f833bb6
```

The RAWGPSSUBFRAME log can be used to receive the data bits with the parity bits stripped out. Alternately, you can use the **RAWGPSWORD** log (see page 881) to receive the parity bits in addition to the data bits.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWGPSSUBFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	decode #	Frame decoder number	Long	4	H
3	PRN	Satellite PRN number	Ulong	4	H+4
4	subframe id	Subframe ID	Ulong	4	H+8
5	data	Raw subframe data	Hex[30]	32[1]	H+12
6	signal channel	Signal channel number that the frame was decoded on	Ulong	4	H+44
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+48
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary log case, an additional 2 bytes of padding are added to maintain 4-byte alignment.

3.169 RAWGPSWORD

Raw GPS L1 C/A navigation word

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This message contains the framed GPS L1 C/A raw navigation words. Each log contains a new 30 bit navigation word (in the least significant 30 bits), plus the last 2 bits of the previous word (in the most significant 2 bits). The 30 bit navigation word contains 24 bits of data plus 6 bits of parity. The GPS reference time stamp in the log header is the time the first bit of the 30 bit navigation word was received. Only navigation data that has passed parity checking appears in this log. One log appears for each PRN being tracked every 0.6 seconds if logged ONNEW, ONCHANGED or ONALL.

Message ID: 407

Log type: Asynch

Recommended input:

```
log rawgpsworda onnew
```

ASCII example:

```
#RAWGPSWORDA,USB1,0,55.5,FINESTEERING,2209,512874.069,02000020,9b16,16809;
29,22c0a120*ed4326e9
```

The RAWGPSWORD log can be used to receive the parity bits in addition to the data bits. Alternately, you can use the RAWGPSSUBFRAME log which already has the parity bits stripped out

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWGPSWORD header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	Satellite PRN number	Ulong	4	H
3	nav word	Raw navigation word	Hex[4]	4	H+4
4	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+8
5	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.170 RAWSBASFRAME

Raw SBAS frame data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw SBAS frame data of 226 bits (8-bit preamble, 6-bit message type and 212 bits of data but without a 24-bit CRC). Only frame data with a valid preamble and CRC are reported.

Message ID: 973

Log type: Asynch

Recommended input:

```
log rawsbasframea onnew
```

ASCII example:

```
#RAWSBASFRAMEA,USB1,0,54.0,SATTIME,2209,512912.000,02000020,58e4,16809;166,131,
2,c6089ffc001ffc008000000011ffc001ffdfffffffe797a15739bb95c0,166*2725a69f
```

The RAWSBASFRAME log output contains all the raw data required for an application to compute its own SBAS correction parameters.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWSBASFRAME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	decode #	Frame decoder number	Ulong	4	H
3	PRN	SBAS satellite PRN number	Ulong	4	H+4
4	SBAS frame ID	SBAS frame ID	Ulong	4	H+8
5	raw frame data	Raw SBAS frame data. There are 226 bits of data and 6 bits of padding.	Hex[29]	32[1]	H+12
6	signal channel	Signal channel number that the frame was decoded on.	Ulong	4	H+44
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+48
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary log case, an additional 3 bytes of padding are added to maintain 4-byte alignment.

3.171 RAWSBASFRAME2

Raw SBAS frame data 2

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the raw SBAS frame data of 226 bits (8-bit preamble, 6-bit message type and 212 bits of data but without a 24-bit CRC). It also contains the transmitted frequency. Only frame data with a valid preamble and CRC are reported.

Message ID: 2185

Log type: Asynch

Recommended input:

```
log rawsbasframe2a onnew
```

ASCII example:

```
#RAWSBASFRAME2A,USB1,0,48.5,SATTIME,2209,512947.000,02000020,b39f,16809;135,160
,1,0,0,3,9a0c9ffc00ffe9ffc033ffc005ffdffc121ffc00403ba2b9b97bbb95c0*4e57856f
```

The **RAWSBASFRAME2** log output contains all the raw data required for an application to compute its own SBAS correction parameters.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWSBASFRAME2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PRN	SBAS satellite PRN number	Ulong	4	H
3	signal channel	Signal channel number that the frame was decoded on	Ulong	4	H+4
4	SBAS Signal Source	Identifies the source of the SBAS signal: 1 – SBASL1CA 2 – SBASL5I	Uchar	1	H+8
5	SBAS Preamble Type	Identifies what preamble was used when tracking the SBAS signal: 0 – 8-bit Preamble (3x8) 1 – 4-bit Preamble (6x4)	Uchar	1	H+9
6	Reserved		Ushort	2	H+10
7	SBAS frame ID	SBAS frame ID	Ulong	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
8	data	Raw SBAS frame data. There are 226 bits of data and 6 bits of padding.	Hex[29]	32[1]	H+16
9	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+48
10	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary log case, an additional 3 bytes of padding are added to maintain 4-byte alignment.

3.172 REFSTATION

Base station position and health

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the ECEF Cartesian position of the base station as received through the RTCMV3 message. It also features a time tag, the health status of the base station and the station ID. This information is set at the base station using the **FIX** command (see page 182) and the **DGPSTXID** command (see page 138). See *Figure 13: WGS84 ECEF coordinate system* on page 547 for a definition of the ECEF coordinates.

The base station health, Field #6, may be one of 8 values (0 to 7). Values 0 through 5 indicate the scale factor that is multiplied with the satellite UDRE one-sigma differential error values. Below are values 0 to 5 and their corresponding UDRE scale factors:

0: 1 (Health OK) 0.75 2: 0.5 3: 0.3 4: 0.2 5: 0.1

The base station health field only applies to RTCM base stations. A value of 6 means the base station transmission is not monitored and a value of 7 means that the base station is not working.

Message ID: 175

Log type: Asynch

Recommended input:

```
log refstationa onchanged
```

ASCII example:

```
#REFSTATIONA,USB1,0,68.0,FINESTEERING,2211,233731.221,02000020,4e46,16809;
00000000,-1632851.222,-3662162.724,4944899.271,0,NOVATELX,"K250"*380be9f1
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	REFSTATION header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	status	Status of the base station information (see *Table 214: Base station status* on the next page)	Ulong	4	H
3	x	ECEF X value (m)	Double	8	H+4
4	y	ECEF Y value (m)	Double	8	H+12
5	z	ECEF Z value (m)	Double	8	H+20
6	health	Base station health, see the description at the start of this section	Ulong	4	H+28
7	stn type	Station type (see *Table 215: Base station type* on the next page)	Enum	4	H+32

Field	Field type	Description	Format	Binary bytes	Binary offset
8	stn ID	Base station ID	String[5]	4 or 8[1]	H+36
9	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+40 or H+44
10	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 214: Base station status

Bit #	Mask	Description	Bit = 0	Bit = 1
0	0x00000001	Validity of the base station	Valid	Invalid

Table 215: Base station type

Binary	ASCII	Description
0	NONE	Base station is not used
1 - 3	Reserved	
4	RTCMV3	Base station is RTCMV3

The REFSTATION log can be used for checking the operational status of a remotely located base station. You can verify that the base station is operating properly without travelling to it. This is especially useful for RTK work on long baselines.

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment. The next defined field starts immediately at the next 4-byte alignment following the NULL.

3.173 REFSTATIONINFO

Base station position information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This is an extended version of the REFSTATION log with latitude, longitude and ellipsoidal height of the base station in WGS84. In addition to the base station position, ARP height, antenna model name and antenna serial number are available if provided by the base station only through RTCMV3.

Message ID: 1325

Log type: Asynch

Recommended input:

```
log refstationinfoa onchanged
```

ASCII example:

```
#REFSTATIONINFOA,USB1,0,65.0,FINESTEERING,2211,233851.222,02000020,d38f,16809;
51.150391053,-114.030694086,1081.916599573,WGS84,0.000,0,NOVATELX,"K250","",""
*bc1b1a21
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	REFSTATIONINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	H	0	
2	latitude	Latitude (degrees)	Double	8	H
3	longitude	Longitude (degrees)	Double	8	H+8
4	height	Ellipsoidal Height (m)	Double	8	H+16
5	datum	Datum ID number 61 = WGS84 63 = USER (default = WGS84)	Enum	4	H+24
6	ARP height	Base Antenna ARP (m)	Float	4	H+28
7	health	Base Station Health, see *Table 214: Base station status* on the previous page	Ulong	4	H+32
8	Ref Stn Type	Base Station Type, see (*Table 215: Base station type* on the previous page)	Enum	4	H+36
9	stn ID	Base Station ID	String[5]	4 or 8[1]	H+40

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment. The next defined field starts immediately at the next 4-byte alignment following the NULL.

Field	Field type	Description	Format	Binary bytes	Binary offset
10	Ant Model	Base Antenna Model Name	Char[32]	32	H+44 or H+48
11	Ant Serial	Base Antenna Serial Number	Char[32]	32	H+76 or H+80
12	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+108 or H+112
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.174 ROVERPOS

Position using ALIGN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7**

ALIGN generates distance and bearing information between a base and rover receiver. This log outputs the position information of the rover when using the ALIGN feature. This log can only be output from a Y ALIGN model and can be output at both Base and Rover ends.

You must have an ALIGN capable receiver to use this log.

- ALIGN is useful for obtaining the relative directional heading of a vessel/body, separation heading between two vessels/bodies, or heading information with moving base and pointing applications.
- The log can be output at the Y model Rover only if it is receiving the RTCAREFEXT message from the Base. The log can be output at any Base if the Base is receiving HEADINGEXTB from the Rover.
- ROVERPOS is dependent on the output frequency of the RTCAREFEXT message from the base to the rover.
- On dual antenna receivers, the **ROVERPOS** log outputs the position for the secondary antenna input.

Message ID: 1052

Log type: Asynch

Recommended input:

```
log roverposa onchanged
```

ASCII example:

```
#ROVERPOSA,COM1,0,21.5,FINESTEERING,1544,340322.000,02000008,7453,4655;
SOL_COMPUTED,NARROW_INT,51.11605565964,-114.03854655975,1055.8559,-16.9000,
WGS84,0.0130,0.0122,0.0206,"RRRR",0.0,0.0,13,12,12,11,0,0,0,0*50acac09
```

Asynchronous logs, such as ROVERPOS, should only be logged ONCHANGED or ONNEW, otherwise the most current data is not output when it is available. This is especially true of the ONTIME trigger, which may cause inaccurate time tags to result.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	ROVERPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol stat	Solution Status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position Type see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	lat	Rover WGS84 latitude (degrees)	Double	8	H+8
5	long	Rover WGS84 longitude (degrees)	Double	8	H+16
6	hgt	Rover MSL Height (m)	Double	8	H+24
7	undulation	Undulation (m)	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER (default = WGS84)	Enum	4	H+36
9	lat σ	Latitude standard deviation (m)	Float	4	H+40
10	long σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Rover ID (default = “RRRR”)	Char[4]	4	H+52
13	Reserved		Float	4	H+56
14	Reserved		Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#obs	Number of satellites above elevation mask angle	Uchar	1	H+66
18	#multi	Number of satellites with multi-frequency signals above elevation mask angle	Uchar	1	H+67
19	Reserved		Hex	1	H+68
20			Uchar	1	H+69
21			Uchar	1	H+70
22			Uchar	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	1	H+72
24	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

3.175 RTCMV3 standard logs

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

NovAtel's RTCMv3 logs are implementations of the messages described by the RTCM SC-104 committee's "Differential GNSS (Global Navigation Satellite Systems) Services – Version 3" standard. These messages are primarily intended to support RTK operations. They are also an alternative raw data format to NovAtel's proprietary messages.

The RTCMv3 logs can be divided into several categories that are described below. An RTK base station must minimally transmit one or more observable message, together with one or more station and antenna message. The **GENERATERTKCORRECTIONS** command on page 200 illustrates an appropriate set of messages and is an easy way to configure logging.

Example input:

```
interfacemode com2 none RTCMV3
fix position 51.1136 -114.0435 1059.4
thisantennatype NOV702
log com2 rtcm1006 ontime 10
log com2 rtcm1230 ontime 10
log com2 rtcm1033 ontime 10 2
log com2 rtcm1004 ontime 1
log com2 rtcm1012 ontime 1
```

Example input using MSM4 messages:

```
interfacemode com1 none rtcmv3 off
thisantennatype nov850
fix position 51.1136 -114.0435 1059.4
log com1 rtcm1006 ontime 10
log com1 rtcm1230 ontime 10
log com1 rtcm1033 ontime 10 2
log com1 rtcm1074 ontime 1
log com1 rtcm1084 ontime 1
log com1 rtcm1094 ontime 1
log com1 rtcm1124 ontime 1
```

3.175.1 Legacy observable messages

The legacy observable messages contain GPS and GLONASS code and phase observables. The *extended* messages additionally contain the C/N0.

Table 216: Legacy observable messages

Log name	Message ID	Description
RTCM1001	772	GPS L1-only observables, basic
RTCM1002	774	GPS L1-only observables, extended
RTCM1003	776	GPS L1/L2 basic observables, basic
RTCM1004	770	GPS L1/L2 basic observables, extended
RTCM1009	885	GLONASS L1-only observables, basic
RTCM1010	887	GLONASS L1-only observables, extended
RTCM1011	889	GLONASS L1/L2 basic observables, basic
RTCM1012	891	GLONASS L1/L2 basic observables, extended

3.175.2 MSM observable messages

The Multiple Signal Messages (MSM) are observable messages for all current GNSS systems. They provide a standardized framework for message content and are designed to support future systems and signals.



Sending legacy (1001-1004 and 1009-1012) and MSM messages in the same stream can cause problems for remote RTK users and is not recommended.

Each GNSS system has a set of seven MSM types numbered from 1 to 7. The MSM type for each GNSS system provides the same generic information. Generally, as the MSM number increases, more information is available in the messages. For example, MSM1 for each GNSS system provides the code measurements for the system, while MSM3 provides both the code and phase.

The information encoded in each MSM variant is described in *Table 217: MSM type descriptions* below for the descriptions of each of the seven MSM types. For RTK operations, MSM3 is minimally recommended.

Table 217: MSM type descriptions

Message	Description
MSM1	Provides the code measurements.
MSM2	Provides the phase measurements.
MSM3	Provides the data from MSM1 (code) and MSM2 (phase) in a single message.
MSM4	Provides all the data from MSM3 (code and phase) and adds the CNR measurements.
MSM5	Provides all the data from MSM4 (code, phase and CNR) and adds the doppler measurements.
MSM6	Provides the same information as MSM4, but has extended resolution on the measurements.
MSM7	Provides the same information as MSM5, but has extended resolution on the measurements.

Table 218: MSM log names on the next page lists the MSM message name and *Table 219: MSM message IDs* on the next page lists the message IDs.

Table 218: MSM log names

Message	GPS	GLONASS	Galileo	QZSS	BeiDou
MSM1	RTCM1071	RTCM1081	RTCM1091	RTCM1111	RTCM1121
MSM2	RTCM1072	RTCM1082	RTCM1092	RTCM1112	RTCM1122
MSM3	RTCM1073	RTCM1083	RTCM1093	RTCM1113	RTCM1123
MSM4	RTCM1074	RTCM1084	RTCM1094	RTCM1114	RTCM1124
MSM5	RTCM1075	RTCM1085	RTCM1095	RTCM1115	RTCM1125
MSM6	RTCM1076	RTCM1086	RTCM1096	RTCM1116	RTCM1126
MSM7	RTCM1077	RTCM1087	RTCM1097	RTCM1117	RTCM1127

Table 219: MSM message IDs

Message	GPS	GLONASS	Galileo	QZSS	BeiDou
MSM1	1472	1479	1486	1648	1592
MSM2	1473	1480	1487	1649	1593
MSM3	1474	1481	1488	1650	1594
MSM4	1475	1482	1489	1651	1595
MSM5	1476	1483	1490	1652	1596
MSM6	1477	1484	1491	1653	1597
MSM7	1478	1485	1492	1654	1598

3.175.3 Station and antenna messages

The station and antenna messages listed in *Table 220: Station and antenna messages* on the next page provide the base station's coordinates and hardware. Remote RTK users require this information so that they can position themselves relative to a base station.

- Message Type 1005 provides the Earth-Centred, Earth-Fixed (ECEF) coordinates of the Antenna Reference Point (ARP). The ARP is an explicit physical point on the antenna, typically the center of its base. It is related to the antenna phase center from where the measurements are emitted via the Phase Center Offsets (PCOs). The PCOs can be set using the **THISANTENNAPCO** command (see page 428) or **THISANTENNATYPE** command (see page 430). If the PCOs are not set, then the coordinates transmitted by Message types 1005 and 1006 will be those that the receiver is fixed to by the **FIX** command (see page 182).
- Message Type 1006 is the same as 1005 but additionally provides the antenna height. This value is always set to zero by the receiver firmware.
- Message Type 1007 provides the base station antenna type. Conventionally, the antenna name from the International GNSS Service (IGS) is used. The antenna name can be set using the **THISANTENNATYPE** command (see page 430).
- Message Type 1008 is the same as 1007 but additionally provides the antenna serial number. The serial number is always set to null by the receiver firmware.

- Message Type 1033, like message types 1007 and 1008, also provides the antenna information. Message type 1033 additionally provides the receiver type and firmware version. The primary use of this information is to more-easily enable RTK rovers to fix their GLONASS ambiguities. This information is filled automatically and appropriately by the receiver firmware.

For a receiver operating as an RTK base station, the recommended messages to transmit are 1006 and 1033. With these messages remote RTK users have all the information describing the base station.

Table 220: Station and antenna messages

Log name	Message ID	RTCM message type	Description
RTCM1005	765	1005	Stationary RTK Base Station Antenna Reference Point (ARP)
RTCM1006	768	1006	Stationary RTK Base Station ARP with Antenna Height
RTCM1007	852	1007	Extended Antenna Descriptor and Setup Information
RTCM1008	854	1008	Extended Antenna Reference Station Description and Serial Number
RTCM1033	1097	1033	Receiver and antenna descriptors

3.175.4 Ephemeris messages

The ephemeris messages listed in *Table 221: Ephemeris messages* below provide the satellite ephemerides. For RTK operations this information is optional, as RTK rovers will be downloading their own ephemerides directly from the satellites.

There are two messages for each ephemeris type. For the messages logged ONTIME (e.g. LOG RTCM1019 ONTIME 10) a single satellite's ephemeris is output at each ONTIME interval. The ephemerides will be cycled through in numerical order. For the messages logged ONCHANGED (e.g., LOG RTCM1019ASYNC ONCHANGED), new or changed ephemerides will be output as soon as they are available.

Table 221: Ephemeris messages

Log name	Message ID	RTCM message type	Description
RTCM1019	893	1019	GPS Ephemerides, logged ONTIME
RTCM1019ASYNC	2088	1019	GPS Ephemerides, logged ONCHANGED
RTCM1020	895	1020	GLONASS Ephemerides, logged ONTIME
RTCM1020ASYNC	2089	1020	GLONASS Ephemerides, logged ONCHANGED
RTCM1042	2171	1042	BeiDou Ephemerides, logged ONTIME
RTCM1042ASYNC	2170	1042	BeiDou Ephemerides, logged ONCHANGED
RTCM1044	2177	1044	QZSS Ephemerides, logged ONTIME
RTCM1044ASYNC	2176	1044	QZSS Ephemerides, logged ONCHANGED
RTCM1045	2173	1045	Galileo F/NAV Ephemerides, logged ONTIME

Log name	Message ID	RTCM message type	Description
RTCM1045ASYNC	2172	1045	Galileo F/NAV Ephemerides, logged ONCHANGED
RTCM1046	2175	1046	Galileo I/NAV Ephemerides, logged ONTIME
RTCM1046ASYNC	2174	1046	Galileo I/NAV Ephemerides, logged ONCHANGED

3.175.5 GLONASS bias information message

Message 1230 communicates the GLONASS Code-Phase Bias (CPB) information. This information allows RTK rovers to compensate for differences in biases between themselves and the base station, enabling or improving the resolution of GLONASS ambiguities.

CPB values for all GLONASS FDMA signals available in the data stream of both MSM and Legacy (1081-1088 and 1009-1012) are mandatory for full GLONASS interoperability.

With some base stations, message 1033 is not sufficient for full GLONASS interoperability. The message 1033 was not originally designed to compensate for CPB and therefore message 1230 has been developed to improve GLONASS interoperability and should be used to assure full interoperability.

Table 222: GLONASS bias information message

Log name	Message ID	RTCM message type	Description
RTCM1230	1655	1230	GLONASS L1 and L2 Code-Phase Biases

3.176 RTKASSISTSTATUS

RTK ASSIST status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides information on the state of RTK ASSIST.

RTK ASSIST operates in two modes: coast and full assist. The RTKASSISTSTATUS log reports which mode is currently available. Coast mode is available as soon as the RTK ASSIST corrections are received from the L-band satellite, while full assist mode requires a convergence period. In coast mode, position error growth during RTK correction outages is slightly worse than in full assist mode and RTK will not resume following a full signal outage until after RTK corrections are restored. Full assist gives the lowest position error growth during RTK correction outages, and makes it possible for RTK to resume even if there are complete GNSS signal outages during the RTK ASSIST period.

The RTK ASSIST ACTIVE state reported in the RTKASSISTSTATUS log is also reported in the RTKPOS and BESTPOS extended solution status field. See *Table 99: Extended solution status* on page 534.

The RTKASSISTSTATUS log reports the time remaining in the RTK ASSIST ACTIVE state. Once RTK ASSIST becomes active, the remaining time will count down from the time out set by the **RTKASSISTTIMEOUT** command (see page 338) .

The corrections age reported in the RTKASSISTSTATUS log should typically be below 30 seconds. If the age exceeds this value, then L-band tracking is likely degraded. The most likely cause of degraded L-band tracking are obstructions between the antenna and the L-band satellite.

Message ID: 2048

Log type: Synch

Recommended input:

```
log rtkassiststatusa ontime 5
```

ASCII example:

```
#RTKASSISTSTATUSA,USB1,0,55.5,FINESTEERING,2209,513133.000,02000020,80fe,16809;
INACTIVE,UNAVAILABLE,0.0,13.0*4966edec
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKASSISTSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	State	State: INACTIVE (0) ACTIVE (1)	Enum	4	H

Field	Field type	Description	Format	Binary bytes	Binary offset
3	Mode	Mode: UNAVAILABLE (0) COAST (1) ASSIST (2)	Enum	4	H+4
4	Remaining time	Time remaining in seconds	Float	4	H+8
5	Corrections age	Age of the RTK ASSIST corrections in seconds. Maximum value of 120 seconds.	Float	4	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+16
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.177 RTKDATUMINFO

Datum information for the RTK position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution in the **RTKPOS** log (see page 903).

Message ID: 2304

Log type: Asynch

Recommended input:

```
log rtkdatuminfoa onchanged
```

ASCII example:

```
#RTKDATUMINFOA,USB1,0,66.5,FINESTEERING,2211,234000.000,02000020,0b0c,16809;
"UNKNOWN",0,0.000,SERVICE_DETAILS_UNKNOWN*08717033
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of the position being output by the **RTKPOS** log. For RTK at the rover location, when the base station datum is not known to the user, "UNKNOWN" is reported as the datum.	Char[32]	variable	H
3	epsg_code	EPSG code of datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year) Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation Status. See *Table 94: Transformation status* on page 524.	Enum	4	variable
6	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
7	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.178 RTKDOP

DOP values for the satellites used in the RTK solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The RTKDOP log contains the Dilution Of Precision (DOP) values for the satellites being used in the RTK solution. Note that unlike the **PSRDOP** log (see page 796), the RTKDOP log is synchronous. DOP values will be calculated at the requested rate, up to a maximum rate of 1 Hz.

DOP values are a measure of the solution strength. Essentially, the DOPs reflect the geometry of the satellites used in the solution. Solutions with good counts of well-distributed satellites will have low DOPs and should be accurate and reliable. Solutions with fewer or poorly-distributed satellites will have high DOPs and be less accurate and reliable. As a rough guideline, PDOP values less than 4 imply a solution with reasonable geometry.

There can be many reasons for high DOP values. The most common reason is that there are obstructions limiting satellite visibility. Even if satellites are visible and being tracked they might still not be used in the solution if, for example, they are unhealthy or there aren't corrections available for them. The **RTKSATS** log (see page 906) will inform which satellites are being tracked and explain why a tracked satellite is not used in the solution.

The DOPs do not consider that different satellites or signals will be weighted differently in the solution. Therefore, they do not completely reflect the solution quality. Ultimately, the standard deviations reported in the **RTKPOS** log (see page 903) are the best reflection of the solution accuracy.

Message ID: 952

Log type: Synch

Recommended input:

```
log rtkdopa ontime 10
```

ASCII example:

```
#RTKDOPA,USB1,0,66.5,FINESTEERING,2211,234163.000,02000020,b42b,16809;
1.3390,1.0580,0.6760,0.8610,0.5340,5.0,16,17,3,6,12,19,2,24,14,1,46,57,38,47,
45,55,56*6757f996
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKDOP header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	GDOP	Geometric DOP	Float	4	H
3	PDOP	Position DOP	Float	4	H+4
4	HDOP	Horizontal DOP	Float	4	H+8
5	HTDOP	Horizontal and time DOP	Float	4	H+12
6	TDOP	GPS Time DOP	Float	4	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
7	elev mask	GPS elevation mask angle	Float	4	H+20
8	#sats	Number of satellites to follow	Ulong	4	H+24
9	sats	Satellites in use at time of calculation	Ulong	4	H+28
10	Next satellite offset = H+28+(#sats * 4)				
11	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+28+(#sats * 4)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.179 RTKDOP2

DOP values for the satellites used in the RTK solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The RTKDOP2 log contains the Dilution Of Precision (DOP) values for the satellites being used in the RTK solution. This log is similar to the **RTKDOP** log (see page 899) but contains the per-system TDOPs; see the **RTKDOP** log on page 899 for more information on the DOPs.

Message ID: 1172

Log type: Synch

Recommended input:

```
log rtkdop2a ontime 10
```

ASCII example:

```
#RTKDOP2A,USB1,0,66.5,FINESTEERING,2211,234263.000,02000020,ab50,16809;
1.4290,1.1150,0.6970,0.8710,2,GPS,0.5660,GLONASS,0.6910*eced00f5
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKDOP2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	GDOP	Geometric DOP	Float	4	H
3	PDOP	Position DOP	Float	4	H+4
4	HDOP	Horizontal DOP	Float	4	H+8
5	VDOP	Vertical DOP	Float	4	H+12
6	#systems	Number of entries to follow	Ulong	4	H+16
7	system	See *Table 223: System used for timing* on the next page	Enum	4	H+20
8	TDOP	Time DOP (Dilution of Precision)	Float	4	H+24
9	Next satellite offset = H+20+(#systems * 8)				
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+20+(#systems * 8)
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 223: System used for timing

Binary	ASCII
0	GPS[1]
1	GLONASS
2	GALILEO
3	BEIDOU
4	NAVIC
99	AUTO[2]

1. GPS setting includes QZSS satellites.

2. AUTO is used only as a backup system (not available for primary system field).

3.180 RTKPOS

RTK low latency position data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the low latency RTK position computed by the receiver, along with two status flags. In addition, it reports other status indicators, including differential age, which is useful in predicting anomalous behaviour brought about by outages in differential corrections. This log is recommended for kinematic operation. Better accuracy can be obtained in static operation with the **MATCHEDPOS** log (see page 728).

With the system operating in an RTK mode, this log reflects if the solution is a good RTK low latency solution (from extrapolated base station measurements) or invalid. A valid RTK low latency solution is computed for up to 60 seconds after reception of the last base station observation. The degradation in accuracy, due to differential age, is reflected in the standard deviation fields. See also the **DGPSTXID** command (see page 138).

The RTK system in the receiver provides two kinds of position solutions. The Matched RTK position is computed with buffered observations, so there is no error due to the extrapolation of base station measurements. This provides the highest accuracy solution possible at the expense of some latency which is affected primarily by the speed of the differential data link. The **MATCHEDPOS** log (see page 728) contains the matched RTK solution and can be generated for each processed set of base station observations.

The Low-Latency RTK position is computed from the latest local observations and extrapolated base station observations. This supplies a valid RTK position with the lowest latency possible at the expense of some accuracy. The degradation in accuracy is reflected in the standard deviation. The amount of time that the base station observations are extrapolated is in the "differential age" field of the position log. The Low-Latency RTK system extrapolates for 60 seconds. The **RTKPOS** log contains the Low-Latency RTK position when valid, and an "invalid" status when a Low-Latency RTK solution could not be computed. The **BESTPOS** log (see page 527) contains either the low-latency RTK, PPP or pseudorange-based position, whichever has the smallest standard deviation.

Message ID: 141

Log type: Synch

Recommended input:

```
log rtkposa ontime 1
```

ASCII example:

```
#RTKPOSA,USB1,0,66.5,FINESTEERING,2211,234400.000,02000020,69d3,16809;
SOL_COMPUTED,NARROW_INT,51.15043865488,-114.03067348527,1098.9222,-17.0000,
WGS84,0.0075,0.0067,0.0124,"K250",1.000,0.000,33,30,30,29,00,01,3f,37*19a70ef3
```

Consider the case of a racing car, on a closed circuit, requiring RTK operation. In this situation, you would have to send live data to the pits using a radio link.

RTK operation enables live centimetre level position accuracy. When answers are required in the field, the base station must transmit information to the rover in real-time. For RTK operation, extra equipment such as radios are required to transmit and receive this information. The base station has a corresponding base radio and the rover station has a corresponding rover radio.

Post-processing can provide post-mission position and velocity data using raw GNSS data collected from the car. The logs necessary for post-processing include:

```
RANGECMPB ONTIME 1
RAWEPHEMB ONNEW
```

These are examples of data collection for post-processing, and real-time operation. OEM7-based output is compatible with post-processing software from the NovAtel's Waypoint Products Group or refer to our website at novatel.com/products/waypoint-software for more details.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (see *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (see *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	lat	Latitude (degrees)	Double	8	H+8
5	lon	Longitude (degrees)	Double	8	H+16
6	hgt	Height above mean sea level (m)	Double	8	H+24
7	undulation	Undulation - the relationship between the geoid and the WGS84 ellipsoid (m) When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+32
8	datum id#	Datum ID number 61 = WGS84 63 = USER	Enum	4	H+36
9	lat σ	Latitude standard deviation (m)	Float	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
10	lon σ	Longitude standard deviation (m)	Float	4	H+44
11	hgt σ	Height standard deviation (m)	Float	4	H+48
12	stn id	Base station ID	Char[4]	4	H+52
13	diff_age	Differential age in seconds	Float	4	H+56
14	sol_age	Solution age in seconds	Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellites used in solution	Uchar	1	H+65
17	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	Reserved		Hex	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.181 RTKSATS

Satellites used in RTKPOS solution

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the used and unused satellites for the corresponding RTKPOS solution. It also describes the signals of the used satellites and reasons for exclusions.

Message ID: 1174

Log type: Synch

Recommended input:

```
log rtksatsa ontime 1
```

Abbreviated ASCII example:

```
<RTKSATS COM1 0 64.0 FINESTEERING 2220 503054.000 02000000 95e7 16807
<     37
<          GPS 18 GOOD 00000007
<          GPS 16 GOOD 00000003
<          GPS 5 GOOD 00000003
<          GPS 27 GOOD 00000007
<          GPS 29 GOOD 00000003
<          GPS 10 GOOD 00000007
<          GPS 23 GOOD 00000007
<          GPS 13 GOOD 00000003
<          GPS 15 GOOD 00000003
<          GPS 26 GOOD 00000007
<          QZSS 194 GOOD 00000007
<          GLONASS 18-3 GOOD 00000003
<          GLONASS 9-2 SUPPLEMENTARY 00000003
<          GLONASS 2-4 GOOD 00000003
<          GLONASS 15 GOOD 00000003
<          GLONASS 1+1 GOOD 00000003
<          GLONASS 24+2 GOOD 00000003
<          GLONASS 23+3 GOOD 00000001
<          GLONASS 17+4 GOOD 00000003
<          GLONASS 8+6 GOOD 00000003
<          GALILEO 15 GOOD 0000000f
<          GALILEO 27 GOOD 0000000f
<          GALILEO 3 GOOD 0000000f
<          GALILEO 36 GOOD 0000000f
<          GALILEO 5 GOOD 0000000f
<          GALILEO 21 GOOD 0000000f
<          GALILEO 30 GOOD 0000000f
<          GALILEO 9 GOOD 0000000f
<          BEIDOU 28 GOOD 0000001d
<          BEIDOU 33 GOOD 0000001d
<          BEIDOU 42 GOOD 0000001d
<          BEIDOU 27 GOOD 0000001d
<          BEIDOU 43 GOOD 0000001d
<          BEIDOU 41 GOOD 0000001d
<          BEIDOU 40 GOOD 0000001d
<          BEIDOU 11 GOOD 00000007
```

```
<           BEIDOU 14 GOOD 00000007
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKSATS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#entries	Number of records to follow	Ulong	4	H
3	system	Satellite system (refer to *Table 145: Satellite system* on page 676)	Enum	4	H+4
4	Satellite ID	Satellite identifiers	Ulong	4	H+8
5	Status	Satellite status. See *Table 101: Observation statuses* on page 536	Enum	4	H+12
6	Signal mask	See *Table 102: GPS signal mask* on page 537, *Table 103: GLONASS signal mask* on page 538, *Table 104: Galileo signal mask* on page 538, *Table 105: BeiDou signal mask* on page 538, *Table 106: QZSS signal mask* on page 538 and *Table 107: NavIC signal mask* on page 538	Hex	4	H+16
7	Next satellite offset = H+4+(#sat x 16)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#sat x 16)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.182 RTKVEL

RTK velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the RTK velocity information computed by the receiver. In addition, it reports a velocity status indicator that is useful in indicating whether or not the corresponding data is valid and differential age is useful in predicting anomalous behaviour brought about by outages in differential corrections. The velocity measurements sometimes have a latency associated with them. The time of validity is the time tag in the log minus the latency value.

Velocities from the RTK filter are calculated from the delta-position. In RTKVEL, the velocity type is the same as the position type.

In an RTKVEL log, the actual speed and direction of the receiver antenna over ground is provided. The receiver does not determine the direction a vessel, craft or vehicle is pointed (heading) but rather the direction of motion of the GNSS antenna relative to ground.

With the system operating in an RTK mode, this log reflects if the solution is a good RTK low latency solution (from extrapolated base station measurements) or invalid. A valid RTK low latency solution is computed for up to 60 seconds after reception of the last base station observation.

The velocity is computed from consecutive RTK low latency updates. As such, it is an average velocity based on the time difference between successive position computations and not an instantaneous velocity at the RTKVEL time tag. The velocity latency to be subtracted from the time tag is normally half the time between filter updates. Under default operation, the RTK low latency filter is updated at a rate of 2 Hz. This translates into a velocity latency of 0.25 seconds. The latency can be reduced by increasing the update rate of the RTK low latency filter by requesting the BESTVEL, RTKVEL, BESTPOS or RTKPOS messages at a rate higher than 2 Hz. For example, a logging rate of 10 Hz would reduce the velocity latency to 0.05 seconds. For integration purposes, the velocity latency should be applied to the record time tag.

Message ID: 216

Log type: Synch

Recommended input:

```
log rtkvela ontime 1
```

ASCII example:

```
#RTKVELA,USB1,0,66.0,FINESTEERING,2211,234952.000,02000020,2e4e,16809;
SOL_COMPUTED,NARROW_INT,0.250,1.000,0.0019,51.860326,-0.0004,0*4a6563f7
```

Consider the case of an unmanned aircraft. A base station must send differential correction data to the remote aircraft. In this type of application, the aircraft's radio may pass the differential solution, for example RTKVEL, to the positioning system so it can process it and generate precise position information for the flight controls.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKVEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	vel type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results	Float	4	H+8
5	age	Differential age in seconds	Float	4	H+12
6	hor spd	Horizontal speed over ground, in metres per second	Double	8	H+16
7	trk gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees	Double	8	H+24
8	vert spd	Vertical speed, in metres per second, where positive values indicate increasing altitude (up) and negative values indicate decreasing altitude (down)	Double	8	H+32
9	Reserved		Float	4	H+40
10	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+44
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.183 RTKXYZ

RTK Cartesian position and velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the receiver's low latency position and velocity in ECEF coordinates. The position and velocity status fields indicate whether or not the corresponding data is valid. See *Figure 13: WGS84 ECEF coordinate system* on page 547 for a definition of the ECEF coordinates.

The velocity measurements have a latency associated with them. The time of validity is the time tag in the log minus the latency value.

With the system operating in an RTK mode, this log reflects if the solution is a good RTK low latency solution (from extrapolated base station measurements) or invalid. A valid RTK low latency solution is computed for up to 60 seconds after reception of the last base station observation. The degradation in accuracy due to differential age is reflected in the standard deviation fields. See also the **DGPSTXID** command (see page 138).

The velocity is computed from consecutive RTK low latency updates. As such, it is an average velocity based on the time difference between successive position computations and not an instantaneous velocity at the RTKVEL time tag. The velocity latency to be subtracted from the time tag is normally half the time between filter updates. Under default operation, the RTK low latency filter is updated at a rate of 2 Hz. This translates into a velocity latency of 0.25 seconds. The latency can be reduced by increasing the update rate of the RTK low latency filter by requesting the **BESTXYZ** message at a rate higher than 2 Hz. For example, a logging rate of 10 Hz would reduce the velocity latency to 0.05 seconds. For integration purposes, the velocity latency should be applied to the record time tag.

See also the **BESTXYZ** log on page 545 and **MATCHEDXYZ** log on page 733.



The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command (see page 284).

Message ID: 244

Log type: Synch

Recommended input:

```
log rtkxyza ontime 1
```

ASCII example:

```
#RTKXYZA,USB1,0,64.5,FINESTEERING,2211,235074.000,02000020,40ee,16809;
SOL_COMPUTED,NARROW_INT,-1632848.2305,-3662159.5450,4944902.5890,0.0074,0.0088,
0.0110,SOL_COMPUTED,NARROW_INT,-0.0010,0.0011,-0.0005,0.0063,0.0067,0.0102,
"K250",0.250,1.000,0.000,37,31,31,30,0,01,3f,37*969e6a51
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RTKXYZ header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	P-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	pos type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	P-X	Position X-coordinate (m)	Double	8	H+8
5	P-Y	Position Y-coordinate (m)	Double	8	H+16
6	P-Z	Position Z-coordinate (m)	Double	8	H+24
7	P-X σ	Standard deviation of P-X (m)	Float	4	H+32
8	P-Y σ	Standard deviation of P-Y (m)	Float	4	H+36
9	P-Z σ	Standard deviation of P-Z (m)	Float	4	H+40
10	V-sol status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H+44
11	vel type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+48
12	V-X	Velocity vector along X-axis (m)	Double	8	H+52
13	V-Y	Velocity vector along Y-axis (m)	Double	8	H+60
14	V-Z	Velocity vector along Z-axis (m)	Double	8	H+68
15	V-X σ	Standard deviation of V-X (m)	Float	4	H+76
16	V-Y σ	Standard deviation of V-Y (m)	Float	4	H+80
17	V-Z σ	Standard deviation of V-Z (m)	Float	4	H+84
18	stn ID	Base station identification	Char[4]	4	H+88
19	V-latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results.	Float	4	H+92
20	diff_age	Differential age in seconds	Float	4	H+96
21	sol_age	Solution age in seconds	Float	4	H+100
22	#SVs	Number of satellites tracked	Uchar	1	H+104
23	#solnSVs	Number of satellites used in solution	Uchar	1	H+105
24	#ggL1	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+106
25	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+107
26	Reserved		Char	1	H+108

Field	Field type	Description	Format	Binary bytes	Binary offset
27	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+109
28	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+110
29	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+111
30	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+112
31	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.184 RXCONFIG

Receiver configuration

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log is used to output the current configuration of the receiver. The commands that are saved as part of a configuration are typically **LOG** requests, communication configuration commands such as **SERIALCONFIG**, and tracking or positioning configuration commands such as **ELEVATIONCUTOFF**. Note that not all commands can be saved using **SAVECONFIG**. All of the commands that make up the configuration, including default commands for the receiver, are listed in the **RXCONFIG** log.

When requested, one **RXCONFIG** log is output for each setting.

Note that **LOGLIST** log on page 712 can be used to see the logging configuration.

Message ID: 128

Log type: Collection

Recommended input:

```
log rxconfiga once
```

ASCII example:

```
#RXCONFIGA,COM2,240,82.0,UNKNOWN,0,0.857,1a4c4020,f702,16942;#ADJUST1PPSA,COM2,
240,82.0,UNKNOWN,0,0.857,1a4c4020,f702,16942;OFF*44ebb463*c212d337

#RXCONFIGA,COM2,239,82.0,UNKNOWN,0,0.858,1a4c4020,f702,16942;#AGCMODEA,COM2,239
,82.0,UNKNOWN,0,0.858,1a4c4020,f702,16942;0,AUTO*7cdceff7*3548e623

#RXCONFIGA,COM2,238,82.0,UNKNOWN,0,0.858,1a4c4020,f702,16942;#AGCMODEA,COM2,238
,82.0,UNKNOWN,0,0.858,1a4c4020,f702,16942;1,AUTO*38d81341*51af2d69

#RXCONFIGA,COM2,237,82.0,UNKNOWN,0,0.860,1a4c4020,f702,16942;#AGCMODEA,COM2,237
,82.0,UNKNOWN,0,0.860,1a4c4020,f702,16942;2,AUTO*ad664e8e*24cbe593

#RXCONFIGA,COM2,236,82.0,UNKNOWN,0,0.860,1a4c4020,f702,16942;#AGCMODEA,COM2,236
,82.0,UNKNOWN,0,0.860,1a4c4020,f702,16942;3,AUTO*e962b238*a7f2317d

#RXCONFIGA,COM2,235,82.0,UNKNOWN,0,0.862,1a4c4020,f702,16942;#ANTENNAPOWERA,COM
2,235,82.0,UNKNOWN,0,0.862,1a4c4020,f702,16942;ON*4e212f4a*3c076320

...

#RXCONFIGA,COM2,225,82.0,UNKNOWN,0,0.877,1a4c4020,f702,16942;#CCOMCONFIGA,COM2,
225,82.0,UNKNOWN,0,0.877,1a4c4020,f702,16942;CCOM5,NONE,NONE,0,0,00*57e233f3*a4
e74dde

#RXCONFIGA,COM2,224,82.0,UNKNOWN,0,0.880,1a4c4020,f702,16942;#CCOMCONFIGA,COM2,
224,82.0,UNKNOWN,0,0.880,1a4c4020,f702,16942;CCOM6,NONE,NONE,0,0,00*2bb09198*bc
103ec9

#RXCONFIGA,COM2,223,82.0,UNKNOWN,0,0.880,1a4c4020,f702,16942;#CLOCKADJUSTA,COM2
,223,82.0,UNKNOWN,0,0.880,1a4c4020,f702,16942;ENABLE*45672fcf*a6db790f

#RXCONFIGA,COM2,222,82.0,UNKNOWN,0,0.880,1a4c4020,f702,16942;#CLOCKOFFSETA,COM2
,222,82.0,UNKNOWN,0,0.880,1a4c4020,f702,16942;0*efd0112a*75ccf8c7

#RXCONFIGA,COM2,221,82.0,UNKNOWN,0,0.882,1a4c4020,f702,16942;#CLOCKSTEERINGBIAS
```

```
TOLERANCEA,COM2,221,82.0,UNKNOWN,0,0.882,1a4c4020,f702,16942;100.0*92e89c27*0c5
8c011

#RXCONFIGA,COM2,220,82.0,UNKNOWN,0,0.882,1a4c4020,f702,16942;#CLOCKSTEERINGSOUR
CEA,COM2,220,82.0,UNKNOWN,0,0.882,1a4c4020,f702,16942;SINGLE*1c34a54a*9e3a5e6d
```

The embedded CRCs are inverted to prevent RXCONFIG output being treated as input by mistake. To make the embedded messages recognizable to the receiver, invert the CRC. For example, consider the first embedded message above.

```
#RXCONFIGA,COM2,240,82.0,UNKNOWN,0,0.857,1a4c4020,f702,16942;
#ADJUST1PPSA,COM2,240,82.0,UNKNOWN,0,0.857,1a4c4020,f702,16942;
OFF*44ebb463*c212d337
```

The embedded CRC for the ADJUST1PPS command is **44ebb463**

This can be inverted with the "Bitwise exclusive OR operator" (XOR) in the following algorithm:

b = 0x44ebb463 ^ 0xFFFFFFFF

b = 0xbb144b9c

The command becomes:

```
#ADJUST1PPSA,COM2,240,82.0,UNKNOWN,0,0.857,1a4c4020,f702,16942;
OFF*bb144b9c
```

Do not use undocumented commands or logs! Doing so may produce errors and void your warranty.

The RXCONFIG log can be used to ensure your receiver is correctly setup for your application.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RXCONFIG header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	e header	Embedded header	-	h	H
3	e msg	Embedded message	Varied	a	H+h
4	e xxxx	Embedded (inverted) 32-bit CRC (ASCII and Binary only). The embedded CRC is inverted so that the receiver does not recognize the embedded messages as messages to be output but continues with the RXCONFIG message. If you wish to use the messages output from the RXCONFIG log, simply flip the embedded CRC around for individual messages	Ulong	4	H+h+a
5	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+h+a+4
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.185 RXCONFIGUSER

User receiver configuration

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log is similar to the **RXCONFIG** log, but rather than showing the complete configuration of the receiver, this log is used to output only the configuration settings that have been changed from the factory default (by the user or by commands triggered internally).

When requested, one **RXCONFIGUSER** log is output for each setting.

Note that **LOGLIST** log on page 712 can be used to see the logging configuration.

Message ID: 2474

Log type: Polled

Recommended input:

```
log rxconfigusera once
```

ASCII example:

```
#RXCONFIGUSERA,COM1,1,80.0,FINESTEERING,2247,336957.009,02440020,857d,32768;
#SBASCONTROLA,COM1,1,80.0,FINESTEERING,2247,336957.009,02440020,675d,32768;
ENABLE,AUTO,0,NONE*428e4d2d*11e8c050
```

```
#RXCONFIGUSERA,COM1,0,80.0,FINESTEERING,2247,336957.009,02440020,857d,32768;
#SERIALCONFIGA,COM1,0,80.0,FINESTEERING,2247,336957.009,02440020,6be8,32768;
COM3,115200,N,8,1,N,ON*302f87ec*76bb6e1d
```

The embedded CRCs are inverted to prevent RXCONFIGUSER output being treated as input by mistake. To make the embedded messages recognizable to the receiver, invert the CRC. For example, consider the first embedded message above.

```
#RXCONFIGUSERA,COM1,1,80.0,FINESTEERING,2247,336957.009,02440020,
857d,32768;#SBASCONTROLA,COM1,1,80.0,FINESTEERING,2247,336957.009,
02440020,675d,32768;ENABLE,AUTO,0,NONE*428e4d2d*11e8c050
```

The embedded CRC for the SBASCONTROL command is **0x428e4d2d**.

This can be inverted with the "Bitwise exclusive OR operator" (XOR) in the following algorithm:

b = 0x428e4d2d ^ 0xFFFFFFFF

b = 0xbd71b2d2

The command becomes:

```
#SBASCONTROLA,COM1,1,80.0,FINESTEERING,2247,336957.009,02440020,
675d,32768;ENABLE,AUTO,0,NONE*bd71b2d2
```

Do not use undocumented commands or logs! Doing so may produce errors and void your warranty.

The **RXCONFIG** log can be used to ensure your receiver is correctly setup for your application. The **RXCONFIGUSER** log is a short list of the RXCONFIG log, mainly used to check customer configuration.

After upgrading firmware from a version without the RXCONFIGUSER log to a version with the RXCONFIGUSER log, a **FRESET** command (see page 192) needs to be issued to have a clean RXCONFIGUSER log.

The **RXCONFIGUSER** log has the same format as the **RXCONFIG** log.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RXCONFIGUSER header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	e header	Embedded header	–	h	H
3	e msg	Embedded message	Varied	a	H+h
4	e xxxx	Embedded (inverted) 32-bit CRC (ASCII and Binary only). The embedded CRC is inverted so that the receiver does not recognize the embedded messages as messages to be output but continues with the RXCONFIG message. If you wish to use the messages output from the RXCONFIGUSER log, simply invert the embedded CRC around for individual messages.	Ulong	4	H+h+a
5	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+h+a+4
6	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.186 RXSTATUS

Receiver status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log conveys various status parameters of the GNSS receiver system. These include the Receiver Status and Error words which contain several flags specifying status and error conditions. If an error occurs (shown in the Receiver Error word), the receiver idles all channels, turns off the antenna and disables the RF hardware as these conditions are considered to be fatal errors. The log contains a variable number of status words to allow for maximum flexibility and future expansion. For information about resolving an error, refer to Examining the RXSTATUS Log in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual.

The receiver gives the user the ability to determine the importance of the status bits. In the case of the Receiver Status, setting a bit in the priority mask causes the condition to trigger an error. This causes the receiver to idle all channels, turn off the antenna and disable the RF hardware, the same as if a bit in the Receiver Error word is set. Setting a bit in an Auxiliary Status priority mask causes that condition to set the bit in the Receiver Status word corresponding to that Auxiliary Status. See also the **STATUSCONFIG** command on page 418.

Field #4, the receiver status word as represented in *Table 225: Receiver status* on page 921, is also in Field #8 of the header. See the ASCII Example below and *Table 225: Receiver status* on page 921 for clarification.

Refer also to Built-In Status Tests in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual.

Message ID: 93

Log type: Asynch

Recommended input:

```
log rxstatusa onchanged
```

Abbreviated ASCII example:

```
<RXSTATUS USB1 0 66.5 FINESTEERING 2210 333374.033 02000020 2ae1 16809
<     00000000 5
<          02000020 00000000 00030000 00020000    (Receiver Status)
<          00040000 00001008 00000000 00000000    (Aux1 Status)
<          00000000 00000000 80000000 00000000    (Aux2 Status)
<          82000000 00000000 10000000 00000000    (Aux3 Status)
<          0030c000 00000000 ffffffff 00000000    (Aux4 Status)
```

Receiver errors automatically generate event messages. These event messages are output in RXSTATUSEVENT logs. It is also possible to have status conditions trigger event messages to be generated by the receiver. This is done by setting/clearing the appropriate bits in the event set/clear masks. The set mask tells the receiver to generate an event message when the bit becomes set. Likewise, the clear mask causes messages to be generated when a bit is cleared. See the **STATUSCONFIG** command on page 418 for details.

If you wish to disable all these messages without changing the bits, simply UNLOG the **RXSTATUSEVENT** logs on the appropriate ports. See the **UNLOG** command on page 452.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RXSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	error	Receiver error (see *Table 224: Receiver error* on the next page). A value of zero indicates no errors	Ulong	4	H
3	# stats	Number of status codes (including Receiver Status). Each status code consists of 4 fields, the status, priority mask, event set mask and event clear mask. Each set is repeated for each status type. Note that for clarity, the Receiver Status, Auxiliary 1 Status, Auxiliary 2 Status, Auxiliary 3 Status and Auxiliary 4 status are listed separately in this message	Ulong	4	H+4
4	rxstat	Receiver status word (see *Table 225: Receiver status* on page 921)	Ulong	4	H+8
5	rxstat pri	Receiver status priority mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+12
6	rxstat set	Receiver status event set mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+16
7	rxstat clear	Receiver status event clear mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+20
8	aux1stat	Auxiliary 1 status word (see *Table 227: Auxiliary 1 status* on page 923)	Ulong	4	H+24
9	aux1stat pri	Auxiliary 1 status priority mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+28
10	aux1stat set	Auxiliary 1 status event set mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+32
11	aux1stat clear	Auxiliary 1 status event clear mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+36
12	aux2stat	Auxiliary 2 status word (see *Table 229: Auxiliary 2 status* on page 926)	Ulong	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
13	aux2stat pri	Auxiliary 2 status priority mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+44
14	aux2stat set	Auxiliary 2 status event set mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+48
15	aux2stat clear	Auxiliary 2 status event clear mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+52
16	aux3stat	Auxiliary 3 status word (see *Table 230: Auxiliary 3 status* on page 927)	Ulong	4	H+56
17	aux3stat pri	Auxiliary 3 status priority mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+60
18	aux3stat set	Auxiliary 3 status event set mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+64
19	aux3stat clear	Auxiliary 3 status event clear mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+68
20	aux4stat	Auxiliary 4 status word (see *Table 233: Auxiliary 4 status* on page 929)	Ulong	4	H+72
21	aux4stat pri	Auxiliary 4 status priority mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+76
22	aux4stat set	Auxiliary 4 status event set mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+80
23	aux4stat clear	Auxiliary 4 status event clear mask, which can be set using the **STATUSCONFIG** command on page 418	Ulong	4	H+84
24	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+88
25	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 224: Receiver error

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N0	0	0x00000001	Dynamic Random Access Memory (DRAM) status RAM failure on an OEM7 card may also be indicated by a flashing red LED.	OK	Error
	1	0x00000002	Invalid firmware	OK	Error
	2	0x00000004	ROM status	OK	Error
	3	0x00000008	Reserved		

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N1	4	0x00000010	Electronic Serial Number (ESN) access status	OK	Error
	5	0x00000020	Authorization code status	OK	Error
	6	0x00000040	Slow ADC Status	OK	Error
	7	0x00000080	Supply voltage status	OK	Error
N2	8	0x00000100	Reserved		
	9	0x00000200	Temperature status (as compared against acceptable limits)	OK	Error
	10	0x00000400	MINOS status	OK	Error
	11	0x00000800	PLL RF status. Error with an RF PLL. See AUX2 status bits (*Table 229: Auxiliary 2 status* on page 926) for individual PLL status	OK	Error
N3	12	0x00001000	Reserved		
	13	0x00002000			
	14	0x00004000			
	15	0x00008000	NVM status	OK	Error
N4	16	0x00010000	Software resource limit exceeded	OK	Error
	17	0x00020000	Model invalid for this receiver	OK	Error
	18	0x00040000	Reserved		
	19	0x00080000			
N5	20	0x00100000	Remote loading has begun	No	Yes
	21	0x00200000	Export restriction	OK	Error
	22	0x00400000	Safe Mode	OK	Error
	23	0x00800000	Reserved		
N6	24	0x01000000			
	25	0x02000000			
	26	0x04000000			
	27	0x08000000			
N7	28	0x10000000			
	29	0x20000000			
	30	0x40000000			
	31	0x80000000	Component hardware failure	OK	Error

Table 225: Receiver status

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N0	0	0x00000001	Error flag, see *Table 224: Receiver error* on page 919	No error	Error
	1	0x00000002	Temperature status	Within specifications	Warning
	2	0x00000004	Voltage supply status	OK	Warning
	3	0x00000008	Primary antenna power status See the **ANTENNAPOWER** command on page 72	Powered	Not powered
N1	4	0x00000010	LNA Failure	OK	Failure
	5	0x00000020	Primary antenna open circuit flag	OK	Open, antenna disconnected
	6	0x00000040	Primary antenna short circuit flag	OK	Short circuit detected
	7	0x00000080	CPU overload flag	No overload	Overload
N2	8	0x00000100	COM port transmit buffer overrun. See AUX2 status bits (*Table 229: Auxiliary 2 status* on page 926) for individual COM port status	OK	COM buffer overrun
	9	0x00000200	Spoofing Detection Status	Not Detected	Detected
	10	0x00000400	Reserved		
	11	0x00000800	Link overrun flag This flag indicates if any of the USB, ICOM, CCOM, NCOM or File ports are overrun. See AUX1, AUX2 and AUX3 status bits (*Table 227: Auxiliary 1 status* on page 923, *Table 229: Auxiliary 2 status* on page 926 or *Table 230: Auxiliary 3 status* on page 927) for the specific port for which the buffer is overrun.	No overrun	Overrun

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N3	12	0x00001000	Input overrun flag This flag is set if any of the receiver ports (COM, USB, ICOM or NCOM) experience an input overrun.	No overrun	Overrun
	13	0x00002000	Aux transmit overrun flag	No overrun	Overrun
	14	0x00004000	Antenna gain state See the AUX3 status bits (*Table 230: Auxiliary 3 status* on page 927) for the antenna gain status.	OK	Out of range
	15	0x00008000	Jammer Detected See the AUX1 status bits (*Table 227: Auxiliary 1 status* on the next page) for individual RF status	OK	Jammer Detected
N4	16	0x00010000	INS reset flag	No INS reset	INS reset
	17	0x00020000	IMU communication failure	No error	No IMU communication
	18	0x00040000	GPS almanac flag/UTC known	Valid	Invalid
	19	0x00080000	Position solution flag	Valid	Invalid
N5	20	0x00100000	Position fixed flag, see the **FIX** command on page 182	Not fixed	Fixed
	21	0x00200000	Clock steering status	Enabled	Disabled
	22	0x00400000	Clock model flag	Valid	Invalid
	23	0x00800000	External oscillator locked flag	Unlocked	Locked
N6	24	0x01000000	Software resource	OK	Warning
	25	0x06000000	Version bit 0	See *Table 226: Version bits* on the next page	
	26		Version bit 1	See *Table 226: Version bits* on the next page	
	27	0x08000000	Tracking mode	Normal tracking	HDR tracking
N7	28	0x10000000	Digital Filtering Enabled	Disabled	Enabled
	29	0x20000000	Auxiliary 3 status event flag	No event	Event
	30	0x40000000	Auxiliary 2 status event flag	No event	Event
	31	0x80000000	Auxiliary 1 status event flag	No event	Event

Table 226: Version bits

Bit 26	Bit 25	Description
0	0	Interpret Status/Error Bits as OEM6 or earlier format
0	1	Interpret Status/Error Bits as OEM7 format
1	0	Reserved for a future version
1	1	Reserved for a future version

Table 227: Auxiliary 1 status

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N0	0	0x00000001	Jammer detected on RF1	OK	Jammer detected
	1	0x00000002	Jammer detected on RF2	OK	Jammer detected
	2	0x00000004	Jammer detected on RF3	OK	Jammer detected
	3	0x00000008	Position averaging	Off	On
N1	4	0x00000010	Jammer detected on RF4	OK	Jammer detected
	5	0x00000020	Jammer detected on RF5	OK	Jammer detected
	6	0x00000040	Jammer detected on RF6	OK	Jammer detected
	7	0x00000080	USB connection status	Connected	Not connected
N2	8	0x00000100	USB1 buffer overrun flag	No overrun	Overrun
	9	0x00000200	USB2 buffer overrun flag	No overrun	Overrun
	10	0x00000400	USB3 buffer overrun flag	No overrun	Overrun
	11	0x00000800	Reserved		
N3	12	0x00001000	Profile Activation Bit	OK	Error
	13	0x00002000	Throttled Ethernet Reception	OK	Throttled
	14	0x00004000	Dynamic Channel Configuration	Disabled	Enabled
	15	0x00008000	Reserved		

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N4	16	0x00010000	Reserved		
	17	0x00020000	Reserved		
	18	0x00040000	Ethernet not connected	Connected	Not connected
	19	0x00080000	ICOM1 buffer overrun flag	No overrun	Overrun
N5	20	0x00100000	ICOM2 buffer overrun flag	No overrun	Overrun
	21	0x00200000	ICOM3 buffer overrun flag	No overrun	Overrun
	22	0x00400000	NCOM1 buffer overrun flag	No overrun	Overrun
	23	0x00800000	NCOM2 buffer overrun flag	No overrun	Overrun
N6	24	0x01000000	NCOM3 buffer overrun flag	No overrun	Overrun
	25	0x02000000	Reserved		
	26	0x04000000	Reserved		
	27	0x08000000	Reserved		
N7	28	0x10000000	Reserved		
	29	0x20000000	Reserved		
	30	0x40000000	Status error reported by the IMU. May be treated as a notice unless the issue persists.	OK	Status Error Reported
	31	0x80000000	IMU measurement outlier detected. Indicates when the SPAN system has detected an outlier in the IMU performance. May be treated as a notice unless the issue persists.	OK	Outlier detected

Table 228: RF paths for OEM7 receivers

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, OEM7600, SMART2
RF1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	1st antenna GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1	GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1 SBAS L1

RF path	OEM719, OEM729, OEM7700, PwrPak7, CPT7700, SMART7	OEM7720, PwrPak7D, CPT7	OEM7500, OEM7600, SMART2
RF2	Reserved	Reserved	GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5
RF3	GPS L2 GLONASS L2 Galileo E6 BDS B3 QZSS L2/L6	1st antenna GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5 SBAS L5	Reserved
RF4	GPS L5 GLONASS L3 Galileo E5 BDS B2 QZSS L5 NavIC L5 SBAS L5	2nd antenna GPS L1 GLONASS L1 Galileo E1 BDS B1 QZSS L1	Reserved
RF5	Reserved	2nd antenna GPS L2/L5 GLONASS L2/L3 Galileo E5 BDS B2 QZSS L2/L5 NavIC L5	Reserved
RF6	Reserved	Reserved	Reserved

Table 229: Auxiliary 2 status

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N0	0	0x00000001	SPI Communication Failure	OK	Error
	1	0x00000002	I^2C Communication Failure	OK	Error
	2	0x00000004	COM4 buffer overrun flag	No overrun	Buffer Overrun
	3	0x00000008	COM5 buffer overrun flag	No overrun	Buffer Overrun
N1	4	0x00000010	Reserved		
	5	0x00000020	Reserved		
	6	0x00000040	Reserved		
	7	0x00000080	Reserved		
N2	8	0x00000100	Reserved		
	9	0x00000200	COM1 buffer overrun flag	OK	Buffer Overrun
	10	0x00000400	COM2 buffer overrun flag	OK	Buffer Overrun
	11	0x00000800	COM3 buffer overrun flag	OK	Buffer Overrun
N3	12	0x00001000	PLL RF1 unlock flag	OK	PLL Unlock
	13	0x00002000	PLL RF2 unlock flag	OK	PLL Unlock
	14	0x00004000	PLL RF3 unlock flag	OK	PLL Unlock
	15	0x00008000	PLL RF4 unlock flag	OK	PLL Unlock
N4	16	0x00010000	PLL RF5 unlock flag	OK	PLL Unlock
	17	0x00020000	PLL RF6 unlock flag	OK	PLL Unlock
	18	0x00040000	CCOM1 buffer overrun	OK	Buffer Overrun
	19	0x00080000	CCOM2 buffer overrun	OK	Buffer Overrun
N5	20	0x00100000	CCOM3 buffer overrun	OK	Buffer Overrun
	21	0x00200000	CCOM4 buffer overrun	OK	Buffer Overrun
	22	0x00400000	CCOM5 buffer overrun	OK	Buffer Overrun
	23	0x00800000	CCOM6 buffer overrun	OK	Buffer Overrun
N6	24	0x01000000	ICOM4 buffer overrun	OK	Buffer Overrun
	25	0x02000000	ICOM5 buffer overrun	OK	Buffer Overrun
	26	0x04000000	ICOM6 buffer overrun	OK	Buffer Overrun
	27	0x08000000	ICOM7 buffer overrun	OK	Buffer Overrun

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N7	28	0x10000000	Secondary antenna power status See the **ANTENNAPOWER** command (see page 72)	Powered	Not Powered
	29	0x20000000	Secondary antenna open circuit This flag is only available on certain products	OK	Open, antenna disconnected
	30	0x40000000	Secondary antenna short circuit This flag is only available on certain products	OK	Short circuit detected
	31	0x80000000	Reset loop detected	OK	Reset Detected

Table 230: Auxiliary 3 status

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N0	0	0x00000001	SCOM buffer overrun flag. This flag is set if any of the SCOM ports (SCOM1 – SCOM4) experience overrun.	No overrun	Overrun
	1	0x00000002	WCOM1 buffer overrun flag	No overrun	Overrun
	2	0x00000004	FILE buffer overrun flag	No overrun	Overrun
	3	0x00000008	Reserved		
N1	4	0x00000010	Antenna 1 Gain State	*Table 231: Antenna gain state* on the next page	
	5	0x00000020			
	6	0x00000040	Antenna 2 Gain State	*Table 231: Antenna gain state* on the next page	
	7	0x00000080			
N2	8	0x00000100	GPS reference time is incorrect. Reset the receiver to correct it.	OK	Time incorrect
	9	0x00000200	Memory usage state	*Table 232: Memory usage state* on page 929	
	10	0x00000400			
	11	0x00000800	Reserved		
N3	12	0x00001000	Reserved		
	13	0x00002000			
	14	0x00004000			
	15	0x00008000			

Nibble	Bit	Mask	Description	Bit = 0	Bit = 1
N4	16	0x00010000	DMI hardware failure detection flag	OK	Error
	17	0x00020000	Reserved		
	18	0x00040000			
	19	0x00080000			
N5	20	0x00100000	Reserved		
	21	0x00200000			
	22	0x00400000			
	23	0x00800000			
N6	24	0x01000000	Spoofing Calibration Status	Successful	Failed
	25	0x02000000	Spoofing Calibration Required	Not required	Required
	26	0x04000000	USB Mass Storage Device Error This flag is only available on certain products.	OK	Error
	27	0x08000000	Internal Storage Device Error This flag is only available on certain products.	OK	Error
N7	28	0x10000000	Receiver is resetting to enable a service period	No reset	Receiver resetting
	29	0x20000000	Web content is corrupt or does not exist	Content is OK	Error with content
	30	0x40000000	RF Calibration Data is present and in error	Data is OK	Data has an error
	31	0x80000000	RF Calibration Data is present	No data found	Data exists and has no errors

Table 231: Antenna gain state

Bits 4-5 or Bits 6-7	Description
00	Antenna Gain in range
01	Antenna Gain Low This state indicates that the input signal is very weak (under -160 dBm/Hz). It can indicate the antenna is not operating correctly, the antenna is not suitable for NovAtel receivers, or there is no antenna connected.

Bits 4-5 or Bits 6-7	Description
10	Antenna Gain High. This state indicates that the input signal is very strong (above -120 dBm/Hz). This can be caused by a strong in-band interference or by too much signal gain or too many LNAs cascaded in the path.
11	Antenna Gain Anomaly. This state indicates that an anomaly has been detected for the input signal. It can be caused by strong in-band or out-of-band interference, or by the antenna being disconnected/changed during operation.

Table 232: Memory usage state

Bits 9 & 10	Description
00	Negligible memory usage
01	Low memory usage
10	Medium memory usage
11	High memory usage

Table 233: Auxiliary 4 status

Nibble	Bit	Mask	Description	Bit = 1
N0	0	0x00000001	GNSS Tracked Status	<60% of available satellites are tracked well
	1	0x00000002		<15% of available satellites are tracked well
	2	0x00000004	Reserved	
	3	0x00000008		
N1	4	0x00000010	Reserved	
	5	0x00000020		
	6	0x00000040		
	7	0x00000080		

Nibble	Bit	Mask	Description	Bit = 1
N2	8	0x00000100	Reserved	
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		
N3	12	0x00001000	Clock freewheeling due to bad position integrity	Clock freewheeling
	13	0x00002000	Reserved	
	14	0x00004000	Usable RTK Corrections Percentage of expected measurements which have timely RTK corrections (latency <20 seconds)	<60% of expected corrections available
	15	0x00008000		<15% of expected corrections available
N4	16	0x00010000	Bad RTK Geometry	PDOP >5.0
	17	0x00020000	Reserved	
	18	0x00040000		
	19	0x00080000	Long RTK Baseline	Baseline >50 km
N5	20	0x00100000	Poor RTK COM Link (poor correction quality)	Corrections quality ≤60%
	21	0x00200000	Poor ALIGN COM Link (poor correction quality)	Corrections quality ≤60%
	22	0x00400000	GLIDE Not Active	GLIDE not active
	23	0x00800000	Bad PDP Geometry	PDOP >5.0
N6	24	0x01000000	No current service period scheduled	No period is current
	25	0x02000000	Reserved	
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000	Bad PPP Geometry	PDOP >5.0
	29	0x20000000	Reserved	
	30	0x40000000	No INS Alignment	No alignment
	31	0x80000000	INS not converged	Not converged

Only GPS and GLONASS are considered in the Auxiliary 4 status word states.



For bits relating to RTK, ALIGN or INS, the bits will only be set if the receiver has that type of positioning is enabled via Auth-Code.

3.187 RXSTATUSEVENT

Status event indicator

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log is used to output event messages as indicated in the **RXSTATUS** log (see page 917). An event message is automatically generated for all receiver errors, which are indicated in the receiver error word. In addition, event messages can be generated when other conditions, which are indicated in the receiver status and auxiliary status words, are met. Whether or not an event message is generated under these conditions is specified using the **STATUSCONFIG** command (see page 418).

On start-up, the receiver is set to log **RXSTATUSEVENTA ONNEW HOLD** on all ports. You can remove this message using the **UNLOG** command (see page 452). To remove this log using an **UNLOGALL** command (see page 454), you must use the **True** option. Logging **RXSTATUSEVENT** on all ports is a factory default setting. If it is unlogged, the **RXSTATUSEVENT** log will not be collected until the next start-up. After a start-up, logging **RXSTATUSEVENT** on all ports will start again.



See also Built-In Status Tests in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual.

Message ID: 94

Log type: Asynch

Recommended input:

```
log rxstatuseventa onchanged
```

ASCII example 1:

```
#RXSTATUSEVENTA,USB1,0,41.5,FINESTEERING,2209,513459.504,02080020,b967,16809;
AUX4,28,SET,"High PPP PDOP"*0b568a59
```

ASCII example 2:

```
#RXSTATUSEVENTA,USB1,0,50.5,FINESTEERING,2209,513460.010,02080020,b967,16809;
AUX4,0,SET,"<60% available SVs tracked well"*a6aeeadd
```



When a fatal event occurs (for example, in the event of a receiver hardware failure), a bit is set in the receiver error word, part of the **RXSTATUS** log (see page 917) to indicate the cause of the problem. Bit 0 is set in the receiver status word to show that an error occurred, the error strobe is driven high and the LED flashes red and yellow showing an error code. An RXSTATUSEVENT log is generated on all ports to show the cause of the error. Receiver tracking is disabled at this point but command and log processing continues to allow you to diagnose the error. Even if the source of the error is corrected at this point, the receiver must be reset to resume normal operation.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RXSTATUSEVENT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	word	The status word that generated the event message (see *Table 234: Status word* below)	Enum	4	H
3	bit position	Location of the bit in the status word (see *Table 225: Receiver status* on page 921, *Table 227: Auxiliary 1 status* on page 923, *Table 229: Auxiliary 2 status* on page 926, *Table 230: Auxiliary 3 status* on page 927 or *Table 233: Auxiliary 4 status* on page 929	Ulong	4	H+4
4	event	Event type (see *Table 235: Event type* below)	Enum	4	H+8
5	description	This is a text description of the event or error	Char[32]	32	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+44
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 234: Status word

Binary	ASCII	Description
0	ERROR	Receiver Error word, see *Table 224: Receiver error* on page 919
1	STATUS	Receiver Status word, see *Table 225: Receiver status* on page 921
2	AUX1	Auxiliary 1 Status word, see *Table 227: Auxiliary 1 status* on page 923
3	AUX2	Auxiliary 2 Status word, see *Table 229: Auxiliary 2 status* on page 926
4	AUX3	Auxiliary 3 Status word, see *Table 230: Auxiliary 3 status* on page 927
5	AUX4	Auxiliary 4 Status word, see *Table 233: Auxiliary 4 status* on page 929

Table 235: Event type

Binary	ASCII	Description
0	CLEAR	Bit was cleared
1	SET	Bit was set

3.188 SAFEMODESTATUS

Safe Mode status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides additional information about the state of the receiver in the event that the *Safe Mode* error bit and/or *Reset Loop Detected* status bit are set in the **RXSTATUS** log (see page 917).

The data within this log is set at receiver start up and will not change over time.

For information about *Safe Mode*, see Safe Mode in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, CPT7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual or SMART2 Installation and Operation User Manual.

Message ID: 2060

Log type: Asynch

Recommended input:

```
log SAFEMODESTATUSA once
```

Abbreviated ASCII example:

```
#SAFEMODESTATUSA,USB1,0,54.0,UNKNOWN,0,0.000,02000020,8e55,16809;
SAFE_MODE_OK,0,"Normal Operation."*484241d0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SAFEMODESTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Status	Safe Mode State. See *Table 236: Safe Mode states* below	Enum	4	H
3	Reset Count	Number of resets since power up or a successful boot	Ulong	4	H+4
4	Description	String for additional information about the Safe Mode State	String	80	H+8
5	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+88
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 236: Safe Mode states

Value	State	Safe Mode error bit	Reset loop detected bit	Notes	Recovery steps
0	SAFE_MODE_OK	0	0	Normal Operation. No reset loop detected.	No action required

Value	State	Safe Mode error bit	Reset loop detected bit	Notes	Recovery steps
1	SAFE_MODE_ WARNING	0	1	An unexpected reset was detected. The receiver will operate as normal	No action required
2	SAFE_MODE_ DISABLE_ SATELLITE_DATA	0	1	Satellite Navigation Data previously saved to NVM is ignored in this state. As the receiver continues to track GNSS satellites, new data will be downloaded. There may be some delay in initial satellite acquisition as this will effectively be a Cold Start, but the receiver will otherwise operate as normal.	No action required
3	SAFE_MODE_ DISABLE_ NON_ COMMUNICATION_ NVM	1	1	All data previously saved to NVM that is not related to communication is ignored in this state. Communication ports (COM, USB, ICOM, etc.) will remain in the configuration previously saved by SAVECONFIG allowing the user to take corrective action.	Depending on what NVM data is causing the problem, a **FRESET** may resolve the issue. If a standard **FRESET** does not resolve the issue, see the **FRESET** command on page 192 for other NVM targets that may be causing the issue and could be removed.
4	SAFE_MODE_ DISABLE_ ALL_NVM	1	1	All data previously saved to NVM is ignored in this state.	See recovery steps for SAFE_MODE_ DISABLE_ NON_ COMMUNICATION_ NVM.
5	SAFE_MODE_ DISABLE_ AUTH	1	1	All data previously saved to NVM and all Auth-Codes are ignored in this state.	Use the **AUTH REMOVE** command to remove the offending Auth-Code. The **AUTHCODES** log (see page 498) can be used to determine what Auth-Codes are currently loaded.

Value	State	Safe Mode error bit	Reset loop detected bit	Notes	Recovery steps
6	SAFE_MODE_ FAILED	1	1	All data previously saved to NVM and all Auth-Codes are ignored in this state.	This state is unexpected. The recovery steps for other states may apply.
7	SAFE_MODE_ UNEXPECTED_ MAIN_FIRMWARE	1	0 or 1	An error related to main firmware loading occurred.	Reload the main firmware.
8	SAFE_MODE_ DISABLE_STARTUP_ EMMC_CHKDSK	1	1	All data previously saved to NVM and all Auth-Codes are ignored in this state. The startup eMMC check disk operation is ignored (if eMMC is equipped).	Issue a **MEDIAFORMAT INTERNAL_FLASH** command to format the eMMC (if equipped) and then issue a **RESET** command.
9	SAFE_MODE_ INCOMPLETE_ CONFIG	1	0	Incomplete system configuration.	Contact NovAtel Customer Support.
10	SAFE_MODE_ DISABLE_ EMBEDDED_APP	1	1	All data previously saved to NVM and all Auth-Codes are ignored in this state, and product specific functionality is disabled.	See recovery steps for SAFE_MODE_ DISABLE_ NON_ COMMUNICATION_ NVM.

3.189 SATEL4INFO

Displays the Satel 400 MHz radio configuration settings

Platform: SMART7 with RELAY7

Use this log to display the configuration settings of the Satel 400 MHz radio.

Message ID: 2216

Log type: Asynch

Recommended input:

```
log SATEL400INFO
```

ASCII example:

```
#SATEL4INFOA,COM1,0,78.0,FINESTEERING,1997,507154.039,02004000,7499,32768;
TRIMTALK450S_T,438000000,438000000,12500,1000,TRUE*bf15bfb0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SATEL4INFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	protocol	Refer to *Table 237: Compatibility mode* below	Enum	4	H
3	Freqtx	Transmit frequency in Hz	Uint	4	H+4
4	Freqrx	Receive frequency in Hz	Uint	4	H+8
5	spacing	Channel spacing in Hz	Uint	4	H+12
6	txpwr	Maximum transmit power in mW	Uint	4	H+16
7	Fec	Forward correction error 0 = FALSE 1 = TRUE	Enum	4	H+20
8	xxxx	32-bit CRC (ASCII or Binary only)	Hex	4	Variable
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 237: Compatibility mode

Value	Enum	Mode
0	SATELLINE_3AS	Satelline-3AS
1	PACCREST_4FSK	PacCrest-4FSK
2	PACCREST_GMSK	PacCrest-GMSK
3	TRIMTALK450S_P	TrimTalk450s (PacCrest transmitter)
4	TRIMTALK450S_T	TrimTalk450s (Trimble transmitter)
5	PACCREST_FST	PacCrest-FST

3.190 SATEL9INFO

Displays the Satel UHF radio configuration settings

Platform: SMART7 with RELAY7

Use this log to display the configuration settings of the Satel UHF radio.

Message ID: 2220

Log type: Asynch

Recommended input:

```
log SATEL9INFO
```

ASCII example:

```
#SATEL9INFOA,COM1,0,78.5,FINESTEERING,1997,507405.578,02004000,9dd6,32768;
P2MP_RX_SLAVE,4,-1,4,534,1,9,10,FF,FALSE,0,0,0,"1111111111111111"*37129a10
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SATEL9INFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	modemmode	Radio role in network	Enum	4	H
3	Leicachannel	Leica virtual channel[1]	Int	4	H+4
4	novchannel	Novariant virtual channel[2]	Int	4	H+8
5	freqkey	Frequency key	Uint	4	H+12
6	nid	Network ID	Uint	4	H+16
7	minpktsize	Minimum packet size	Uint	4	H+20
8	maxpktsize	Maximum packet size	Uint	4	H+24
9	retrytimeout	Number of failed attempts to receive packets before the connection is dropped	Uint	4	H+28
10	subnet	Multipoint subnet: 00=Roaming FF=Disabled	Uint	4	H+32
11	repeaters	Boolean to specify if repeaters are present in the network	Bool	4	H+36
12	masterpacketrepeat	How many time master will repeat packets	Uint	4	H+40

1. If the current configuration does not translate to a valid Leica virtual channel, the reported value will be -1.
2. If the current configuration does not translate to a valid Novariant virtual channel, the reported value will be -1.

Field	Field type	Description	Format	Binary bytes	Binary offset
13	txpower	The transmitter output power (mW)	Uint	4	H+44
14	hoptablever	Hop table version	Uint	4	H+48
15	freqzone	Frequency zone	FixedUCha Array	16	H+52
16	xxxx	32-bit CRC (ASCII or Binary only)	Hex	4	Variable
17	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 238: ASCII and binary values

Type	ASCII	Binary	Description
SATEL9INFO header	-	-	For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.
modemmode	P2MP_ MASTER	2	Role in radio network
	P2MP_ SLAVE	3	
	P2MP_ RX_SLAVE	8	
leicachannel	1-9, -1		Leica virtual channel
novchannel	1-3824, -1		Novariant virtual channel
freqkey	0-14		Frequency key
nid	0-4095		Network ID
minpktsize	0-9		Minimum packet size
maxpktsize	0-9		Maximum packet size
retrytimeout	8-255		Number of failed attempts to receive packets before connection drops off
subnet	0x00, 0xFF		Multipoint subnet: 00=Roaming FF=Disabled
repeaters	FALSE	0	Boolean to specify if repeaters are present in the network
	TRUE	1	
masterpacketrepeat	0-9		Number of times master will repeat packets
txpower	0-1000		The transmitter output power (mW)
hoptablever	0-6		Hop table version
freqzone	"1111111111111111"		Frequency zone

3.191 SATELSTATUS

Delivers status updates for any asynchronous radio operations

Platform: SMART7 with RELAY7

Use this log to display the status of the last operation attempted on the RELAY7 radio. Settings are saved on the radio so it is not necessary to configure the radio for each session. The SATELSTATUS log reports UNDETECTED until the radio is used. If hardware power control is available, OFF may also be reported.



There is no state monitoring, so a radio can be detached after being configured and the status would not update until a radio command is issued.

Message ID: 2205

Log type: Asynch

Recommended input:

```
log SATELSTATUS onchanged
```

ASCII example:

```
#SATELSTATUSA,COM1,0,68.5,FINESTEERING,1883,338273.235,03040040,ea7e,32768;
UNDETECTED,OK,""*f6ce6088

#SATELSTATUSA,COM1,0,68.5,FINESTEERING,1883,338273.235,03040040,ea7e,32768;
UNDETECTED,NONE,""*be410d2e

#SATELSTATUSA,COM1,0,68.5,FINESTEERING,1883,338273.235,03040040,ea7e,32768;
READY,NONE,""*68137390

#SATELSTATUSA,COM1,0,68.5,FINESTEERING,1883,338273.235,03040040,ea7e,32768;
ERROR,COMMAND_FAILED,"SL&FR=900.0000"*d55feb42
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SATELSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	state	State of the radio. See *Table 239: Radio state* on the next page.	Enum	4	H
3	error	Error type. See *Table 240: Error types* on the next page.	Uint	4	H+4
4	error_ source	Last SATEL radio command issued	String	Variable	H+8
5	xxxx	32-bit CRC (ASCII or Binary only)	Hex	4	Variable
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 239: Radio state

ASCII	Binary	Description
OFF	0	The radio power is configured OFF
DETECTING	1	The radio is being queried for identity and current configuration
UNDETECTED	2	The radio may be operating but it must be detected before responding to configuration commands
READY	3	The radio is operating and ready to respond to configuration commands
BUSY	4	The radio is being configured. Data may be interrupted
ERROR	5	The radio is in an error state

Table 240: Error types

ASCII	Binary	Description
NONE	0	Error type
COMMAND_FAILED	1	
TIMEOUT	2	

3.192 SATVIS2

Satellite visibility

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains satellite visibility data for all available systems with additional satellite and satellite system information. One log is output for each available satellite system.

1. The SATVIS2 log is meant to provide a brief overview. The satellite positions and velocities used in the computation of this log are based on Almanac orbital parameters, not the higher precision Ephemeris parameters.
2. In the SATVIS2 log output, there may be double satellite number entries. These are GLONASS antipodal satellites in the same orbit plane separated by 180 degrees latitude. Refer to the GLONASS section of *An Introduction to GNSS* available on our website at novatel.com/an-introduction-to-gnss.
3. The SATVIS2 log data is re-computed at a minimum of every 10 seconds. It will also be re-computed asynchronously as new navigation data is downloaded in the receiver. If the log is requested at a faster rate than ontime 10, it will be output at the requested rate, but may not contain newly computed data.

Message ID: 1043

Log type: Asynch

Recommended input:

```
log satvis2a ontime 10
```

Abbreviated ASCII example:

```
<SATVIS2 USB1 6 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     GPS TRUE TRUE 31
<          29 0 73.9 298.1 1006.524 1006.471
<          5 0 63.2 127.7 829.350 829.298
...
<          21 0 -78.0 245.7 1008.686 1008.634
<          1 0 -82.3 91.7 -329.712 -329.765

<SATVIS2 USB1 5 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     GLONASS TRUE TRUE 24
<          18-3 0 63.2 47.6 -1112.813 -1112.867
<          19+3 0 52.6 301.3 1883.220 1883.167
...
<          7+5 0 -57.3 300.1 -1966.130 -1966.184
<          22-3 0 -74.8 221.7 612.703 612.650

<SATVIS2 USB1 4 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     SBAS TRUE FALSE 4
<          131 0 31.6 183.8 0.016 -0.036
<          138 0 31.4 171.3 0.017 -0.035
<          135 0 30.7 194.0 0.014 -0.038
<          133 0 30.0 199.2 0.013 -0.039
```

```
<SATVIS2 USB1 3 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     GALILEO TRUE TRUE 23
<          34 0 69.1 59.8 -928.064 -928.116
<          15 0 53.3 267.2 1517.165 1517.113
...
<          12 0 -65.5 86.6 -1047.031 -1047.083
<          33 0 -76.0 240.3 632.424 632.371

<SATVIS2 USB1 2 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     QZSS TRUE TRUE 4
<          194 0 13.5 310.7 203.666 203.614
<          195 0 -16.0 274.7 -306.102 -306.154
<          199 0 -25.6 293.3 2.197 2.145
<          196 0 -47.1 271.8 449.579 449.527

<SATVIS2 USB1 1 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     BEIDOU TRUE TRUE 59
<          43 88 79.1 302.7 545.401 545.349
<          11 0 69.0 83.5 -960.045 -960.097
...
<          13 0 -81.1 244.3 116.464 116.413
<          29 88 -81.6 120.6 -430.185 -430.237

<SATVIS2 USB1 0 54.0 FINESTEERING 2209 513610.000 02000020 a867 16809
<     NAVIC TRUE FALSE 0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SATVIS2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Satellite System	GNSS satellite system identifier. See *Table 145: Satellite system* on page 676	Enum	4	H
3	sat vis	Is satellite visibility valid? 0 = FALSE 1 = TRUE	Enum	4	H+4
4	almanac flag	Was complete almanac used? 0 = FALSE 1 = TRUE	Enum	4	H+8
5	#sat	Number of satellites with data to follow	Ulong	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
6	Satellite ID	In binary logs, the satellite ID field is 4 bytes. The 2 lowest order bytes, interpreted as a USHORT, are the system identifier: for instance, the PRN for GPS or the slot for GLONASS. The 2 highest-order bytes are the frequency channel for GLONASS, interpreted as a SHORT and zero for all other systems. In ASCII and abbreviated ASCII logs, the satellite ID field is the system identifier. If the system is GLONASS and the frequency channel is not zero, then the signed channel is appended to the system identifier. For example, slot 13, frequency channel -2 is output as 13-2. For more information, refer to *PRN numbers* on page 55	Ulong	4	H+16
7	health	Satellite health Satellite health values may be found in the applicable Interface Control Document for each system.	Ulong	4	H+20
8	elev	Elevation (degrees)	Double	8	H+24
9	az	Azimuth (degrees)	Double	8	H+32
10	true Doppler	Theoretical Doppler of satellite - the expected Doppler frequency based on a satellite's motion relative to the receiver. It is computed using the satellite's coordinates and velocity along with the receiver's coordinates and velocity (Hz).	Double	8	H+40
11	apparent Doppler	Apparent Doppler for this receiver - the same as Theoretical Doppler above but with clock drift correction added (Hz).	Double	8	H+48
12	Next satellite offset = H + 16 + (#sat x 40)				
13	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+16+ (#sat x 40)
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.193 SATXYZ2

Satellite positions in ECEF Cartesian coordinates

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

When combined with a RANGE log, this data set contains the decoded satellite information necessary to compute the solution: satellite coordinates (ECEF), satellite clock correction, ionospheric corrections and tropospheric corrections. See the calculation examples in the usage box below. Only those satellites used in the corresponding PSRPOS solution are reported here. See also *Figure 13: WGS84 ECEF coordinate system* on page 547.

The position coordinates are provided in the datum configured by the **OUTPUTDATUM** command (see page 284).

Message ID: 1451

Log type: Synch

Recommended input:

```
log satxyz2 ontime 1
```

Abbreviated ASCII example:

```
<SATXYZ2 USB1 0 68.5 FINESTEERING 2210 335347.000 02000020 7513 16809
<     33
<          GPS 5 -5020461.7928 -25680412.1145 3895185.6848 -24674.365 7.451
3.734 0.0 0.0
<          GPS 6 17719519.1461 -7620594.3470 18357851.0315 92492.352 8.923 6.449
0.0 0.0
<          GPS 29 -17763264.5350 -2136772.7366 19599826.2346 -154398.173 5.339
3.151 0.0 0.0
<          GPS 12 -9148026.7576 -24014583.7810 6678087.9193 -65209.710 6.008
3.091 0.0 0.0
<          GPS 9 18287652.1028 730576.0171 19192008.9639 -100642.405 10.945
14.299 0.0 0.0
...
<          QZSS 194 -24965113.5911 24703385.9532 28399888.3498 -74.060 9.319
11.140 0.0 0.0
<          GLONASS 22-3 7699005.7624 -11043302.0832 21669033.1478 -55159.517
7.696 2.922 0.0 0.0
<          GLONASS 12-1 -15776044.3967 -19935215.2933 -2172302.8981 5551.124
11.793 6.465 0.0 0.0
<          GLONASS 14-7 -9924647.1145 5441857.5868 22869748.6581 7687.030 10.285
4.219 0.0 0.0
<          GLONASS 13-2 -18443739.0480 -11030605.9522 13725659.4436 -6740.531
6.909 2.806 0.0 0.0
<          GLONASS 24+2 -24194892.7729 158595.4159 8103819.1464 28295.396 10.608
7.975 0.0 0.0
...
<          GALILEO 26 11908959.5845 -13702223.9079 23377702.1405 -347773.553
7.083 3.176 0.0 0.0
```

```
<          GALILEO 7 22792674.3142 -12903431.3874 13791966.8186 -200807.963
11.538 9.629 0.0 0.0
<          GALILEO 24 -16791994.0871 2450155.5014 24241175.8702 -186539.254
6.992 3.469 0.0 0.0
<          GALILEO 31 -18231691.1561 -17046216.1699 15920139.1514 -148949.282
6.140 2.485 0.0 0.0
<          GALILEO 33 -9401282.9993 -16271727.7340 22863722.0668 -136856.054
5.559 2.128 0.0 0.0
...
<          BEIDOU 37 -18620975.4950 -20106704.6345 -5303071.3088 -273075.077
16.311 9.289 0.0 0.0
<          BEIDOU 46 -23602968.9441 -7543827.2273 12872870.3614 -99460.897 9.808
3.573 0.0 0.0
<          BEIDOU 27 -14195438.5868 -10662737.8554 21501016.4435 217428.319
8.585 2.310 0.0 0.0
<          BEIDOU 42 15931468.6323 639406.2465 22950291.6443 -291213.434 13.427
7.528 0.0 0.0
<          BEIDOU 33 13384960.0662 -19323978.0538 15033146.5546 -289635.111
10.878 3.898 0.0 0.0
```

The OEM7 family defines ionospheric and tropospheric corrections positively which means that ionospheric and tropospheric corrections are added to the geometric ranges or subtracted from the measured pseudoranges. A positive clock offset indicates the clock is running ahead of the reference time. For example:

P = p + pd + c(dT - dt) + d(ion) + d(trop) + Ep

is equivalent to

P - c(dT - dt) - d(ion) - d(trop) = p + pd + Ep

where

P = measured pseudorange
p = geometric range
pd = orbit error
dt = satellite clock offset
dT = receiver clock offset
d (ion) = ionospheric delay
d (trop) = tropospheric delay
c = speed of light
Ep = noise and multipath

Note that when dual frequency ionosphere corrections are used, the corrections include receiver biases. Consequently, the correction does not provide a measure of the ionosphere delay in an absolute sense.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SATXYZ2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	#sat	Number of satellites to follow	Ulong	4	H
3	System	Satellite system (refer to *Table 145: Satellite system* on page 676)	Enum	4	H+4
4	Satellite ID	Satellite ID	Ulong	4	H+8
5	X	Satellite X co-ordinates (ECEF,m)	Double	8	H+12
6	Y	Satellite Y co-ordinates (ECEF,m)	Double	8	H+20
7	Z	Satellite Z co-ordinates (ECEF,m)	Double	8	H+28
8	clk corr	Satellite clock correction (m)	Double	8	H+36
9	iono delay	Ionosphere delay (m)	Double	8	H+44
10	tropo delay	Troposphere delay (m)	Double	8	H+52
11	Reserved1		Double	8	H+60
12	Reserved2		Double	8	H+68
13	Next satellite offset = H+4+(#sat x 72)				
14	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+(#sat x 72)
15	[CR][LF]	Sentence terminator (ASCII only)			

3.194 SAVEDSURVEYPOSITIONS

Saved surveyed positions

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log lists the surveyed positions saved on the receiver.

A surveyed position is saved using the **AUTOSURVEY** command (see page 89) or **SURVEYPOSITION** command (see page 423).

The maximum number of surveys that can be saved to memory is 32. If this number is exceeded, the new position entry will overwrite the last entry reported by the **SAVEDSURVEYPOSITIONS** log.

Message ID: 1951

Log type: Polled

Recommended input:

```
log savedsurveypositions once
```

Abbreviated ASCII example:

```
<SAVEDSURVEYPOSITIONS USB1 0 52.5 FINESTEERING 2209 514133.104 02000020 ddf2
16809
<     3
<          "MN01" 51.11600000000 -114.03800000000 1065.0000
<          "MN02" 55.11600000000 -114.03800000000 1065.0000
<          "MN03" 55.11600000000 -94.03800000000 65.0000
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SAVEDSURVEYPOSITIONS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#Positions	Number of records to follow.	Ulong	4	H
3	Position ID	ID for the saved position.	String[5]	4 or 8[1]	H+4
4	Latitude	Latitude of the position (-90 to 90 degrees) where a '-' sign denotes south and a '+' sign denotes north	Double	8	H+8 or H+12
5	Longitude	Longitude of the position (-360 to 360 degrees) where a '-' sign denotes west and a '+' sign denotes east	Double	8	H+16 or H+20

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment. The next defined field starts immediately at the next 4-byte alignment following the NULL.

Field	Field type	Description	Format	Binary bytes	Binary offset
6	Height	Mean Sea Level height of the position in metres	Double	8	H+24 or H+28
7	Next reading offset = H+4+(#Positions * 28) or H+4+(#Positions * 32)				
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4+ (#Positions * 28) or H+4+ (#Positions * 32)
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.195 SBAS0

Do not use for safety applications

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This message specifies the PRN if GEO transmitting SBAS corrections is operating in test mode, and should not be used for safety applications for a period of time outlined in the SBAS signal specification.

The GEO transmitting SBAS corrections is operating in test mode, and should not be used for safety-of-life applications.

See how the SBAS0 message relates to the SBAS testing modes in the **SBASCONTROL** command on page 370.

Message ID: 976

Log type: Asynch

Recommended input:

```
log SBAS0a onchanged
```

ASCII example:

```
#SBAS0A,COM1,0,72.5,SATTIME,2073,327283.000,1a000000,5a84,15761;130*8390deb3
```

Although the SBAS was designed for aviation users, it supports a wide variety of non-aviation uses including agriculture, surveying, recreation, and surface transportation.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS0 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN message - also PRN not to use	Ulong	4	H
3	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4
4	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.196 SBAS1

PRN mask assignments

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The PRN mask is given in SBAS1. The transition of the PRN mask to a new one (which will be infrequent) is controlled with the 2-bit IODP, which sequences to a number between 0 and 3. The same IODP appears in the applicable SBAS2, SBAS3, SBAS4, SBAS5, SBAS7, SBAS24 and SBAS25 messages (SBAS32, SBAS33, SBAS34, SBAS35 and SBAS45). This transition would probably only occur when a new satellite is launched or when a satellite fails and is taken out of service permanently. A degraded satellite may be flagged as a “do not use” satellite temporarily.

Message ID: 977

Log type: Asynch

Recommended input:

```
log SBAS1a onchanged
```

ASCII example:

```
#SBAS1A,USB1,0,46.5,SATTIME,2209,514210.000,02000020,5955,16809;135,ffffffff000
00000000000000000002a4000000000000000000,2*193c8b8a
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS1 message can be logged to view the data breakdown of SBAS frame 1 which contains information about the PRN mask assignment.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS1 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	mask	PRN bit mask	Uchar [27]	28 [1]	H+4
4	iodp	Issue of PRN mask data	Ulong	4	H+32
5	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+36
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary log case, an additional 1 byte of padding is added to maintain 4-byte alignment.

3.197 SBAS2

Fast correction slots 0-12

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS2 are fast corrections for slots 0-12 in the mask of SBAS1. This message may or may not come when SBAS is in testing mode (see the **SBASCONTROL** command on page 370 for details).

Message ID: 982

Log type: Asynch

Recommended input:

```
log SBAS2a onchanged
```

ASCII example:

```
#SBAS2A,USB1,0,52.5,SATTIME,2209,514322.000,02000020,e194,16809;133,2,2,2047,0,
2047,2,-2,-1,-2,2047,0,2047,2047,0,1,14,5,14,9,5,6,11,14,7,14,14,5,6*34dbdcec
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS2 message can be logged to view the data breakdown of SBAS frame 2 which contains information about fast correction slots 0-12.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS2 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iodf	Issue of fast corrections data	Ulong	4	H+4
4	iodp	Issue of PRN mask data	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	prc0	prc(i): Fast corrections (-2048 to +2047) for the PRN in slot i (i = 0-12)	Long	4	H+12
6	prc1		Long	4	H+16
7	prc2		Long	4	H+20
8	prc3		Long	4	H+24
9	prc4		Long	4	H+28
10	prc5		Long	4	H+32
11	prc6		Long	4	H+36
12	prc7		Long	4	H+40
13	prc8		Long	4	H+44
14	prc9		Long	4	H+48
15	prc10		Long	4	H+52
16	prc11		Long	4	H+56
17	prc12		Long	4	H+60
18	udre0	udre(i): User differential range error indicator for the PRN in slot i (i = 0-12) See *Table 241: Evaluation of UDREI* on the next page for scaling information.	Ulong	4	H+64
19	udre1		Ulong	4	H+68
20	udre2		Ulong	4	H+72
21	udre3		Ulong	4	H+76
22	udre4		Ulong	4	H+80
23	udre5		Ulong	4	H+84
24	udre6		Ulong	4	H+88
25	udre7		Ulong	4	H+92
26	udre8		Ulong	4	H+96
27	udre9		Ulong	4	H+100
28	udre10		Ulong	4	H+104
29	udre11		Ulong	4	H+108
30	udre12		Ulong	4	H+112
31	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+116
32	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 241: Evaluation of UDREI

UDREI	UDRE metres	$\sigma^2_{i.udre}$ metres^2
0	0.75	0.0520
1	1.0	0.0924
2	1.25	0.1444
3	1.75	0.2830
4	2.25	0.4678
5	3.0	0.8315
6	3.75	1.2992
7	4.5	1.8709
8	5.25	2.5465
9	6.0	3.3260
10	7.5	5.1968
11	15.0	20.7870
12	50.0	230.9661
13	150.0	2078.695
14	Not Monitored	Not Monitored
15	Do Not Use	Do Not Use

The s2UDRE broadcast in SBAS2, SBAS3, SBAS4, SBAS5, SBAS6, and SBAS24 applies at a time prior to or at the time of applicability of the associated corrections.

3.198 SBAS3

Fast corrections slots 13-25

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS3 are fast corrections for slots 13-25 in the mask of SBAS1.

Message ID: 987

Log type: Asynch

Recommended input:

```
log sbas3a onchanged
```

ASCII example:

```
#SBAS3A,USB1,0,51.0,SATTIME,2209,514339.000,02000020,bff5,16809;131,1,2,2047,
-8,-12,2047,10,2047,2,2047,2047,10,2047,-2,7,14,7,8,14,6,14,5,14,14,10,14,5,6
*b79dcab9
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS3 message can be logged to view the data breakdown of SBAS frame 3 which contains information about fast correction slots 13-25.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS3 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iodf	Issue of fast corrections data	Ulong	4	H+4
4	iodp	Issue of PRN mask data	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	prc13	prc(i): Fast corrections (-2048 to +2047) for the PRN in slot i (i = 13-25)	Long	4	H+12
6	prc14		Long	4	H+16
7	prc15		Long	4	H+20
8	prc16		Long	4	H+24
9	prc17		Long	4	H+28
10	prc18		Long	4	H+32
11	prc19		Long	4	H+36
12	prc20		Long	4	H+40
13	prc21		Long	4	H+44
14	prc22		Long	4	H+48
15	prc23		Long	4	H+52
16	prc24		Long	4	H+56
17	prc25		Long	4	H+60
18	udre13	udre(i): User differential range error indicator for the PRN in slot i (i = 13-25) See *Table 241: Evaluation of UDREI* on page 954 for scaling information.	Ulong	4	H+64
19	udre14		Ulong	4	H+68
20	udre15		Ulong	4	H+72
21	udre16		Ulong	4	H+76
22	udre17		Ulong	4	H+80
23	udre18		Ulong	4	H+84
24	udre19		Ulong	4	H+88
25	udre20		Ulong	4	H+92
26	udre21		Ulong	4	H+96
27	udre22		Ulong	4	H+100
28	udre23		Ulong	4	H+104
29	udre24		Ulong	4	H+108
30	udre25		Ulong	4	H+112
31	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+116
32	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.199 SBAS4

Fast correction slots 26-38

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS4 are fast corrections for slots 26-38 in the mask of SBAS1.

Message ID: 992

Log type: Asynch

Recommended input:

```
log sbas4a onchanged
```

ASCII example:

```
#SBAS4A,USB1,0,50.5,SATTIME,2209,514359.000,02000020,5b17,16809;131,0,2,2047,
2047,-2,-2,-2,2047,-12,-7,-10,-13,2047,2047,2047,14,14,5,14,6,14,10,10,10,10,
15,15,15*21e3ed26
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS4 message can be logged to view the data breakdown of SBAS frame 4 which contains information about fast correction slots 26-38.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS4 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iodf	Issue of fast corrections data	Ulong	4	H+4
4	iodp	Issue of PRN mask data	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	prc26	prc(i): Fast corrections (-2048 to +2047) for the PRN in slot i (i = 26-38)	Long	4	H+12
6	prc27		Long	4	H+16
7	prc28		Long	4	H+20
8	prc29		Long	4	H+24
9	prc30		Long	4	H+28
10	prc31		Long	4	H+32
11	prc32		Long	4	H+36
12	prc33		Long	4	H+40
13	prc34		Long	4	H+44
14	prc35		Long	4	H+48
15	prc36		Long	4	H+52
16	prc37		Long	4	H+56
17	prc38		Long	4	H+60
18	udre26	udre(i): User differential range error indicator for the PRN in slot i (i = 26-38) See *Table 241: Evaluation of UDREI* on page 954 for scaling information.	Ulong	4	H+64
19	udre27		Ulong	4	H+68
20	udre28		Ulong	4	H+72
21	udre29		Ulong	4	H+76
22	udre30		Ulong	4	H+80
23	udre31		Ulong	4	H+84
24	udre32		Ulong	4	H+88
25	udre33		Ulong	4	H+92
26	udre34		Ulong	4	H+96
27	udre35		Ulong	4	H+100
28	udre36		Ulong	4	H+104
29	udre37		Ulong	4	H+108
30	udre38		Ulong	4	H+112
31	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+116
32	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.200 SBAS5

Fast correction slots 39-50

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS5 are fast corrections for slots 39-50 in the mask of SBAS1.

Message ID: 994

Log type: Asynch

Recommended input:

```
log sbas5a onchanged
```

ASCII example:

```
#SBAS5A,COM1,0,72.5,SATTIME,1093,161480.000,02040020,31d4,209;122,1,3,-7,2047,
2047,2047,-4,2047,2047,2047,9,2047,2047,-3,-2,11,14,14,14,4,14,14,14,5,14,14,4,
2*9adf5971
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS5 message can be logged to view the data breakdown of SBAS frame 5 which contains information about fast correction slots 39-50.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS5 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iodf	Issue of fast corrections data	Ulong	4	H+4
4	iodp	Issue of PRN mask data	Ulong	4	H+8

Field	Field type	Description	Format	Binary bytes	Binary offset
5	prc39	prc(i): Fast corrections (-2048 to +2047) for the PRN in slot i (i = 39-50)	Long	4	H+12
6	prc40		Long	4	H+16
7	prc41		Long	4	H+20
8	prc42		Long	4	H+24
9	prc43		Long	4	H+28
10	prc44		Long	4	H+32
11	prc45		Long	4	H+36
12	prc46		Long	4	H+40
13	prc47		Long	4	H+44
14	prc48		Long	4	H+48
15	prc49		Long	4	H+52
16	prc50		Long	4	H+56
17	prc51 (Invalid, do not use)		Long	4	H+60
18	udre39	udre(i): User differential range error indicator for the PRN in slot i (i = 39-50) See *Table 241: Evaluation of UDREI* on page 954 for scaling information.	Ulong	4	H+64
19	udre40		Ulong	4	H+68
20	udre41		Ulong	4	H+72
21	udre42		Ulong	4	H+76
22	udre43		Ulong	4	H+80
23	udre44		Ulong	4	H+84
24	udre45		Ulong	4	H+88
25	udre46		Ulong	4	H+92
26	udre47		Ulong	4	H+96
27	udre48		Ulong	4	H+100
28	udre49		Ulong	4	H+104
29	udre50		Ulong	4	H+108
30	udre51 (Invalid, do not use)		Ulong	4	H+112
31	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+116
32	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.201 SBAS6

Integrity message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS6 is the integrity information message. Each message includes an IODF for each fast corrections message. The σ^2_{UDRE} information for each block of satellites applies to the fast corrections with the corresponding IODF.

Message ID: 995

Log type: Asynch

Recommended input:

```
log sbas6a onchanged
```

ASCII example:

```
#SBAS6A,COM1,0,57.5,SATTIME,1093,273317.000,02000020,526a,209;122,3,3,3,3,9,14,
14,2,3,10,2,14,14,3,14,14,5,14,14,7,14,14,14,14,14,14,3,3,14,14,14,14,3,15,11,
11,15,0,0,0,0,0,0,0,0,0,0,0,0,0,0,0,0,0*11495f69
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS6 message can be logged to view the data breakdown of SBAS frame 6 which contains information about the integrity message.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS6 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iodf2	Issue of fast corrections data	Ulong	4	H+4
4	iodf3	Issue of fast corrections data	Ulong	4	H+8
5	iodf4	Issue of fast corrections data	Ulong	4	H+12
6	iodf5	Issue of fast corrections data	Ulong	4	H+16
7	udre0	udre(i): User differential range error indicator for the PRN in slot i (i = 0-50) See *Table 241: Evaluation of UDREI* on page 954 for scaling information.	Ulong	4	H+20
8	udre1		Ulong	4	H+24

Field	Field type	Description	Format	Binary bytes	Binary offset
9	udre2		Ulong	4	H+28
10	udre3		Ulong	4	H+32
11	udre4		Ulong	4	H+36
12	udre5		Ulong	4	H+40
13	udre6		Ulong	4	H+44
14	udre7		Ulong	4	H+48
15	udre8		Ulong	4	H+52
16	udre9		Ulong	4	H+56
17	udre10		Ulong	4	H+60
18	udre11		Ulong	4	H+64
19	udre12		Ulong	4	H+68
20	udre13		Ulong	4	H+72
21	udre14		Ulong	4	H+76
22	udre15		Ulong	4	H+80
23	udre16		Ulong	4	H+84
24	udre17		Ulong	4	H+88
25	udre18		Ulong	4	H+92
26	udre19		Ulong	4	H+96
27	udre20		Ulong	4	H+100
28	udre21		Ulong	4	H+104
29	udre22		Ulong	4	H+108
30	udre23		Ulong	4	H+112
31	udre24		Ulong	4	H+116
32	udre25		Ulong	4	H+120
33	udre26		Ulong	4	H+124
34	udre27		Ulong	4	H+128
35	udre28		Ulong	4	H+132
36	udre29		Ulong	4	H+136
37	udre30		Ulong	4	H+140
38	udre31		Ulong	4	H+144

Field	Field type	Description	Format	Binary bytes	Binary offset
39	udre32		Ulong	4	H+148
40	udre33		Ulong	4	H+152
41	udre34		Ulong	4	H+156
42	udre35		Ulong	4	H+160
43	udre36		Ulong	4	H+164
44	udre37		Ulong	4	H+168
45	udre38		Ulong	4	H+172
46	udre39		Ulong	4	H+176
47	udre40		Ulong	4	H+180
48	udre41		Ulong	4	H+184
49	udre42		Ulong	4	H+188
50	udre43		Ulong	4	H+192
51	udre44		Ulong	4	H+196
52	udre45		Ulong	4	H+200
53	udre46		Ulong	4	H+204
54	udre47		Ulong	4	H+208
55	udre48		Ulong	4	H+212
56	udre49		Ulong	4	H+216
57	udre50		Ulong	4	H+220
58	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+224
59	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.202 SBAS7

Fast correction degradation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The SBAS7 message specifies the applicable IODP, system latency time and fast degradation factor indicator for computing the degradation of fast and long term corrections.

Message ID: 996

Log type: Asynch

Recommended input:

```
log sbas7a onchanged
```

ASCII example:

```
#SBAS7A,USB1,0,52.5,SATTIME,2209,514449.000,02000020,12e3,16809;133,1,2,0,15,15
,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,15,
15,15,15,15,15,15,15,15,0,0,0,0,0,0,0,0,0,0,0,0,0,0,0*cccea62b
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS7 message can be logged to view the data breakdown of SBAS frame 7 which contains information about fast correction degradation.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS7 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	latency	System latency (s)	Ulong	4	H+4
4	iodp	Issue of PRN mask data	Ulong	4	H+8
5	spare bits	Unused spare bits	Ulong	4	H+12
6	al(0)	al(i): Degradation factor indicator for the PRN in slot i (i = 0-50)	Ulong	4	H+16
7	al(1)		Ulong	4	H+20
8	al(2)		Ulong	4	H+24
9	al(3)		Ulong	4	H+28
10	al(4)		Ulong	4	H+32
11	al(5)		Ulong	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
12	al(6)		Ulong	4	H+40
13	al(7)		Ulong	4	H+44
14	al(8)		Ulong	4	H+48
15	al(9)		Ulong	4	H+52
16	al(10)		Ulong	4	H+56
17	al(11)		Ulong	4	H+60
18	al(12)		Ulong	4	H+64
19	al(13)		Ulong	4	H+68
20	al(14)		Ulong	4	H+72
21	al(15)		Ulong	4	H+76
22	al(16)		Ulong	4	H+80
23	al(17)		Ulong	4	H+84
24	al(18)		Ulong	4	H+88
25	al(19)		Ulong	4	H+92
26	al(20)		Ulong	4	H+96
27	al(21)		Ulong	4	H+100
28	al(22)		Ulong	4	H+104
29	al(23)		Ulong	4	H+108
30	al(24)		Ulong	4	H+112
31	al(25)		Ulong	4	H+116
32	al(26)		Ulong	4	H+120
33	al(27)		Ulong	4	H+124
34	al(28)		Ulong	4	H+128
35	al(29)		Ulong	4	H+132
36	al(30)		Ulong	4	H+136
37	al(31)		Ulong	4	H+140
38	al(32)		Ulong	4	H+144
39	al(33)		Ulong	4	H+148
40	al(34)		Ulong	4	H+152
41	al(35)		Ulong	4	H+156

Field	Field type	Description	Format	Binary bytes	Binary offset
42	al(36)		Ulong	4	H+160
43	al(37)		Ulong	4	H+164
44	al(38)		Ulong	4	H+168
45	al(39)		Ulong	4	H+172
46	al(40)		Ulong	4	H+176
47	al(41)		Ulong	4	H+180
48	al(42)		Ulong	4	H+184
49	al(43)		Ulong	4	H+188
50	al(44)		Ulong	4	H+192
51	al(45)		Ulong	4	H+196
52	al(46)		Ulong	4	H+200
53	al(47)		Ulong	4	H+204
54	al(48)		Ulong	4	H+208
55	al(49)		Ulong	4	H+212
56	al(50)		Ulong	4	H+216
57	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+220
58	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.203 SBAS9

GEO navigation message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS9 provides the GEO navigation message representing the position, velocity and acceleration of the geostationary satellite, in ECEF coordinates and its apparent clock time and frequency offsets.

Also included is the time of applicability, an Issue of Data (IOD) and an accuracy exponent (URA) representing the estimated accuracy of the message. The time offset and time drift are with respect to SBAS Network Time. Their combined effect is added to the estimate of the satellite's transmit time.

Message ID: 997

Log type: Asynch

Recommended input:

```
log sbas9a onchanged
```

ASCII example:

```
#SBAS9A,USB1,3,52.0,SATTIME,2209,514470.000,02000020,b580,16809;131,237,82496,
0,-19136930.4000,-37573052.2400,-2757.2000,-0.221875000,-0.001875000,
-0.2160000,-0.0000125,0.0000250,0.000000000,2.607703209e-08,-8.185452316e-12
*e31c3f2e

#SBAS9A,USB1,2,52.0,SATTIME,2209,514470.000,02000020,b580,16809;135,172,82496,
0,-24165841.7600,-34542291.9200,1690.8000,0.700000000,-1.039375000,-1.3040000,
-0.0000750,0.0000125,0.000000000,4.563480616e-08,-1.364242053e-11*e3afca34

#SBAS9A,USB1,1,52.0,SATTIME,2209,514470.000,02000020,b580,16809;138,172,82496,
0,-12514381.3600,-40257277.6000,82561.6000,0.581250000,-1.101250000,23.3200000,
-0.0001250,0.0000250,-0.000437500,2.328306437e-08,-1.091393642e-11*53ac8a8b

#SBAS9A,USB1,0,52.0,SATTIME,2209,514473.000,02000020,b580,16809;133,237,82496,
0,-26616356.6400,-32700988.0000,15871.2000,-0.046250000,-0.230000000,
-0.7200000,-0.0000250,0.0000250,-0.000062500,2.002343535e-08,-4.547473509e-12
*2e70df43
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS9 message can be logged to view the data breakdown of SBAS frame 9 which contains the GEO navigation message.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS9 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iodn	Issue of GEO navigation data	Ulong	4	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	t_0	Time of applicability	Ulong	4	H+8
5	ura	URA value	Ulong	4	H+12
6	x	ECEF x coordinate (m)	Double	8	H+16
7	y	ECEF y coordinate (m)	Double	8	H+24
8	z	ECEF z coordinate (m)	Double	8	H+32
9	xvel	X rate of change (m/s)	Double	8	H+40
10	yvel	Y rate of change (m/s)	Double	8	H+48
11	zvel	Z rate of change (m/s)	Double	8	H+56
12	xaccel	X rate of rate change (m/s^2)	Double	8	H+64
13	yaccel	Y rate of rate change (m/s^2)	Double	8	H+72
14	zaccel	Z rate of rate change (m/s^2)	Double	8	H+80
15	a_{f0}	Time offset (s)	Double	8	H+88
16	a_{f1}	Time drift (s)	Double	8	H+96
17	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+104
18	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.204 SBAS10

Degradation factor

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The fast corrections, long term corrections and ionospheric corrections are all provided in the SBAS10 message.

Message ID: 978

Log type: Asynch

Recommended input:

```
log SBAS10a onchanged
```

ASCII example:

```
#SBAS10A,USB1,0,52.5,SATTIME,2209,514522.000,02000020,c305,16809;131,54,38,76,
256,152,100,311,83,256,6,836,300,0,0,0,00000000000000000000000*028dd85b
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS10 message can be logged to view the data breakdown of SBAS frame 10 which contains information about degradation factors.

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
1	Log header	SBAS10 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0	-
2	prn	Source PRN of message	Ulong	4	H	-
3	b_{rcc}	Estimated noise and round off error parameter	Ulong	4	H+4	0.002
4	c_{ltc_lsb}	Maximum round off due to the least significant bit (lsb) of the orbital clock	Ulong	4	H+8	0.002
5	c_{ltc_vl}	Velocity error bound	Ulong	4	H+12	0.00005
6	i_{ltc_vl}	Update interval for v=1 long term	Ulong	4	H+16	-
7	c_{ltc_v0}	Bound on update delta	Ulong	4	H+20	0.002
8	i_{ltc_v1}	Minimum update interval v = 0	Ulong	4	H+24	-
9	c_{geo_lsb}	Maximum round off due to the lsb of the orbital clock	Ulong	4	H+28	0.0005
10	c_{geo_v}	Velocity error bound	Ulong	4	H+32	0.00005
11	i_{geo}	Update interval for GEO navigation message	Ulong	4	H+36	-

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
12	c_{er}	Degradation parameter	Ulong	4	H+40	0.5
13	c_{iono_step}	Bound on ionospheric grid delay difference	Ulong	4	H+44	0.001
14	i_{iono}	Minimum ionospheric update interval	Ulong	4	H+48	-
15	c_{iono_ramp}	Rate of ionospheric corrections change	Ulong	4	H+52	0.000005
16	rss_{udre}	User differential range error flag	Ulong	4	H+56	-
17	rss_{iono}	Root sum square flag	Ulong	4	H+60	-
18	spare bits	Spare 88 bits, possibly GLONASS	Hex[11]	11	H+64	-
19	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+75	-
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-	-

3.205 SBAS12

SBAS network time and UTC

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS12 contains information bits for the UTC parameters and UTC time standard from which an offset is determined. The UTC parameters correlate UTC time with the SBAS network time rather than with GPS reference time.

Message ID: 979

Log type: Asynch

Recommended input:

```
log SBAS12a onchanged
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS12 message can be logged to view the data breakdown of SBAS frame 12 which contains information about time parameters.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS12 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	A_1	Time drift (s/s)	Double	8	H+4
4	A_0	Time offset (s)	Double	8	H+12
5	seconds	Seconds into the week (s)	Ulong	4	H+20
6	week	Week number	Ushort	2	H+24
7	dt_{ls}	Delta time due to leap seconds	Short	2	H+26
8	wn_{lsf}	Week number, leap second future	Ushort	2	H+28
9	dn	Day of the week (the range is 1 to 7 where Sunday = 1 and Saturday = 7)	Ushort	2	H+30
10	dt_{lsf}	Delta time, leap second future	Ushort	2	H+32
11	utc id	UTC type identifier	Ushort	2	H+34
12	gpstow	GPS reference time of the week	Ulong	4	H+36
13	gpswn	GPS de-modulo week number	Ulong	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
14	glo indicator	Is GLONASS information present? 0 = FALSE 1 = TRUE	Enum	4	H+44
15	Reserved array of hexabytes for GLONASS		Char[10]	12	H+48
16	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+60
17	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.206 SBAS17

GEO almanac message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

Almanacs for all GEOs are broadcast periodically to alert you of their existence, location, the general service provided, status and health.

Unused almanacs have a PRN number of 0 and should be ignored, see *ASCII Example* below.

Message ID: 980

Log type: Asynch

Recommended input:

```
log SBAS17a onchanged
```

ASCII example:

```
#SBAS17A,USB1,0,52.0,SATTIME,2209,514511.000,02000020,896c,16809;133,3,0,131,0,-
19136000,-37572600,0,0,0,0,0,133,0,-26616200,-32700200,26000,0,0,0,0,135,0,
-24167000,-34541000,0,0,0,0,82496*a44a79e8
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS17 message can be logged to view the data breakdown of SBAS frame 17 which contains GEO almanacs.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS17 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	#ents	Number of almanac entries with information to follow	Ulong	4	H+4
4	data id	Data ID type	Ushort	2	H+8
5	entry prn	PRN for this entry	Ushort	2	H+10
6	health	Health bits	Ushort	4[1]	H+12
7	x	ECEF x coordinate (m)	Long	4	H+16
8	y	ECEF y coordinate (m)	Long	4	H+20
9	z	ECEF z coordinate (m)	Long	4	H+24

1. In the binary log case, an additional 2 bytes of padding is added to maintain 4-byte alignment.

Field	Field type	Description	Format	Binary bytes	Binary offset
10	x vel	X rate of change (m/s)	Long	4	H+28
11	y vel	Y rate of change (m/s)	Long	4	H+32
12	z vel	Z rate of change (m/s)	Long	4	H+36
13...	Next entry = H+8+(#ents x 32)				
14	t0	Time of day in seconds (0 to 86336) Scaling = 64	Ulong	4	H+8+ (#ents x 32)
15	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+12+ (#ents x 32)
16	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.207 SBAS18

IGP mask

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The ionospheric delay corrections are broadcast as vertical delay estimates, at specified ionospheric grid points (IGPs), applicable to a signal on L1. The predefined IGPs are contained in 11 bands (numbered 0 to 10). Bands 0-8 are vertical bands on a Mercator projection map and bands 9-10 are horizontal bands on a Mercator projection map. Since it is impossible to broadcast IGP delays for all possible locations, a mask is broadcast to define the IGP locations providing the most efficient model of the ionosphere at the time.

Message ID: 981

Log type: Asynch

Recommended input:

```
log SBAS18a onchanged
```

ASCII example:

```
#SBAS18A,USB1,0,52.5,SATTIME,2209,514594.000,02000020,f2c0,16809;133,5,9,3,ffff
fffe000000000fffff00007ffff00007fffe00007f810000,0*396a66e6
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS18 message can be logged to view the data breakdown of SBAS frame 18 which contains information about ionospheric grid points.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS18 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	#bands	Number of bands broadcast	Ulong	4	H+4
4	band num	Specific band number that identifies which of the 11 IGP bands the data belongs to	Ulong	4	H+8
5	iodi	Issue of ionospheric data	Ulong	4	H+12
6	igp mask	IGP mask	Uchar [26]	28[1]	H+16
7	spare bit	One spare bit	Ulong	4	H+44
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+48
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary log case, an additional 2 bytes of padding are added to maintain 4-byte alignment.

3.208 SBAS24

Mixed fast/slow corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

If there are 6 or fewer satellites in a block, they may be placed in this mixed correction message. There is a fast data set for each satellite and a UDRE indicator. Each message also contains an IODP indicating the associated PRN mask.

The fast correction (PRC) has a valid range of -2048 to +2047. If the range is exceeded, a don't use indication is inserted into the user differential range error indicator (UDREI) field, see *Table 241: Evaluation of UDREI* on page 954. You should ignore extra data sets not represented in the PRN mask.

The time of applicability (T0) of the PRC is the start of the epoch of the WNT second that is coincident with the transmission at the GEO satellite of the first bit of the message block.

Message ID: 983

Log type: Asynch

Recommended input:

```
log SBAS24a onchanged
```

ASCII example:

```
#SBAS24A,COM1,0,34.0,SATTIME,1337,417108.000,02000000,0a33,1984;134,2047,2047,
2047,2047,-1,-2,14,14,14,14,11,14,2,2,0,0,1,0,0,0,0,0,0,0,0,0,0,0,0,0,0,0,0
*923df3cc
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS24 message can be logged to view the data breakdown of SBAS frame 24 which contains mixed fast/slow corrections.

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
1	Log header	SBAS24 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0	-
2	prn	Source PRN of message	Ulong	4	H	-
3	prc0	prc(i): Fast corrections (-2048 to +2047) for the PRN in slot i (i = 0-5)	Long	4	H+4	-
4	prc1		Long	4	H+8	-
5	prc2		Long	4	H+12	-
6	prc3		Long	4	H+16	-
7	prc4		Long	4	H+20	-
8	prc5		Long	4	H+24	-

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
9	udre0	udre(i): User differential range error indicator for the PRN in slot i (i = 0-5)	Ulong	4	H+28	See *Table 241: Evaluation of UDREI* on page 954
10	udre1		Ulong	4	H+32	
11	udre2		Ulong	4	H+36	
12	udre3		Ulong	4	H+40	
13	udre4		Ulong	4	H+44	
14	udre5		Ulong	4	H+48	
15	iodp	Issue of PRN mask data	Ulong	4	H+52	-
16	block id	Associated message type	Ulong	4	H+56	
17	iodf	Issue of fast corrections data	Ulong	4	H+60	-
18	spare	Spare value	Ulong	4	H+64	-
19	vel	Velocity code flag	Ulong	4	H+68	-
20	mask1	Index into PRN mask (Type 1)	Ulong	4	H+72	-
21	iode1	Issue of ephemeris data	Ulong	4	H+76	-
22	dx1	Delta x (ECEF)	Long	4	H+80	0.125
23	dy1	Delta y (ECEF)	Long	4	H+84	0.125
24	dz1	Delta z (ECEF)	Long	4	H+88	0.125
25	da_{f0}	Delta a_{f0} clock offset	Long	4	H+92	2^{-31}
26	mask2	Second index into PRN mask (Type 1)	Ulong	4	H+96	-
27	iode2	Second issue of ephemeris data	Ulong	4	H+100	-
28	ddx	Delta delta x (ECEF)	Long	4	H+104	2^{-11}
29	ddy	Delta delta y (ECEF)	Long	4	H+108	2^{-11}
30	ddz	Delta delta z (ECEF)	Long	4	H+112	2^{-11}
31	da_{f1}	Delta a_{f1} clock offset	Long	4	H+116	2^{-39}
32	t_0	Applicable time of day	Ulong	4	H+120	16
33	iodp	Issue of PRN mask data	Ulong	4	H+124	-
34	corr spare	Spare value when velocity code is equal to 0	Ulong	4	H+128	-
35	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+132	-
36	[CR][LF]	Sentence terminator (ASCII only)	-	-	-	-

3.209 SBAS25

Long term slow satellite corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS25 provides error estimates for slow varying satellite ephemeris and clock errors with respect to WGS84 ECEF coordinates.

Message ID: 984

Log type: Asynch

Recommended input:

```
log SBAS25a onchanged
```

ASCII example:

```
#SBAS25A,USB1,0,51.5,SATTIME,2209,514661.000,02000020,b8ff,16809;133,1,16,94,
23,-11,1,-3,0,0,-1,-1,1,-6,5157,2,0,1,31,75,0,12,1,12,0,0,-1,-1,1,0,5157,2,0
*3341fe84
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS25 message can be logged to view the data breakdown of SBAS frame 25 which contains long term slow satellite corrections.

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
1	Log header	SBAS25 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0	-
2	prn	Source PRN of message	Ulong	4	H	-
3	1st half vel	Velocity code flag (0 or 1)	Ulong	4	H+4	-
4	1st half mask1	Index into PRN mask (Type 1)	Ulong	4	H+8	-
5	1st half iode1	Issue of ephemeris data	Ulong	4	H+12	-
6	1st half dx1	Delta x (ECEF)	Long	4	H+16	0.125
7	1st half dy1	Delta y (ECEF)	Long	4	H+20	0.125
8	1st half dz1	Delta z (ECEF)	Long	4	H+24	0.125

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
9	1st half a_{f0}	Delta a_{f0} clock offset	Long	4	H+28	2^{-31}
10	1st half mask2	Second index into PRN mask (Type 1) Dummy value when velocity code = 1	Ulong	4	H+32	-
11	1st half iode2	Second issue of ephemeris data Dummy value when velocity code = 1	Ulong	4	H+36	-
12	1st half ddx	Delta delta x (ECEF) when velocity code = 1 Delta x (dx) when velocity code = 0	Long	4	H+40	2^{-11}
13	1st half ddy	Delta delta y (ECEF) when velocity code = 1 Delta y (dy) when velocity code = 0	Long	4	H+44	2^{-11}
14	1st half ddz	Delta delta z (ECEF) when velocity code = 1 Delta z (dz) when velocity code = 0	Long	4	H+48	2^{-11}
15	1st half a_{f1}	Delta a_{f1} clock offset when velocity code = 1 Delta a_{f0} clock offset when velocity code = 0	Long	4	H+52	2^{-39}
16	1st half t_0	Applicable time of day Dummy value when velocity code = 0	Ulong	4	H+56	16
17	1st half iodp	Issue of PRN mask data	Ulong	4	H+60	-
18	1st half corr spare	Spare value when velocity code = 0 Dummy value when velocity code = 1	Ulong	4	H+64	-
19	2nd half vel	Velocity code flag (0 or 1)	Ulong	4	H+68	-
20	2nd half mask1	Index into PRN mask (Type 1)	Ulong	4	H+72	-
21	2nd half iode1	Issue of ephemeris data	Ulong	4	H+76	-
22	2nd half dx1	Delta x (ECEF)	Long	4	H+80	0.125
23	2nd half dy1	Delta y (ECEF)	Long	4	H+84	0.125
24	2nd half dz1	Delta z (ECEF)	Long	4	H+88	0.125
25	2nd half a_{f0}	Delta a_{f0} clock offset	Long	4	H+92	2^{-31}
26	2nd half mask2	Second index into PRN mask (Type 1) Dummy value when velocity code = 1	Ulong	4	H+96	-

Field	Field type	Description	Format	Binary bytes	Binary offset	Scaling
27	2nd half iode2	Second issue of ephemeris data Dummy value when velocity code = 1	Ulong	4	H+100	-
28	2nd half ddx	Delta delta x (ECEF) when velocity code = 1 Delta x (dx) when velocity code = 0	Long	4	H+104	2^{-11}
29	2nd half ddy	Delta delta y (ECEF) when velocity code = 1 Delta y (dy) when velocity code = 0	Long	4	H+108	2^{-11}
30	2nd half ddz	Delta delta z (ECEF) when velocity code = 1 Delta z (dz) when velocity code = 0	Long	4	H+112	2^{-11}
31	2nd half a_{f1}	Delta a_{f1} clock offset when velocity code = 1 Delta a_{f0} clock offset when velocity code = 0	Long	4	H+116	2^{-39}
32	2nd half t_0	Applicable time of day Dummy value when velocity code = 0	Ulong	4	H+120	16
33	2nd half iodp	Issue of PRN mask data	Ulong	4	H+124	-
34	2nd half corr spare	Spare value when velocity code = 0 Dummy value when velocity code = 1	Ulong	4	H+128	-
35	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+132	-
36	[CR][LF]	Sentence terminator (ASCII only)	-	-	-	-

3.210 SBAS26

Ionospheric delay corrections

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS26 provides vertical delays (relative to an L1 signal) and their accuracy at geographically defined IGPs identified by the BAND NUMBER and IGP number. Each message contains a band number and a block ID, which indicates the location of the IGPs in the respective band mask.

Message ID: 985

Log type: Asynch

Recommended input:

```
log SBAS26a onchanged
```

ASCII example:

```
#SBAS26A,USB1,0,50.5,SATTIME,2209,514696.000,02000020,ec70,16809;131,2,0,15,91,
12,73,11,60,9,52,9,44,9,39,9,35,9,34,10,31,11,85,12,70,11,58,10,50,9,43,9,39,9,
3,0*d3271683
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS26 message can be logged to view the data breakdown of SBAS frame 26 which contains ionospheric delay corrections

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS26 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	band num	Band number	Ulong	4	H+4
4	block id	Block ID	Ulong	4	H+8
5	#pts	Number of grid points with information to follow	Ulong	4	H+12
6	igp_{vde}	IGP vertical delay estimates Scaling = 0.125	Ulong	4	H+16
7	givei	Grid ionospheric vertical error indicator	Ulong	4	H+20
8...	Next #pts entry = H + 16 + (#pts x 8)				
9	iodi	Issue of data - ionosphere	Ulong	4	H+16+ (#pts x 8)

Field	Field type	Description	Format	Binary bytes	Binary offset
10	spare	7 spare bits	Ulong	4[1]	H+20+ (#pts x 8)
11	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+24+ (#pts x 8)
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.

3.211 SBAS27

SBAS service message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

SBAS27 messages apply only to the service provider transmitting the message. The number of service messages indicates the total number of unique SBAS27 messages for the current IODS. Each unique message for that IODS includes a sequential message number. The IODS is incremented in all messages, each time that any parameter in any SBAS27 message is changed.

Message ID: 986

Log type: Asynch

Recommended input:

```
log SBAS27a onchanged
```

Each raw SBAS frame gives data for a specific frame decoder number. The SBAS27 message can be logged to view the data breakdown of SBAS frame 27 which contains information about SBAS service messages.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBAS27 header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	prn	Source PRN of message	Ulong	4	H
3	iods	Issue of slow corrections data	Ulong	4	H+4
4	#messages	Low-by-one count of messages	Ulong	4	H+8
5	message num	Low-by-one message number	Ulong	4	H+12
6	priority code	Priority code	Ulong	4	H+16
7	dudre inside	Delta user differential range error – inside	Ulong	4	H+20
8	dudre outside	Delta user differential range error – outside	Ulong	4	H+24
9...	#reg	Number of regions with information to follow	Ulong	4	H+28
10	lat1	Coordinate 1 latitude	Long	4	H+32
11	lon1	Coordinate 1 longitude	Long	4	H+36
12	lat2	Coordinate 2 latitude	Long	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
13	lon2	Coordinate 2 longitude	Long	4	H+44
14	shape	Shape where: 0 = triangle, 1 = square	Ulong	4	H+48
15	Next #reg entry = H+32+(#reg x 20)				
16	Reserved		Ulong	4	H+32+(#reg x 20)
17	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+36+(#reg x 20)
18	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.212 SBASALMANAC

SBAS almanac collection

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains a collection of all current SBAS almanacs that have been decoded by the receiver and may contain almanac data for multiple PRNs. The SBASALMANAC log is populated by the GEO Almanac Message Type 17 which is available in the **SBAS17** log (see page 973). These PRNs are broken out into individual SBAS almanac entries for this message and output individually. If multiple SBAS subsystems (e.g., WAAS, EGNOS, GAGAN, MSAS) are tracked, this message will include almanac data collected from each with the subsystem identified in each message entry. The almanac data contains all of the information required to compute the satellite position as well as health and status information.

The OEM7 family of receivers automatically save almanacs in their Non-Volatile Memory (NVM), so creating an almanac boot file is not necessary.

Message ID: 1425

Log type: Asynch

Recommended input:

```
Log SBASALMANACA onchanged
```

ASCII example:

```
#SBASALMANACA,COM1,2,70.5,SATTIME,2401,255135.000,02000008,b46b,17665;131,WAAS,
82112,0,0,-19136000,-37572600,0,0,0,0*79a5a0a4

#SBASALMANACA,COM1,1,70.5,SATTIME,2401,255135.000,02000008,b46b,17665;133,WAAS,
82112,0,0,-26631800,-32687200,0,0,0,0*92f8f702

#SBASALMANACA,COM1,0,70.5,SATTIME,2401,255135.000,02000008,b46b,17665;135,WAAS,
82112,0,0,-24182600,-34533200,-26000,0,0,0*c2e5ed6f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SBASALMANAC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Satellite ID	Satellite ID	Ulong	4	H
3	Variant	System variant (refer to *Table 242: SBAS subsystem types* on the next page)	Enum	4	H + 4
4	Time	Time of day (s)	Ulong	4	H + 8
5	Data ID	Data identification	Ushort	2	H + 12
6	Health	Satellite health	Ushort	2	H + 14
7	X	ECEF X coordinate (m)	Long	4	H + 16
8	Y	ECEF Y coordinate (m)	Long	4	H + 20

Field	Field type	Description	Format	Binary bytes	Binary offset
9	Z	ECEF Z coordinate (m)	Long	4	H + 24
10	X Velocity	X rate of change (m/s)	Long	4	H + 28
11	Y Velocity	Y rate of change (m/s)	Long	4	H + 32
12	Z Velocity	Z rate of change (m/s)	Long	4	H + 36
13	CRC	32-bit CRC (ASCII and binary only)	Ulong	4	H + 40
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 242: SBAS subsystem types

ASCII	Binary	Country/Region
NONE	0	N/A
UNKNOWN	1	N/A
WAAS	2	USA
EGNOS	3	European Union
MSAS	4	Japan
GAGAN	5	India
UNSUPPORTED	6	N/A
QZSS	7	Japan
BDSBAS	8	China
KASS	9	Korea
ANGA	10	Africa
SOUTHPAN	11	Australia / New Zealand
SDCM	12	Russia

3.213 SOFTLOADSTATUS

Describes the status of the SoftLoad process

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log describes the status of the SoftLoad process.

Status values >= 16 (ERROR) indicate that an error has occurred during the loading process. Status < 16 (ERROR) are part of normal SoftLoad operation.

Message ID: 1235

Log type: Asynch

Recommended input:

```
log softloadstatusa onchanged
```

ASCII example:

```
#SOFTLOADSTATUSA,USB1,0,50.5,UNKNOWN,0,0.000,02000020,2d64,16809;
NOT_STARTED*248aced3
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SOFTLOADSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	status	Status of the SoftLoad process see *Table 243: SoftLoad status type* below	Enum	4	H
3	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4
4	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 243: SoftLoad status type

Value	Name	Description
1	NOT_STARTED	SoftLoad process has not begun.
2	READY_FOR_SETUP	SoftLoad process is ready to receive setup information in the form of the **SOFTLOADSETUP** command or **SOFTLOADSREC** command with S0 records. Once sufficient setup data has been sent, the process is also ready for the **SOFTLOADDATA** command.
3	READY_FOR_DATA	SoftLoad process is ready to receive data in the form of the **SOFTLOADDATA** command or **SOFTLOADSREC** command with S3 records. Once all data has been sent, send the **SOFTLOADCOMMIT** command.

Value	Name	Description
4	DATA_VERIFIED	SoftLoad data has passed CRC. This status occurs after a **SOFTLOADCOMMIT** command.
5	WRITING_FLASH	SoftLoad data is being written to flash. This status occurs after a **SOFTLOADCOMMIT** command. During a firmware upload, the receiver may remain in this state for 300 seconds or longer.
6	WROTE_FLASH	SoftLoad data has been written to flash.
7	WROTE_ AUTHCODE	The embedded Auth-Code was successfully written.
8	COMPLETE	SoftLoad process has completed. The next step is to send the **RESET** command to reset the receiver.
9	VERIFYING_DATA	SoftLoad is verifying the downloaded image.
10	COPIED_ SIGNATURE_ AUTH	Signature Auth-Codes have been copied from the current firmware to the downloaded firmware.
11	WROTE_ TRANSACTION_ TABLE	The downloaded firmware has been activated and will be executed if the receiver is reset. This status is effectively identical to COMPLETE.
13	PROCESSING_ FILE	The **SOFTLOADFILE** command is processing the firmware file.
16	ERROR	Indicates an internal error in the SoftLoad process. This error is not expected to occur. Contact NovAtel Customer Support for assistance.
17	RESET_ERROR	Error resetting SoftLoad. Reset the receiver and restart the SoftLoad process.
18	BAD_SRECORD	A bad S Record was received. Ensure that S Records are enclosed in double quotes within the **SOFTLOADSREC** command.
19	BAD_PLATFORM	This data cannot be loaded onto this platform. Ensure that the correct *.shex file for the platform is being used.
20	BAD_MODULE	This module cannot be loaded with SoftLoad. This file must be loaded using NovAtel Application Suite or a similar loader.
21	BAD_AUTHCODE	Bad Auth-Code received for this PSN.
22	NOT_READY_ FOR_SETUP	A **SOFTLOADSETUP** command was entered before a **SOFTLOADRESET** command or after a **SOFTLOADDATA** command.
23	NO_MODULE	No data type was entered before a **SOFTLOADDATA** command was received. Set the data type using the **SOFTLOADSETUP** command or **SOFTLOADSREC** command with an "S0~T~" S Record.
24	NO_PLATFORM	No platform was entered before a **SOFTLOADDATA** command was received. Set the platform using the **SOFTLOADSETUP** command or **SOFTLOADSREC** command with an "S0~P~" S Record.

Value	Name	Description
25	NOT_READY_ FOR_DATA	A **SOFTLOADDATA** command was received but the receiver was not ready for it.
26	MODULE_ MISMATCH	The SoftLoad data module was changed in the middle of loading. Restart the SoftLoad process using the **SOFTLOADRESET** command.
27	OUT_OF_ MEMORY	SoftLoad has run out of RAM to store the incoming data. Reset the receiver and restart the SoftLoad process.
28	DATA_OVERLAP	SoftLoad data has overlapped. Ensure that the correct address and length is set in the **SOFTLOADDATA** command or **SOFTLOADSREC** command.
29	BAD_IMAGE_CRC	CRC of the downloaded image has failed. Ensure that all content from the *.shex file has been successfully downloaded.
30	IMAGE_ OVERSIZE	The downloaded image is too big for the intended data module.
31	AUTHCODE_ WRITE_ERROR	An error occurred when writing the embedded Auth-Code to flash.
32	BAD_FLASH_ ERASE	Erasing of the flash failed. This could indicate a failure in the flash hardware.
33	BAD_FLASH_ WRITE	Writing to the flash failed. This could indicate a failure in the flash hardware.
34	TIMEOUT	SoftLoad time out has occurred.
35	INCOMPATIBLE_ FLASH	Application image that does not support the onboard flash rejected.

3.214 SOURCETABLE

NTRIP source table entries

Platform: OEM729, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, SMART7-W, SMART7-I

This log outputs the NTRIP source table entries from the NTRIP caster set by the **NTRIPSOURCETABLE** command (see page 281). The entry data field in the first entry is always the header of the retrieved SOURCETABLE. The entry data field in the last entry is the string “ENDSOURCETABLE” which indicates the end of the source table. Entries in between these fields are the real SOURCETABLE entries.



Under certain conditions, the **SOURCETABLE** log may not output all entries. The maximum number of entries is set to 500 and the maximum size of all entries is 64 kB. If the source table provided by the caster exceeds either of these values, the SOURCETABLE log will not contain the entire table. If the last entry (sequence number 0) does not have the string "ENDSOURCETABLE", this indicates that not all of the caster entries available are shown in the log.

Message ID: 1344

Log type: Polled

Recommended input:

```
log sourcetablea once
```

ASCII example:

```
#SOURCETABLEA,COM1,17,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"HTTP/1.1 200 OK;Ntrip-Version: Ntrip/2.0;Ntrip-
Flags: st_filter,st_auth,st_match,st_strict,rtsp,plain_rtp;Server: NTRIP
Caster/2.0.15;Date: Fri, 27 Jan 2017 18:12:01 GMT;Connection: close;Content-
Type: gnss/sourcetable;Content-Length: 2057"*87a7d39d

#SOURCETABLEA,COM1,16,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"CAS;hera.novatel.ca;80,2101;NovAtel;NovAtel;0;CAN;
51;-115;http://www.novatel.com"*e3ec11a0

#SOURCETABLEA,COM1,15,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"NET;GREF;NovAtel;B;N;http://novatel.com;none;novat
el.com;none"*2a6b50eb

#SOURCETABLEA,COM1,14,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_rtcmv3;Office Roof DL1L2;RTCM 3.0;1033
(10),1005(10),1019(60),1020(60),1003(1),1011(1);2;GPS+GLO;NovAtel;CAN;51;-115;
0;0;NovAtel OEM628;none;B;N;9600;Test"*8a7c760f

#SOURCETABLEA,COM1,13,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_rtcm;Office Roof DL1L2;RTCM 2.3;1(1),3
(10),31(1),32(10);0;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel OEM628;none;B;N;
9600;Test"*08c57cb7

#SOURCETABLEA,COM1,12,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_rtca;Office Roof DL1L2;RTCA;RTCAREF
(10),RTCA1(1),RTCAEPHEM(60);0;GPS;NovAtel;CAN;51;-115;0;0;NovAtel OEM628;none;
B;N;9600;Test"*006997bc

#SOURCETABLEA,COM1,11,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_cmr;Office Roof DL1L2;CMR;CMRREF(10),
```

```
CMROBS(1),CMRGLOOBS(1);2;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel OEM628;none;
B;N;9600;Test"*0955ccb7

#SOURCETABLEA,COM1,10,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_rtcaobs2;Office Roof DL1L2;RTCA;
rtcaref(10),rtcaobs2(1),rtcaephem(60);2;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel
OEM628;none;B;N;9600;Test"*426e39a5

#SOURCETABLEA,COM1,9,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_cmrplus;Office Roof DL1L2;CMR+;cmrplus
(1),cmrobs(1),cmrgloobs(1);2;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel OEM628;
none;B;N;9600;Test"*2d5ba56e

#SOURCETABLEA,COM1,8,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;"h
era.novatel.com:2101",0,0,"STR;novatel_rtcm2021;Office Roof DL1L2;RTCM 2.3;3
(10),2021(1);2;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel
OEM628;none;B;N;9600;Test"*d82df5de

#SOURCETABLEA,COM1,7,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_1819;Office Roof DL1L2;RTCM 2.3;3(10),
22(10),23(60),24(60),1819(1);2;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel OEM628;
none;B;N;9600;Test"*7aead153

#SOURCETABLEA,COM1,6,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;"h
era.novatel.com:2101",0,0,"STR;novatel_rtcaobs;Office Roof DL1L2;RTCA;rtcaref
(10),rtcaobs(1),rtcaephem(60);2;GPS+GLO;NovAtel;CAN;51;-115;0;0;NovAtel
OEM628;none;B;N;9600;Test"*530a51c4

#SOURCETABLEA,COM1,5,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;novatel_novatelx;Office Roof;NovatelX;
novatelobs;2;GPS+GLO;NovAel;CAN;51;-114;0;0;NovAtel OEM628;none;B;N;9600;
Test"*4438c2e2

#SOURCETABLEA,COM1,4,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;Hyderabad1;hyderabad test1;unknown;unknown;
2;GPS+GLO;NovAtel;INDIA;17;78;0;0;NovAtel OEM628;none;B;N;9600;Test"*de6c19f0

#SOURCETABLEA,COM1,3,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;Hyderabad2;hyderabad
test1;unknown;unknown;2;GPS+GLO;NovAtel;INDIA;17;78;0;0;NovAtel
OEM628;none;B;N;9600;Test"*27e9eee1

#SOURCETABLEA,COM1,2,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;"h
era.novatel.com:2101",0,0,"STR;Hyderabad3;hyderabad test1;unknown;unknown;
2;GPS+GLO;NovAtel;INDIA;17;78;0;0;NovAtel OEM628;none;B;N;9600;Test"*3ed5941b

#SOURCETABLEA,COM1,1,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"STR;Hyderabad4;hyderabad test1;unknown;unknown;
2;GPS+GLO;NovAtel;INDIA;17;78;0;0;NovAtel OEM628;none;B;N;9600;Test"*a3a188e2

#SOURCETABLEA,COM1,0,84.0,COARSESTEERING,1933,497547.000,02400020,71dd,32768;
"hera.novatel.com:2101",0,0,"ENDSOURCETABLE"*7758fba9
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SOURCETABLE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	endpoint	NTRIPCASTER Endpoint	String with varied length up to 80 bytes	a[1]	H
3	Reserved1	reserved	Ulong	4	H+a
4	Reserved2	reserved	Ulong	4	H+a+4
5	Entry data	Source table entry data	String with varied length up to 512 bytes	b[1]	H+a+8
6	xxxx	32-bit CRC (ASCII and binary only)	Ulong	4	H+a+b+8
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

3.215 TECTONICSCOMPENSATION

Tectonics compensation status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log shows the status of the tectonics compensation.

Message ID: 2291

Log type: Asynch

Recommended input:

```
log tectonicscompensationa onchanged
```

ASCII example:

```
#TECTONICSCOMPENSATIONA,USB1,0,51.0,COARSESTEERING,2209,511539.016,02000020,3af
4,16809;AVAILABLE,"North America",-0.018,-0.000,-0.006*6dac1168
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TECTONICSCOMPENSATION header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	status	Status of plate tectonics compensation. See *Table 244: Tectonics compensation status* below.	Enum	4	H
3	name	Name of the plate that is being used for determining station velocities.	Char(32)	Variable	H+4
4	xvel	Station velocities for the location of the receiver (metres/year)	Float	4	Variable
5	yvel		Float	4	Variable
6	zvel		Float	4	Variable
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	Variable
8	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 244: Tectonics compensation status

Binary	ASCII	Description
0	UNAVAILABLE	Tectonics compensation is not available.
1	AVAILABLE	Tectonics compensation is available.
2	WARNING	The receiver is either close to a plate boundary or inside a region where the tectonics compensation is not well modelled.
4	OFF_PLATE	The receiver has moved from the plate that was initially selected. The receiver will not change the plate to avoid discontinuities in the positions.

3.216 TERRASTARINFO

TerraStar subscription information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains details on any currently active TerraStar subscription.



See the **DISPATCHSCHEDULE** log on page 571 for details on current and upcoming subscriptions.



For information about subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 1719

Log type: Asynch

Recommended input:

```
log terrastarinfoa onchanged
```

ASCII example:

```
#TERRASTARINFOA,USB1,0,72.0,FINESTEERING,2366,259754.918,02000000,91ea,17398;
"QU240:9251:5812",TERM,80002700,137,2025,0,NEARSHORE,0.00000,0.00000,0*2e1dfbe4
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TERRASTARINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	PAC	Product activation code	Char[16]	16	H
3	Type	Subscription type (see *Table 245: TerraStar subscription type* on the next page)	Enum	4	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
4	Subscription permissions	Services permitted by the subscription (see *Table 246: TerraStar subscription details mask* on the next page) Multiple bits may be set when the active subscriptions include multiple services. Bits in the Reserved areas of this field may be set, but the Reserved bits should be ignored.	Hex	4	H+20
5	Service End Day	Last day of the year for which service is available. Service expires on midnight local time on the end of this day. For example, if the Service End Year and Day are 2019 and 15, respectively, then the service will expire on January 15, 2019 at 24:00 local time.	Ulong	4	H+24
6	Service End Year	Year that subscription ends	Ulong	4	H+28
7	Reserved		Ulong	4	H+32
8	Region restriction	For region restricted subscriptions, the type of region restriction (see *Table 247: TerraStar region restriction* on the next page)	Enum	4	H+36
9	Reserved		Float	4	H+40
10	Reserved		Float	4	H+44
11	Reserved		Ulong	4	H+48
12	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+52
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 245: TerraStar subscription type

Binary	ASCII	Description
0	UNASSIGNED	No TerraStar service is active.
1	TERM	Active service period includes TerraStar service.
5	MODEL	No service period is active but RTK Assist service is enabled due to the software model.

Table 246: TerraStar subscription details mask

Bit	Mask	Description
0-9	0x000003FF	Reserved
10	0x00000400	TerraStar-L service
11	0x00000800	RTK ASSIST service
12	0x00001000	RTK ASSIST PRO service
13	0x00002000	TerraStar-C PRO service
14	0x00004000	TerraStar-X Regional service
15-30	0x7FFF8000	Reserved
31	0x80000000	Secure Internet Delivery

Table 247: TerraStar region restriction

Binary	ASCII	Description
0	NONE	TerraStar operation has no region restrictions.
1	GEOGATED	TerraStar operation limited to on-land. GEOGATED is also the default value reported if there is no subscription.
3	NEARSHORE	TerraStar operation limited to on land and near shore (coastal) regions.

3.217 TERRASTARSTATUS

TerraStar decoder and subscription status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains status information for the TerraStar decoder and subscription.



See the **DISPATCHSCHEDULE** log on page 571 for more detailed information on current and upcoming service periods.



For information about subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 1729

Log type: Asynch

Recommended input:

```
log terrastarstatusa onchanged
```

ASCII example:

```
#TERRASTARSTATUSA,USB1,0,50.0,FINESTEERING,2209,515067.036,02000020,32bc,16809;
ENABLE,LOCKED,0,IN_RANGE,DISABLED*a17b5059
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TERRASTARSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Access	Access status. ENABLE (1) if the subscription is valid. DISABLE (0) otherwise.	Enum	4	H
3	Sync state	Decoder data synchronization state (see *Table 248: Decoder data synchronization state* on the next page)	Enum	4	H+4
4	Reserved		Ulong	4	H+8
5	Reserved		Enum	4	H+12
6	Geogating status	Geogating status (see *Table 249: TerraStar geogating status* on the next page)	Enum	4	H+16
7	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+20
8	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 248: Decoder data synchronization state

Binary	ASCII	Description
0	NO_SIGNAL	None of the decoders have received data in the last 30 seconds.
1	SEARCH	At least one decoder is receiving data and is searching for the format.
2	LOCKED	At least one decoder has locked onto the format.

Table 249: TerraStar geogating status

Binary	ASCII	Description
0	DISABLED	No region restriction. This is also the value when there is no subscription.
1	WAITING_FOR_POSITION	Waiting for a position
129	ONSHORE	Receiver is over land
130	OFFSHORE	Receiver is over water
255	POSITION_TOO_OLD	Position is too old
1000	PROCESSING	Geogater is determining status

3.218 TILTDATA

Tilt filter accelerometer measurements and computed inclination

Platform: SMART7-I, SMART7-W, SMART2-TB

For SMART antenna products with Terrain Compensation, this log contains the instantaneous horizontal accelerometer measurements, as well as the filtered inclination values computed based on the movement of the vehicle.

Message ID: 1220

Log type: Synch

Recommended input:

```
log tiltdataa ontime 1
```

ASCII example:

```
#TILTDATAA,COM1,0,73.0,FINESTEERING,2045,504349.000,02000000,16f3,32768;
00000000,0.002557007,0.000229843,0.000000000,0.064623833,-1.836378931,
0.000000000,0*5ec9e0e3
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TILTDATA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Sensor Status	Sensor reported status data. 0 = Bad 1 = Good	Hex	4	H
3	X Acceleration	X-axis acceleration ($m/^{s2}$)	Double	8	H+4
4	Y Acceleration	Y-axis acceleration (m/s^2)	Double	8	H+12
5	Reserved		N/A	8	H+20
6	X Inclination	Pitch angle (degrees)	Double	8	H+28
7	Y Inclination	Roll angle (degrees)	Double	8	H+36
8	Reserved		N/A	8	H+44
9	Reserved		N/A	4	H+52
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+56
11	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

3.219 TIME

Time data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log provides several time related pieces of information including receiver clock offset and UTC time and offset. It can also be used to determine any offset in the PPS signal relative to GPS reference time.

To find any offset in the PPS signal, log the TIME log 'ontime' at the same rate as the PPS output. For example, if the PPS output is configured to output at a rate of 0.5 seconds (see the **PPSCONTROL** command on page 307) log the TIME log 'ontime 0.5' as follows:

```
log time ontime 0.5
```

The TIME log offset field can then be used to determine any offset in PPS output relative to GPS reference time.

GPS reference time is the receiver's estimate of the true GPS system time. GPS reference time can be found in the header of the TIME log. The relationship between GPS reference time and true GPS system time is:
GPS system time = GPS reference time - offset

Message ID: 101

Log type: Synch

Recommended input:

```
log timea ontime 1
```

ASCII example:

```
#TIMEA,USB1,0,50.5,FINESTEERING,2209,515163.000,02000020,9924,16809;VALID,
-2.501488425e-09,6.133312031e-10,-17.99999999630,2022,5,13,23,5,45000,VALID
*1100ad64
```

Consider the case where you used the **ADJUST1PPS** command (see page 63) to synchronize two receivers in a primary/secondary relationship to a common external clock. You can use the TIME log after the clock model status is valid to monitor the time difference between the Primary and Secondary receivers.

The header of the TIME log gives you the GPS reference time (the week number since January 5th, 1980) and the seconds into that week. The TIME log outputs the UTC offset (offset of GPS system time from UTC time) and the receiver clock offset from GPS system time.

If you want the UTC time in weeks and seconds, take the week number from the header. Then take the seconds into that week, also from the header, and add the correction to the seconds using the 2 offsets. Ensure not to go negative or rollover (go over the total number of seconds, 604800, in a week). In the case of a rollover, add a week and the left over seconds become the seconds into this new week. If negative, subtract a week and the remainder from the seconds of that week become the seconds into this new week.

For example:

```
TIME COM1 0 73.5 FINESTEERING 1432 235661.000 02000000 9924 2616 VALID
-0.000000351 0.000000214 -14.00000000106 2007 6 19 17 27 27000 VALID
```

From the time information above:

GPS reference time = 1432 (GPS reference week), 235661.000 (GPS seconds) from the header.

From the description in *UTC offset* row in the following table:

UTC time = GPS reference time - offset + UTC offset
UTC time

= week 1432, 235661.000 s – (- 0.000000351 (offset)) - 14.00000000106 (UTC offset)
= week 1432, seconds 235647.00000034994

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TIME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	clock status	Clock model status (not including current measurement data), see *Table 110: Clock model status* on page 556	Enum	4	H
3	offset	Receiver clock offset in seconds from GPS system time. A positive offset implies that the receiver clock is ahead of GPS system time. To derive GPS system time, use the following formula: GPS system time = GPS reference time - offset. The GPS reference time can be obtained from the log header.	Double	8	H+4
4	offset std	Receiver clock offset standard deviation (s)	Double	8	H+12
5	utc offset	The offset of GPS system time from UTC time, computed using almanac parameters. UTC time is GPS reference time plus the current UTC offset minus the receiver clock offset: UTC time = GPS reference time - offset + UTC offset	Double	8	H+20
6	utc year	UTC year	Ulong	4	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
7	utc month	UTC month (0-12) If UTC time is unknown, the value for month is 0.	Uchar	1	H+32
8	utc day	UTC day (0-31) If UTC time is unknown, the value for day is 0.	Uchar	1	H+33
9	utc hour	UTC hour (0-23)	Uchar	1	H+34
10	utc min	UTC minute (0-59)	Uchar	1	H+35
11	utc ms	UTC millisecond (0-60999) Maximum of 60999 when leap second is applied.	Ulong	4	H+36
12	utc status	UTC status 0 = Invalid 1 = Valid 2 = Warning[1]	Enum	4	H+40
13	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+44
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. Indicates that the leap second value is used as a default due to the lack of an almanac.

3.220 TIMESYNC

Synchronize time between GNSS receivers

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The TIMESYNC log is used in conjunction with the **ADJUST1PPS** command (see page 63) to synchronize the time between GNSS receivers.

Message ID: 492

Log type: Synch

Recommended input:

```
log timesynca ontime 1
```

ASCII example:

```
#TIMESYNCA,USB1,0,50.0,FINESTEERING,2209,515196.000,02000020,bd3f,16809;
2209,515196000,FINESTEERING*bd19b2d0
```

The time data embedded in this log represents the time of the most recent 1PPS signal. Refer to *Figure 2: 1PPS alignment* on page 63 to see the alignment between a Fine and a Cold Clock receiver. Also refer to Transferring Time Between Receivers in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TIMESYNC header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	week	GPS reference week number	Ulong	4	H
3	ms	Number of milliseconds into the GPS reference week	Ulong	4	H+4
4	time status	GPS reference time Status, see *Table 13: GPS reference time status* on page 55	Enum	4	H+8
5	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+12
6	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.221 TRACKSTAT

Tracking status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The TRACKSTAT log contains an entry for each channel. If there are multiple signal channels for one satellite (for example L1, L2 P(Y), L2C, and L5 for GPS), then there will be multiple entries for that satellite.

As shown in *Table 182: Channel tracking status* on page 832 these entries can be differentiated by bit 20, which is set if there are multiple observables for a given satellite, and bits 21-25, which denote the signal type for the observation.

A zero in the PRN/slot of the TRACKSTAT log indicates the channel should be considered idle with the exception of those for GLONASS. A GLONASS channel should only be considered idle if the tracking state is 0 in the channel tracking status word.



For dual antenna receivers, a **TRACKSTAT_1** log can be requested to get TRACKSTAT data from the second antenna. As described in *Table 4: Binary message header structure* on page 40, the message type indicates the log is from the second antenna. To request an ASCII log enter **TRACKSTATA_1** and for a binary log enter **TRACKSTATB_1**.

The TRACKSTAT and TRACKSTAT_1 logs use the same message ID.

Message ID: 83

Log type: Synch

Recommended input:

```
log trackstata ontime 1
```

Abbreviated ASCII example:

```
<TRACKSTAT USB1 0 50.0 FINESTEERING 2209 515256.000 02000020 457c 16809
<    SOL_COMPUTED PPP 5.0 312
<        26 0 1810dc04 22959963.689 1368.049 47.443 1767.330 -0.428 GOOD 0.591
<        26 0 11305c0b 22959969.244 1066.013 45.559 1766.738 0.000 OBSL2 0.000
<        26 0 0230dc0b 22959969.108 1066.013 47.623 1767.281 0.000 OBSL2 0.000
<        26 0 01d0dc04 22959968.716 1021.637 48.652 1771.039 0.000 OBSL5 0.000
<        0 0 02008000 0.000 0.000 0.000 0.000 0.000 NA 0.000
<        2 0 0810dc24 23818626.401 -2643.823 44.784 1766.721 0.344 GOOD 0.836
<        2 0 01305c2b 23818628.678 -2060.130 44.380 1766.721 0.000 OBSL2 0.000
<        0 0 0220c020 0.000 0.000 0.000 0.000 0.000 NA 0.000
<        18 0 0810dc44 21881022.854 2511.170 49.936 1766.761 0.558 GOOD 0.917
<        18 0 01305c4b 21881025.040 1956.757 46.530 1766.761 0.000 OBSL2 0.000
<        18 0 0230dc4b 21881025.958 1956.757 49.643 1765.443 0.000 OBSL2 0.000
<        18 0 01d0dc44 21881030.540 1875.185 53.632 1771.842 0.000 OBSL5 0.000
...
<        12 0 080680c1 0.000 -500.000 0.000 0.000 0.000 NA 0.000
<        8 0 080680e1 0.000 -4500.000 0.000 0.000 0.000 NA 0.000
<        11 0 08068101 0.000 -500.000 0.000 0.000 0.000 NA 0.000
<        6 0 0a670924 0.000 -391.971 40.146 1768.092 0.000 NA 0.000
<        1 0 0a670944 0.000 -49.230 44.610 1737.318 0.000 NA 0.000
<        3 0 0a670161 0.000 639.268 0.000 0.000 0.000 NA 0.000
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TRACKSTAT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	sol status	Solution status (see *Table 95: Solution status* on page 530)	Enum	4	H
3	pos type	Position type (see *Table 96: Position or velocity type* on page 531)	Enum	4	H+4
4	cutoff	GPS tracking elevation cut-off angle	Float	4	H+8
5	# chans	Number of hardware channels with information to follow	Ulong	4	H+12
6	PRN/slot	Satellite PRN number of range measurement Refer to *PRN numbers* on page 55	Short	2	H+16
7	glofreq	(GLONASS Frequency + 7), see *GLONASS slot and frequency numbers* on page 54 FW 7.10 Firmware **7.10.02** and greater. If the channel is QZSS L1C/B, this field will output the L1C/B PRN. The L1C/B PRN differs from the QZSS satellite PRN used for all other signals on the satellite. For all signals except for GLONASS signals and QZSS L1C/B, this field will be zero.	Short	2	H+18
8	ch-tr-status	Channel tracking status (see *Table 182: Channel tracking status* on page 832)	Ulong	4	H+20
9	psr	Pseudorange (m) - if this field is zero but the channel tracking status in the previous field indicates that the card is phase locked and code locked, the pseudorange has not been calculated yet	Double	8	H+24
10	Doppler	Doppler frequency (Hz)	Float	4	H+32
11	C/No	Carrier to noise density ratio (dB-Hz)	Float	4	H+36
12	locktime	Number of seconds of continuous tracking (no cycle slips) The locktime will be set to zero for valid PSR output when the phase lock flag is cleared and the tracking mode is in a non PLL mode.	Float	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
13	psr res	Pseudorange residual from pseudorange position filter (m)	Float	4	H+44
14	reject	Range reject code from pseudorange position filter (see *Table 101: Observation statuses* on page 536)	Enum	4	H+48
15	psr weight	Pseudorange filter weighting	Float	4	H+52
16...	Next PRN offset = H+16+(#chans x 40)				
17	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+16 (#chans x 40)
18	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.222 TRANSFERPORTSTATUS

Display the state of the USB transfer port

Platform: PwrPak7

PwrPak7M variants do not support this log.

This log displays the current state of the USB transfer port.

Message ID: 2114

Log type: Asynch

Recommended input:

```
log transferportstatusa onchanged
```

ASCII example:

```
#TRANSFERPORTSTATUSA,USB1,0,50.0,FINESTEERING,2209,515351.867,02000020,4b3f,168
09;USBSTICK,HOST*c9620422
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TRANSFERPORTSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	USB Detection Type	Type of connection detected See *Table 250: USB detection type* below	Enum	4	H
3	USB Mode	Current USB operation mode See *Table 251: USB mode* on the next page	Enum	4	H+4
4	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+8
5	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 250: USB detection type

Binary	ASCII	Description
0	NONE	Nothing is detected
1	USBSTICK	A flash drive is detected
2	PC	A computer is detected
3	ERROR	This is an error state

Table 251: USB mode

Binary	ASCII	Description
0	DEVICE	The USB port is in device mode
1	HOST	The USB port is in host mode
2	OTG	The USB port is in OTG mode
3	INVALID	The USB port is in an invalid mode
4	NONE	The USB port is not in an operation mode
5	TRANSITION	The USB port operation mode is transitioning

3.223 UPTIME

Report the running time of the receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the number of seconds the receiver's firmware has been running, after the application of power or after the completion of a reset.

Message ID: 1777

Log type: Polled

Recommended input:

```
log uptimea once
```

ASCII example:

```
#UPTIMEA,USB1,0,49.0,FINESTEERING,2209,515393.000,02000020,27d2,16809;3896*171a
bba2
```

In this example, 151639 seconds since power-on = 42.1 hours.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	UPTIME header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Uptime	The number of seconds the receiver has been running after a power up or reset.	Ulong	4	H
3	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+4
4	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

3.224 USERANTENNA

Display user defined antennas

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This log lists the stored used defined antennas and their parameters.

Message ID: 2282

Recommended input:

```
log userantennaa onchanged
```

ASCII example:

```
#USERANTENNAA,USB1,0,67.5,FINESTEERING,2211,235864.286,02000020,7fac,16809;
USER_ANTENNA_1,"NOVCUSTOM",2,GPSL1,0.09,0.00,51.74,0.00,-0.03,-0.11,-0.20,0.23,
-0.17,-0.04,0.14,0.26,0.25,0.07,-0.24,-0.54,-0.67,-0.49,-0.02,0.55,0.84,0.47,
GPSL2,-1.54,1.66,52.00,0.00,0.00,0.00,-0.03,-0.13,-0.28,-0.48,-0.61,-0.56,
-0.28,0.23,0.84,1.29,1.31,0.77,-0.16,-0.95,-0.81,0.97*7fbbf0bf
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	USERANTENNA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Antenna type	User defined antenna type See *Table 252: User-defined antenna type* on the next page	Enum	4	H
3	Antenna name	Name of the user defined antenna	Char[16]	16	H+4
4	Number of frequencies	Number of frequencies for which corrections are stored	Ulong	8	H+20
5	Frequency	The frequency for which the phase centre corrections are valid See *Table 22: Frequency type* on page 93	Enum	4	H+28
6	NorthOffset	North phase centre offset in millimetres	Float	4	H+32
7	EastOffset	East phase centre offset in millimetres	Float	4	H+36
8	UpOffset	Up phase centre offset in millimetres	Float	4	H+40
9	PCVArray	19 element array of Phase Centre Variations, in millimetres, in 5-degree elevation increments from 90 to 0	Float[19]	76	H+44
10	Next Frequency = H + 28 + (Number of frequencies x 92)				
11	xxxx	32-bit CRC (ASCII and binary only)	Hex	4	Variable
12	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

Table 252: User-defined antenna type

Binary	ASCII
1001	USER_ANTENNA_1
1002	USER_ANTENNA_2
1003	USER_ANTENNA_3
1004	USER_ANTENNA_4
1005	USER_ANTENNA_5

3.225 USERCANDATA

Basic frame data from a CAN port

Platform: OEM719, OEM729, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7

The **USERCANDATA** log reports the received CAN basic frame data. Depending on the number of frames in the RX FIFO buffer, there will be multiple **USERCANDATA** logs published. There is an index field indicating the order of the frames received.

USERCANDATA messages are asynchronously published based on Message ID matches set by the acceptance filters of the **USERCANOPEN** command (see page 457).

Message ID: 2316

Recommended input:

```
log USERCANDATA onnew
```

Abbreviated ASCII examples:

```
<USERCANDATA COM1 0 84.0 FINESTEERING 1994 257885.895 02000000 e3f6 32768
<     CAN1 STD 178 8 AABBCCDDEEFF1122 123456 0

<USERCANDATA COM1 0 84.0 FINESTEERING 1994 257885.895 02000000 e3f6 32768
<     CAN1 STD 178 5 3344556677 123456 1

<USERCANDATA COM1 0 84.0 FINESTEERING 1994 257885.895 02000000 e3f6 32768
<     CAN1 EXT 1F567 8 1122334455667788 123456 2
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	USERCANDATA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Port ID	CAN port ID. See *Table 253: CAN port ID* on the next page.	Enum	4	H
3	Message Type	Message type. See *Table 254: CAN message type* on the next page.	Enum	4	H+4
4	Message ID	The Standard message ID has 11 bits. The Extended message ID has 29 bits.	HexUlong	4	H+8
5	DataLength	The length of data to be written in bytes. Valid range is 0 to 8 inclusive.	Ulong	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
6	Data	The data of this frame.	HexByte Array	N[1]	H+16
7	TransactionID	The Transaction ID provided to the command.	Ulong	4	H+16+4*INT ((N+3)/4)
8	Frame Index	The frame order.	Ulong	4	H+20+4*INT ((N+3)/4)

Table 253: CAN port ID

Binary	ASCII	Description
1	CAN1	CAN port 1
2	CAN2	CAN port 2

Table 254: CAN message type

Binary	ASCII	Description
1	STD	Standard message
2	EXT	Extended message

1. In the binary command/log case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.

3.226 USERCANSTATUS

Status of commands sent to a CAN port

Platform: OEM719, OEM729, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7

The **USERCANSTATUS** log reports the status of a previously executed **USERCANOPEN**, **USERCANCLOSE** or **USERCANWRITE** command. There is one log output for each command that is executed.

For the **USERCANWRITE** command (see page 460), the *Number of Frames* field of the **USERCANSTATUS** log indicates the number of frames placed into the TX FIFO buffer, 0 or 1.

Message ID: 2315

Recommended input:

```
log USERCANSTATUS onnew
```

Abbreviated ASCII examples:

```
USERCANWRITE CAN1 STANDARD 0x234 8 ABCDEF0123456789 23 234578
<USERCANSTATUS COM1 0 84.0 FINESTEERING 1994 257885.895 02000000 e3f6 32768
<     CAN1 WRITE 234578 OK 1
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	USERCANSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	Port ID	The CAN port Identifier. See *Table 255: CAN port ID* below.	Enum	4	H
3	Operation	Operation performed. See *Table 256: Operation mode* on the next page.	Enum	4	H+4
4	TransactionID	This is the copy of Transaction ID provided to the command.	HexUlong	4	H+8
5	Status	Status message. See *Table 257: CAN status message* on the next page.	Enum	4	H+12
6	Number of Frames	For a WRITE operation, this is the number of frames placed in the TX FIFO (0 - 1). For a READ operation, this is the number of frames available in RX FIFO (0 - 32).	Ulong	4	H+16

Table 255: CAN port ID

Binary	ASCII	Description
1	CAN1	CAN port 1
2	CAN2	CAN port 2

Table 256: Operation mode

Binary	ASCII	Description
0	NONE	No operation
1	OPEN	Open operation
2	CLOSE	Close operation
3	READ	Read operation
4	WRITE	Write operation

Table 257: CAN status message

Binary	ASCII	Description
0	OK	CAN operation is successful.
1	FAIL	CAN operation failed.
2	PortAlreadOpened	Attempt to open a CAN port that is already open
3	PortAlreadyClosed	Attempt to close a CAN port that is already closed
4	TX FIFO full	Unable to write a frame to the TX FIFO as the buffer is full
5	RX FIFO empty	No frame available to read from the RX FIFO

3.227 USERI2CRESPONSE

Status of USERI2CREAD or USERI2CWRITE Command

Platform: OEM7600, OEM7700, OEM7720

This log reports the status of a previously executed **USERI2CREAD** or **USERI2CWRITE** command. There is one log emitted for each command that is executed.

For the **USERI2CREAD** command (see page 469), this log outputs the data read from the device on the I2C bus and the status of the read operation.

For the **USERI2CWRITE** command (see page 471), the status of the write operation is reported and the data field will always be 0.

Message ID: 2234

Recommended input:

```
log USERI2CRESPONSE onnew
```

Abbreviated ASCII example 1:

```
USERI2CREAD 70 4 aabbccdd 12 6789

<USERI2CRESPONSE COM1 0 84.0 FINESTEERING 1994 257885.895 02000000 e3f6 32768
<     70 aabbccdd OK READ 6789 12 000102030405060708090a0b
```

Abbreviated ASCII example 2:

```
USERI2CWRITE 70 3 aabbcc 8 0001020304050607 12345

<USERI2CRESPONSE COM1 0 84.0 FINESTEERING 1994 257885.895 02000000 e3f6 32768
<     70 aabbcc OK WRITE 12345 0
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	USERI2CRESPONSE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	DeviceAddress	The 7 bit address of the I2C device. Valid values are 0 through 127. For ASCII and Abbreviated commands, this field is a hexadecimal string of two digits. There is no 0x prefix and spaces are not allowed in the string.	Uchar	1[1]	H
3	RegisterAddress	The actual register address used for the operation. This is a ULONG value in hexadecimal format (without 0x prefix).	Ulong	4	H+4
4	ErrorCode	Error code for the operation. See *Table 258: Error code* on the next page.	Enum	4	H+8

1. In the binary case, additional bytes of padding are added after this field to maintain 4-byte alignment for the fields that follow.

Field	Field type	Description	Format	Binary bytes	Binary offset
5	OperationMode	Operation mode code. See *Table 259: Operation mode code* below.	Enum	4	H+12
6	TransactionID	This is the copy of Transaction ID provided to the command.	Ulong	4	H+16
7	ReadDataLength	For a Read operation, this is the actual number of bytes read from the I2C device. For a Write operation, this value is always zero.	Ulong	4	H+20
8	ReadData	For a Read operation, this is the data read from the device. For ASCII logs this field is displayed as a string of hexadecimal digits, with two digits per byte. The first byte retrieved from the I2C device is the first byte displayed and so on. The maximum size of this field is 256 bytes. When ReadDataLength is zero, this field will be empty.	Hexbyte Array	Y	H+24

Table 258: Error code

Binary	ASCII	Description
0	OK	I2C transaction is successful
1	IN_PROGRESS	I2C transaction is currently in progress
2	DATA_TRUNCATION	I2C transaction read data was truncated
3	BUS_BUSY	I2C bus is busy
4	NO_DEVICE_REPLY	No device replied to the I2C transaction request
5	BUS_ERROR	I2C bus error or bus arbitration lost
6	TIMEOUT	I2C transaction has timed out
7	UNKNOWN_FAILURE	I2C transaction has an unexplained failure

Table 259: Operation mode code

Binary	ASCII	Description
0	NONE	No Operation
1	READ	Read Operation
2	WRITE	Write Operation
3	SHUTDOWN	Shut down Operation

3.228 VALIDMODELS

Valid model information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

The **VALIDMODELS** log gives a list of valid authorized software models available and expiry date information.



See the **VERSION** log on page 1023 or the **DISPATCHSCHEDULE** log on page 571 for the currently active model.



The **MODEL** command (see page 265) selects a permanent model from this list to be used outside any service period. When a current service period specifies a model to use (the model shown in the **DISPATCHSCHEDULE** *Receiver features* field for the current service period), the active model may differ from the selected permanent model. During that service period the entry “SERVICEPERIOD” appears as the last model entry in the log.

It is not recommended to use the **MODEL** or **AUTH** command during a service period, but in the case one has overridden the service period model, the command **MODEL SERVICEPERIOD** can be used to revert to the service period features.

If a model has no expiry date, it reports the year, month and day fields as 0s.

Changes made with the **AUTH** command update this log after the next reset.



For information about receiver features and software models, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 206

Log type: Asynch

Recommended input:

```
log validmodelsa once
```

ASCII example:

```
#VALIDMODELSA,USB1,0,49.0,FINESTEERING,2209,515587.940,02000020,342f,16809;
1,"FFNRNNCBES1",0,0,0*0d1a3309
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	VALIDMODELS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	#mod	Number of models with information to follow	Ulong	4	H
3	model	Model name	String [Max16]	Variable[1]	H+4
4	expyear	Expiry year (0 means model does not expire)	Ulong	4	Variable Max: H+20
5	expmonth	Expiry month (0 means model does not expire)	Ulong	4	Variable Max: H+24
6	expday	Expiry day (0 means model does not expire)	Ulong	4	Variable: Max: H+28
7...	Next model offset = H+4+(#mod x variable [max:28])				
8	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#mod x variable [max:28])
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

1. In the binary case, each string field needs to be NULL terminated and additional bytes of padding added to maintain 4-byte alignment, up to the maximum defined by the string size. The next defined field starts immediately at the next 4-byte alignment following the NULL.

3.229 VERIPOSINFO

Veripos subscription information

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This log contains details on any currently active Veripos subscription.

See the **DISPATCHSCHEDULE** log on page 571 for more detailed information on current and upcoming service periods.

For information about subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 1728

Log type: Asynch

Recommended input:

```
log veriposinfoa onchanged
```

Abbreviated ASCII example:

```
<VERIPOSINFO COM1 0 22.5 FINESTEERING 2394 495123.254 02040020 2bd7 32768
<     3442293 NCC_CONTROLLED 80000f31 ""
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	VERIPOSINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Serial number	Receiver serial number	Ulong	4	H
3	Mode	Subscription status (see *Table 260: Veripos operating mode* on the next page)	Enum	4	H+4
4	Details	Subscription details (refer to *Table 261: Veripos subscription details mask* on the next page)	Hex	4	H+8
5	Reserved		Char[4]	4	H+12
6	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+16
7	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 260: Veripos operating mode

ASCII	Binary	Description
UNASSIGNED	0	No Veripos service is active.
NCC_CONTROLLED	7	Veripos service currently active.
MODEL_DENIED	101	Decoder operation is not permitted on the current firmware model.

Table 261: Veripos subscription details mask

Bit	Mask	Description
0	0x00000001	Subscription permits differential positioning (Standard Service)
1-3	0x0000000E	Reserved
4	0x00000010	Subscription permits Ultra PPP positioning
5	0x00000020	Subscription permits Ultra2 PPP positioning
6-7	0x000000C0	Reserved
8	0x00000100	Subscription permits Apex PPP positioning
9	0x00000200	Subscription permits Apex2 PPP positioning
10	0x00000400	Subscription permits Apex5 PPP positioning
11	0x00000800	Subscription permits Apex-AR PPP positioning
12-31	0xFFFFF000	Reserved

3.230 VERIPOSSTATUS

Veripos decoder and subscription status

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This log contains status information for the Veripos decoder and subscription.



See the **DISPATCHSCHEDULE** log on page 571 for more detailed information about current and upcoming service periods.



For information about subscriptions, refer to Receiver Features: Authorization and Subscriptions in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, SMART7 Installation and Operation User Manual, SMART2 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 1730

Log type: Asynch

Recommended input:

```
log veriposstatusa onchanged
```

Abbreviated ASCII example:

```
<VERIPOSSTATUS COM1 0 22.5 FINESTEERING 2394 495123.254 02040020 0719 32768
<     ENABLE LOCKED
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	VERIPOSSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	Access	Access status. ENABLE (1) if the subscription is valid. DISABLE (0) otherwise.	Enum	4	H
3	Sync state	Decoder data synchronization state (see *Table 262: Decoder data synchronization state* below)	Enum	4	H+4
4	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+8
5	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 262: Decoder data synchronization state

Binary	ASCII	Description
0	NO_SIGNAL	None of the decoders have received data in the last 30 seconds.
1	SEARCH	At least one decoder is receiving data and is searching for the format.
2	LOCKED	At least one decoder has locked onto the format.

3.231 VERSION

Version information

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log contains the version information for all components of a system. A component may be hardware (for example, a receiver or data collector) or firmware in the form of applications or data (for example, data blocks for height models or user applications). See *Table 264: Firmware and boot version field formats* on page 1026 for details on the format of key fields.

The GPSCARD entry indicates the currently active software model, which determines which receiver features are authorized.

See also the **VALIDMODELS** log on page 1018.

Message ID: 37

Log type: Polled

Recommended input:

```
log versiona once
```

Abbreviated ASCII example:

```
<VERSION USB1 0 49.0 FINESTEERING 2209 515707.883 02000020 3681 16809
<    12
<        GPSCARD "FFNRNNCBES1" "BMHR17090005E" "OEM7700-1.00" "OM7CR0810RN0000"
"OM7BR0001RBG000" "2021/Dec/06" "11:16:48"
<        OEM7FPGA "" "" "" "OMV070001RN0000" "" "" ""
<        APPLICATION "" "" "" "EP7AR0810RN0000" "" "2021/Dec/06" "11:16:59"
<        DEFAULT_CONFIG "" "" "" "EP7CR0810RN0000" "" "2021/Dec/06" "11:17:11"
<        PACKAGE "" "" "" "EP7PR0810RN0000" "" "2021/Dec/06" "11:17:05"
<        DB_WWWISO "WWWISO" "0" "" "1.8.0" "" "2022/Apr/11" "15:44:16"
<        ENCLOSURE "PWRPAK7-E1" "NMNE17200009B" "" "" "" "" ""
<        WIFI "RS9113" "" "" "1.7.12" "" "2021/Dec/06" "11:17:22"
<        REGULATORY "US" "" "" "" "" "" ""
<        IMUCARD "Epson G320N 125" "00000354" "G320PDGN" "2510" "" "" ""
<        WHEELSENSOR "" "" "" "SWS000201RN0000" "" "" ""
<    SERVICE "PERIOD" "TerraStar-C PRO" "ALIGN" "" "" "" ""
```

The **VERSION** log is a useful log as a first communication with your receiver. Once connected, using NovAtel Application Suite or a terminal emulator program, log VERSION and check that the output makes sense. Also, ensure that you have the receiver components you expected.

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	VERSION header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	# comp	Number of components (cards, and so on)	Long	4	H
3	type	Component type (see *Table 263: Component types* on the next page)	Enum	4	H+4
4	model	When type is **GPSCARD**: Currently active software model name, e.g., CFNPNNTVN, indicates the receiver's current model functionality. When type is **ENCLOSURE**: Name of the enclosure type. When type is **SERVICE**: Source of the currently active software model, see *Table 117: Receiver features source* on page 577.	Char[16]	16	H+8
5	psn	Product serial number When type is **SERVICE**: Name of the first active service, if any. See the **DISPATCHSCHEDULE** log *Active Service Names* field.	Char[16]	16	H+24
6	hw version	When type is **GPSCARD**: Hardware version in the format: <hardware platform>-<hardware revision> eg. OEM7700-1.0 When type is **SERVICE**: Name of the second active service, if any. See the **DISPATCHSCHEDULE** log *Active Service Names* field.	Char[16]	16	H+40
7	sw version	Firmware version, see *Table 264: Firmware and boot version field formats* on page 1026 When type is **SERVICE**: Name of the third active service, if any. See the **DISPATCHSCHEDULE** log *Active Service Names* field.	Char[16]	16	H+56
8	boot version	Boot code version, see *Table 264: Firmware and boot version field formats* on page 1026 When type is **SERVICE**: Name of the fourth active service, if any. See the **DISPATCHSCHEDULE** log *Active Service Names* field.	Char[16]	16	H+72

Field	Field type	Description	Format	Binary bytes	Binary offset
9	comp date	Firmware compile date in the format: YYYY/Mmm/DD Where YYYY = year Mmm = month DD = day (1-31) Example: 2018/Jul/10 When type is **SERVICE**: Name of the fifth active service, if any. See the **DISPATCHSCHEDULE** log *Active Service Names* field.	Char[12]	12	H+88
10	comp time	Firmware compile time in the format: HH:MM:SS Where: HH = hours MM = minutes SS = seconds Example: 14:37:01 When type is **SERVICE**: Name of the sixth active service, if any. See the **DISPATCHSCHEDULE** log *Active Service Names* field.	Char[12]	12	H+100
11...	Next component offset = H + 4 + (#comp x 108)				
12	xxxx	32-bit CRC (ASCII and Binary only)	Ulong	4	H+4+ (#comp x 108)
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 263: Component types

Binary	ASCII	Description
0	UNKNOWN	Unknown component
1	GPSCARD	OEM7 family receiver In an enclosure product this is the receiver card in the enclosure.
2	CONTROLLER	Reserved
3	ENCLOSURE	OEM card enclosure
4-6	Reserved	
7	IMUCARD	IMU integrated in the enclosure

Binary	ASCII	Description
8	USERINFO	Application specific information
12-14	Reserved	
15	WIFI	Wi-Fi radio firmware
16-17	Reserved	
18	RADIO	UHF radio component
19	WWW_CONTENT	Web Server content
20	Regulatory	Regulatory configuration
21	OEM7FPGA	OEM7 FPGA version
22	APPLICATION	Embedded application
23	Package	Package
24	Reserved	
25	DEFAULT_CONFIG	Default configuration data
26	WHEELSENSOR	Wheel sensor in the enclosure
27	EMBEDDED_AUTH	Embedded Auth-Code data
30	SERVICE	Current subscription service period status. See the **DISPATCHSCHEDULE** log on page 571 for details.
981073920 (0x3A7A0000)	DB_HEIGHTMODEL	Height/track model data
981073928 (0x3A7A0008)	DB_WWWISO	Web UI ISO Image
981073930 (0x3A7A000A)	DB_LUA_SCRIPTS	Lua Script ISO Image

Table 264: Firmware and boot version field formats

Field format (ASCII)	Description	Example	
NWXYZFFMMRN0000	N = Family Name The Family Name can be: O = OEM	Software Version: OM7CR0500RN0000 Boot Version: OM7BR0001RB0000	In both examples, the Family Name is **O**.
	WX = Product The Product can be: M7: OEM7 product A7: Agriculture optimized OEM7 product		In both examples, the Product is **M7**.

Field format (ASCII)	Description	Example	
	Y = Image Type The Image Type can be: B: boot code M: main firmware application C: combined main firmware application and user application		In the Software Version example, the Image Type is **C**. In the Boot Version example, the Image Type is **B**.
	Z = Signature The Signature can be: R: Officially signed H: High Speed signed		In both examples the Signature is **R**.
	FF = Feature Release Number		In the Software Version example, the Feature Release Number is **05**. In the Boot Version example, the Feature Release Number is **00**.
	MM = Maintenance Release Number		In the Software Version example, the Maintenance Release Number is **00**. In the Boot Version example, the Maintenance Release Number is **01**.
	R = Release Type The Release Type can be: A: Alpha B: Beta R: Release S: Special E: Engineering Special C: Customer Approved Special		In both examples, the Release Type is **R**.

Field format (ASCII)	Description	Example	
	N = Distribution Permit The Distribution Permit can be: N: No restrictions B: Boot Code H: High Speed Build (Requires a permit to use)		In the Software Version example, the Distribution Permit is **N**. In the Boot Version example, the Distribution Permit is **B**.
	0000 = Minor Release Indicator		In both examples, the Minor Release Indicator is **0000**.



The firmware version of a receiver is also presented in a short version (e.g. 7.05.04). The short version is the product number, feature release number and maintenance release number separated by dots. For example, the firmware version OM7MR0504RN0000 has a short version of 7.05.04.

3.232 WIFIAPSETTINGS

Display the Wi-Fi access point configuration

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this log to display the Wi-Fi access point configuration. If the access point is not currently operational, the log reports the access point configuration to be applied the next time the **WIFIMODE AP** or **WIFIMODE CONCURRENT** command is received.

The term passkey and password are the same.

Message ID: 2093

Log type: Polled

Recommended input:

```
LOG WIFIAPSETTINGS
```

ASCII example:

```
#WIFIAPSETTINGSA,USB1,0,49.5,FINESTEERING,2209,515774.000,02000020,fc0e,16809;
"PwrPak7-NMNE17200009B","P3YSXG8D",2P4GHZ,WPA2,CCMP,US,11,"00:23:a7:b6:de:9c"
*aa09a912
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	WIFIAPSETTINGS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	SSID	SSID of the AP	String [Max 33]	Variable	H
3	passkey	Passkey of the AP	String [Max 65]	Variable	Variable
4	band	Wi-Fi operating band. See *Table 265: Wi-Fi band* on the next page.	Enum	4	Variable
5	security protocol	Wireless security protocol. See *Table 266: Wi-Fi security protocol* on the next page.	Enum	4	Variable
6	encryption	Wireless encryption type. See *Table 267: Wi-Fi encryption type* on the next page.	Enum	4	Variable

Field	Field type	Description	Format	Binary bytes	Binary offset
7	region	Regulatory region. See *Table 268: Regulatory region* on the next page.	Enum	4	Variable
8	channel	Wireless channel used by access point to communicate with connected clients.	Int	4	Variable
9	BSSID	BSSID of the AP (MAC of the Wi-Fi interface)	String [Max 18]	Variable	Variable
10	xxxx	32-bit CRC (ASCII or Binary only)	Hex	4	Variable
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 265: Wi-Fi band

Binary	ASCII	Description
1	2P4GHZ	2.4 GHz

Table 266: Wi-Fi security protocol

Binary	ASCII	Description
1	OPEN	Open network (No security)
2	WPA	Wi-Fi Protected Access
3	WPA2	Wi-Fi Protected Access version 2

NovAtel Wi-Fi access points only support the WPA2 security protocol. As a result, the **WIFIAPSETTINGS** log will only report **WPA2**.

NovAtel Wi-Fi Clients support OPEN, WPA, and WPA2 security protocols.

Table 267: Wi-Fi encryption type

Binary	ASCII	Description
1	OPEN	Open (no encryption)
2	TKIP	Temporal Key Integrity Protocol (used with WPA)
3	CCMP	AES-based CCMP (Cipher Chaining Message Authentication) used with WPA2

NovAtel Wi-Fi access points only support the WPA2 security protocol. As a result, the **WIFIAPSETTINGS** log will only report **CCMP**.

Table 268: Regulatory region

Binary	ASCII	Description
0	None	Receiver has not been configured to comply with any regional regulatory requirements. Wireless components (e.g. Wi-Fi) will not operate. Contact NovAtel Customer Support.
1	US	United States
2	EU	Europe
3	AU	Australia
4	JP	Japan
5	NZ	New Zealand
6	BR	Brazil

3.233 WIFINETLIST

Display a list of Wi-Fi networks in range of client

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this log to display information about Wi-Fi access points detected by the receiver when configured in either Client or Concurrent mode.

Message ID: 2210

Log type: Asynch

Recommended input:

```
log wifinetlist onchanged
```

ASCII example:

```
<WIFINETLIST USB1 0 65.5 FINESTEERING 2210 340950.380 02000020 0c90 16809
<     7
<          "PwrPak7-NMNE17200016X" -37 11 "00:23:a7:b6:df:7c" WPA2
<          "Hexagon" -47 6 "38:17:c3:81:7b:e5" OPEN
<          "Geosytems" -47 6 "38:17:c3:81:7b:e6" WPA2
<          "PwrPak7-NMPM18040011A" -47 11 "88:da:1a:04:cc:d4" WPA2
<          "SM7-NMPX18500007B" -47 11 "88:da:1a:43:73:20" WPA2
<          "PwrPak7-NMND21220024J" -51 11 "80:c9:55:0b:da:60" WPA2
<          "PwrPak7-NMND18280030D" -54 11 "88:da:1a:07:97:70" WPA2
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	WIFINETLIST header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	num_ networks	Number of network records to follow	Ulong	4	H
3	SSID	SSID of scanned access point.	String [Max 33]	variable	H+4
4	RSSI	Absolute value of RSSI (dBm)	Int	4	variable
5	channel	RF channel to use	Ulong	4	variable
6	BSSID	MAC address of the access point.	String [Max 18]	variable	variable
7	security	Security mode of access point. *Table 269: Wi-Fi security type* on the next page	Enum	4	variable

Table 269: Wi-Fi security type

Binary	ASCII	Description
1	OPEN	Open network (no security)
2	WPA	Wi-Fi protected access
3	WPA2	Wi-Fi protected access II

3.234 WIFISTATUS

Display status information of receiver Wi-Fi

Platform: PwrPak7, SMART7-I, SMART7-SI, SMART7-W

PwrPak7M and PwrPak7Q variants do not support this command.

Use this log to display the current status of a Wi-Fi Client and or Access Point in addition to information about any connected Access Point and or Clients.

Message ID: 2207

Log type: Asynch

Recommended input:

```
log wifistatus onchanged
```

ASCII example:

```
#WIFISTATUSA,USB1,0,50.0,UNKNOWN,0,8.029,02000020,8a58,16809;
ACCESSPOINT_OPERATIONAL,"",0,0,"",OPEN,0*dfc10e04
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	WIFISTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	status	Wi-Fi operational status. Refer to *Table 270: Wi-Fi status* on the next page.	String [Max 33]	Variable	H
3	AP SSID	SSID of connected access point. This field is blank if the client is not connected to an access point.	String [Max 33]	Variable	
4	AP RSSI	Value of RSSI (dBm) of connection to access point. This field is zero if the client is not connected to an access point.	Ulong	4	
5	AP channel	Channel use to connect to access point. This field is zero if the client is not connected to an access point.	Ulong	4	
6	AP BSSID	MAC address of connected access point. This field is blank if the client is not connected to an access point.	Ulong	4	
7	AP security	Security mode of connected access point. See *Table 269: Wi-Fi security type* on the previous page in the **WIFINETLIST** command (see page 1032). The value of this field is only valid if the AP SSID field is not blank.	Enum	4	
8	#clients	Number of clients connected to an access point to follow.	Ulong	4	

Field	Field type	Description	Format	Binary bytes	Binary offset
9	BSSID	MAC address of connected client.	String [Max 18]	Variable	
10...	Next Client				

Table 270: Wi-Fi status

Binary	ASCII	Description
0	STARTUP	
1	OFF	Wi-Fi hardware is powered off
2	ON	Wi-Fi hardware is powered on but not configured
3	CONFIGURING_ ACCESSPOINT	Wi-Fi hardware is being configured as an access point
4	ACCESSPOINT_ OPERATIONAL	Wi-Fi hardware is operating as an access point and is ready to accept client connections
5	CONFIGURING_CLIENT	Wi-Fi hardware is being configured as a client station
6	CLIENT_OPERATIONAL	Wi-Fi hardware is operating as a client but is not connected to an access point
7	BOOTING_UP	Wi-Fi hardware is booting up
8	BOOTUP_COMPLETE	Wi-Fi hardware has booted up
9	UPGRADE_REQUIRED	Wi-Fi firmware version does not match required version
10	UPGRADING_FIRMWARE	Wi-Fi firmware is being upgraded
11	UPGRADING_ FIRMWARE_10	Wi-Fi firmware update is 10% complete
12	UPGRADING_ FIRMWARE_20	Wi-Fi firmware update is 20% complete
13	UPGRADING_ FIRMWARE_30	Wi-Fi firmware update is 30% complete
14	UPGRADING_ FIRMWARE_40	Wi-Fi firmware update is 40% complete
15	UPGRADING_ FIRMWARE_50	Wi-Fi firmware update is 50% complete
16	UPGRADING_ FIRMWARE_60	Wi-Fi firmware update is 60% complete
17	UPGRADING_ FIRMWARE_70	Wi-Fi firmware update is 70% complete

Binary	ASCII	Description
18	UPGRADING_ FIRMWARE_80	Wi-Fi firmware update is 80% complete
19	UPGRADING_ FIRMWARE_90	Wi-Fi firmware update is 90% complete
20	UPGRADING_ FIRMWARE_COMPLETE	Wi-Fi firmware update is 100% complete
21	ERROR	An error has occurred
22	CONFIGURING_ CONCURRENT	Wi-Fi hardware is being configured to operate as both an access point and client concurrently
23	CONCURRENT_ OPERATIONAL	Wi-Fi hardware is operating as both an access point and client. The client is not connected to an access point.
24	CONNECTING_TO_AP	Wi-Fi hardware is attempting to connect to an access point
25	CONNECTED_TO_AP	Wi-Fi hardware has successfully connected to an access point
26	CONNECTION_FAILURE	Wi-Fi client failed to connect to an access point. Possible causes include invalid password provided in the **WIFINETCONFIG** command (see page 486)
27	CONFIGURING_ NETWORK_ PARAMETERS	Wi-Fi client is configuring its network parameters based on active connection to an access point
28	CONNECTION_REFUSED	Wi-Fi client failed on initial attempt to connect to an access point due to the connection being actively refused by the access point Possible causes include invalid configuration settings in the **WIFINETCONFIG** command on page 486
29	PREFERRED_ NETWORK_ MISCONFIGURED	Wi-Fi client cannot connect to preferred access point due to a misconfiguration of network parameters in the **WIFINETCONFIG** command on page 486
30	CONCURRENT_ CONNECTING_TO_AP	Wi-Fi concurrent client is configuring its network parameters based on active connection to an access point
31	CONCURRENT_ CONFIGURING_ NETWORK_PARAMS	Wi-Fi concurrent client is configuring its network parameters based on active connection to an access point
32	CONCURRENT_ CONNECTED_TO_AP	Wi-Fi concurrent client has successfully connected to an access point
33	DISCONNECTING_ FROM_AP	Wi-Fi client is disconnecting from an access point
34	CONCURRENT_ DISCONNECTING_ FROM_AP	Wi-Fi concurrent is disconnecting from an access point

Binary	ASCII	Description
35	BOOTUP_CONNECTING_TO_WIFI_MODULE	
36	BOOTUP_ERROR	

Chapter 4 SPAN commands

The commands used to configure GNSS+INS functions are described in the following sections.

For information about other available commands, refer to *Commands* on page 61.

4.1 ALIGNMENTMODE


Set the alignment mode

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to set the alignment method priority used to initialize the SPAN system.

In default mode (AUTOMATIC), the first available alignment type is used to complete an alignment of the SPAN system.

For additional details on the available alignment mode options see System Start-Up and Alignment Techniques in the OEM7 SPAN Installation and Operation User Manual.



NVM Seeded and Manual (SETINITAZIMUTH command (see page 1076)) alignments are valid for all alignment modes and will supersede all other options if valid and available.

Message ID: 1214

Abbreviated ASCII syntax:

```
ALIGNMENTMODE mode
```

Abbreviated ASCII example:

```
ALIGNMENTMODE AIDED_TRANSFER
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	ALIGNMENTMODE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	mode	UNAIDED	0	Static coarse alignment or kinematic alignment methods are available.	Enum	4	H
		AIDED_ TRANSFER	2	Seed the initial azimuth estimate from the ALIGN solution.			
		AUTOMATIC	3	Seed the full attitude from the ALIGN solution, perform a regular static coarse alignment or perform a kinematic alignment, whichever is possible first.			
		STATIC	4	Static coarse alignment method only.			
		KINEMATIC	5	Kinematic alignment method only.			

4.2 CONNECTIMU

Connects an IMU to a port

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7

Use this command to specify the type of IMU connected to the receiver and the receiver port used by the IMU.

Message ID: 1428

Abbreviated ASCII syntax:

```
CONNECTIMU IMUPort IMUType
```

Abbreviated ASCII example:

```
CONNECTIMU COM2 LN200
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	CONNECTIMU header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	IMUPort	COM1	1	IMU Port is COM port 1	Enum	4	H
		COM2	2	IMU Port is COM port 2			
		COM3	3	IMU Port is COM port 3			
		SPI	7	IMU Port is the SPI port			
		COM4	19	IMU Port is COM port 4			
		COM5	31	IMU Port is COM port 5			
3	IMUType	See *Table 271: IMU type* on the next page		IMU Type	Enum	4	H+4

SPI is available only on the OEM7500, OEM7600, OEM7700, and OEM7720.

COM4 and COM5 are available only on the OEM7600, OEM7700 and OEM7720.

For the **CONNECTIMU** command, COM2 is available only on the OEM719 with hardware revisions 1.04 and earlier. For the OEM719, it is recommended to use COM1 to connect to an IMU.

The IMU-ISA-100C, IMU-FSAS, IMU-HG1900, IMU-LN200, IMU-LN200C, IMU-µIMU-IC, IMU-CPT, IMU-P1750, IMU-KVH1750 and OEM-IMU-µIMU-IC-UART use RS-422 protocol and must be connected to a receiver port that is configured to use RS-422. Refer to Serial port communications in the OEM7 Installation and Operation User Manual or PwrPak7 Installation and Operation User Manual for information about which receiver ports support RS-422 and instructions for enabling RS-422.

Table 271: IMU type

Binary	ASCII	IMU name	Description
0	UNKNOWN		Unknown IMU type (default)
1	HG1700_AG11		Honeywell HG1700 AG11
4	HG1700_AG17		Honeywell HG1700 AG17
5	HG1900_CA29		Honeywell HG1900 CA29
8	LN200	IMU-LN200 IMU-LN200C UIMU-LN200	Northrop Grumman LN200/LN200C
11	HG1700_AG58	UIMU-HG1700-AG58	Honeywell HG1700 AG58
12	HG1700_AG62	UIMU-HG1700-AG62	Honeywell HG1700 AG62
13	IMAR_FSAS	IMU-FSAS	iMAR iIMU-FSAS
16	KVH_COTS	IMU-CPT	KVH CPT IMU
20	HG1930_AA99	OEM-HG1930	Honeywell HG1930 AA99
26	ISA100C	IMU-ISA-100C OEM-IMU-ISA-100C	Northrop Grumman Litef ISA-100C
27	HG1900_CA50	IMU-HG1900 OEM-HG1900	Honeywell HG1900 CA50
28	HG1930_CA50	OEM-HG1930	Honeywell HG1930 CA50
31	ADIS16488	IMU-IGM-A1 OEM-IMU-ADIS-16488	Analog Devices ADIS16488
32	STIM300	IMU-IGM-S1 OEM-IMU-STIM300	Sensonor STIM300
33	KVH_1750	IMU-KVH1750 IMU-P1750	KVH 1750 IMU KVH P-1750 IMU
41	EPSON_G320	OEM-IMU-EG320N	Epson G320N
52	LITEF_MICROIMU	IMU-µIMU-IC OEM-IMU-µIMU-IC	Northrop Grumman Litef µIMU-IC
56	STIM300D	OEM-IMU-STIM300D	Sensonor STIM300, Direct Connection

Binary	ASCII	IMU name	Description
58	HG4930_AN01	OEM-IMU-HG4930	Honeywell HG4930 AN01
61	EPSON_G370	OEM-IMU-EG370N	Epson G370N
62	EPSON_G320_200HZ	OEM-IMU-EG320N (200 Hz)	Epson G320N – 200 Hz
68	HG4930_AN04	OEM-IMU-HG4930	Honeywell HG4930 AN04 – 100 Hz
69	HG4930_AN04_400HZ	OEM-IMU-HG4930 (400 Hz)	Honeywell HG4930 AN04 – 400 Hz
71	LITEF_MICROIMUD_ 400HZ	OEM-IMU-µIMU-IC-UART	Northrop Grumman Litef µIMU-IC-UART – 400 Hz

4.3 DMICONFIG

Configure a DMI input

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to configure a Distance Measurement Instrument (DMI) input.

For more information about using a DMI, see Distance Measurement Instrument in the OEM7 SPAN Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

Message ID: 2270

Abbreviated ASCII syntax:

```
DMICONFIG dmi_ID switch [source]
```

Abbreviated ASCII examples:

```
DMICONFIG DMI1 ENABLE IMU
DMICONFIG DMI1 DISABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	DMICONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	DMI_ID	DMI1	0	ID of the DMI sensor	Enum	4	H
3	Switch	DISABLE	0	Disable the DMI sensor	Enum	4	H+4
		ENABLE	1	Enable the DMI sensor for use			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	Source	EXT_COUNT	0	Select how the value of the RAWDMI input will be interpreted. Use **EXT_COUNT** for sending **RAWDMI** commands to the receiver where the DMI Input Value is a cumulative distance or tick count. Use **EXT_VELOCITY** for sending **RAWDMI** commands to the receiver where the DMI Input Value is a tick velocity (i.e. number of ticks since last command, not cumulative). Use **IMU** for the MIC, UIC, or enclosed IMUs. Use **ENCLOSURE** for the PwrPak7 or CPT7. Default = EXT_COUNT	Enum	4	H+8
		EXT_ VELOCITY	1				
		IMU	2				
		ENCLOSURE	3				
5	Reserved	Default = OFF	Default = 1	Reserved Field (Optional) If entering, use default values.	Enum	4	H+12

4.4 EXTERNALPVAS

Enter PVA update

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This command should only be used by advanced users of GNSS+INS.

The standard deviations entered using this command must be representative of actual input error.

Relative updates should only be used when they are input at consistent rates.

The **EXTERNALPVAS** command uses a short header if the command is entered in ASCII or Binary.

This command allows the user to provide their own update for INS in full position, velocity, attitude and other updates, and in any combination. The user can also provide height or attitude only updates, along with Zero Velocity Updates (ZUPTs). The position and velocity updates can be entered in local level or ECEF.

The **EXTERNALPVAS** command is designed to provide a method for additional sensor information to be input into the SPAN filter, specifically during GNSS denied environments. This will provide a method to constrain the error growth that is typical in an Inertial Kalman Filter when GNSS observations are unavailable (environments such as: urban canyon, tunnels, jamming etc.). It is important to ensure that the external update and its corresponding standard deviations are accurate and input with minimal latency to provide optimal effectiveness. Entering an external update or its standard deviation inappropriately may have an adverse effect on the SPAN solution.

The default input frame is ECEF. Updates are entered in ECEF unless Local Level is specified using the OptionsMask parameter.

Message ID: 1463

Abbreviated ASCII syntax:

```
EXTERNALPVAS Position1 Position2 Position3 Velocity1 Velocity2 Velocity3
Attitude1 Attitude2 Attitude3 PosStdDev1 PosStdDev2 PosStdDev3 VelStdDev1
VelStdDev2 VelStdDev3 AttStdDev1 AttStdDev2 AttStdDev3 UpdateMask OptionsMask
```

Abbreviated ASCII example: (Local Level Velocity Update)

```
EXTERNALPVAS 0.0 0.0 0.0 0.4502 10.54 -0.09598 0.0 0.0 0.0 0.0 0.0 0.0 0.01
0.01 0.01 0.0 0.0 0.0 4000 10
```

Full ASCII example: (Local Level Velocity Update)

```
%EXTERNALPVASA,2051,493713.000;0.00000000000,0.00000000000,0.00000000000,
0.1333,17.1424,-0.3311,0.000000000,0.000000000,0.000000000,0.0000,0.0000,
0.0000,0.0119,0.0096,0.0132,0.0000,0.0000,0.0000,00004000,00000010*edced535
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	EXTERNALPVAS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Position1			Latitude (degrees), ECEF X-coordinate (m) or X relative coordinate (m)	Double Array [3]	24	H
	Position2			Longitude (degrees), ECEF Y-coordinate (m) or Y relative coordinate (m)			
	Position3			Height (ellipsoidal m), ECEF Z-coordinate (m) or Z relative coordinate (m)			
3	Velocity1			North velocity or velocity along the X-axis (m/s)	Float Array [3]	12	H+24
	Velocity2			East velocity or velocity along the Y-axis (m/s)			
	Velocity3			Up velocity or velocity along the Z-axis (m/s)			
4	Attitude1			Pitch – Local Level to SPAN User Output Frame or relative delta from SPAN User Output Frame (degrees)	Float Array [3]	12	H+36
	Attitude2			Roll – Local Level to SPAN User Output Frame or relative delta from SPAN User Output Frame (degrees)			
	Attitude3			Azimuth – Local Level to SPAN User Output Frame or relative delta from SPAN User Output Frame (degrees)			
5	PosStdDev1			Position1 standard deviation (m)	Float Array [3]	12	H+48
	PosStdDev2			Position2 standard deviation (m)			
	PosStdDev3			Position3 standard deviation (m)			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
6	VelStdDev1			Velocity1 standard deviation (m/s)	Float Array [3]	12	H+60
	VelStdDev2			Velocity2 standard deviation (m/s)			
	VelStdDev3			Velocity3 standard deviation (m/s)			
7	AttStdDev1			Attitude1 standard deviation (degrees)	Float Array [3]	12	H+72
	AttStdDev2			Attitude2 standard deviation (degrees)			
	AttStdDev3			Attitude3 standard deviation (degrees)			
8	UpdateMask			This mask selects which updates are applied. Setting a bit applies the update. More than one update can be applied at one time. See *Table 272: EXTERNALPVAS updates mask* below for the external update bits that can be used.	HEX Ulong	4	H+84
9	OptionsMask			This mask selects the update options for various updates, such as using an ECEF or Local Level system for the position updates. See *Table 273: EXTERNALPVAS options mask* on the next page for details.	HEX Ulong	4	H+88

Table 272: EXTERNALPVAS updates mask

Bit	Mask	Description
0	0x00001	Reserved
1	0x00002	Reserved
2	0x00004	ZUPT Update. No fields are required in the **EXTERNALPVAS** command for this update.
3	0x00008	Reserved
4	0x00010	Reserved
5	0x00020	External Position Update. This update is entered using Position1 to Position3 in the **EXTERNALPVAS** command.

Bit	Mask	Description
6	0x00040	Reserved
7	0x00080	Reserved
8	0x00100	Reserved
9	0x00200	Reserved
10	0x00400	Reserved
11	0x00800	Reserved
12	0x01000	Reserved
13	0x02000	Reserved
14	0x04000	External Velocity Update. This update is entered using Velocity1 to Velocity3 in the **EXTERNALPVAS** command.
15	0x08000	External Attitude Update. This update is entered using Attitude1 to Attitude3 in the **EXTERNALPVAS** command.
16	0x10000	External Heading Update. This update is entered using Attitude3 in the **EXTERNALPVAS** command.
17	0x20000	External Height Update. This update is entered using Position3 in the **EXTERNALPVAS** command.

If both the External Position Update and External Height Update bits are set, only the External Position Update will be applied. Issuing External Position or External Height updates will both report an EXTPOS update was applied in *Extended solution status* on page 1124.

If both the External Attitude Update and External Heading Update bits are set, only the External Attitude Update will be applied. Issuing External Attitude or External Heading updates will both report an EXTATT update was applied in *Extended solution status* on page 1124.

Table 273: EXTERNALPVAS options mask

Bit	Mask	Description	Range value
0	0x00000001	Reserved	
1	0x00000002	Reserved	
2–3	0x0000000C	Position input frame	00 – ECEF
			01 – LLH
			10 - Vehicle frame (Relative update only)
4–5	0x00000030	Velocity input frame	00 – ECEF
			01 – LLH
			10 - Vehicle frame (Absolute update only)

Bit	Mask	Description	Range value
6	0x00000040	Position update type	0 – Absolute
			1 – Relative
7	0x00000080	Attitude update type	0 – Absolute
			1 – Relative

4.5 INPUTGIMBALANGLE

Input gimbal angles into the receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to input information about the current mount gimbal angles. Gimbal angles are the angle from the locked mount frame to the current gimbal location. They are input in the mount body frame. See Variable Lever Arm in the OEM7 SPAN Installation and Operation User Manual or CPT7 Installation and Operation User Manual for details on frame definitions.

It is very important to follow the order of rotations (Z, X, Y) when determining the rotations from the locked mount frame to the current gimbal location.

Message ID: 1317

Abbreviated ASCII syntax:

```
INPUTGIMBALANGLE XAngle YAngle ZAngle [XUncertainty] [YUncertainty]
[ZUncertainty]
```

Abbreviated ASCII examples:

```
INPUTGIMBALANGLE 0.003 -0.1234 12.837
INPUTGIMBALANGLE 0.003 -0.1234 12.837 0.001 0.001 0.005
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INPUTGIMBALANGLE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	X Angle	±180		Right hand rotation from the locked mount frame X axis to the current gimbal location in degrees.	Double Array [3]	24	H
	Y Angle	±180		Right hand rotation from the locked mount frame Y axis to the current gimbal location in degrees.			
	Z Angle	±180		Right hand rotation from the locked mount frame Z axis to the current gimbal location to in degrees.			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	X Uncertainty	0 – 180		Uncertainty of X rotation in degrees. Default is 0	Double Array [3]	24	H+24 H+40
	Y Uncertainty	0 – 180		Uncertainty of Y rotation in degrees. Default is 0			
	Z Uncertainty	0 – 180		Uncertainty of Z rotation in degrees. Default is 0			

4.6 INSALIGNCONFIG

Configure ALIGN parameters for SPAN receiver

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use the **INSALIGNCONFIG** command to configure ALIGN for a SPAN base receiver to a secondary rover receiver. The command will configure the port on the base and rover and setup corrections at the desired rate. It also attempts to re-establish these corrections should they stop.

Important

- This command must be used to define the ALIGN communication between the receivers that SPAN is to configure.
- When using ICOM ports, the Ethernet settings on the SPAN base and rover receiver must be manually configured.
- The base and rover ports must be the same interface type (i.e. Serial to Serial or Ethernet to Ethernet).
- The **INSALIGNCONFIG** command can be used to set the output rate for dual antenna receivers (e.g. OEM7720). In these cases, the port configuration fields are ignored.

Message ID: 2163

Abbreviated ASCII syntax:

```
INSALIGNCONFIG baseport [roverport] [baudrate] [outputrate]
```

Abbreviated ASCII example:

```
INSALIGNCONFIG COM1 COM2 230400 5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INSALIGNCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	baseport	NOPORT	0	Specify which COM port on the base receiver to use to communicate with an external ALIGN capable receiver. Selecting NOPORT disables automatic dual antenna configuration.	Enum	4	H
		COM1	1				
		COM2	2				
		COM3	3				
		COM4	19				
		COM5	31				
		ICOM1	23				
		ICOM2	24				
		ICOM3	25				
		ICOM4	29				
		ICOM5	46				
		ICOM6	47				
		ICOM7	48				
3	roverport	COM1	1	Specify which rover COM port is connected to the base receiver (Default = COM2)	Enum	4	H+4
		COM2	2				
		COM3	3				
		COM4	19				
		COM5	31				
		ICOM1	23				
		ICOM2	24				
		ICOM3	25				
		ICOM4	29				
		ICOM5	46				
		ICOM6	47				
		ICOM7	48				
4	baudrate	57600, 115200, 230400, or 460800		Baud rate for communication (Default = 230400)	Ulong	4	H+8
5	outputrate	1, 2, 4, 5, 10		The data rate, in Hz, in which ALIGN will be output (Default = 1 Hz)	Ulong	4	H+12

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
6	Reserved	Reserved (Default = 0) If entering, use the default value.			Ulong	4	H+16

The SPAN filter only requires ALIGN updates at 1 Hz. Increasing the output rate (using the *outputrate* field) does not increase performance, it only provides ALIGN logs at higher rates.

4.7 INSCALIBRATE

Initiate calibration of the INS offsets

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to initiate the calibration of INS offsets.

The RBV calibration requires a valid RBV estimate to be entered prior to initializing the calibration. See the **SETINSROTATION** command on page 1079 for details on entering a RBV estimate.

For optimal performance of Dual Antenna with SPAN, an accurate ALIGN angular offset is required for each unique installation. This value can be calibrated should the entered value or the value derived from the input lever arms be less accurate than 5 degrees.

Message ID: 1882

Abbreviated ASCII syntax:

```
INSCALIBRATE Offset [Trigger] [SDThreshold]
```

Abbreviated ASCII example:

```
INSCALIBRATE RBV NEW 1.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INSCALIBRATE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	Offset	ANT1	1	Use this option to set the INS calibration offset from the IMU to the primary GNSS antenna The ANT1 option is available only on IMU Grade 2 or higher IMUs. See Models and Features in the OEM7 SPAN Installation and Operation User Manual.	Enum	4	H
		ALIGN	8	Use this option to set the INS calibration offset from the IMU Body frame to ALIGN frame rotation.			
		RBV	11	Use this option to set the INS calibration offset from the IMU Body frame to Vehicle frame rotation.			
3	Trigger	STOP	0	Ends the INS calibration and applies the resulting estimate to the system.	Enum	4	H+4
		NEW	1	Begins a new calibration, overwriting any previous input.			
		ADD	2	Begins a new calibration, the results of which will be cumulatively averaged with previously calibrated offsets. If no previous calibration is present, this trigger behaves as the NEW trigger.			
		RESET	3	Resets the current calibration process and removes it from the cumulative average computation. The previous inputs of calibrated values remain.			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	SDThreshold			Standard Deviation Threshold (default for lever arm calibration = 0.10 m) (default for RBV and ALIGN calibration = 0.5 degrees)	Float	4	H+8

4.8 INSCOMMAND

INS control command

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to enable or disable INS. When INS is disabled, no INS position, velocity or attitude is output (however IMU data is still available). Also, INS aiding of tracking reacquisition is disabled. If the command is used to disable INS and then re-enable it, the INS system has to go through its alignment procedure (equivalent to issuing a **RESET** command). See System Start-Up and Alignment Techniques in the OEM7 SPAN Installation and Operation User Manual, CPT7 Installation and Operation User Manual or SMART7 Installation and Operation User Manual for information about the SPAN alignment procedures.

Message ID: 379

Abbreviated ASCII syntax:

```
INSCOMMAND action
```

Abbreviated ASCII example:

```
INSCOMMAND ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INSCOMMAND header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Action	RESET	0	Resets the GNSS/INS alignment without clearing the INS biases.	Enum	4	H
		DISABLE	1	Disables INS navigation.			
		ENABLE	2	Enables INS navigation where alignment initialization starts again if the Action parameter was previously set to DISABLE.			
		START_NO_TIME	3	Raw IMU data will begin to flow upon system startup. IMU data collection can begin before the receiver has a GNSS solution. (default)			
		START_FINE_TIME	4	RAWIMU data will only be output after the system reaches FINESTEERING.			
		RESTART	5	Resets the GNSS/INS alignment and clears the INS biases.			

4.9 INSSEED

INS seed configuration

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This command enables or disables the saving and restoration of the last known SPAN solution from NVM.

Message ID: 1906

Abbreviated ASCII syntax:

```
INSSEED Options [Azimuth Options] [Error Model Options]
```

Abbreviated ASCII example:

```
INSSEED ENABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INSSEED header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Options	DISABLE	0	Disable the INS seed functionality	Enum	4	H
		ENABLE	1	Enable the INS seed functionality			
		CLEAR	2	Clear the currently saved seed value so it will not be used until re-saved			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	Azimuth Options	VALIDATE	0	Validate INS Seed azimuth data using GNSS solution (default)	Enum	4	H+4
		INJECT	1	Force an INS seed azimuth value (if available) to be used, without any validation. **Using this option to force the seed to be used can result in an unstable INS solution if the vehicle has moved. For advanced users only.**			
		IGNORE	2	Do not use INS seed azimuth data at all.			
4	Error Model Options	INJECT	0	Use INS seed error model data, if available.	Ulong	4	H+8
		IGNORE	1	Do not use INS seed error model data.			
5	Reserved (Default = 0) If entering, use the default value.				Ulong	4	H+12

4.10 INSTHRESHOLDS

Change the INS_HIGH_VARIANCE threshold

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This command should only be used by advanced users of GNSS+INS.

The **INSTHRESHOLDS** command allows you to customize the criteria by which the system reports the inertial solution status. This criteria is used to determine whether the solution status is reported as INS_SOLUTION_GOOD or INS_HIGH_VARIANCE.

This command is useful in situations where system dynamics are known to be challenging.

Message ID: 1448

Abbreviated ASCII syntax:

```
INSTHRESHOLDS Threshold_Configuration
```

Abbreviated ASCII example:

```
INSTHRESHOLDS DEFAULT
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INSTHRESHOLDS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Threshold_ Configuration	DEFAULT	0	Standard INS status threshold settings	Enum	4	H
		LOW	1	Low INS status threshold settings (only checks the Attitude standard deviation)			
3	Reserved (Default = 0) If entering, use the default value.				Double	8	H+4

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	Reserved (Default = 0) If entering, use the default value.				Double	8	H+12
5	Reserved (Default = 0) If entering, use the default value.				Double	8	H+20

4.11 INSZUPT

Request Zero Velocity Update

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to manually perform a Zero Velocity Update (ZUPT).

NovAtel's SPAN Technology System does ZUPTs automatically. It is not necessary to use this command under normal circumstances.

This command should only be used by advanced users of GNSS/INS and only when the system is truly stationary.
Applying a ZUPT while moving will result in severe instability of the solution.

Message ID: 382

Abbreviated ASCII syntax:

```
INSZUPT
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	INSZUPT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Reserved Default = TRUE This parameter is optional when using abbreviated ASCII syntax.				BOOL	4	H

4.12 RELINSAUTOMATION

Enables Relative INS on the rover

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to configure the Relative INS plug and play feature on the rover receiver. RELINSAUTOMATION enables/disables the plug and play feature, sets the rover COM port to which the base receiver is connected, sets the baud rate for communication, sets the correction transfer rate and enables/disables sending the HEADINGEXTB/HEADINGEXT2B log back to the base receiver.

On issuing this command at the rover receiver, the rover will automatically sync with the base receiver and configure it to send corrections at the specified baud rate and specified data rate.

The recommended method for configuring Relative INS is to use the **RELINSCONFIG** command (see page 1067).

This command should only be issued at the rover receiver.

if the rover receiver is not connected to the base receiver using a serial COM port, use the **RELINSCONFIG** command (see page 1067).

To use the **RELINSAUTOMATION** command, the receiver requires a Relative INS capable model.

Message ID: 1763

Abbreviated ASCII syntax:

```
RELINSAUTOMATION option [comport] [baudrate] [datarate] [headingextb_option]
```

Abbreviated ASCII example:

```
RELINSAUTOMATION enable com2 230400 10 on
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RELINSAUTOMATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	option	ENABLE	0	Enables or disables the plug and play feature.	Enum	4	H
		DISABLE	1				
3	comport	COM1	1	The COM port on the rover receiver to which the base receiver is connected. (default = COM2)	Enum	4	H+4
		COM2	2				
		COM3	3				
4	baudrate	9600, 19200, 38400, 57600, 115200, 230400, 460800		The baud rate used for communication between the base and rover receivers.	Ulong	4	H+8
5	datarate	1, 2, 4, 5, 10 or 20 Hz		The rate at which corrections are transferred between the receivers. (default =10 Hz)	Ulong	4	H+12
6	headingextb_ option	ON OFF		Enables or disables sending the HEADINGEXTB/ HEADINGEXT2B log back to the base receiver. (default = ON)	Enum	4	H+16

4.13 RELINSCONFIG

Configure Relative INS

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to configure Relative INS on this receiver.

To use the **RELINSCONFIG** command, the receiver requires a Relative INS capable model.

Message ID: 1797

Abbreviated ASCII syntax:

```
RELINSCONFIG enable rxtype [port] [baud] [rateinhz]
```

Abbreviated ASCII example:

```
RELINSCONFIG ENABLE ROVER COM2 230400 10
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	RELINSCONFIG header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	enable	DISABLE	0	Enables or disables the Relative INS functionality.	Enum	4	H
		ENABLE	1				
3	rxtype	ROVER	1	Defines the receiver as the rover in a Relative INS configuration.	Enum	4	H+4
		MASTER	2	Defines the receiver as the base in a Relative INS configuration.			
4	port	See *Table 274: COM ports* on the next page		Communication port used to communicate with the other receiver. (default = COM2)	Enum	4	H+8
5	baud	9600, 19200, 38400, 57600, 115200, 230400, 460800		The baud rate used for communication between the base and rover receivers. (default = 230400)	Ulong	4	H+12
6	rateinhz	1, 2, 4, 5, 10 or 20 Hz		The rate at which corrections are transferred between the receivers. (default =10 Hz)	Ulong	4	H+16

Table 274: COM ports

Decimal	ASCII	Description
1	COM1	COM port 1
2	COM2	COM port 2
3	COM3	COM port 3
13	USB1	USB port 1
14	USB2	USB port 2
15	USB3	USB port 3
19	COM4	COM port 4
23	ICOM1	IP virtual COM port 1
24	ICOM2	IP virtual COM port 2
25	ICOM3	IP virtual COM port 3
29	ICOM4	IP virtual COM port 4
31	COM5	COM port 5
46	ICOM5	IP virtual COM port 5
47	ICOM6	IP virtual COM port 6
48	ICOM7	IP virtual COM port 7
49	SCOM1	Scripted application COM port 1
50	SCOM2	Scripted application COM port 2
51	SCOM3	Scripted application COM port 3
52	SCOM4	Scripted application COM port 4
65	LCOM1	Lua COM port 1 (Firmware 7.10.xx)
66	LCOM2	Lua COM port 2 (Firmware 7.10.xx)
67	LCOM3	Lua COM port 3 (Firmware 7.10.xx)
68	LCOM4	Lua COM port 4 (Firmware 7.10.xx)

4.14 SETALIGNMENTORIENTATION

Enable or disable orientation verification

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This command enables or disables the orientation verification condition for INS alignment. If the detected enclosure frame roll or pitch exceeds the defined thresholds, INS alignment will not occur.

This command is specifically designed for use on smart antenna products where the GNSS antenna is rotating with the IMU and the customer wants to ensure the enclosure is in the proper orientation (right side up) prior to SPAN completing alignment.

Message ID: 2164

Abbreviated ASCII syntax:

```
SETALIGNMENTORIENTATION switch [Roll/Pitch Threshold]
```

Abbreviated ASCII example:

```
SETALIGNMENTORIENTATION ENABLE 60.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	SETALIGNMENT ORIENTATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Switch	Disable	0	Disable orientation check on INS alignment.	Enum	4	H
		Enable	1	Enable orientation check on INS alignment.			
3	Roll/Pitch Threshold	0.0 - 90.0		Roll and pitch lower limit for preventing INS alignment (degrees, default = 60.0).	Double	8	H+4

4.15 SETALIGNMENTVEL

Set the minimum kinematic alignment velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use the **SETALIGNMENTVEL** command to adjust the minimum required velocity for a kinematic alignment.

Useful in cases, such as helicopters, where alignment velocity should be increased to prevent a poor alignment before the vehicle/aircraft is able to flight straight and level.

Message ID: 1397

Abbreviated ASCII syntax:

```
SETALIGNMENTVEL velocity
```

Abbreviated ASCII example

```
SETALIGNMENTVEL 5.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETALIGNMENTVEL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Velocity	Minimum: 0.2 m/s (Default is 5 m/s)		The minimum velocity, in m/s, required to kinematically align.	Double	8	H

4.16 SETHEAVEWINDOW

Set Heave filter length

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to control the length of the heave filter. This filter determines the heave (vertical displacement) of the IMU, relative to a long term level surface. This command does not control the DELAYEDHEAVE filter window.

Message ID: 1383

Abbreviated ASCII syntax:

```
SETHEAVEWINDOW filterlength
```

Abbreviated ASCII example:

```
SETHEAVEWINDOW 35
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETHEAVEWINDOW header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	FilterLength	Integer (1 – 300 s) (default = 20 s)		This filter length will be used in the heave filter. Typically, set the filter length to 5 x wave period	Long	4	H

4.17 SETIMUEVENT

IMU event selection command

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7

This command is used to select the event used for timing the IMU data. IMUs that use a Time of Validity (ToV) signal send a pulse (using an Event IN) to the receiver. IMUs that synchronize the IMU clock with the receiver clock require a signal from the receiver (using an Event OUT).

Message ID: 1965

Abbreviated ASCII syntax:

```
SETIMUEVENT Direction Event
```

Abbreviated ASCII example:

```
SETIMUEVENT OUT EVENT3
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	–	–	SETIMUEVENT header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	–	H	0
2	Direction	IN	1	Direction of event IN2 is only available on the OEM7500 and is intended for IMUs with multiple ToVs.	Enum	4	H
		OUT	2				
		IN2	3				
3	Event	OFF	1	The event to assign to the direction. The DEFAULT event is EVENT2 for the IN direction and EVENT1 for the OUT direction.	Enum	4	H+4
		DEFAULT	2				
		EVENT1	3				
		EVENT2	4				
		EVENT3	5				
		EVENT4	6				

4.18 SETIMUPORTPROTOCOL

Sets the protocol used for the IMU serial port

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7

Use the **SETIMUPORTPROTOCOL** command to change the IMU serial port to use either RS-232 or RS-422 protocol. This overrides the default configured internally when the **CONNECTIMU** command is sent.

Before changing the IMU serial port protocol:

1. Make sure the receiver port connected to the IMU is capable of RS-422 protocol. Refer to the OEM7 Installation and Operation User Manual for information about the receiver serial ports.
2. The IMU data message is input into the receiver at that particular protocol.

Message ID: 1767

Abbreviated ASCII syntax:

```
SETIMUPORTPROTOCOL SerialProtocol
```

Abbreviated ASCII example:

```
SETIMUPORTPROTOCOL RS422
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETIMUPORTPROTOCOL header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	SerialProtocol	RS232 RS422		The protocol for the IMU serial port.	Enum	4	H

4.19 SETIMUSPECS

Specify error specifications and data rate

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7

This command should only be used by advanced users of GNSS/INS.

Use the **SETIMUSPECS** command to specify the error specifications and data rate for the desired IMU. If the default specs for the supported models are different than the unit used then this command can be used to override the default values.

This command is only available for the following IMUs:

- Honeywell HG1930 (default specifications are for the AA99/CA50 model)
- Honeywell HG1900 (default specifications are for the CA29/CA50 model)

Message ID: 1295

Abbreviated ASCII syntax:

```
SETIMUSPECS DataRate AccelBias AccelVRW GyroBias GyroARW AccelSFError
GyroSFError [DataLatency]
```

Abbreviated ASCII example: (iMAR-FSAS specs)

```
SETIMUSPECS 200 1 .0198 0.75 0.0028 300 300 2.5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETIMUSPECS header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	DataRate	100 Hz to 400 Hz		Data rate of the IMU	Ushort	2	H
3	AccelBias	-		Total accelerometer bias in milli-g	Double	8	H+2
4	AccelVRW	-		Accelerometer velocity random walk in m/s/rt-hr	Double	8	H+10
5	GyroBias	-		Total gyroscope bias in deg/hr	Double	8	H+18
6	GyroARW	-		Gyroscope angular random walk in deg/rt-hr	Double	8	H+26

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
7	AccelSFError	> 0		Accelerometer scale factor error in parts per million. Optional. Default = 1000 ppm.	Ulong	4	H+34
8	GyroSFError	> 0		Gyroscopic scale factor error in parts per million. Optional. Default = 1000 ppm.	Ulong	4	H+38
9	DataLatency	> 0		Time delay in milliseconds from the time of validity of the IMU data to the time the input pulse is received by the SPAN enabled receiver. This may include filtering delays, processing delays and transmission times depending on the timing method (TOV, ASYNC, SYNC) and the internal IMU handling. Optional. Default = 0.0.	Double	8	H+42
10	Reserved	SCALE_ DEFAULT	0	Reserved. If using ASCII format, enter SCALE_DEFAULT. If using binary format, enter 0.	Enum	4	H+50
11	CRC	-		32-bit CRC	Hex	4	H+54

4.20 SETINITAZIMUTH

Set initial azimuth and standard deviation

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to start SPAN operation with a previously known azimuth. Azimuth is the weakest component of a coarse alignment and is also the easiest to know from an external source (i.e., like the azimuth of roadway). When using this command, SPAN operation through alignment will appear the same as with a usual coarse alignment. Roll and pitch is determined using averaged gyro and accelerometer measurements. The input azimuth is used rather than what is computed by the normal coarse alignment routine.

- Input azimuth values must be accurate for good system performance.
- Sending **SETINITAZIMUTH** resets the SPAN filter. Following realignment, vehicle dynamics are required for the filter to re-converge. Bridging performance is poor before filter convergence.
- The entered azimuth angle is with respect to the configured output frame. This is generally the vehicle frame unless a User Frame offset has been configured using the **SETINSROTATION** command (see page 1079). All offsets should be entered before entering the **SETINITAZIMUTH** command.
- This command is not save configurable and must be re-entered after each start-up. The command can be entered at any time and will be used automatically when the system is ready to begin alignment.



Azimuth is positive in a clockwise direction when looking towards the z-axis origin.

Message ID: 863

Abbreviated ASCII syntax:

```
SETINITAZIMUTH azimuth azSTD
```

Abbreviated ASCII example:

```
SETINITAZIMUTH 90 5
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETINITAZIMUTH header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	azimuth	0 to 360		Input azimuth angle (degrees)	Double	8	H
3	azSTD	1 to 25		Input azimuth standard deviation angle (degrees)	Float	4	H+8

4.21 SETINSPROFILE

Sets filter behaviour depending on system environment

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This command sets specific filter behaviour depending on the environment the system is installed in. The DEFAULT profile is the legacy setting from earlier SPAN products. The other profiles make changes specific to that environment.

See INS Profiles in the OEM7 SPAN Installation and Operation User Manual or CPT7 Installation and Operation User Manual for a detailed description of each profile's effect.

Message ID: 1944

Abbreviated ASCII syntax:

```
SETINSPROFILE profile
```

Abbreviated ASCII example:

```
SETINSPROFILE LAND
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETINSPROFILE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
2	Profile	Default	0	Default INS profile with standard SPAN behaviour.	Enum	4	H
		LAND	1	INS profile for land vehicles			
		MARINE	2	INS profile for marine vehicles			
		FIXEDWING	3	INS profile for fixed wing aircraft			
		FOOT	4	INS profiles for walking/backpack applications			
		VTOL	5	INS profile for vertical takeoff and landing vehicles (UAVs, helicopters, etc.)			
		RAIL	6	INS profile for trains			
		AGRICULTURE	7	INS profile for agriculture applications			

4.22 SETINSROTATION

Specifies rotational offsets between the IMU frame and other reference frames

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use the **SETINSROTATION** command to specify rotational offsets between the IMU frame and other reference frames, such as the vehicle frame or an ALIGN baseline. Offsets must be entered as the rotation from the IMU body frame, to the frame of interest. The order of rotations is Z, X, Y. All rotations are right handed.

It is very important to follow the order of rotations (Z, X, Y) when determining the rotations from IMU body frame to frame of interest.

It is strongly recommended to enter meaningful standard deviations when entering an ALIGN or RBV rotation.

To specify translational offsets between frames, see the **SETINSTRANSLATION** command on page 1082.

Message ID: 1921

Abbreviated ASCII syntax:

```
SETINSROTATION INSRotation XRotation YRotation ZRotation [XRotationSD]
[YRotationSD] [ZRotationSD]
```

Abbreviated ASCII example:

```
SETINSROTATION RBV 0 0 90 3.0 3.0 3.0
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETINSROTATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	INSRotation	*Table 275: Rotational offset types* on the next page		Rotational offset to be set.	Enum	4	H

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	XRotation	±180		X rotation offset from IMU origin (degrees)	Float Array [3]	12	H+4
	YRotation	±180		Y rotation offset from IMU origin (degrees)			
	ZRotation	±180		Z rotation offset from IMU origin (degrees)			
4	XRotationSD	0.25 to 45		Optional X rotation offset standard deviation (degrees). Applicable for RBV and ALIGN rotations. (Default = 3.0)	Float Array [3]	12	H+16
	YRotationSD	0.25 to 45		Optional Y rotation offset standard deviation (degrees). Applicable for RBV and ALIGN rotations. (Default = 3.0)			
	ZRotationSD	0.25 to 45		Optional Z rotation offset standard deviation (degrees). Applicable for RBV and ALIGN rotations. (Default = 3.0)			
5	Reserved (Default = 0) If entering, use the default value.				Long	4	H+28

Table 275: Rotational offset types

ASCII	Binary	Description
USER	4	Rotation from the IMU body frame to the user output frame. This offset shifts the attitude information in the INSPVA, INSATT, INSATTQS, INSPVACMP, IMURATEPVA, GIMBALLEDPVA, PASHR and TSS1 logs, along with their short header and extended versions. As well it changes the output frame for the CORRIMUS, IMURATECORRIMUS, INSVELUSER, RELINSPVA and SYNCRELINSPVA logs.
MARK1	5	Rotation from the IMU body frame to the desired output for MARK1. This offset rotates the attitude information in the MARK1PVA log.

ASCII	Binary	Description
MARK2	6	Rotation from the IMU body frame to the desired output for MARK2. This offset rotates the attitude information in the MARK2PVA log.
ALIGN	8	Rotation from the IMU body frame to an ALIGN dual antenna solution. When using a dual antenna ALIGN solution with SPAN, this offset will be calculated automatically if translational offsets to both the primary and secondary GNSS antennas are provided using the **SETINSTRANSLATION** command on the next page.
MARK3	9	Rotation from the IMU body frame to the desired output for MARK3. This offset rotates the attitude information in the MARK3PVA log.
MARK4	10	Rotation from the IMU body frame to the desired output for MARK4. This offset rotates the attitude information in the MARK4PVA log.
RBV	11	Rotation from the IMU body frame to the vehicle frame.
RBM	12	Rotation from the IMU body frame to the gimbal mount body frame.

4.23 SETINSTRANSLATION

Specifies translational offsets between the IMU frame and other reference frames

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use the **SETINSTRANSLATION** command to specify translational offsets between the IMU frame and other reference frames, including GNSS antennas or the desired output frame. Offsets must be entered as the vector from the IMU, to the frame or position of interest. Offsets can be entered either in the IMU body frame, or the vehicle frame; offsets in the vehicle frame will be automatically rotated into the IMU body frame using the best available IMU Body to Vehicle Rotation (RBV).

For details on entering the RBV rotation or other angular offsets, see the **SETINSROTATION** command on page 1079.

Message ID: 1920

Abbreviated ASCII syntax:

```
SETINSTRANSLATION INSTranslation XTranslation YTranslation ZTranslation
[XTranslationSD] [YTranslationSD] [ZTranslationSD] [InputFrame]
```

Abbreviated ASCII example:

```
SETINSTRANSLATION USER 1.0 2.0 3.0 0.05 0.05 0.05 VEHICLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETINSTRANSLATION header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	InsTranslation	See *Table 276: Translation offset types* on page 1084		Translation offset to be set	Enum	4	H
3	XTranslation	±100		X translation offset from IMU origin (m)	Float Array [3]	12	H+4
	YTranslation	±100		Y translation offset from IMU origin (m)			
	ZTranslation	±100		Z translation offset from IMU origin (m)			

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
4	XTranslationSD	0 to 10		Optional X translation offset standard deviation (m)	Float Array [3]	12	H+16
	YTranslationSD	0 to 10		Optional Y translation offset standard deviation (m)			
	ZTranslationSD	0 to 10		Optional Z translation offset standard deviation (m)			
5	InputFrame	*Table 277: Translation input frame* on page 1086		Optional input frame for translation offset values	Enum	4	H+28

For the ANT1, ANT2, EXTERNAL and GIMBAL translations, the standard deviation defaults are set to 10% of the translation value (up to a max of 10 metres).

The offset standard deviation values are not optional when entering a value for the Input Frame.

For USER translations, standard deviation values are assumed to be zero unless specified by the user. When a USER offset is configured in the system, the INS solution standard deviations calculated at the IMU centre of navigation will be propagated taking into account the INS attitude errors, USER offset values, and the USER offset standard deviations. This will result in larger scale INS position and velocity standard deviations compared to those calculated without a USER offset configured, but will be more representative of the estimated variance at the location of interest.

It is important to keep in mind that as the USER offset is moved further from the IMU centre of navigation, the PVA solution will become noisier due to the projection of angular changes over a longer distance.

For MARK1, MARK2, MARK3 and MARK4 translations, standard deviations values are not used in the solution.

Large translation standard deviations can lead to an inaccurate INS position and velocity solution. Therefore, it is highly recommended to measure translation offsets as accurately as possible and to manually enter translation offset standard deviations that reflect that accuracy.

Table 276: Translation offset types

ASCII	Binary	Description
ANT1	1	Offset from the IMU centre of navigation to the phase centre of the primary GNSS antenna. The standard deviation defaults are set to 10% of the translation value (up to a max of 10 meters). **Do not use the ANT1 option (SETINSTRANSLATION ANT1) on a SMART7-S. The correct lever arm value has been set at the factory.**
ANT2	2	Offset from the IMU centre of navigation to the phase centre of the secondary GNSS antenna. The standard deviation defaults are set to 10% of the translation value (up to a max of 10 meters). **Do not enter an ANT2 translation offset that is identical to the ANT1 offset.** **If the translation offsets are identical, SPAN will not be able to compute a valid SETINSROTATION ALIGN rotation.**
EXTERNAL	3	Offset from the IMU centre of navigation to the external position source location. This offset type is for use with the **EXTERNALPVAS** command (see page 1046). The standard deviation defaults are set to 10% of the translation value (up to a max of 10 meters).

ASCII	Binary	Description
USER	4	Translation from the IMU centre of navigation to the new common position and velocity output location. This offset shifts the position and velocity information in the standard INS positioning logs. USERVEL and/or USERPOS offsets will be applied on top of this offset. It is recommended to just use USERPOS/USERVEL. The standard deviation defaults are set to 0.
MARK1	5	Translation from the IMU centre of navigation to the MARK1 output location. This offset shifts the position and velocity information in the MARK1PVA log. The standard deviation values are not used in the solution. The default values are set to 0.
MARK2	6	Translation from the IMU centre of navigation to the MARK2 output location. This offset shifts the position and velocity information in the MARK2PVA log. The standard deviation values are not used in the solution. The default values are set to 0.
GIMBAL	7	Translation from the IMU centre of navigation to the gimbal mount centre of rotation. The standard deviation defaults are set to 10% of the translation value (up to a max of 10 meters).
MARK3	9	Translation from the IMU centre of navigation to the MARK3 output location. This offset shifts the position and velocity information in the MARK3PVA log. The standard deviation values are not used in the solution. The default values are set to 0.

ASCII	Binary	Description
MARK4	10	Translation from the IMU centre of navigation to the MARK4 output location. This offset shifts the position and velocity information in the MARK4PVA log. The standard deviation values are not used in the solution. The default values are set to 0.
USERVEL	19	Translation of INS velocity from common INS output location (IMU centre of navigation, or USER offset if it exists) to the defined location. The covariances calculated from the entered standard deviations are added with those entered in USER offset should it exist. This offset shifts the velocity information in the standard INS positioning logs. See Output location for logs in the OEM7 SPAN Installation and Operation User Manual. The standard deviation defaults are set to 0.
USERPOS	20	Translation of INS position from common INS output location (IMU centre of navigation, or USER offset if it exists) to defined location. The covariances calculated from the entered standard deviations are added with those entered in USER offset should it exist. This offset shifts the position information in the standard INS positioning logs. See Output location for logs in the OEM7 SPAN Installation and Operation User Manual. The standard deviation defaults are set to 0.

Table 277: Translation input frame

ASCII	Binary	Description
IMUBODY	0	Offset is provided in the IMU enclosure frame. Default: IMUBODY
VEHICLE	1	Offset is provided in the vehicle frame. Offsets entered in the vehicle frame will be automatically rotated into the IMU frame using the best available RBV (rotation from IMU Body to Vehicle) information when required. Vehicle frame offsets should only be used if the RBV is known accurately, either through user measurement or calibration. The order of entry for vehicle frame offsets and the RBV rotation does not matter.

4.24 SETINSUPDATE

Enable/Disable INS filter updates

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This command should only be used by advanced users of GNSS+INS.

Use this command to enable or disable the available INS filter updates.

Message ID: 1821

Abbreviated ASCII syntax:

```
SETINSUPDATE INSUpdate Trigger
```

Abbreviated ASCII example:

```
SETINSUPDATE ZUPT DISABLE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETINSUPDATE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	INSUpdate	POS	0	Position updates	Enum	4	H
		ZUPT	1	Zero velocity updates			
		PSR	2	Pseudorange updates			
		ADR	3	Carrier phase updates			
		DOPPLER	4	Doppler updates			
		ALIGN	5	Heading updates			
		DMI	6	Distance measuring instrument (wheel sensor) updates			
3	Trigger	DISABLE	0	Disable the INS update specified in the INSUpdate field.	Enum	4	H+4
		ENABLE	1	Enable the INS update specified in the INSUpdate field.			

4.25 SETMAXALIGNMENTTIME

Set a time limit for static course alignment

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to set a maximum time limit allowed for static coarse alignments. Coarse alignments typically take under 60 seconds, but in heavy vibration conditions they can take much longer trying to compensate for the vibration induced noise. This command is used to cap the time to a specific length.

This command is for advanced users only.
Alignment accuracy cannot be guaranteed if the alignment time is capped using this command.

Message ID: 1800

Abbreviated ASCII syntax:

```
SETMAXALIGNMENTTIME switch [duration]
```

Abbreviated ASCII example:

```
SETMAXALIGNMENTTIME ENABLE 90
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETMAXALIGNMENTTIME header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	switch	DISABLE	0	Disables the static alignment time limit.	Enum	4	H
		ENABLE	1	Enables the static alignment time limit.			
3	duration	30 - 300		Maximum static alignment time in seconds. Default is 180.	Ulong	4	H+4

4.26 SETRELINSOUTPUTFRAME

Sets the Relative INS output frame

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use this command to change the frame of the output solution provided in all Relative INS logs (for example, **RELINSPVA**).

See in the OEM7 SPAN Installation and Operation User Manual or CPT7 Installation and Operation User Manual for information about the Relative INS functionality.

Message ID: 1775

Abbreviated ASCII syntax:

```
SETRELINSOUTPUTFRAME OutputFrame [DiffCriteria]
```

Abbreviated ASCII example:

```
SETRELINSOUTPUTFRAME ECEF TRUE
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETRELINSOUTPUT FRAME header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	OutputFrame	ROVER	1	Frame of the output solution. ROVER – the output frame of the Rover receiver INS solution MASTER – the output frame of the Base receiver INS solution ECEF – Earth Centered Earth Fixed LOCALLEVEL – Local level The default is the ROVER.	Enum	4	H
		MASTER	2				
		ECEF	3				
		LOCALLEVEL	4				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	DiffCriteria	FALSE	0	The delta solution is computed as Rover minus Base. (default)	Bool	4	H+4
		TRUE	1	The delta solution is computed as Base minus Rover.			

4.27 SETUPSENSOR

Add a new sensor object

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to add a new sensor object to the system. A sensor object consists of an ID, an Event_Out line and an Event_In line. This is intended as a simplified way to set up triggering to and from a sensor rather than configuring all connections independently. It also allows for event pulses to be sent to a sensor at specific GPS times (see the **TIMEDEVENTPULSE** command on page 1094).

Message ID: 1333

Abbreviated ASCII syntax:

```
SETUPSENSOR SensorID EventOut OPP OAP EventIn EIC IPP ITB ITG
```

Abbreviated ASCII example:

```
SETUPSENSOR SENSOR3 MARK1 POSITIVE 2 MARK4 EVENT POSITIVE 0 2
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	SETUPSENSOR header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Sensor ID	SENSOR1	0	The sensor to configure.	Enum	4	H
		SENSOR2	1				
		SENSOR3	2				
3	EventOut	MARK1	0	Associate a specific MARK Event_Out line to this sensor configuration.	Enum	4	H+4
		MARK2	1				
		MARK3	2				
		MARK4	3				
4	OPP	NEGATIVE	0	Mark output pulse polarity	Enum	4	H+8
		POSITIVE	1				
5	OAP	2 - 500		Mark output active period in milliseconds. Value must be divisible by 2.	Ulong	4	H+12
6	EventIn	MARK1	0	Associate a specific MARK Event_In line to this sensor configuration.	Enum	4	H+16
		MARK2	1				
		MARK3	2				
		MARK4	3				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
7	EIC	DISABLE	0	Event in control	Enum	4	H+20
		EVENT	1				
8	IPP	NEGATIVE	0	Mark input pulse polarity	Enum	4	H+24
		POSITIVE	1				
9	ITB	-99999999 to 99999999		Mark input time bias in milliseconds	Long	4	H+28
10	ITG	2 to 3599999		Mark input time guard in milliseconds	Ulong	4	H+32

The Event_In and Event_Out options available are dependent on the receiver used in the SPAN system. For information about the Event lines supported, see the Strobe Specifications for the receiver in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual, or CPT7 Installation and Operation User Manual.

MARK4 is available only on SPAN systems with an OEM7600, OEM7700 or OEM7720 receiver.

4.28 TAGNEXTMARK

Tags the next incoming Mark event

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to tag the next incoming mark event on the selected mark with a 32-bit number. This is available in the **TAGGEDMARK1PVA, TAGGEDMARK2PVA, TAGGEDMARK3PVA and TAGGEDMARK4PVA** log (see page 1214) to easily associate the PVA log with a supplied event.

Message ID: 1257

Abbreviated ASCII syntax:

```
TAGNEXTMARK Mark Tag
```

Abbreviated ASCII example:

```
TAGNEXTMARK MARK1 1234
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	TAGNEXTMARK header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	Mark	MARK1	0	Event line	Enum	4	H
		MARK2	1				
		MARK3	2				
		MARK4	3				
3	Tag	-	-	Tag for next mark event	Ulong	4	H+4

The Mark options available are dependent on the receiver used in the SPAN system. For information about the Event lines supported, see the Strobe Specifications for the receiver in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

4.29 TIMEDEVENTPULSE

Add a new camera event

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this command to add a new camera event to the system. **TIMEDEVENTPULSE** sends a pulse on the sensor MARK output at the selected GPS time and sets the trigger on the sensor MARK input to be tagged with an event ID (see the **TAGGEDMARK1PVA, TAGGEDMARK2PVA, TAGGEDMARK3PVA and TAGGEDMARK4PVA** log on page 1214). The lines connected to each sensor are configured using the **SETUPSENSOR** command (see page 1091).

A maximum of 10 unprocessed events can be buffered into the system. A TIMEDEVENTPULSE command must be entered at least 1 second prior to the requested event time.

The receiver will accept the **TIMEDEVENTPULSE** command only if the receiver time status is FINESTEERING.

Message ID: 1337

Abbreviated ASCII syntax:

```
TIMEDEVENTPULSE SensorID GPSWeek GPSSeconds [Event ID]
```

Abbreviated ASCII example:

```
TIMEDEVENTPULSE -1 1617 418838 100
```

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
1	Command header	-	-	TIMEDEVENTPULSE header This field contains the command name for abbreviated ASCII or the message header for *ASCII* on page 35 or *Binary* on page 39.	-	H	0
2	SensorID	ALL	-1 (0xffffffff)	The sensor(s) affected by the trigger command. The decimal representation of the combination of bits 0-2 can be used to select a combination of active sensors (e.g. 5 [101] will select sensors 1 and 3).	Long	4	H
		SENSOR1	0x01				
		SENSOR2	0x02				
		SENSOR3	0x04				

Field	Field type	ASCII value	Binary value	Description	Format	Binary bytes	Binary offset
3	GPSWeek	0 - MAX Ulong		The GPS week that triggers the event.	Ulong	4	H+4
4	GPSSeconds	0 - 604800		The GPS week seconds that triggers the event.	Double	8	H+8
5	Event ID	0- MAX Ulong		The event's identifier, used to tag the TAGGEDMARKxPVA logs if a sensor input is enabled. Optional Default = 0	Ulong	4	H+16

Chapter 5 SPAN logs

The SPAN specific logs follow the same general logging scheme as normal OEM7 Family logs. They are available in ASCII or binary formats and are defined as being either synchronous or asynchronous. All the logs in this chapter are used only with the SPAN system.

For information on other available logs and output logging, refer to *Logs* on page 489.

One difference from the standard OEM7 Family logs is there are two possible headers for the ASCII and binary versions of the logs. Which header is used for a given log is described in the log definitions in this chapter. The reason for the alternate short headers is that the normal OEM7 binary header is quite long at 28 bytes. This is nearly as long as the data portion of many of the INS logs and creates excess storage and baud rate requirements. Note that the INS related logs contain a time tag within the data block in addition to the time tag in the header. The time tag in the data block should be considered the exact time of applicability of the data. All INS Position, Velocity and Attitude logs can be obtained at a rate of up to 200 Hz. The standard deviation and update logs are available once per second.



Each ASCII log ends with a hexadecimal number preceded by an asterisk and followed by a line termination using the carriage return and line feed characters, for example, ***1234ABCD[CR][LF]**. This value is a 32-bit CRC of all bytes in the log, excluding the '#' or '%' identifier and the asterisk preceding the four checksum digits. See also *Description of ASCII and binary logs with short headers* on page 51.

Table 278: Inertial solution status on page 1119 shows the status values included in the INS position, velocity and attitude output logs. If the IMU is connected properly and a good status value is not being received, check the hardware setup to ensure it is properly connected. This situation can be recognized in the RAWIMU data by observing accelerometer and gyro values which are not changing with time.

Logging restriction important notice

Logging excessive amounts of high rate data can overload the system. When configuring the output for SPAN, NovAtel recommends that only one high rate (>50Hz) message be configured for output at a time. It is possible to log more than one message at high rates, but doing so could have negative impacts on the system. Also, if logging 100/125/200/400Hz data, always use the binary format and, if possible, the short header binary format (available on most INS logs).

For optimal performance, log only one high rate output at a time. These logs could be:

- Raw data for post processing
  RAWIMUXSB ONNEW
  - RAWIMU logs are not valid with the ONTIME trigger. The raw IMU observations contained in these logs are sequential changes in velocity and rotation. As such, you can only use them for navigation if they are logged at their full rate.
- Real time INS solution
  IMURATEPVA ONNEW or IMURATEPVAS ONNEW

  Other possible INS solution logs available at high rates are: INSPVASB, INSPOSSB, INSVELSB, INSATTSB

The periods available when using the ONTIME trigger are 0.005 (200 Hz), 0.01 (100 Hz), 0.02 (50 Hz), 0.05, 0.1, 0.2, 0.25, 0.5, 1, and any integer number of seconds.

5.1 Logs with INS or GNSS data

There are several logs in the system designed to output the best available solution as well as many logs that output only a specific solution type (PSR, RTK, INS, etc). The table below lists the logs that can provide either a GNSS solution or an INS solution. Most of these derive from the solution the system picks as the best solution. SPAN systems also have a secondary best solution that derives from the GNSS solution only (**BESTGNSSPOS** log (see page 1098) and **BESTGNSSVEL** log (see page 1100)). The position output from these logs is at the phase center of the antenna.

Log	Log format	GNSS/INS
BESTPOS	NovAtel	YES
BESTVEL	NovAtel	YES
BESTUTM	NovAtel	YES
BESTXYZ	NovAtel	YES
GPGGA	NMEA	YES
GPGLL	NMEA	YES
GPRMC	NMEA	YES
GPVTG	NMEA	YES

5.2 BESTGNSSPOS

Best GNSS position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the best available GNSS position (without INS) computed by the receiver. In addition, it reports several status indicators, including differential age, which is useful in predicting anomalous behaviour brought about by outages in differential corrections. A differential age of 0 indicates that no differential correction was used.

With the system operating in an RTK mode, this log reflects the latest low latency solution for up to 60 seconds after reception of the last base station observations. After this 60 second period, the position reverts to the best solution available and the degradation in accuracy is reflected in the standard deviation fields. If the system is not operating in an RTK mode, pseudorange differential solutions continue for the time specified in the **PSRDIFFTIMEOUT** command (see page 319).

BESTGNSSPOS always outputs positions at the antenna phase centre.

Message ID: 1429

Log type: Synch

Recommended input:

```
log bestgnssposa ontime 1
```

ASCII example:

```
#BESTGNSSPOSA,USB1,0,65.0,FINESTEERING,2209,487877.000,02000020,c292,16809;
SOL_COMPUTED,PPP,51.15043712234,-114.03067870773,1097.3556,-17.0001,WGS84,
0.0176,0.0123,0.0317,"TSTR",17.000,0.000,42,38,38,37,00,00,3f,37*5fea7d4b
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTGNSSPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Sol Status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	Pos Type	Position type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	Lat	Latitude (degrees)	Double	8	H+8
5	Lon	Longitude (degrees)	Double	8	H+16
6	Hgt	Height above mean sea level (metres)	Double	8	H+24

Field	Field type	Description	Format	Binary bytes	Binary offset
7	Undulation	Undulation - the relationship between the geoid and the ellipsoid (m) of the chosen datum When using a datum other than WGS84, the undulation value also includes the vertical shift due to differences between the datum in use and WGS84.	Float	4	H+32
8	Datum ID	Datum ID 61 = WGS84 63 = USER	Enum	4	H+36
9	Lat σ	Latitude standard deviation (metres)	Float	4	H+40
10	Lon σ	Longitude standard deviation (metres)	Float	4	H+44
11	Hgt σ	Height standard deviation (metres)	Float	4	H+48
12	Stn ID	Base station ID	Char[4]	4	H+52
13	Diff_age	Differential age in seconds	Float	4	H+56
14	Sol_age	Solution age in seconds	Float	4	H+60
15	#SVs	Number of satellites tracked	Uchar	1	H+64
16	#solnSVs	Number of satellite solutions used in solution	Uchar	1	H+65
17	#solnL1SVs	Number of satellites with L1/E1/B1 signals used in solution	Uchar	1	H+66
18	#solnMultiSVs	Number of satellites with multi-frequency signals used in solution	Uchar	1	H+67
19	Reserved		Uchar	1	H+68
20	ext sol stat	Extended solution status (see *Table 99: Extended solution status* on page 534)	Hex	1	H+69
21	Galileo and BeiDou sig mask	Galileo and BeiDou signals used mask (see *Table 98: Galileo and BeiDou signal-used mask* on page 533)	Hex	1	H+70
22	GPS and GLONASS sig mask	GPS and GLONASS signals used mask (see *Table 97: GPS and GLONASS signal-used mask* on page 533)	Hex	1	H+71
23	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+72
24	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.3 BESTGNSSVEL

Best available GNSS velocity data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the best available GNSS velocity information (without INS) computed by the receiver. In addition, it reports a velocity status indicator, which is useful to indicate whether or not the corresponding data is valid. The velocity measurements sometimes have a latency associated with them. The time of validity is the time tag in the log minus the latency value.

The velocity is typically computed from the average change in pseudorange over the time interval or the RTK Low Latency filter. As such, it is an average velocity based on the time difference between successive position computations and not an instantaneous velocity at the BESTGNSSVEL time tag. The velocity latency to be subtracted from the time tag is normally half the time between filter updates. Under default operation, the positioning filters are updated at a rate of 2 Hz. This translates into a velocity latency of 0.25 seconds. The latency is reduced by increasing the update rate of the positioning filter used by requesting the BESTGNSSVEL or BESTGNSSPOS messages at a rate higher than 2 Hz. For example, a logging rate of 10 Hz reduces the velocity latency to 0.005 seconds. For integration purposes, the velocity latency should be applied to the record time tag.

A valid solution with a latency of 0.0 indicates the instantaneous Doppler measurement was used to calculate velocity.

Message ID: 1430

Log type: Synch

Recommended input:

```
log bestgnssvela ontime 1
```

ASCII example:

```
#BESTGNSSVELA,USB1,0,64.0,FINESTEERING,2209,488172.000,02000020,00b0,16809;
SOL_COMPUTED,PPP,0.250,12.000,0.0025,23.890175,0.0021,0.0*f40aab04
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	BESTGNSSVEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Sol Status	Solution status, see *Table 95: Solution status* on page 530	Enum	4	H
3	Vel Type	Velocity type, see *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	Latency	A measure of the latency in the velocity time tag in seconds. It should be subtracted from the time to give improved results.	Float	4	H+8
5	Age	Differential age	Float	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
6	Hor Spd	Horizontal speed over ground, in metres per second	Double	8	H+16
7	Trk Gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees	Double	8	H+24
8	Vert Spd	Vertical speed, in metres per second, where positive values indicate increasing altitude (up) and negative values indicate decreasing altitude (down)	Double	8	H+32
9	Reserved		Float	4	H+40
10	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+44
11	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.4 CORRIMUDATA

Corrected IMU measurements

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

The **CORRIMUS** log on page 1106 was introduced in firmware version OEM 7.07.0x and is designed to replace the **CORRIMUDATA** and **CORRIMUDATAS** logs. It is recommended to upgrade to **CORRIMUS** log on page 1106 when collecting corrected IMU measurements synchronously. The **CORRIMUDATA** and **CORRIMUDATAS** logs are still available, but will eventually be phased out.

The CORRIMUDATA log contains the raw IMU data corrected for gravity, the earth's rotation and estimated sensor errors. The values in this log are incremental values, accumulated over the logging interval of CORRIMUDATA, in units of radians for the attitude rate and m/s for the accelerations. Data output is not in the IMU Body frame, but is automatically rotated into the user configured output frame (configured with the **SETINSROTATION** command (see page 1079), default Vehicle frame).

The short header format, CORRIMUDATAS, is recommended, as it is for all high data rate logs.

CORRIMUDATA can be logged with the ONTIME trigger, up to a rate of 200 Hz.

Since the CORRIMUDATA log is synchronous, if you log at a rate less than the full data rate of the IMU, the corrected IMU data is accumulated to match the requested time interval. For asynchronous full rate data, see the **IMURATECORRIMUS** log on page 1112.

To obtain the instantaneous rates of acceleration (in m/s/s) or rotation (in rad/s) from the output values of measurements per sample rate (m/s/sample and rad/sample), multiply the output values by the CORRIMUDATA logging rate in Hz.

Message ID: 812

Log type: Synch

Recommended input:

```
log corrimudatab ontime 0.01
```

Example log:

```
#CORRIMUDATAA,USB1,0,65.0,FINESTEERING,2209,488261.000,02000020,e5fc,16809;2209
,488261.000000000,-0.0000097404099474,0.0000046348926633,0.0000137198213235,
-0.0000719383196058,0.0003131269933030,0.0005105002543702*0c6740ba
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CORRIMUDATA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS week	Ulong	4	H+
3	Seconds	GNSS seconds from week start	Double	8	H+4
4	PitchRate	About x axis rotation (right-handed) (rad/sample)	Double	8	H+12
5	RollRate	About y axis rotation (right-handed) (rad/sample)	Double	8	H+20
6	YawRate	About z axis rotation (right-handed) (rad/sample)	Double	8	H+28
7	LateralAcc	INS Lateral Acceleration (along x axis) (m/s/sample)	Double	8	H+36
8	LongitudinalAcc	INS Longitudinal Acceleration (along y axis) (m/s/sample)	Double	8	H+44
9	VerticalAcc	INS Vertical Acceleration (along z axis) (m/s/sample)	Double	8	H+52
10	xxxx	32-bit CRC	Hex	4	H+56
11	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.5 CORRIMUDATAS

Short corrected IMU measurements

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

The **CORRIMUS** log on page 1106 was introduced in firmware version OEM 7.07.0x and is designed to replace the **CORRIMUDATA** and **CORRIMUDATAS** logs. It is recommended to upgrade to **CORRIMUS** log on page 1106 when collecting corrected IMU measurements synchronously. The **CORRIMUDATA** and **CORRIMUDATAS** logs are still available, but will eventually be phased out.

This log is the short header version of the **CORRIMUDATA** log (see page 1102).

To obtain the instantaneous rates of acceleration (in m/s/s) or rotation (in rad/s) from the output values of measurements per sample rate (m/s/sample and rad/sample), multiply the output values by the CORRIMUDATAS logging rate in Hz.

Message ID: 813

Log type: Synch

Recommended input:

```
log corrimudatasb ontime 0.01
```

Example log:

```
%CORRIMUDATASA,2209,488331.000;2209,488331.000000000,-0.0000016434879909,
0.0000053888857361,-0.0000077180775912,-0.0001338946509402,
-0.0013131748634920,-0.0002721905080061*bd5ba919
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CORRIMUDATAS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS week	Ulong	4	H+
3	Seconds	GNSS seconds from week start	Double	8	H+4
4	PitchRate	About x-axis rotation (right-handed) (rad/sample)	Double	8	H+12
5	RollRate	About y-axis rotation (right-handed) (rad/sample)	Double	8	H+20
6	YawRate	About z-axis rotation (right-handed) (rad/sample)	Double	8	H+28
7	LateralAcc	INS Lateral Acceleration (along x-axis) (m/s/sample)	Double	8	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
8	LongitudinalAcc	INS Longitudinal Acceleration (along y-axis) (m/s/sample)	Double	8	H+44
9	VerticalAcc	INS Vertical Acceleration (along z-axis) (m/s/sample)	Double	8	H+52
10	xxxx	32-bit CRC	Hex	4	H+56
11	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.6 CORRIMUS

Corrected IMU measurements

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

The **CORRIMUS** log replaces the **CORRIMUDATA** and **CORRIMUDATAS** logs.

The **CORRIMUS** log contains the raw IMU data corrected for gravity, the earth's rotation and estimated sensor errors. The values in this log are incremental values, accumulated over the logging interval of **CORRIMUS**, in units of radians for the attitude rate and m/s for the accelerations. Data output is not in the IMU Body frame, but is automatically rotated into the user configured output frame (configured with the **SETINSROTATION** command (see page 1079), default is Vehicle frame).

The **CORRIMUS** log uses the short header format and can be used for high data rate logs. **CORRIMUS** can be logged with the ONTIME trigger, up to a rate of 200 Hz.

Since the **CORRIMUS** log is synchronous, if you log at a rate less than the full data rate of the IMU, the corrected IMU data is accumulated to match the requested time interval. For asynchronous full rate data, see the **IMURATECORRIMUS** log on page 1112.

To obtain the instantaneous rates of acceleration (in m/s/s) or rotation (in rad/s) from the output values of accumulated delta measurements (m/s and rad); multiply the output values by: **IMUDataRate (Hz) / IMUDataCount** (Field 2).

The number of samples included in each log instance may vary log by log depending on the relative difference between IMU data period and log request period. This is due to asynchronous IMU data being accumulated into a synchronous log.

Message ID: 2264

Log type: Synch

Recommended input:

```
log corrimusb ontime 0.01
```

Example log:

```
%CORRIMUSA,2209,488407.000;112,-0.0000242405098038,0.0000287475625144,
-0.0000016866224967,0.0015291995267506,-0.0013533739686903,-0.0018536657202395
,8.168,0*2135fe3d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	CORRIMUS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	–	H	0
2	IMUDataCount	Count of the number of IMU Samples used in each log output accumulation.	Ulong	4	H
3	PitchRate	About x-axis rotation (right-handed) (rad/sample)	Double	8	H+4
4	RollRate	About y-axis rotation (right-handed) (rad/sample)	Double	8	H+12
5	YawRate	About z-axis rotation (right-handed) (rad/sample)	Double	8	H+20
6	LateralAcc	INS Lateral Acceleration (along x-axis) (m/s/sample)	Double	8	H+28
7	LongitudinalAcc	INS Longitudinal Acceleration (along y-axis) (m/s/sample)	Double	8	H+36
8	VerticalAcc	INS Vertical Acceleration (along z-axis) (m/s/sample)	Double	8	H+44
9	Reserved		Float	4	H+52
10	Reserved		Ulong	4	H+56
11	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+60
12	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

5.7 DELAYEDHEAVE

Delayed Heave filter

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This log contains the value of the delayed heave filter. The delayed heave value differs from the heave value in that delayed heave uses forward and backward smoothing, while heave uses backward smoothing only. This heave solution is calculated at the location entered in the **SETINSTRANSLATION USER** command.

The **DELAYEDHEAVE** log will not contain valid data until the delayed heave window conditions have been met. You must have an inertial solution to use this log.

Message ID: 1709

Log type: Synch

Recommended input:

```
log delayedheaveb ontime 0.1
```

ASCII example:

```
#DELAYEDHEAVEA,USB1,0,59.5,FINESTEERING,2209,494152.000,02000020,27a3,16809;
0.000000000,1.000000000*01dbc61c
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	DELAYEDHEAVE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Delayed Heave	Delayed heave value	Double	8	H
3	Std. Dev.	Standard deviation of the delayed heave value	Double	8	H+8
4	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+16
5	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.8 GIMBALLEDPVA

Display gimballed position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

Use the GIMBALLEDPVA log to view the re-calculated position, velocity and attitude of the gimbal null position whenever a new **INPUTGIMBALANGLE** command (see page 1051) is received.

This log should only be requested with the ONCHANGED or ONNEW trigger.

This log provides the position information in the user datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 1321

Log type: Asynch

Recommended input:

```
log gimballedpvaa onnew
```

ASCII example:

```
#GIMBALLEDPVAA,USB1,0,58.0,FINESTEERING,2209,492397.728,02000020,65c2,16809;
2209,492397.728000000,51.15043715731,-114.03067884053,1080.3608,-0.0013,0.0007,
0.0012,-0.317910813,0.298591270,157.994258109,INS_SOLUTION_GOOD*a8ca2418
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	GIMBALLEDPVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GPS week	Ulong	4	H
3	Seconds	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude [degrees]	Double	8	H+20
6	Height	Ellipsoidal height [m]	Double	8	H+28
7	North Velocity	Velocity in a northerly direction	Double	8	H+36
8	East Velocity	Velocity in an easterly direction	Double	8	H+44
9	Up Velocity	Velocity in an upward direction	Double	8	H+52

Field	Field type	Description	Format	Binary bytes	Binary offset
10	Roll	Right-handed rotation from local level around the y-axis in degrees	Double	8	H+60
11	Pitch	Right-handed rotation from local level around the x-axis in degrees	Double	8	H+68
12	Azimuth	Right-handed rotation from local level around the z-axis in degrees	Double	8	H+76
13	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
14	xxxx	32-bit CRC	Hex	4	H+88
15	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.9 HEAVE

Heave filter log

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This log provides vessel heave computed by the integrated heave filter. Refer also to information in the **SETHEAVEWINDOW** command on page 1071. This log is asynchronous, but is available at approximately 10 Hz. This heave solution is calculated at the location entered in the **SETINSTRANSLATION USER** command.



You must have an inertial solution to use this log.

Message ID: 1382

Log type: Asynch

Recommended input:

```
log heaveb onnew
```

Example:

```
#HEAVEA,USB1,0,65.0,FINESTEERING,2209,488914.441,02000020,0fc8,16809;
2209,488914.440742000,0.016366779*511a7948
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	HEAVE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Heave	Instantaneous heave in metres	Double	8	H+12
5	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+20
6	[CR][LF]	Sentence Terminator (ASCII Only)	-	-	-

5.10 IMURATECORRIMUS

Asynchronous corrected IMU data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides the same information as the **CORRIMUS** log (see page 1106), but is available asynchronously at the full rate of the IMU.

Using this log consumes significant system resources and should only be used by experienced users.

However, using this log consumes less resources than logging the synchronous CORRIMUDATAS log at the same rate.

To obtain the instantaneous rates of acceleration (in m/s/s) or rotation (in rad/s) from the output values of measurements per sample rate (m/s/sample and rad/sample), multiply the output values by the IMU data rate in Hz.

This log should only be requested with the ONNEW trigger.

Message ID: 1362

Log type: Asynch

Recommended input:

```
log imuratecorrimusb onnew
```

Example log:

```
%IMURATECORRIMUSA,2209,489768.026;2209,489768.026275000,-0.000000298,
-0.000000690,-0.000001034,-0.000043357,0.000009959,-0.000012101*36ef5bdd
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	IMURATECORRIMUS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS week	Ulong	4	H+
3	Seconds	GNSS seconds from week start	Double	8	H+4
4	PitchRate	About x axis rotation (rad/sample)	Double	8	H+12
5	RollRate	About y axis rotation (rad/sample)	Double	8	H+20
6	YawRate	About z axis rotation (right-handed) (rad/sample)	Double	8	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
7	LateralAcc	INS Lateral Acceleration (along x-axis) (m/s/sample)	Double	8	H+36
8	LongitudinalAcc	INS Longitudinal Acceleration (along y-axis) (m/s/sample)	Double	8	H+44
9	VerticalAcc	INS Vertical Acceleration (along z-axis) (m/s/sample)	Double	8	H+52
10	xxxx	32-bit CRC	Hex	4	H+60
11	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.11 IMURATEPVA

Asynchronous INS position, velocity and attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides the same information as the **INSPVA** log (see page 1138), but is available asynchronously at the full rate of the IMU.

Using this log consumes significant system resources and should only be used by experienced users.

However, using this log consumes less resources than logging the synchronous INSPVA log at the same rate.

This log should only be requested with the ONNEW trigger.

This log provides the position information in the user datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 1778

Log type: Asynch

Recommended input:

```
log imuratepvaa onnew
```

ASCII example:

```
#IMURATEPVAA,USB1,0,62.5,FINESTEERING,2209,489768.026,02000020,81ba,16809;
2209,489768.026275000,51.15043706787,-114.03067862997,1080.3569,-0.0021,0.0003,
-0.0009,-0.314843800,0.320501757,158.167631576,INS_SOLUTION_GOOD*d377f22f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	IMURATEPVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude [degrees]	Double	8	H+20
6	Height	Ellipsoidal Height [m]	Double	8	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
7	North Velocity	Velocity in a northerly direction (a negative value implies a southerly direction) [m/s]	Double	8	H+36
8	East Velocity	Velocity in an easterly direction (a negative value implies a westerly direction) [m/s]	Double	8	H+44
9	Up Velocity	Velocity in an up direction [m/s]	Double	8	H+52
10	Roll	Right-handed rotation from local level around y-axis in degrees	Double	8	H+60
11	Pitch	Right-handed rotation from local level around x-axis in degrees	Double	8	H+68
12	Azimuth	Left-handed rotation around z-axis in degrees clockwise from North This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+76
13	Status	INS Status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
14	xxxx	32-bit CRC	Hex	4	H+88
15	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.12 IMURATEPVAS

Asynchronous INS position, velocity and attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides the same information as the **INSPVAS** log (see page 1142), but is available asynchronously at the full rate of the IMU.

Using this log consumes significant system resources and should only be used by experienced users.

However, using this log consumes less resources than logging the synchronous INSPVAS log at the same rate.

This log should only be requested with the ONNEW trigger.

This log provides the position information in the user datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 1305

Log type: Asynch

Recommended input:

```
log imuratepvasa onnew
```

ASCII example:

```
%IMURATEPVASA,2209,489768.026;2209,489768.026275000,51.15043706787,
-114.03067862997,1080.3569,-0.0021,0.0003,-0.0009,-0.314843800
,0.320501757,158.167631576,INS_SOLUTION_GOOD*bf2d3f18
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	IMURATEPVAS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude [degrees]	Double	8	H+20
6	Height	Ellipsoidal Height [m]	Double	8	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
7	North Velocity	Velocity in a northerly direction (a negative value implies a southerly direction) [m/s]	Double	8	H+36
8	East Velocity	Velocity in an easterly direction (a negative value implies a westerly direction) [m/s]	Double	8	H+44
9	Up Velocity	Velocity in an up direction [m/s]	Double	8	H+52
10	Roll	Right-handed rotation from local level around y-axis in degrees	Double	8	H+60
11	Pitch	Right-handed rotation from local level around x-axis in degrees	Double	8	H+68
12	Azimuth	Left-handed rotation around z-axis in degrees clockwise from North	Double	8	H+76
13	Status	INS Status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
14	xxxx	32-bit CRC	Hex	4	H+88
15	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.13 INSATT

INS attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the most recent attitude measurements computed by the SPAN filter. This attitude definition may not correspond to other definitions of the terms pitch, roll and azimuth. By default, the output attitude is with respect to the vehicle frame. If the attitude output is desired with respect to another frame of reference, use the **SETINSROTATION USER** command (see the **SETINSROTATION** command on page 1079) to configure the user output frame offset rotation.

Message ID: 263

Log type: Synch

Recommended input:

```
log insatta ontime 1
```

ASCII example:

```
#INSATTA,USB1,0,65.5,FINESTEERING,2209,489963.000,02000020,c6a7,16809;2209,4899
63.000000000,-0.325157913,0.303361140,158.066428095,INS_SOLUTION_GOOD*13a0c733
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSATT header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Roll	Right-handed rotation from local level around y-axis in degrees.	Double	8	H+12
5	Pitch	Right-handed rotation from local level around x-axis in degrees.	Double	8	H+20
6	Azimuth	Left-handed rotation around z-axis in degrees clockwise from North. This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on the next page.	Enum		H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex		H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 278: Inertial solution status

Binary	ASCII	Description
0	INS_INACTIVE	IMU logs are present, but the alignment routine has not started; INS is inactive.
1	INS_ALIGNING	INS is in alignment mode.
2	INS_HIGH_VARIANCE	The INS solution uncertainty contains outliers and the solution may be outside specifications.[1] The solution is still valid but you should monitor the solution uncertainty in the **INSSTDEV** log. It may be encountered during times when GNSS is absent or poor.
3	INS_SOLUTION_GOOD	The INS filter is in navigation mode and the INS solution is good.
6	INS_SOLUTION_FREE	The INS Filter is in navigation mode and the GNSS solution is suspected to be in error. The inertial filter will report this status when there are no available updates (GNSS or other) being accepted and used.
7	INS_ALIGNMENT_ COMPLETE	The INS filter is in navigation mode, but not enough vehicle dynamics have been experienced for the system to be within specifications.
8	DETERMINING_ ORIENTATION	INS is determining the IMU axis aligned with gravity.
9	WAITING_INITIALPOS	The INS filter has determined the IMU orientation and is awaiting an initial position estimate to begin the alignment process.
10	WAITING_AZIMUTH	The INS filer has orientation, initial biases, initial position and valid roll/pitch estimated. Will not proceed until initial azimuth is entered.
11	INITIALIZING_BIASES	The INS filter is estimating initial biases during the first 10 seconds of stationary data.
12	MOTION_DETECT	The INS filter has not completely aligned, but has detected motion.
14	WAITING_ ALIGNMENTORIENTATION	The INS filter is waiting to start alignment until the current Vehicle Frame roll and pitch estimates are within the configured threshold of the expected orientation (set by the **SETALIGNMENTORIENTATION** command). **Note**: This requires an accurate RBV rotation to be configured, see the **SETINSROTATION** command.

1. The solution uncertainty threshold levels can be adjusted using the **INSTHRESHOLDS** command.

5.14 INSATTQS

Short INS quaternion attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the attitude from the INSATT log, but the rotation from local level is given as a Quaternion rather than Euler Angles. The quaternion takes the form:

$$\boldsymbol{q}_l^b = [w \quad x \quad y \quad z]^T$$

The element w is the rotational component, defining the magnitude of the rotation to be performed. The elements x, y, and z are the vector portion of the rotation, which define the axis about which the rotation is to be performed.

If θ is the rotational angle, and the axis of rotation is defined by the vector $\boldsymbol{v} = [v_x \; v_y \; v_z]^T$, then the elements of the quaternion can be written as:

$$w = \cos\frac{\theta}{2}$$

$$x = v_x \sin\frac{\theta}{2}$$

$$y = v_y \sin\frac{\theta}{2}$$

$$z = v_z \sin\frac{\theta}{2}$$

Message ID: 2118

Log type: Synch

Recommended input:

```
log insattqsa ontime 1
```

ASCII example:

```
%INSATTQSA,2209,490002.000;2209,490002.000000000,0.190321570,-0.002193610,
-0.003030327,-0.981714676,INS_SOLUTION_GOOD*a67493fa
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSATTQS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Quaternion w	Quaternion rotation from local level, w component	Double	8	H+12
5	Quaternion x	Quaternion rotation from local level, x component	Double	8	H+20
6	Quaternion y	Quaternion rotation from local level, y component	Double	8	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
7	Quaternion z	Quaternion rotation from local level, z component	Double	8	H+36
8	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+44
9	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+48
10	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.15 INSATTS

Short INS attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **INSATT** log (see page 1118).

Message ID: 319

Log type: Synch

Recommended input:

```
log insattsa ontime 1
```

ASCII example:

```
%INSATTSA,2209,490065.000;2209,490065.000000000,-0.316596979,0.329117050,
158.038475648,INS_SOLUTION_GOOD*85ec8455
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSATTS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Roll	Right-handed rotation from local level around y-axis in degrees	Double	8	H+12
5	Pitch	Right-handed rotation from local level around x-axis in degrees	Double	8	H+20
6	Azimuth	Left-handed rotation around z-axis in degrees clockwise from North This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.16 INSATTX

Inertial attitude – extended

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log includes the information from the **INSATT** log (see page 1118), as well as information about the attitude standard deviation. The position type and solution status fields indicate whether or not the corresponding data is valid.

The INSATTX log is a large log and is not recommend for high rate logging.

If you want to use high rate logging, log the **INSATTS** log at a high rate and the **INSSTDEVS** log ontime 1.

Message ID: 1457

Log type: Synch

Recommended input:

```
log insattxa ontime 1
```

ASCII example:

```
#INSATTXA,USB1,0,66.0,FINESTEERING,2209,490101.000,02000020,5d25,16809;
INS_SOLUTION_GOOD,INS_PPP,-0.312617220,0.320251425,158.010043982,0.0297,
0.0297,0.0580,13001041,0*6557406d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSATTX header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	INS Status	Solution status See *Table 278: Inertial solution status* on page 1119	Enum	4	H
3	Pos Type	Position type See *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	Roll	Roll in Local Level (degrees)	Double	8	H+8
5	Pitch	Pitch in Local Level (degrees)	Double	8	H+16
6	Azimuth	Azimuth in Local Level (degrees) This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+24
7	Roll σ	Roll standard deviation (degrees)	Float	4	H+32
8	Pitch σ	Pitch standard deviation (degrees)	Float	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
9	Azimuth σ	Azimuth standard deviation (degrees)	Float	4	H+40
10	Ext sol stat	Extended solution status See *Table 279: Extended solution status* below	Hex	4	H+44
11	Time Since Update	Elapsed time since the last ZUPT or position update (seconds)	Ushort	2	H+48
12	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+50
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 279: Extended solution status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Position update	0 = Unused 1 = Used
	1	0x00000002	Phase update	0 = Unused 1 = Used
	2	0x00000004	Zero velocity update	0 = Unused 1 = Used
	3	0x00000008	Wheel sensor update	0 = Unused 1 = Used
N1	4	0x00000010	ALIGN (heading) update	0 = Unused 1 = Used
	5	0x00000020	External position update	0 = Unused 1 = Used
	6	0x00000040	INS solution convergence flag	0 = Not converged 1 = Converged
	7	0x00000080	Doppler update	0 = Unused 1 = Used
N2	8	0x00000100	Pseudorange update	0 = Unused 1 = Used
	9	0x00000200	Velocity update	0 = Unused 1 = Used
	10	0x00000400	Reserved	
	11	0x00000800	Dead reckoning update	0 = Unused 1 = Used

Nibble	Bit	Mask	Description	Range value
N3	12	0x00001000	Phase wind up update	0 = Unused 1 = Used
	13	0x00002000	Course over ground update	0 = Unused 1 = Used
	14	0x00004000	External velocity update	0 = Unused 1 = Used
	15	0x00008000	External attitude update	0 = Unused 1 = Used
N4	16	0x00010000	Reserved	
	17	0x00020000	Reserved	
	18	0x00040000	Reserved	
	19	0x00080000	Reserved	
N5	20	0x00100000	Reserved	
	21	0x00200000	Reserved	
	22	0x00400000	Secondary INS solution	0 = Unused 1 = Used
	23	0x00800000	Reserved	
N6	24	0x01000000	Turn on biases estimated	0 = Static turn-on biases not estimated (starting from zero) 1 = Static turn-on biases estimated
	25	0x02000000	Alignment direction verified	0 = Not verified / Not applicable 1 = Verified Alignment direction verification only occurs for RAIL, AGRICULTURE and LAND INS Profiles performing either a NVM Seed and Kinematic Alignment Type.
	26	0x04000000	Alignment Indication 1	0 = Not set, 1 = Set Refer to *Table 280: Alignment indication* on the next page
	27	0x08000000	Alignment Indication 2	0 = Not set, 1 = Set Refer to *Table 280: Alignment indication* on the next page
N7	28	0x10000000	Alignment Indication 3	0 = Not set, 1 = Set Refer to *Table 280: Alignment indication* on the next page
	29	0x20000000	NVM Seed Indication 1	0 = Not set, 1 = Set Refer to *Table 281: NVM seed indication* on the next page
	30	0x40000000	NVM Seed Indication 2	0 = Not set, 1 = Set Refer to *Table 281: NVM seed indication* on the next page
	31	0x80000000	NVM Seed Indication 3	0 = Not set, 1 = Set Refer to *Table 281: NVM seed indication* on the next page

Table 280: Alignment indication

Bits 28-26 values[1]	Hex value	Completed alignment type
000	0x00	Incomplete Alignment
001	0x01	Static
010	0x02	Kinematic
011	0x03	Dual Antenna
100	0x04	User Command
101	0x05	NVM Seed

Table 281: NVM seed indication

Bit 31-29 values[2]	Hex value	NVM seed type
001	0x01	INS Seed in non-volatile memory is invalid
010	0x02	INS Seed has failed validation and has been discarded
011	0x03	INS Seed is pending validation
100	0x04	INS Seed alignment data has successfully been injected

1. The values from left to right are Bit 28, Bit 27 and Bit 26.

2. The values from left to right are Bit 31, Bit 30 and Bit 29.

5.17 INSCALSTATUS

Offset calibration status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log reports the status and estimated values of the currently running offset calibration.

Message ID: 1961

Log type: Asynch

Abbreviated ASCII syntax:

```
log inscalstatus onchanged
```

ASCII example:

```
#INSCALSTATUSA,USB1,0,51.5,FINESTEERING,2209,494041.015,02010020,c0db,16809;
RBV,0.0000,0.0000,-0.0000,45.0000,45.0000,45.0000,INSUFFICIENT_SPEED,0*62a2839c
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSCALSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Offset Type	Type of offset (see *Table 282: Offset type* on the next page).	Enum	4	H
3	X axis offset	IMU body frame X-axis offset (metres or degrees)	Float	4	H+4
4	Y axis offset	IMU body frame Y-axis offset (metres or degrees)	Float	4	H+8
5	Z axis offset	IMU body frame Z-axis offset (metres or degrees)	Float	4	H+12
6	X uncertainty	IMU body frame X-axis offset uncertainty (metres or degrees)	Float	4	H+16
7	Y uncertainty	IMU body frame Y-axis offset uncertainty (metres or degrees)	Float	4	H+20
8	Z uncertainty	IMU body frame Z-axis offset uncertainty (metres or degrees)	Float	4	H+24
9	Source Status	Source from which offset values originate (see *Table 283: Source status* on the next page).	Enum	4	H+28
10	Multi-line Calibration Count	Counter for number of completed calibrations cumulatively averaged.	Ulong	4	H+32
11	xxxx	32-bit CRC (ASCII and Binary only).	Hex	4	H+36
12	[CR][LF]	Sentence terminator (ASCII only).	-	-	-

Units for the axis offset and uncertainty values (fields 3-8) are in metres for translational offset components and degrees for rotational offset components.

Table 282: Offset type

Binary	ASCII	Description
1	ANT1	Primary IMU to antenna lever arm
8	ALIGN	Align offset
11	RBV	IMU body to vehicle offset

Table 283: Source status

Binary	ASCII	Description
1	FROM_NVM	Offset values originate from saved parameters in NVM
2	CALIBRATING	Offset values originate from a currently running calibration process
3	CALIBRATED	Offset values originate from a completed calibration process
4	FROM_ COMMAND	Offset values originate from a user command
5	Reserved	
6	FROM_DUAL_ ANT	Offset values originate from a dual antenna Align solution
7	INS_ CONVERGING	Offset values originate from initial input values. Calibration process on hold until INS solution is converged.
8	INSUFFICIENT_ SPEED	Offset values originate from a currently running calibration process. Further estimation on hold due to insufficient speed.
9	HIGH_ROTATION	Offset values originate from a currently running calibration process. Further estimation on hold due to high vehicle rotations.

5.18 INSCONFIG

Determine required settings for post-processing or system analysis

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the single message required to determine all required settings for post-processing or system analysis. This log is asynchronous and published for any change to the included fields. It is intended to be recorded occasionally though it could be updated frequently at system startup. The **INSCONFIG** log may also be logged synchronously with the ONTIME trigger, but this log should **NOT** be requested at a high rate (limited to 1 Hz).

Message ID: 1945

Log type: Asynch

Recommended input:

```
log insconfig onchanged
```

ASCII example:

```
#INSCONFIGA,USB1,0,66.5,FINESTEERING,2209,338183.000,02000020,bba4,16809;
EPSON_G320,5,50,20,DEFAULT,7fd1bf,AUTOMATIC,ROVER,FALSE,0,0,0,17,0,0,0,0,0,0,0,
1,RBV,IMUBODY,0.0000,0.0000,0.0000,3.0000,3.0000,3.0000,FROM_COMMAND*996d7655
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSCONFIG header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	IMU Type	IMU type. See *Table 271: IMU type* on page 1042.	Enum	4	H
3	Mapping	Mapping / Orientation	Uchar	1	H+4
4	Initial Alignment Velocity	Minimum Alignment Velocity entered by the user (see the **SETALIGNMENTVEL** command on page 1070). Velocity (m/s) is scaled by 10 for 10 cm/s precision	Uchar	1	H+5
5	Heave Window	Length of the heave window in seconds (if set using the **SETHEAVEWINDOW** command on page 1071)	Ushort	2	H+6
6	Profile	Profile setting (see the **SETINSPROFILE** command on page 1077)	Enum	4	H+8
7	INS Enabled Updates	Enabled INS updates (see *Table 289: INS update values* on page 1158)	Hex	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
8	Alignment Mode	Alignment mode configured on the system (see the **ALIGNMENTMODE** command on page 1039)	Enum	4	H+16
9	Relative INS Output Frame	The user specified output frame of the Relative INS Vector (see **SETRELINSOUTPUTFRAME** command on page 1089) If not specified, the default value appears.	Enum	4	H+20
10	Relative INS Output Direction	The User specified Output direction of the Relative INS Vector (From or To Base-Rover) (see the **SETRELINSOUTPUTFRAME** command on page 1089). If not specified, the default value appears. TRUE if From Base, FALSE (Default) if From Rover	Bool	4	H+24
11	INS Receiver Status	Lower byte- INS Reset. Corresponds numerically to the INS Reset as described by the INSResetEnum Second byte- = 0x01 if an IMU Communication Error (Receiver status bit 17). = 0x00 otherwise. Other values are reserved for future use. Upper 2 bytes - reserved.	Hex	4	H+28
12	INS Seed Enabled	INS Seed Enable setting (see the **INSSEED** command on page 1060) Enabled = 1, Disabled = 0	Uchar	1	H+32
13	INS Seed Validation	INS Seed Validation setting (see *Table 284: INS Seed injection options mask* on page 1132)	Uchar	1	H+33
14	Reserved 1		N/A	2	H+34
15	Reserved 2		N/A	4	H+36
16	Reserved 3		N/A	4	H+40
17	Reserved 4		N/A	4	H+44
18	Reserved 5		N/A	4	H+48
19	Reserved 6		N/A	4	H+52
20	Reserved 7		N/A	4	H+56
21	Number of Translations	Number of translation entries to follow	Ulong	4	H+60
22	Translation	Translation to follow (see *Table 276: Translation offset types* on page 1084)	Enum	4	variable

Field	Field type	Description	Format	Binary bytes	Binary offset
23	Frame	Frame of translation (IMUBODY or VEHICLE)	Enum	4	variable
24	X Offset	X Offset	Float	4	variable
25	Y Offset	Y Offset	Float	4	variable
26	Z Offset	Z Offset	Float	4	variable
27	X Uncertainty	X Uncertainty	Float	4	variable
28	Y Uncertainty	Y Uncertainty	Float	4	variable
29	Z Uncertainty	Z Uncertainty	Float	4	variable
30	Translation Source	Source of translation (see *Table 283: Source status* on page 1128)	Enum	4	variable
	Next Translation				
variable	Number of Rotations	Number of rotation entries to follow	Ulong	4	variable
variable	Rotation	Rotation to follow (see *Table 275: Rotational offset types* on page 1080)	Enum	4	variable
variable	Frame	Frame of rotation (IMUBODY or VEHICLE)	Enum	4	variable
variable	X Rotation	X Rotation	Float	4	variable
variable	Y Rotation	Y Rotation	Float	4	variable
variable	Z Rotation	Z Rotation	Float	4	variable
variable	X Rotation Std Dev	X Rotation offset standard deviation (degrees)	Float	4	variable
variable	Y Rotation STD Dev	Y Rotation offset standard deviation (degrees)	Float	4	variable
variable	Z Rotation STD Dev	Z Rotation offset standard deviation (degrees)	Float	4	variable
variable	Rotation Source	Source of rotation (see *Table 283: Source status* on page 1128)	Enum	4	variable
	Next Rotation				
variable	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 284: INS Seed injection options mask

Binary value	Azimuth Option ASCII value	Error Model Option ASCII value	Description
0	VALIDATE	INJECT	Inject azimuth with validation, inject IMU biases
1	INJECT	INJECT	Inject azimuth without validation, inject IMU biases
2	IGNORE	INJECT	Do not inject azimuth, inject IMU biases
3	VALIDATE	IGNORE	Inject azimuth with validation, do not inject IMU biases
4	INJECT	IGNORE	Inject azimuth without validation, do not inject IMU biases
5	IGNORE	IGNORE	Do not inject azimuth, do not inject IMU biases

5.19 INSDATUMINFO

Datum information for INS position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7, SMART2**

This log reports the datum and co-ordinate epoch of the solution for all INS logs with position output (**INSPVA**, **INSPVAS**, **INSPVAX**, **INSPVACMP**, **INSPOS**, **INSPOSS**, **INSPOSX**, **MARKxPVA** and **TAGGEDMARKxPVA**).

Message ID: 2384

Log type: Asynch

Recommended input:

```
log insdatuminfoa onchanged
```

ASCII example:

```
#INSDATUMINFOA,USB1,0,66.0,FINESTEERING,2209,490200.000,02000020,f6f5,16809;
"ITRF2014",1165,2022.363,GOOD,0.000000000,0*21d0a220
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSDATUMINFO header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	datum	Datum of the position being output by the INS position logs.	Char[32]	variable	H
3	epsg_ code	EPSG code of the datum.	Ulong	4	variable
4	epoch	Co-ordinate epoch (decimal year). Example: 2011.00 = Jan 1, 2011 2011.19 = Mar 11, 2011	Double	8	variable
5	status	Transformation status. See *Table 94: Transformation status* on page 524.	Enum	4	variable
6	reserved	Reserved for future use	Float	4	variable
7	reserved	Reserved for future use	Ulong	4	variable
8	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	variable
9	[CR][LF]	Sentence terminator (ASCII only)	–	–	–

5.20 INSPOS

INS position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the most recent position measurements in WGS84 coordinates and includes an INS status indicator. The log reports the position at the IMU centre, unless the **SETINSTRANSLATION USER** command was issued. See the **SETINSTRANSLATION** command on page 1082.



This log provides the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 265

Log type: Synch

Recommended input:

```
log insposa ontime 1
```

ASCII example:

```
#INSPOSA,USB1,0,66.5,FINESTEERING,2209,490404.000,02000020,5b52,16809;2209,
490404.000000000,51.15043709813,-114.03067863568,1080.3587,INS_SOLUTION_GOOD
*18ee6937
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSPOS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude[degrees]	Double	8	H+20
6	Height	Ellipsoidal Height [m]	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.21 INSPOSS

Short INS position

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **INSPOS** log (see page 1134).

This log provides the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 321

Log type: Synch

Recommended input:

```
log inspossa ontime 1
```

ASCII example:

```
%INSPOSSA,2209,490447.000;2209,490447.000000000,51.15043708257,
-114.03067868674,1080.3587,INS_SOLUTION_GOOD*94c38497
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSPOSS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude [degrees]	Double	8	H+20
6	Height	Ellipsoidal Height [m]	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.22 INSPOSX

Inertial position – extended

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log includes the information from the INSPOS log, as well as information about the position standard deviation. The position type and solution status fields indicate whether or not the corresponding data is valid.

The INSPOSX log is a large log and is not recommend for high rate logging.

If you want to use high rate logging, log the **INSPOSS** log at a high rate and the **INSSTDEVS** log ontime 1.

This log provides the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 1459

Log type: Synch

Recommended input:

```
log insposxa ontime 1
```

ASCII example:

```
#INSPOSXA,USB1,0,67.5,FINESTEERING,2209,490485.000,02000020,7e79,16809;
INS_SOLUTION_GOOD,INS_PPP,51.15043706246,-114.03067867866,1097.3569,
-17.0001,0.1819,0.1819,0.1812,13000045,0*2b90352c
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSPOSX header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	INS Status	Solution status See *Table 278: Inertial solution status* on page 1119	Enum	4	H
3	Pos Type	Position type See *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	Lat	Latitude	Double	8	H+8
5	Long	Longitude	Double	8	H+16
6	Height	Height above sea level (m)	Double	8	H+24
7	Undulation	Undulation (m)	Float	4	H+32
8	Lat σ	Latitude standard deviation	Float	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
9	Long σ	Longitude standard deviation	Float	4	H+34
10	Height σ	Height standard deviation	Float	4	H+44
11	Ext sol stat	Extended solution status See *Table 279: Extended solution status* on page 1124	Hex	4	H+48
12	Time Since Update	Elapsed time since the last ZUPT or position update (seconds)	Ushort	2	H+52
13	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+54
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

The INS standard deviation values reported by the SPAN filter are an estimate of the Inertial filter solution quality. In lower accuracy GNSS position modes, such as SINGLE or WAAS (see *Table 96: Position or velocity type* on page 531), the position standard deviation values can appear to become optimistic compared with the absolute GNSS accuracy. This is due to the INS filter's ability to smooth short term noise in the GNSS solution, although the overall position error envelope still reflects the GNSS accuracy. Therefore, if the desired application requires absolute GNSS position accuracy, it is recommended to also monitor GNSS position messages such as BESTGNSSPOS (see **BESTGNSSPOS** log on page 1098).

5.23 INSPVA

INS position, velocity and attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log allows INS position, velocity and attitude, with respect to the SPAN frame, to be collected in one log, instead of using three separate logs. Refer to the **INSATT** log (see page 1118) for an explanation of how the SPAN frame may differ from the IMU enclosure frame.



This log provides the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 507

Log type: Synch

Recommended input:

```
log inspvaa ontime 1
```

ASCII example:

```
#INSPVAA,USB1,0,67.5,FINESTEERING,2209,490558.000,02000020,18bc,16809;2209,
490558.000000000,51.15043714042,-114.03067871718,1080.3548,0.0051,-0.0014,
-0.0012,-0.296402993,0.311887972,157.992156267,INS_SOLUTION_GOOD*cc698020
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSPVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude [degrees]	Double	8	H+20
6	Height	Ellipsoidal Height [m]	Double	8	H+28
7	North Velocity	Velocity in a northerly direction (a negative value implies a southerly direction) [m/s]	Double	8	H+36
8	East Velocity	Velocity in an easterly direction (a negative value implies a westerly direction) [m/s]	Double	8	H+44
9	Up Velocity	Velocity in an up direction [m/s]	Double	8	H+52
10	Roll	Right-handed rotation from local level around y-axis in degrees	Double	8	H+60

Field	Field type	Description	Format	Binary bytes	Binary offset
11	Pitch	Right-handed rotation from local level around x-axis in degrees	Double	8	H+68
12	Azimuth	Left-handed rotation around z-axis in degrees clockwise from North This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+76
13	Status	INS Status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
14	xxxx	32-bit CRC	Hex	4	H+88
15	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.24 INSPVACMP

Compressed version of the INSPVA log for CAN

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the **INSPVA** log (see page 1138) information compressed as a NMEA 2000 fast packet message for CAN output. The PGN of this message is configured using the **PGNCONFIG** command on page 290. The information in the table below is the data portion of the INSPVACMP NMEA 2000 message. Refer to the *NATIONAL MARINE ELECTRONICS ASSOCIATION (NMEA) NMEA2000(r) rev 2.0 - January/2013* document for full details on this message output and the NMEA 2000 fast packet protocol.

Message ID: 1889

Log type: Synch

Abbreviated ASCII syntax:

```
LOG CCOM1 INSPVACMP ONTIME 1
```

Field	Field type	Description	Format	Binary bytes	Units	Scale factor
1	Message Time	Seconds from week start	Ulong	4	seconds	0.001
2	INS Status	INS solution status (see *Table 278: Inertial solution status* on page 1119)	Uchar	1	N/A	N/A
3	GNSS Position Type	GNSS position type (see *Table 96: Position or velocity type* on page 531)	Uchar	1	N/A	N/A
4	Latitude	Latitude (WGS84)	5 byte Long	5	degrees	$180/2^{39}$
5	Longitude	Longitude (WGS84)	5 byte Long	5	degrees	$180/2^{39}$
6	Height	Ellipsoidal Height (WGS84)	Long	4	metres	0.0001
7	North Velocity	Velocity in a northerly direction (a negative value implies a southerly direction)	Short	2	m/s	0.002
8	East Velocity	Velocity in an easterly direction (a negative value implies a westerly direction)	Short	2	m/s	0.002
9	Up Velocity	Velocity in an up direction	Short	2	m/s	0.002
10	Roll	Right-handed rotation from local level around y axis	Short	2	degrees	0.01
11	Pitch	Right-handed rotation from local level around x axis	Short	2	degrees	0.01

Field	Field type	Description	Format	Binary bytes	Units	Scale factor
12	Azimuth	Left-handed rotation around z-axis clockwise from North This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Ushort	2	degrees	0.01
13	Azimuth Rate	Rate of change of the Azimuth	Short	2	degrees/s	0.01

5.25 INSPVAS

Short INS position, velocity and attitude

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **INSPVA** log (see page 1138).



This log provides the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 508

Log type: Synch

Recommended input:

```
log inspvasa ontime 1
```

ASCII example:

```
%INSPVASA,2209,490712.000;2209,490712.000000000,51.15043713712,
-114.03067872932,1080.3580,0.0014,-0.0007,0.0015,-0.293782412,
0.302470613,157.989827209,INS_SOLUTION_GOOD*a87ab88b
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSPVAS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds	Seconds from week start	Double	8	H+4
4	Latitude	Latitude [degrees]	Double	8	H+12
5	Longitude	Longitude [degrees]	Double	8	H+20
6	Height	Ellipsoidal Height [m]	Double	8	H+28
7	North Velocity	Velocity in a northerly direction (a negative value implies a southerly direction) [m/s]	Double	8	H+36
8	East Velocity	Velocity in an easterly direction (a negative value implies a westerly direction) [m/s]	Double	8	H+44
9	Up Velocity	Velocity in an up direction [m/s]	Double	8	H+52
10	Roll	Right-handed rotation from local level around y-axis in degrees	Double	8	H+60
11	Pitch	Right-handed rotation from local level around x-axis in degrees	Double	8	H+68

Field	Field type	Description	Format	Binary bytes	Binary offset
12	Azimuth	Left-handed rotation around z-axis in degrees clockwise from north This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+76
13	Status	INS Status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
14	xxxx	32-bit CRC	Hex	4	H+88
15	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.26 INSPVASDCMP

Standard deviation information for the INSPVACMP CAN message

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the standard deviation information for the **INSPVACMP** log (see page 1140) information compressed in a NMEA 2000 fast packet message for CAN output. The PGN of this message is configured using the **PGNCONFIG** command on page 290. The information in the table below is the data portion of the INSPVASDCMP NMEA 2000 message. Refer to the *NATIONAL MARINE ELECTRONICS ASSOCIATION (NMEA) NMEA2000(r) rev 2.0 - January/2013* document for full details on this message output and the NMEA 2000 fast packet protocol.

Message ID: 1890

Log type: Synch

Abbreviated ASCII syntax:

```
LOG CCOM1 INSPVASDCMP ONTIME 1
```

Field	Field type	Description	Format	Binary bytes	Units	Scale format
1	Week	GNSS Week	Ushort	2	weeks	1
2	Message Time	Seconds from week start	Ulong	4	seconds	0.001
3	Sigma Latitude	Latitude Standard Deviation	Ushort	2	metres	0.001
4	Sigma Longitude	Longitude Standard Deviation	Ushort	2	metres	0.001
5	Sigma Height	Height Standard Deviation	Ushort	2	metres	0.001
6	Sigma North Velocity	North Velocity Standard Deviation	Ushort	2	m/s	0.001
7	Sigma East Velocity	East Velocity Standard Deviation	Ushort	2	m/s	0.001
8	Sigma Up Velocity	Up Velocity Standard Deviation	Ushort	2	m/s	0.001
9	Sigma Roll	Roll Standard Deviation	Ushort	2	degrees	0.01
10	Sigma Pitch	Pitch Standard Deviation	Ushort	2	degrees	0.01
11	Sigma Azimuth	Azimuth Standard Deviation	Ushort	2	degrees	0.01
12	Update Counter	Elapsed time since the last ZUPT or position update	Uchar	1	seconds	1
13	INS Position Type	INS position type (see *Table 96: Position or velocity type* on page 531)	Uchar	1	N/A	N/A

Field	Field type	Description	Format	Binary bytes	Units	Scale format
14	Extended Solution Status	Extended Solution Status (see *Table 279: Extended solution status* on page 1124)	Hex	4	N/A	N/A
15	ALIGN Age	Elapsed time since a valid ROVERPOS solution was available	Uchar	1	seconds	1

5.27 INSPVAX

Inertial PVA – extended

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log includes the information from the INSPVA log, as well as information about the position standard deviation. The position type and solution status fields indicate whether or not the corresponding data is valid.

The INSPVAX log is a large log and is not recommend for high rate logging.

If you want to use high rate logging, log the **INSPVAS** log (see page 1142) at a high rate and the **INSSTDEV** log on page 1152 ontime 1.

INS standard deviations are calculated at 1 Hz. Therefore, logging **INSSTDEV ONTIME 1** will capture all of the available standard deviation information.

This log provides the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: 1465

Log type: Synch

Recommended input:

```
log inspvaxa ontime 1
```

ASCII example:

```
#INSPVAXA,USB1,0,65.5,FINESTEERING,2209,490782.000,02000020,46eb,16809;
INS_SOLUTION_GOOD,INS_PPP,51.15043710672,-114.03067871892,1097.3598,-17.0001,
-0.0016,0.0002,0.0029,-0.308665944,0.297893298,157.960833016,0.1816,0.1816,
0.1808,0.0018,0.0018,0.0016,0.0292,0.0292,0.0582,13000045,0*a74644a2
```

Field	Field type	Data Description	Format	Binary bytes	Binary offset
1	Log header	INSPVAX header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	INS Status	Solution status See *Table 278: Inertial solution status* on page 1119	Enum	4	H
3	Pos Type	Position type See *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	Lat	Latitude (degrees)	Double	8	H+8
5	Long	Longitude (degrees)	Double	8	H+16

Field	Field type	Data Description	Format	Binary bytes	Binary offset
6	Height	Height above mean sea level (m)	Double	8	H+24
7	Undulation	Undulation (m)	Float	4	H+32
8	North Vel	North velocity (m/s)	Double	8	H+36
9	East Vel	East velocity (m/s)	Double	8	H+44
10	Up Vel	Up velocity (m/s)	Double	8	H+52
11	Roll	Roll in Local Level (degrees)	Double	8	H+60
12	Pitch	Pitch in Local Level (degrees)	Double	8	H+68
13	Azimuth	Azimuth in Local Level (degrees) This is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	Double	8	H+76
14	Lat σ	Latitude standard deviation (m)	Float	4	H+84
15	Long σ	Longitude standard deviation (m)	Float	4	H+88
16	Height σ	Height standard deviation (m)	Float	4	H+92
17	North Vel σ	North velocity standard deviation (m/s)	Float	4	H+96
18	East Vel σ	East velocity standard deviation (m/s)	Float	4	H+100
19	Up Vel σ	Up velocity standard deviation (m/s)	Float	4	H+104
20	Roll σ	Roll standard deviation (degrees)	Float	4	H+108
21	Pitch σ	Pitch standard deviation (degrees)	Float	4	H+112
22	Azimuth σ	Azimuth standard deviation (degrees)	Float	4	H+116
23	Ext sol stat	Extended solution status See *Table 279: Extended solution status* on page 1124	Hex	4	H+120
24	Time Since Update	Elapsed time since the last ZUPT or position update (seconds)	Ushort	2	H+124
25	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+126
26	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

The INS standard deviation values reported by the SPAN filter are an estimate of the Inertial filter solution quality. In lower accuracy GNSS position modes, such as SINGLE or WAAS (see *Table 96: Position or velocity type* on page 531), the position standard deviation values can appear to become optimistic compared with the absolute GNSS accuracy. This is due to the INS filter's ability to smooth short term noise in the GNSS solution, although the overall position error envelope still reflects the GNSS accuracy. Therefore, if the desired application requires absolute GNSS position accuracy, it is recommended to also monitor GNSS position messages such as BESTGNSSPOS (see **BESTGNSSPOS** log on page 1098).

5.28 INSSEEDSTATUS

Status of INS seed

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log reports the current status of the INS Seed. See INS Seed / Fast INS Initialization in the OEM7 SPAN Installation and Operation User Manual, CPT7 Installation and Operation User Manual or SMART7 Installation and Operation User Manual for more information about an INS Seed.



The INS Seed functionality is supported on all INS profiles, however the INS Seed validation criteria varies depending on the INS profile. If the receiver uses the LAND, AGRICULTURE or RAIL profile, the position and azimuth are validated before the INS Seed is injected and a kinematic validation is performed. If the receiver does not use one of these profiles, only the position is validated. Hence, non-Agriculture type profile users should be aware that the INS Seed will be injected as long as the position is within the threshold when the validation option is enabled. See INS Profiles in the OEM7 SPAN Installation and Operation User Manual, CPT7 Installation and Operation User Manual or SMART7 Installation and Operation User Manual for more information about INS Profiles.

Message ID: 2129

Log type: Asynch

Abbreviated ASCII syntax:

```
log insseedstatusa onnew
```

Example:

```
#INSSEEDSTATUSA,USB1,0,65.5,FINESTEERING,2209,493827.000,02000020,0d1f,16809;
IGNORED,ALLVALID,0.3286,0.0293,352.9208,-1632848.2546,-3662158.6358,
4944901.2915,-17.0001,0,0,0,0*db3c246f
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSSEEDSTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Injection Status	Status of the INS Seed being injected into the solution. See *Table 285: Injection status* on the next page	Enum	4	H
3	Validity Status	Flag to indicate if current seed data in NVM is valid. See *Table 286: Validity status* on the next page	Bool	4	H+4
4	Pitch	IMU frame pitch angle (degrees)	Float	4	H+8
5	Roll	IMU frame roll angle (degrees)	Float	4	H+12
6	Azimuth	IMU frame azimuth angle (degrees)	Float	4	H+16
7	PositionX	ECEF-based x-coordinate	Double	8	H+20

Field	Field type	Description	Format	Binary bytes	Binary offset
8	PositionY	ECEF-based y-coordinate	Double	8	H+28
9	PositionZ	ECEF-based z-coordinate	Double	8	H+36
10	Undulation	Geoid undulation	Float	4	H+44
11	Reserved		Ulong	4	H+48
12	Reserved		Ulong	4	H+52
13	Reserved		Ulong	4	H+56
14	Reserved		Ulong	4	H+60
15	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+64
16	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

Table 285: Injection status

Binary	ASCII	Description
1	INVALID	Valid INS Seed does not exist in non-volatile memory
2	FAILED	INS Seed has failed validation and has been discarded
3	PENDING	INS Seed is awaiting validation
4	INJECTED	INS Seed alignment data has successfully been injected

Table 286: Validity status

Binary	ASCII	Description
0	INVALID	INS Seed in NVM is not valid
1	ALLVALID	INS Seed in NVM is valid
2	ERRORMODELVALID	INS Seed error model in NVM is valid (alignment data is not valid)

5.29 INSSPD

INS speed

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the most recent speed measurements in the horizontal and vertical directions and includes an INS status indicator.

Message ID: 266

Log type: Synch

Recommended input:

```
log insspda ontime 1
```

ASCII example:

```
#INSSPDA,USB1,0,65.5,FINESTEERING,2209,490925.000,02000020,0a39,16809;2209,
490925.000000000,247.102818,0.0021,-0.0007,INS_SOLUTION_GOOD*714af7ba
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSSPD header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Trk gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees Track over ground is best used when the vehicle is moving. When the vehicle is stationary, position error can make the direction of motion appear to change randomly.	Double	8	H+12
5	Horizontal Speed	Magnitude of horizontal speed in m/s.	Double	8	H+20
6	Vertical Speed	Magnitude of vertical speed in m/s where a positive value indicates speed upward and a negative value indicates speed downward.	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.30 INSSPDS

Short INS speed

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **INSSPD** log (see page 1150).

Message ID: 323

Log type: Synch

Recommended input:

```
log insspdsa ontime 1
```

ASCII example:

```
%INSSPDSA,2209,490957.000;2209,490957.000000000,354.197009,0.0045,0.0028,
INS_SOLUTION_GOOD*253f4d87
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSSPDS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	Trk gnd	Actual direction of motion over ground (track over ground) with respect to True North, in degrees. Track over ground is best used when the vehicle is moving. When the vehicle is stationary, position error can make the direction of motion appear to change randomly.	Double	8	H+12
5	Horizontal Speed	Magnitude of horizontal speed in m/s.	Double	8	H+20
6	Vertical Speed	Magnitude of vertical speed in m/s where a positive value indicates speed upward and a negative value indicates speed downward.	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.31 INSSTDEV

INS PVA standard deviations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log displays the INS PVA standard deviations.

Message ID: 2051

Log type: Synch

Abbreviated ASCII syntax:

```
log insstdev ontime 1
```

ASCII example:

```
#INSSTDEVA,USB1,0,66.0,FINESTEERING,2209,491004.000,02000020,2396,16809;0.1813,
0.1813,0.1806,0.0018,0.0018,0.0017,0.0292,0.0291,0.0577,13000045,0,0,7fd1bf,0
*b490ddee
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSSTDEV header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Latitude σ	Latitude standard deviation (m)	Float	4	H
3	Longitude σ	Longitude standard deviation (m)	Float	4	H+4
4	Height σ	Height standard deviation (m)	Float	4	H+8
5	North Velocity σ	North velocity standard deviation (m/s)	Float	4	H+12
6	East Velocity σ	East velocity standard deviation (m/s)	Float	4	H+16
7	Up Velocity σ	Up velocity standard deviation (m/s)	Float	4	H+20
8	Roll σ	Roll standard deviation (degrees)	Float	4	H+24
9	Pitch σ	Pitch standard deviation (degrees)	Float	4	H+28
10	Azimuth σ	Azimuth standard deviation (degrees)	Float	4	H+32
11	Ext sol stat	Extended solution status See *Table 279: Extended solution status* on page 1124	Ulong	4	H+36

Field	Field type	Description	Format	Binary bytes	Binary offset
12	Time Since Update	Elapsed time since the last ZUPT or position update (seconds)	Ushort	2	H+40
13	Reserved		Ushort	2	H+42
14	Reserved		Ulong	4	H+44
15	Reserved		Ulong	4	H+48
16	xxxx	32-bit CRC (ASCII and Binary only).	Hex	4	H+52
17	[CR][LF]	Sentence terminator (ASCII only).	-	-	-

The INS standard deviation values reported by the SPAN filter are an estimate of the Inertial filter solution quality. In lower accuracy GNSS position modes, such as SINGLE or WAAS (see *Table 96: Position or velocity type* on page 531), the position standard deviation values can appear to become optimistic compared with the absolute GNSS accuracy. This is due to the INS filter's ability to smooth short term noise in the GNSS solution, although the overall position error envelope still reflects the GNSS accuracy. Therefore, if the desired application requires absolute GNSS position accuracy, it is recommended to also monitor GNSS position messages such as BESTGNSSPOS (see **BESTGNSSPOS** log on page 1098).

5.32 INSSTDEVS

Short INS PVA standard deviations

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **INSSTDEV** log (see page 1152).

Message ID: 2052

Log type: Synch

Abbreviated ASCII syntax:

```
log insstdevs ontime 1
```

ASCII example:

```
%INSSTDEVSA,2209,491032.000;0.1812,0.1812,0.1805,0.0018,0.0018,0.0017,0.0291,
0.0291,0.0575,13000045,0,0,7fd1bf,0*b6d40807
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSSTDEVS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Latitude σ	Latitude standard deviation (m)	Float	4	H
3	Longitude σ	Longitude standard deviation (m)	Float	4	H+4
4	Height σ	Height standard deviation (m)	Float	4	H+8
5	North Velocity σ	North velocity standard deviation (m/s)	Float	4	H+12
6	East Velocity σ	East velocity standard deviation (m/s)	Float	4	H+16
7	Up Velocity σ	Up velocity standard deviation (m/s)	Float	4	H+20
8	Roll σ	Roll standard deviation (degrees)	Float	4	H+24
9	Pitch σ	Pitch standard deviation (degrees)	Float	4	H+28
10	Azimuth σ	Azimuth standard deviation (degrees)	Float	4	H+32
11	Ext sol stat	Extended solution status See *Table 279: Extended solution status* on page 1124	Ulong	4	H+36
12	Time Since Update	Elapsed time since the last ZUPT or position update (seconds)	Ushort	2	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
13	Reserved		Ushort	2	H+42
14	Reserved		Ulong	4	H+44
15	Reserved		Ulong	4	H+48
16	xxxx	32-bit CRC (ASCII and Binary only).	Hex	4	H+52
17	[CR][LF]	Sentence terminator (ASCII only).	-	-	-

The INS standard deviation values reported by the SPAN filter are an estimate of the Inertial filter solution quality. In lower accuracy GNSS position modes, such as SINGLE or WAAS (see *Table 96: Position or velocity type* on page 531), the position standard deviation values can appear to become optimistic compared with the absolute GNSS accuracy. This is due to the INS filter's ability to smooth short term noise in the GNSS solution, although the overall position error envelope still reflects the GNSS accuracy. Therefore, if the desired application requires absolute GNSS position accuracy, it is recommended to also monitor GNSS position messages such as BESTGNSSPOS (see **BESTGNSSPOS** log on page 1098).

5.33 INSUPDATESTATUS

INS update status

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides the most recent INS update information used by the system. It provides information about what updates were performed in the INS filter at the specified time.

Multiple **INSUPDATESTATUS** logs may be published each epoch. For example, any DMI or external updates will trigger an independent, asynchronous log. These asynchronous logs may show that other updates are not being used because they are the only valid update applied at the specified time.

In the ASCII example below, the first INSUPDATESTATUS log shows 22 phase and 24 doppler updates were applied at 416218.000 and the second INSUPDATESTATUS log shows the DMI update was USED at 416218.002.

Message ID: 1825

Log type: Asynch

Recommended input:

```
log insupdatestatus onchanged
```

ASCII example:

```
#INSUPDATESTATUSA,COM3,0,49.0,FINESTEERING,2117,416218.000,02004020,78f1,32768;
INS_PSRSP,0,22,24,INACTIVE,USED,0b0020c3,007ff3bf,0,0*c1d6e8bc

#INSUPDATESTATUSA,COM3,0,49.0,FINESTEERING,2117,416218.002,02004020,78f1,32768;
INS_PSRSP,0,0,0,USED,INACTIVE,0b0020c3,007ff3bf,0,0*0aa584c7
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSUPDATESTATUS header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	PosType	Type of GNSS solution used for the last INS filter update. See *Table 96: Position or velocity type* on page 531	Enum	4	H
3	NumPSR	Number of raw pseudorange observations used in the last INS filter update.	Integer	4	H+4
4	NumADR	Number of raw phase observations used in the last INS filter update.	Integer	4	H+8
5	NumDOP	Number of raw doppler observations used in the last INS filter update.	Integer	4	H+12
6	DMI Update Status	Distance measurement instrument (wheel sensor) status. See *Table 287: DMI update status* on the next page.	Enum	4	H+16

Field	Field type	Description	Format	Binary bytes	Binary offset
7	ALIGN Update Status	Status of the ALIGN update during the last INS filter update. See *Table 288: ALIGN update values* below	Enum	4	H+20
8	Ext sol stat	Extended solution status See *Table 279: Extended solution status* on page 1124	Hex	4	H+24
9	INS Enabled Updates	Enabled INS updates. See *Table 289: INS update values* on the next page	Hex	4	H+28
10	Reserved		Ulong	4	H+32
11	Reserved		Ulong	4	H+36
12	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
13	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 287: DMI update status

Binary	ASCII	Description
0	INACTIVE	The DMI sensor is not connected.
1	ACTIVE	The DMI sensor is connected but not used.
2	USED	The DMI sensor is connected and used in the INS solution.
3	RESERVED	Reserved
4	BAD_MISC	The measurement of the DMI sensor resulted in bad misclosure and was rejected.
5	HIGH_ ROTATION	The measurement of the DMI sensor was not used because the system is undergoing high rotation.

Table 288: ALIGN update values

Binary	ASCII	Description
0	INACTIVE	An ALIGN update was not available.
1	ACTIVE	ALIGN updates are running, but the epoch is not used as an update. When all other rejection criteria pass, an ALIGN update will still only be applied once every 5 seconds (20 seconds when stationary).
2	USED	The update for that epoch was taken.
5	BAD_MISC	ALIGN updates are running, but was not performed this epoch due to a large disagreement with filter estimates.

Table 289: INS update values

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Position update	0 = Disabled 1 = Enabled
	1	0x00000002	Phase update	0 = Disabled 1 = Enabled
	2	0x00000004	Zero velocity update	0 = Disabled 1 = Enabled
	3	0x00000008	Wheel sensor update	0 = Disabled 1 = Enabled
N1	4	0x00000010	ALIGN update	0 = Disabled 1 = Enabled
	5	0x00000020	External position update	0 = Disabled 1 = Enabled
	6	0x00000040	Reserved	
	7	0x00000080	Doppler update	0 = Disabled 1 = Enabled
N2	8	0x00000100	Pseudorange update	0 = Disabled 1 = Enabled
	9	0x00000200	Velocity update	0 = Disabled 1 = Enabled
	10	0x00000400	Reserved	
	11	0x00000800	Dead reckoning update	0 = Disabled 1 = Enabled
N3	12	0x00001000	Phase wind up update	0 = Disabled 1 = Enabled
	13	0x00002000	Course over ground update	0 = Disabled 1 = Enabled
	14	0x00004000	External velocity update	0 = Disabled 1 = Enabled
	15	0x00008000	External attitude update	0 = Disabled 1 = Enabled
N4	16	0x00010000	External heading update	0 = Disabled 1 = Enabled
	17	0x00020000	External height update	0 = Disabled 1 = Enabled
	18	0x00040000	Reserved	
	19	0x00080000	Reserved	

5.34 INSVEL

INS velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the most recent North, East and Up velocity vector values, with respect to the local level frame and also includes an INS status indicator.

Message ID: 267

Log type: Synch

Recommended input:

```
log insvela ontime 1
```

ASCII example:

```
#INSVELA,USB1,0,67.0,FINESTEERING,2209,491133.000,02000020,29aa,16809;2209,
491133.000000000,-0.0035,0.0010,0.0004,INS_SOLUTION_GOOD*73237b3a
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSVEL header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	North Velocity	Velocity North in m/s	Double	8	H+12
5	East Velocity	Velocity East in m/s	Double	8	H+20
6	Up Velocity	Velocity Up in m/s	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.35 INSVELS

Short INS velocity

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **INSVEL** log (see page 1159).

Message ID: 324

Log type: Synch

Recommended input:

```
log insvelsa ontime 1
```

ASCII example:

```
%INSVELSA,2209,491166.000;2209,491166.000000000,-0.0033,-0.0004,-0.0003,
INS_SOLUTION_GOOD*24448c97
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSVELS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	North Velocity	Velocity North m/s	Double	8	H+12
5	East Velocity	Velocity East m/s	Double	8	H+20
6	Up Velocity	Velocity Up m/s	Double	8	H+28
7	Status	INS status, see *Table 278: Inertial solution status* on page 1119	Enum	4	H+36
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.36 INSVELUSER

INS velocity in user output frame

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log outputs INS Velocity information in the user defined output frame as per the **SETINSROTATION USER** command. The default, when no USER rotation is defined, is the vehicle frame assuming a valid RBV rotation has been entered.

The velocity information will be translated to the reference point defined by the **SETINSTRANSLATION USER** command.

The *Slip Angle Validity* flag provides an indication of the confidence in the slip angle calculation based on the solution quality. Included in the quality indicators for a valid slip angle is a check for minimum vehicle speed. The user should consider the velocity standard deviations when using both the velocity and slip angle values.

The range of the Slip Angle is -180 to 180 degrees. When the Slip Angle is positive, the vehicle is slipping to the driver's right (starboard) assuming the user frame Y axis coincides with the vehicle forward direction of travel. When the Slip Angle is negative, the vehicle is slipping to the driver's left (port). This corresponds to the sign of the velocity in the user frame X axis.

Message ID: 2318

Log type: Synch

Recommended input:

```
LOG INSVELUSER ONTIME 1
```

Abbreviated ASCII example:

```
#INSVELUSERA,USB1,0,66.5,FINESTEERING,2209,491218.000,02000020,9ac8,16809;
INS_SOLUTION_GOOD,-0.0015,-0.0008,-0.0007,0.0018,0.0018,0.0016,-119.785,0,0,
00000000*89b473ba
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSVELUSER header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0
2	INS Status	Solution status See *Table 278: Inertial solution status* on page 1119	Enum	4	H

Field	Field type	Description	Format	Binary bytes	Binary offset
3	X-Axis Velocity	Velocity in the Output Frame X-Axis (Across Track for Vehicle)	Double	8	H+4
4	Y-Axis Velocity	Velocity in the Output Frame Y-Axis (Along Track for Vehicle)	Double	8	H+12
5	Z-Axis Velocity	Velocity in the Output Frame Z-Axis (Vertical for Vehicle)	Double	8	H+20
6	X-Axis Velocity StDev	Velocity Standard Deviation in the Output Frame X-Axis (Across Track for Vehicle)	Float	4	H+28
7	Y-Axis Velocity StDev	Velocity Standard Deviation in the Output Frame Y-Axis (Along Track for Vehicle)	Float	4	H+32
8	Z-Axis Velocity StDev	Velocity Standard Deviation in the Output Frame Z-Axis (Vertical for Vehicle)	Float	4	H+36
9	Slip Angle	Heading angle offset from actual motion over ground (Track over Ground) to Output Frame ($Heading_{GroundTrack}$ - $Heading_{UserFrame}$)	Float	4	H+40
10	Reserved	Reserved	Ulong	4	H+44
11	Reserved	Reserved	Ulong	4	H+48
12	Extended Velocity Status	Extended Velocity Status, see *Table 290: Extended velocity status* below.	Hex Ulong	4	H+52
13	XXXX	32-bit CRC (ASCII and Binary only)	Hex	4	H+56
14	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

Table 290: Extended velocity status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Slip Angle Validity	0 = Invalid 1 = Valid
	1	0x00000002	Reserved	
	2	0x00000004	Reserved	
	3	0x00000008	Reserved	

Nibble	Bit	Mask	Description	Range value
N1	4	0x00000010	Reserved	
	5	0x00000020	Reserved	
	6	0x00000040	Reserved	
	7	0x00000080	Reserved	
N2	8	0x00000100	Reserved	
	9	0x00000200	Reserved	
	10	0x00000400	Reserved	
	11	0x00000800	Reserved	
N3	12	0x00001000	Reserved	
	13	0x00002000	Reserved	
	14	0x00004000	Reserved	
	15	0x00008000	Reserved	

5.37 INSVELX

Inertial velocity – extended

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log includes the information from the INSVEL log, as well as information about the velocity standard deviation. The position type and solution status fields indicate whether or not the corresponding data is valid.

The INSVELX log is a large log and is not recommend for high rate logging.

If you want to use high rate logging, log the **INSVELS** log at a high rate and the **INSSTDEVS** log ontime 1.

Message ID: 1458

Log type: Synch

Recommended input:

```
log insvelxa ontime 1
```

ASCII example:

```
#INSVELXA,USB1,0,66.5,FINESTEERING,2209,491263.000,02000020,1a1f,16809;
INS_SOLUTION_GOOD,INS_PPP,-0.0007,-0.0009,0.0017,0.0018,0.0018,0.0017,
13000045,0*b2e79695
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	INSVELX header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.		H	0
2	INS Status	Solution status See *Table 278: Inertial solution status* on page 1119	Enum	4	H
3	Pos Type	Position type See *Table 96: Position or velocity type* on page 531	Enum	4	H+4
4	North Vel	North velocity (m/s)	Double	8	H+8
5	East Vel	East velocity (m/s)	Double	8	H+16
6	Up Vel	Up velocity (m/s)	Double	8	H+24
7	North Vel σ	North velocity standard deviation (m/s)	Float	4	H+32
8	East Vel σ	East velocity standard deviation (m/s)	Float	4	H+36
9	Up Vel σ	Up velocity standard deviation (m/s)	Float	4	H+40

Field	Field type	Description	Format	Binary bytes	Binary offset
10	Ext sol stat	Extended solution status See *Table 279: Extended solution status* on page 1124	Hex	4	H+44
11	Time Since Update	Elapsed time since the last ZUPT or position update (seconds)	Ushort	2	H+48
11	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+50
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.38 MARK1PVA, MARK2PVA, MARK3PVA and MARK4PVA

Position, velocity and attitude at Mark input event

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

These logs output position, velocity and attitude information, with respect to the IMU Body frame, when an event is received on the Mark input. If the **SETINSTRANSLATION** command (see page 1082) and **SETINSROTATION** command (see page 1079) have been entered with a MARKx parameter, the MARKxPVA log will contain the solution translated, and then rotated, by the values provided in the commands (e.g. **SETINSTRANSLATION MARK1** and **SETINSROTATION MARK1** commands for the MARK1PVA log). See the **SETINSTRANSLATION** command on page 1082 and **SETINSROTATION** command on page 1079.

The MARKxPVA logs available are dependent on the receiver used in the SPAN system. For information about the Event lines supported, see the Strobe Specifications for the receiver in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

These logs should only be requested with the ONCHANGED or ONNEW trigger.

These logs provide the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: **1067 (MARK1PVA)**
1068 (MARK2PVA)
1118 (MARK3PVA)
1119 (MARK4PVA)

Log type: Asynch

Recommended input:

```
log mark1pva onnew
log mark2pva onnew
log mark3pva onnew
log mark4pva onnew
```

ASCII example:

```
#MARK1PVAA,COM1,0,74.5,FINESTEERING,1732,247231.455,02040020,5790,12002;1732,
247231.454623850,51.11693182283,-114.03885213810,1047.4525,0.0004,0.0004,
-0.0006,0.847121689,1.124640813,278.577037489,INS_SOLUTION_GOOD*47b2778f

#MARK2PVAA,COM1,0,74.5,FINESTEERING,1732,247232.271,02040020,2425,12002;1732,
247232.271459820,51.11693179023,-114.03885206704,1047.4529,0.0004,-0.0011,
-0.0007,0.837101074,1.134127754,278.346498557,INS_SOLUTION_GOOD*9282f407

#MARK3PVAA,COM1,0,74.5,FINESTEERING,1732,247232.271,02040020,2425,12002;1732,
247232.271459820,51.11693179023,-114.03885206704,1047.4529,0.0004,-0.0011,
-0.0007,0.837101074,1.134127754,278.346498557,INS_SOLUTION_GOOD*748983db
```

```
#MARK4PVAA,COM1,0,74.5,FINESTEERING,1732,247232.271,02040020,2425,12002;1732,
247232.271459820,51.11693179023,-114.03885206704,1047.4529,0.0004,-0.0011,
-0.0007,0.837101074,1.134127754,278.346498557,INS_SOLUTION_GOOD*ab2ace0c
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	MARK1PVA / MARK2PVA / MARK3PVA / MARK4PVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week at Mark input	Ulong	4	H
3	Seconds	Seconds from week at Mark input	Double	8	H+4
4	Latitude	Latitude at Mark input (degrees)	Double	8	H+12
5	Longitude	Longitude at Mark input (degrees)	Double	8	H+20
6	Height	Ellipsoidal height at Mark input (metres)	Double	8	H+28
7	North Velocity	Velocity in a northerly direction (a negative value implies a southerly direction) at Mark input (metres/second)	Double	8	H+36
8	East Velocity	Velocity in an easterly direction (a negative value implies a westerly direction) at Mark input (metres/second)	Double	8	H+44
9	Up Velocity	Velocity in an up direction at Mark input (metres/second)	Double	8	H+52
10	Roll	Right-handed rotation from local level around y-axis in degrees at Mark input (degrees)	Double	8	H+60
11	Pitch	Right-handed rotation from local level around x-axis in degrees at Mark input (degrees)	Double	8	H+68
12	Azimuth	Left-handed rotation around z-axis in degrees clockwise from North at Mark input (degrees)	Double	8	H+76
13	Status	INS Status, see *Table 278: Inertial solution status* on page 1119 at Mark input	Enum	4	H+84
14	xxxx	32-bit CRC	Hex	4	H+88
15	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.39 PASHR

NMEA, inertial attitude data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

The PASHR log uses a UTC time, calculated with default parameters, to output NMEA messages without waiting for a valid almanac. The UTC time status is set to WARNING since it may not be 100% accurate. When a valid almanac is available, the receiver uses the real parameters and sets the UTC time to VALID. For more information about NMEA, refer to *NMEA standard logs* on page 752. The PASHR log contains only INS derived attitude information and is only filled when an inertial solution is available.



As of firmware version 7.03.00, an INS status flag (field 12) has been added to the PASHR log. This change was made to match the industry accepted form of the message. Previous firmware versions on OEM7 and OEM6 do not output this field.

Message ID: 1177

Log type: Synch

Recommended input:

```
log pashr ontime 1
```

Example:

```
$PASHR,163029.000,158.09,T,-0.30,+0.31,+0.01,0.029,0.029,0.059,1,1*3B
```

Field	Structure	Description	Symbol	Example
1	$PASHR	Log header	---	$PASHR
2	Time	UTC Time	hhmmss.sss	195124.00
3	Heading	Heading value in decimal degrees The heading is the inertial azimuth calculated from the IMU gyros and the SPAN filters.	HHH.HH	305.30
4	True Heading	T displayed if heading is relative to true north.	T	T
5	Roll	Roll in decimal degrees. The ± sign will always be displayed.	RRR.RR	+0.05
6	Pitch	Pitch in decimal degrees. The ± sign will always be displayed.	PPP.PP	-0.13
7	Heave	Instantaneous heave in metres. The ± will always be displayed	Heave	+0.01
8	Roll Accuracy	Roll standard deviation in decimal degrees.	rr.rrr	0.180
9	Pitch Accuracy	Pitch standard deviation in decimal degrees.	pp.ppp	0.185

Field	Structure	Description	Symbol	Example
10	Heading Accuracy	Heading standard deviation in decimal degrees.	hh.hhh	4.986
11	GPS Update Quality Flag	0 = No position 1 = All non-RTK fixed integer positions 2 = RTK fixed integer position	1	1
12	INS Status Flag	0 = All SPAN Pre-Alignment INS Status 1 = All SPAN Post-Alignment INS Status - These include: INS_ALIGNMENT_COMPLETE, INS_SOLUTION_GOOD, INS_HIGH_VARIANCE, INS_SOLUTION_FREE	1	1
13	Checksum	Checksum	*XX	*2B
14	[CR][LF]	Sentence terminator		[CR][LF]

5.40 RAWDMI

Raw Distance Measurement Instrument (DMI) measurements

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

This log contains the raw measurements from the Distance Measurement Instruments (DMI) connected to the receiver and enabled by the **DMICONFIG** command (see page 1044).

RAWDMI can also be used as a command. If DMI inputs are not supported on the OEM7 receiver or IMU, the DMI wheel ticks can be collected by a separate device and sent to the receiver using RAWDMI as a command.



The RAWDMI command does not need to be sent if the SPAN system has a PwrPak7 receiver or one of the following NovAtel enclosure IMUs: IMU-ISA-100C, IMU-LN200, IMU-LN200C, IMU-HG1900, IMU-µIMU-IC, IMU-IGM-A1, IMU-IGM-S1, IMU-FSAS or IMU-CPT. For these devices, connect the DMI to the DMI inputs on the PwrPak7 or IMU and SPAN system will collect the wheel tick.

Message ID: 2269

Log type: Synch

Recommended input:

```
log rawdmia onnew
```

Example log:

```
#RAWDMIA,COM1,0,24.0,FINESTEERING,2048,427043.137,02004048,b411,32768;2297,0,0,
0,00000001*61b727c0
```

Command abbreviated ASCII syntax:

```
RAWDMI DMI1 DMI2 DMI3 DMI4 Mask
```

Command example:

```
RAWDMI 1000 0 0 0 1 (indicates 1000 wheel ticks from DMI1)
RAWDMI 0 0 0 2000 8 (indicates 2000 wheel ticks from DMI4)
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWDMI header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	–	H	0

Field	Field type	Description	Format	Binary bytes	Binary offset
2	DMI1	DMI Input Value for DMI1	Long Array [4]	16	H
	DMI2	DMI Input Value for DMI2 (Inactive - support coming in a future release)			
	DMI3	DMI Input Value for DMI3 (Inactive - support coming in a future release)			
	DMI4	DMI Input Value for DMI4 (Inactive - support coming in a future release)			
3	Mask	Mask to indicate which DMI inputs are used in the solution. Bit 0 = DMI1 Bit 1 = DMI2 Bit 2 = DMI3 Bit 3 = DMI4	Long	4	H+16
4	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+20
5	[CR][LF]	Sentence Terminator (ASCII only)	–	–	–

The DMI Input Values are interpreted based on the configuration of that input in the **DMICONFIG** command (see page 1044).

Only DMI1 is currently supported.

5.41 RAWIMU

Raw IMU data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains an IMU status indicator and the measurements from the accelerometers and gyros with respect to the IMU enclosure frame. If logging this data, consider the **RAWIMUS** log (see page 1176) to reduce the amount of data.

The change in velocity (acceleration) and angle (rotation rate) scale factors for each IMU type can be found in *Table 302: Raw IMU scale factors* on page 1197. Multiply the appropriate scale factor by the count value for the velocity (field 5-7) and angle (field 8-10) increments.

To obtain acceleration in m/s/s or rotation rate in rad/s, multiply the velocity/rotation increments by the output rate of the IMU:

- 100 Hz for UIMU-HG1700-AG58, UIMU-HG1700-AG62, IMU-HG1900, OEM-HG1900, OEM-HG1930, OEM-IMU-HG4930, CPT7 and CPT7700
- 125 Hz for OEM-IMU-STIM300, OEM-IMU-EG320N, PwrPak7-E1, PwrPak7D-E1 and SMART7-S
- 200 Hz for IMU-ISA-100C, IMU-LN200, IMU-LN200C, IMU-µIMU-IC, OEM-IMU-µIMU-IC, IMU-P1750, OEM-IMU-EG370N, OEM-IMU-EG320N_200Hz, PwrPak7-E2 and PwrPak7D-E2
- 400 Hz for OEM-IMU-HG4930_400Hz, CPT7_400Hz, CPT7700_400Hz and OEM-IMU-µIMU-IC-UART

The units of acceleration and rotation rate will depend on the IMU Scale Factors.

This log is output in the IMU Body frame.

Logging restriction important notice

Logging excessive amounts of high rate data can overload the system. When configuring the output for SPAN, NovAtel recommends that only one high rate (>50Hz) message be configured for output at a time. It is possible to log more than one message at high rates, but doing so could have negative impacts on the system. Also, if logging 100/125/200/400Hz data, always use the binary format and, if possible, the short header binary format (available on most INS logs).

For optimal performance, log only one high rate output at a time. These logs could be:

- Raw data for post processing
  RAWIMUXSB ONNEW
  - RAWIMU logs are not valid with the ONTIME trigger. The raw IMU observations contained in these logs are sequential changes in velocity and rotation. As such, you can only use them for navigation if they are logged at their full rate.
- Real time INS solution
  IMURATEPVA ONNEW or IMURATEPVAS ONNEW

  Other possible INS solution logs available at high rates are: INSPVASB, INSPOSSB, INSVELSB, INSATTSB

Message ID: 268

Log type: Asynch

Recommended input:

```
log rawimua onnew
```

ASCII example:

```
#RAWIMUA,USB1,0,65.5,FINESTEERING,2209,491571.654,02000020,8358,16809;2209,4915
71.653515,ea59fe00,329181823,-2557458,4291497,234324,232588,-1010826*4b79604d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWIMU header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	IMU Status	The status of the IMU. This field is given in a fixed length (n) array of bytes in binary but in ASCII or Abbreviated ASCII is converted into 2 character hexadecimal pairs. For the raw IMU status, see one of the following tables: • *Table 291: HG1700 IMU status* on page 1182 • *Table 292: IMU-LN200 IMU status* on page 1183 • *Table 293: IMU-ISA-100C IMU status* on page 1184 • *Table 294: IMU-P1750 IMU status* on page 1186 • *Table 295: HG1900 and HG1930 IMU status* on page 1187 • *Table 296: OEM-IMU-HG4930 AN01 IMU status* on page 1188 • *Table 297: OEM-IMU-HG4930 AN04 IMU status* on page 1190 • *Table 298: OEM-IMU-STIM300 IMU status* on page 1191 • *Table 299: IMU-µIMU-IC IMU status* on page 1193 • *Table 300: OEM-IMU-EG320N IMU status* on page 1194 • *Table 301: OEM-IMU-EG370N IMU status* on page 1196	Hex Ulong	4	H+12
5	Z Accel Output	Change in velocity count along z axis	Long	4	H+16
6	- (Y Accel Output)	- (Change in velocity count along y axis) A negative value implies the output is along the positive y-axis marked on the IMU. A positive value implies the change is in the direction opposite to that of the y-axis marked on the IMU.	Long	4	H+20
7	X Accel Output	Change in velocity count along x axis	Long	4	H+24
8	Z Gyro Output	Change in angle count around z axis Right-handed	Long	4	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
9	- (Y Gyro Output)	- (Change in angle count around y axis). Right-handed A negative value implies a positive right-handed rotation about the y-axis marked on the IMU. A positive value implies a negative right-handed rotation about the y-axis marked on the IMU.	Long	4	H+32
10	X Gyro Output	Change in angle count around x axis Right-handed	Long	4	H+36
11	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.42 RAWIMUS

Short raw IMU data

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is the short header version of the **RAWIMU** log (see page 1172).

The change in velocity (acceleration) and angle (rotation rate) scale factors for each IMU type can be found in *Table 302: Raw IMU scale factors* on page 1197. Multiply the appropriate scale factor by the count value for the velocity (field 5-7) and angle (field 8-10) increments.

To obtain acceleration in m/s/s or rotation rate in rad/s, multiply the velocity/rotation increments by the output rate of the IMU:

- 100 Hz for UIMU-HG1700-AG58, UIMU-HG1700-AG62, IMU-HG1900, OEM-HG1900, OEM-HG1930, OEM-IMU-HG4930, CPT7 and CPT7700
- 125 Hz for OEM-IMU-STIM300, OEM-IMU-EG320N, PwrPak7-E1, PwrPak7D-E1 and SMART7-S
- 200 Hz for IMU-ISA-100C, IMU-LN200, IMU-LN200C, IMU-µIMU-IC, OEM-IMU-µIMU-IC, IMU-P1750, OEM-IMU-EG370N, OEM-IMU-EG320N_200Hz, PwrPak7-E2 and PwrPak7D-E2
- 400 Hz for OEM-IMU-HG4930_400Hz, CPT7_400Hz, CPT7700_400Hz and OEM-IMU-µIMU-IC-UART

The units of acceleration and rotation rate will depend on the IMU Scale Factors.

This log is output in the IMU Body frame.

Logging restriction important notice

Logging excessive amounts of high rate data can overload the system. When configuring the output for SPAN, NovAtel recommends that only one high rate (>50Hz) message be configured for output at a time. It is possible to log more than one message at high rates, but doing so could have negative impacts on the system. Also, if logging 100/125/200/400Hz data, always use the binary format and, if possible, the short header binary format (available on most INS logs).

For optimal performance, log only one high rate output at a time. These logs could be:

- Raw data for post processing
  RAWIMUXSB ONNEW
  - RAWIMU logs are not valid with the ONTIME trigger. The raw IMU observations contained in these logs are sequential changes in velocity and rotation. As such, you can only use them for navigation if they are logged at their full rate.
- Real time INS solution
  IMURATEPVA ONNEW or IMURATEPVAS ONNEW

  Other possible INS solution logs available at high rates are: INSPVASB, INSPOSSB, INSVELSB, INSATTSB

Message ID: 325

Log type: Asynch

Recommended input:

```
log rawimusa onnew
```

ASCII example:

```
%RAWIMUSA,2209,491612.254;2209,491612.253588,ea5afe00,329303960,-2512321,
4410363,309705,607017,-1009773*1fb76c28
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWIMUS header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	Week	GNSS Week	Ulong	4	H
3	Seconds into Week	Seconds from week start	Double	8	H+4
4	IMU Status	The status of the IMU. This field is given in a fixed length (n) array of bytes in binary but in ASCII or Abbreviated ASCII is converted into 2 character hexadecimal pairs. For the raw IMU status, see one of the following tables: • *Table 291: HG1700 IMU status* on page 1182 • *Table 292: IMU-LN200 IMU status* on page 1183 • *Table 293: IMU-ISA-100C IMU status* on page 1184 • *Table 294: IMU-P1750 IMU status* on page 1186 • *Table 295: HG1900 and HG1930 IMU status* on page 1187 • *Table 296: OEM-IMU-HG4930 AN01 IMU status* on page 1188 • *Table 297: OEM-IMU-HG4930 AN04 IMU status* on page 1190 • *Table 298: OEM-IMU-STIM300 IMU status* on page 1191 • *Table 299: IMU-µIMU-IC IMU status* on page 1193 • *Table 300: OEM-IMU-EG320N IMU status* on page 1194 • *Table 301: OEM-IMU-EG370N IMU status* on page 1196	Hex Ulong	4	H+12

Field	Field type	Description	Format	Binary bytes	Binary offset
5	Z Accel Output	Change in velocity count along z axis	Long	4	H+16
6	- (Y Accel Output)	- (Change in velocity count along y axis) A negative value implies the output is along the positive y-axis marked on the IMU. A positive value implies the change is in the direction opposite to that of the y-axis marked on the IMU.	Long	4	H+20
7	X Accel Output	Change in velocity count along x axis	Long	4	H+24
8	Z Gyro Output	Change in angle count around z axis Right-handed	Long	4	H+28
9	- (Y Gyro Output)	- (Change in angle count around y axis) Right-handed A negative value implies a positive right-handed rotation about the y-axis marked on the IMU. A positive value implies a negative right-handed rotation about the y-axis marked on the IMU.	Long	4	H+32
10	X Gyro Output	Change in angle count around x axis Right-handed	Long	4	H+36
11	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+40
12	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.43 RAWIMUSX

IMU data extended

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This is the short header version of the extended RAWIMUX log intended for use with post-processing. The extended version includes IMU information that is used by the NovAtel Inertial Explorer post-processing software.

The change in velocity (acceleration) and angle (rotation rate) scale factors for each IMU type can be found in *Table 302: Raw IMU scale factors* on page 1197. Multiply the appropriate scale factor by the count value for the velocity (field 7-9) and angle (field 10-12) increments.

To obtain acceleration in m/s/s or rotation rate in rad/s, multiply the velocity/rotation increments by the output rate of the IMU:

- 100 Hz for UIMU-HG1700-AG58, UIMU-HG1700-AG62, IMU-HG1900, OEM-HG1900, OEM-HG1930, OEM-IMU-HG4930, CPT7 and CPT7700
- 125 Hz for OEM-IMU-STIM300, OEM-IMU-EG320N, PwrPak7-E1, PwrPak7D-E1 and SMART7-S
- 200 Hz for IMU-ISA-100C, IMU-LN200, IMU-LN200C, IMU-µIMU-IC, OEM-IMU-µIMU-IC, IMU-P1750, OEM-IMU-EG370N, OEM-IMU-EG320N_200Hz, PwrPak7-E2 and PwrPak7D-E2
- 400 Hz for OEM-IMU-HG4930_400Hz, CPT7_400Hz, CPT7700_400Hz and OEM-IMU-µIMU-IC-UART

The units of acceleration and rotation rate will depend on the IMU Scale Factors.

This log is output in the IMU Body frame.

Logging restriction important notice

Logging excessive amounts of high rate data can overload the system. When configuring the output for SPAN, NovAtel recommends that only one high rate (>50Hz) message be configured for output at a time. It is possible to log more than one message at high rates, but doing so could have negative impacts on the system. Also, if logging 100/125/200/400Hz data, always use the binary format and, if possible, the short header binary format (available on most INS logs).

For optimal performance, log only one high rate output at a time. These logs could be:

- Raw data for post processing
  RAWIMUXSB ONNEW
  - RAWIMU logs are not valid with the ONTIME trigger. The raw IMU observations contained in these logs are sequential changes in velocity and rotation. As such, you can only use them for navigation if they are logged at their full rate.
- Real time INS solution
  IMURATEPVA ONNEW or IMURATEPVAS ONNEW

  Other possible INS solution logs available at high rates are: INSPVASB, INSPOSSB, INSVELSB, INSATTSB

Message ID: 1462

Log type: Asynch

Recommended input:

```
log rawimusxb onnew
```

ASCII example:

```
%RAWIMUSXA,2209,491674.014;04,41,2209,491674.013699,ea59fe00,329308016
,-2706935,4508389,196192,417138,-1000837*038422a7
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWIMUSX header For information about short log headers, see *Description of ASCII and binary logs with short headers* on page 51.	-	H	0
2	IMU Info	IMU Info Bits Bit 0: If set, an IMU error was detected. Check the IMU Status field for details. Bit 1: If set, the IMU data is encrypted and should not be used. Bits 2 to 7: Reserved	Hex Uchar	1	H
3	IMU Type	IMU Type identifier. See *Table 271: IMU type* on page 1042.	Uchar	1	H+1
4	GNSS Week	GNSS Week	Ushort	2	H+2

Field	Field type	Description	Format	Binary bytes	Binary offset
5	GNSS Week Seconds	Seconds from week start	Double	8	H+4
6	IMU Status	The status of the IMU. This field is given in a fixed length (n) array of bytes in binary but in ASCII or Abbreviated ASCII is converted into 2 character hexadecimal pairs. For the raw IMU status, see one of the following tables: • *Table 291: HG1700 IMU status* on the next page • *Table 292: IMU-LN200 IMU status* on page 1183 • *Table 293: IMU-ISA-100C IMU status* on page 1184 • *Table 294: IMU-P1750 IMU status* on page 1186 • *Table 295: HG1900 and HG1930 IMU status* on page 1187 • *Table 296: OEM-IMU-HG4930 AN01 IMU status* on page 1188 • *Table 297: OEM-IMU-HG4930 AN04 IMU status* on page 1190 • *Table 298: OEM-IMU-STIM300 IMU status* on page 1191 • *Table 299: IMU-µIMU-IC IMU status* on page 1193 • *Table 300: OEM-IMU-EG320N IMU status* on page 1194 • *Table 301: OEM-IMU-EG370N IMU status* on page 1196	Hex Ulong	4	H+12
7	Z Accel	Change in velocity count along Z-axis.	Long	4	H+16
8	-(Y Accel)	- (Change in velocity count along y-axis.) A negative value implies the output is along the positive y-axis marked on the IMU. A positive value implies the change is in the direction opposite to that of the y-axis marked on the IMU.	Long	4	H+20
9	X Accel	Change in velocity count along x axis.	Long	4	H+24
10	Z Gyro	Change in angle count around z axis. Right-handed	Long	4	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
11	-(Y Gyro)	- (Change in angle count around y axis.) Right-handed A negative value implies a positive right-handed rotation about the y-axis marked on the IMU. A positive value implies a negative right-handed rotation about the y-axis marked on the IMU.	Long	4	H+32
12	X Gyro	Change in angle count around x axis. Right-handed	Long	4	H+36
13	XXXX	32-bit CRC (ASCII, Binary, and Short Binary only)	Hex	4	H+40
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 291: HG1700 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Reserved	
	1	0x00000002	Reserved	
	2	0x00000004	Reserved	
	3	0x00000008	Reserved	
N1	4	0x00000010	IMU Status	0 = Passed, 1 = Failed
	5	0x00000020	IMU Status	0 = Passed, 1 = Failed
	6	0x00000040	IMU Status	0 = Passed, 1 = Failed
	7	0x00000080	IMU Status	0 = Passed, 1 = Failed
N2	8	0x00000100	Reserved	
	9	0x00000200	Reserved	
	10	0x00000400	Reserved	
	11	0x00000800	Reserved	
N3	12	0x00001000	Reserved	
	13	0x00002000	Reserved	
	14	0x00004000	Reserved	
	15	0x00008000	Reserved	
N4	16	0x00010000	Reserved	
	17	0x00020000	Reserved	
	18	0x00040000	Reserved	
	19	0x00080000	Reserved	

Nibble	Bit	Mask	Description	Range value
N5	20	0x00100000	Reserved	
	21	0x00200000	Reserved	
	22	0x00400000	Reserved	
	23	0x00800000	Reserved	
N6	24	0x01000000	Reserved	
	25	0x02000000	Reserved	
	26	0x04000000	Reserved	
	27	0x08000000	IMU Status	0 = Passed, 1= Failed
N7	28	0x10000000	IMU Status	0 = Passed, 1 = Failed
	29	0x20000000	IMU Status	0 = Passed, 1 = Failed
	30	0x40000000	IMU Status	0 = Passed, 1 = Failed
	31	0x80000000	IMU Status	0 = Passed, 1 = Failed

The values in *Table 291: HG1700 IMU status* on the previous page also apply to the UIMU-HG1700-AG58 and UIMU-HG1700-AG62.

Table 292: IMU-LN200 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	IMU Status	0 = Passed, 1 = Failed
	1	0x00000002	IMU Status	0 = Passed, 1 = Failed
	2	0x00000004	IMU Status	0 = Passed, 1 = Failed
	3	0x00000008	IMU Status	0 = Passed, 1 = Failed
N1	4	0x00000010	IMU Status	0 = Passed, 1 = Failed
	5	0x00000020	IMU Status	0 = Passed, 1 = Failed
	6	0x00000040	IMU Status	0 = Passed, 1 = Failed
	7	0x00000080	IMU Status	0 = Passed, 1 = Failed
N2	8	0x00000100	IMU Status	0 = Passed, 1 = Failed
	9	0x00000200	IMU Status	0 = Passed, 1 = Failed
	10	0x00000400	IMU Status	0 = Passed, 1 = Failed
	11	0x00000800	IMU Status	0 = Passed, 1 = Failed

Nibble	Bit	Mask	Description	Range value
N3	12	0x00001000	IMU Status	0 = Passed, 1 = Failed
	13	0x00002000	IMU Status	0 = Passed, 1 = Failed
	14	0x00004000	IMU Status	0 = Passed, 1 = Failed
	15	0x00008000	Reserved	
N4	16	0x00010000	Reserved	
	17	0x00020000	Reserved	
	18	0x00040000	Reserved	
	19	0x00080000	Reserved	
N5	20	0x00100000	Reserved	
	21	0x00200000	Reserved	
	22	0x00400000	Reserved	
	23	0x00800000	Reserved	
N6	24	0x01000000	IMU Status	0 = Passed, 1 = Failed
	25	0x02000000	IMU Status	0 = Passed, 1 = Failed
	26	0x04000000	IMU Status	0 = Passed, 1 = Failed
	27	0x08000000	IMU Status	0 = Passed, 1 = Failed
N7	28	0x10000000	IMU Status	0 = Passed, 1 = Failed
	29	0x20000000	Reserved	
	30	0x40000000	IMU Status	0 = Passed, 1 = Failed
	31	0x80000000	Reserved	

The values in *Table 292: IMU-LN200 IMU status* on the previous page also apply to the IMU-LN200C and UIMU-LN200.

Table 293: IMU-ISA-100C IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Maintenance Indication	0 = Normal, 1 = System Maintenance Indicator
	1	0x00000002	Accelerometers Invalid	0 = Normal, 1 = Invalid
	2	0x00000004	Accelerometer X Warning	0 = Normal, 1 = Warning
	3	0x00000008	Accelerometer Y Warning	0 = Normal, 1 = Warning

Nibble	Bit	Mask	Description	Range value
N1	4	0x00000010	Accelerometer Z Warning	0 = Normal, 1 = Warning
	5	0x00000020	Accelerometer X NOGO	0 = Normal, 1 = NOGO
	6	0x00000040	Accelerometer Y NOGO	0 = Normal, 1 = NOGO
	7	0x00000080	Accelerometer Z NOGO	0 = Normal, 1 = NOGO
N2	8	0x00000100	Reset Occurred	0 = Normal, 1 = First Message after ISA-100C Reset
	9	0x00000200	Gyroscopes Invalid	0 = Normal, 1 = Invalid
	10	0x00000400	Gyroscope X Warning	0 = Normal, 1 = Warning
	11	0x00000800	Gyroscope Y Warning	0 = Normal, 1 = Warning
N3	12	0x00001000	Gyroscope Z Warning	0 = Normal, 1 = Warning
	13	0x00002000	Gyroscope X NOGO	0 = Normal, 1 = NOGO
	14	0x00004000	Gyroscope Y NOGO	0 = Normal, 1 = NOGO
	15	0x00008000	Gyroscope Z NOGO	0 = Normal, 1 = NOGO
N4	16	0x00010000	IMU temperature reading as follows: Signed 2-byte value (SHORT) 1 LSB = $3.90625e^{-3}$ Celsius Temperature Range +/- 128 Celsius	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

Table 294: IMU-P1750 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Gyro X Status	1 = Valid, 0 = Invalid
	1	0x00000002	Gyro Y Status	1 = Valid, 0 = Invalid
	2	0x00000004	Gyro Z Status	1 = Valid, 0 = Invalid
	3	0x00000008	Unused	Set to 0
N1	4	0x00000010	Accelerometer X Status	1 = Valid, 0 = Invalid
	5	0x00000020	Accelerometer Y Status	1 = Valid, 0 = Invalid
	6	0x00000040	Accelerometer Z Status	1 = Valid, 0 = Invalid
	7	0x00000080	Unused	Set to 0
N2	8	0x00000100	IMU Data Sequence Counter read in a Ushort. Increments for each message and resets to 0 after 127.	
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		
N3	12	0x00001000		
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		

Nibble	Bit	Mask	Description	Range value
N4	16	0x00010000	IMU temperature reading as follows: Signed 2-byte value (SHORT) Rounded to the nearest degree Example: <RAWIMU COM1 0 75.0 FINESTEERING 1813 514207.000 00000020 fa9a 45836 1813 514207.000000000 **00260077** 32164 -47 -305 1 -10 0 IMU status = 00260077 Temperatures bytes = 0026 Decimal value = 38 degrees C	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

Table 295: HG1900 and HG1930 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Reserved	
	1	0x00000002		
	2	0x00000004		
	3	0x00000008		
N1	4	0x00000010	IMU Status	0 = Passed, 1 = Failed
	5	0x00000020	IMU Status	0 = Passed, 1 = Failed
	6	0x00000040	IMU Status	0 = Passed, 1 = Failed
	7	0x00000080	IMU Status	0 = Passed, 1 = Failed
N2	8	0x00000100	Reserved	
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		

Nibble	Bit	Mask	Description	Range value
N3	12	0x00001000	Reserved	
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000	Reserved	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000	Reserved	
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000	IMU Status	0 = Passed, 1 = Failed
	25	0x02000000	Reserved	
	26	0x04000000	IMU Status	0 = Passed, 1 = Failed
	27	0x08000000	IMU Status	0 = Passed, 1 = Failed
N7	28	0x10000000	IMU Status	0 = Passed, 1 = Failed
	29	0x20000000	IMU Status	0 = Passed, 1 = Failed
	30	0x40000000	IMU Status	0 = Passed, 1 = Failed
	31	0x80000000	Reserved	

The values in *Table 295: HG1900 and HG1930 IMU status* on the previous page also apply to the IMU-HG1900, OEM-HG1900 and OEM-HG1930.

Table 296: OEM-IMU-HG4930 AN01 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	IMU Status	0 = Passed, 1 = Failed
	1	0x00000002	Reserved	
	2	0x00000004		
	3	0x00000008	Gyro Status	0 = Passed, 1 = Failed

Nibble	Bit	Mask	Description	Range value
N1	4	0x00000010	Accelerometer Status	0 = Passed, 1 = Failed
	5	0x00000020	Reserved	
	6	0x00000040	IMU Status	0 = Passed, 1 = Failed
	7	0x00000080	Reserved	
N2	8	0x00000100	MU temperature reading as follows: Signed 2-byte integer (SHORT, two's complement) 0°C = 0x0000 1LSB = 0.01 °C Available only on firmware versions 7.08.02 and later	
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		
N3	12	0x00001000		
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000		
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000	Reserved	
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000	Reserved	
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

The values in *Table 296: OEM-IMU-HG4930 AN01 IMU status* on the previous page also apply to the legacy CPT7.

Table 297: OEM-IMU-HG4930 AN04 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Reserved	
	1	0x00000002		
	2	0x00000004		
	3	0x00000008		
N1	4	0x00000010	Reserved	
	5	0x00000020	IMU status	0 = Passed, 1 = Failed
	6	0x00000040	Reserved	
	7	0x00000080		
N2	8	0x00000100	IMU temperature reading as follows: Signed 2-byte integer (SHORT, two's complement) 0°C = 0x0000 1LSB = 0.01 °C Available only on firmware versions 7.08.02 and later	
	9	0x00000200		
	10	0x00000400		
	11	0x00000800		
N3	12	0x00001000		
	13	0x00002000		
	14	0x00004000		
	15	0x00008000		
N4	16	0x00010000		
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000	Reserved	
	25	0x02000000		
	26	0x04000000		
	27	0x08000000	Time synchronization	0: Normal 1: IMU time synchronization instability warning. IMU power cycle recommended if issue persists.

Nibble	Bit	Mask	Description	Range value
N7	28	0x10000000	IMU variant match	0: Normal 1: IMU reported variant code does not match IMU type setting.
	29	0x20000000	Data overflow	0: Normal 1: IMU data accumulation overflowed.
	30	0x40000000	Data rate	0: IMU data rate 400 Hz mode operation. 1: IMU data rate 100 Hz mode operation (accumulated from 400 Hz).
	31	0x80000000	IMU Axes remap	0: IMU axes have not been remapped. 1: IMU axes have been remapped for the CPT7 enclosure.

The values in *Table 297: OEM-IMU-HG4930 AN04 IMU status* on the previous page also apply to the CPT7 and CPT7700.

Table 298: OEM-IMU-STIM300 IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Gyro status	0 = OK, 1 = X-channel
	1	0x00000002		0 = OK, 1 = Y-channel
	2	0x00000004		0 = OK, 1 = Z-channel
	3	0x00000008		0 = OK, 1 = Error in measurement channel (Bits 0-2 flag the error channels)
N1	4	0x00000010		0 = OK, 1 = Overload (Bits 0-2 flag the error channels)
	5	0x00000020		0 = OK, 1 = Outside operating conditions
	6	0x00000040		0 = OK, 1 = Startup
	7	0x00000080		0 = OK, 1 = System integrity error

Nibble	Bit	Mask	Description	Range value
N2	8	0x00000100	Accelerometer Status	0 = OK, 1 = X-channel
	9	0x00000200		0 = OK, 1 = Y-channel
	10	0x00000400		0 = OK, 1 = Z-channel
	11	0x00000800		0 = OK, 1 = Error in measurement channel (Bits 0-2 flag the error channels)
N3	12	0x00001000		0 = OK, 1 = Overload (Bits 0-2 flag the error channels)
	13	0x00002000		0 = OK, 1 = Outside operating conditions
	14	0x00004000		0 = OK, 1 = Startup
	15	0x00008000		0 = OK, 1 = System integrity error
N4	16	0x00010000	Temperature of the X gyro sensor 0ºC = 0x0000 1 LSB = 2^{-8} ºC Use the following formula to convert the temperature word to °C. $Output\left[^{\circ}C\right] = \frac{(T_1)\times 2^8+(T_2)-(T_{b15})\times 2^{16}}{2^8}$ where: T_1 is the most significant byte of the 16 bit output T_2 is the least significant byte of the 16 bit output T_{b15} is the most significant bit of T_1 See *Figure 17: STIM300 temperature word* on the next page	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

Figure 17: STIM300 temperature word




Table 299: IMU-µIMU-IC IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Reset Acknowledged	0 = Normal, 1 = Reset
	1	0x00000002	Gyros Not Initialized	0 = Normal, 1 = Not Initialized
	2	0x00000004	Gyro X Warning	0 = Normal, 1 = Warning
	3	0x00000008	Gyro Y Warning	0 = Normal, 1 = Warning
N1	4	0x00000010	Gyro Z Warning	0 = Normal, 1 = Warning
	5	0x00000020	Gyro X NOGO	0 = Normal, 1 = NOGO
	6	0x00000040	Gyro Y NOGO	0 = Normal, 1 = NOGO
	7	0x00000080	Gyro Z NOGO	0 = Normal, 1 = NOGO
N2	8	0x00000100	Reserved	
	9	0x00000200	Accels Not Initialized	0 = Normal, 1 = Not Initialized
	10	0x00000400	Accel X Warning	0 = Normal, 1 = Warning
	11	0x00000800	Accel Y Warning	0 = Normal, 1 = Warning
N3	12	0x00001000	Accel Z Warning	0 = Normal, 1 = Warning
	13	0x00002000	Accel X NOGO	0 = Normal, 1 = NOGO
	14	0x00004000	Accel Y NOGO	0 = Normal, 1 = NOGO
	15	0x00008000	Accel Z NOGO	0 = Normal, 1 = NOGO

Nibble	Bit	Mask	Description	Range value
N4	16	0x00010000	IMU temperature reading as follows: Signed 2-byte value (SHORT) 1 LSB = 3.90625e^-3 ºC Temperature Range +/- 128 ºC	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

The values in *Table 299: IMU-µIMU-IC IMU status* on the previous page also apply to the OEM-IMU-µIMU-IC and OEM-IMU-µIMU-IC-UART.

Table 300: OEM-IMU-EG320N IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Error All	0 = Normal, 1 = Sensor Failure
	1	0x00000002	Reserved	
	2	0x00000004		
	3	0x00000008		
N1	4	0x00000010		
	5	0x00000020		
	6	0x00000040		
	7	0x00000080		

Nibble	Bit	Mask	Description	Range value
N2	8	0x00000100		
	9	0x00000200	Accel Z - New Data	New Data = 1, No Data = 0
	10	0x00000400	Accel Y - New Data	New Data = 1, No Data = 0
	11	0x00000800	Accel X - New Data	New Data = 1, No Data = 0
N3	12	0x00001000	Gyro Z - New Data	New Data = 1, No Data = 0
	13	0x00002000	Gyro Y - New Data	New Data = 1, No Data = 0
	14	0x00004000	Gyro X - New Data	New Data = 1, No Data = 0
	15	0x00008000	Temperature - New Data	New Data = 1, No Data = 0
N4	16	0x00010000	IMU temperature reading as follows: Signed 2-byte integer (SHORT, two's complement) 34.9876012 °C = 0x0000 1 LSB = -0.0037918 °C Conversion: Temperature [°C] = -0.0037918 * (VALUE - 2634) + 25 OR Temperature [°C] = -0.0037918 * VALUE + 34.9876012	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

The values in *Table 300: OEM-IMU-EG320N IMU status* on the previous page also apply to the PwrPak7-E1, PwrPak7D-E1 and SMART7-S.

Table 301: OEM-IMU-EG370N IMU status

Nibble	Bit	Mask	Description	Range value
N0	0	0x00000001	Error All	0 = Normal, 1 = Sensor Failure
	1	0x00000002	Run Time Diagnostics	0 = Normal, 1 = At least one abnormality detected in run time self-diagnosis result
	2	0x00000004	Reserved	
	3	0x00000008		
N1	4	0x00000010		
	5	0x00000020		
	6	0x00000040		
	7	0x00000080		
N2	8	0x00000100	Range Over	0 = Normal, 1 = At least one over range condition detected
	9	0x00000200	Accel Z - New Data	New Data = 1, No Data = 0
	10	0x00000400	Accel Y - New Data	New Data = 1, No Data = 0
	11	0x00000800	Accel X - New Data	New Data = 1, No Data = 0
N3	12	0x00001000	Gyro Z - New Data	New Data = 1, No Data = 0
	13	0x00002000	Gyro Y - New Data	New Data = 1, No Data = 0
	14	0x00004000	Gyro X - New Data	New Data = 1, No Data = 0
	15	0x00008000	Temperature - New Data	New Data = 1, No Data = 0

Nibble	Bit	Mask	Description	Range value
N4	16	0x00010000	IMU temperature reading as follows: Signed 2-byte integer (SHORT, two's complement) 34.9876012 °C = 0x0000 1 LSB = -0.0037918 °C Conversion: Temperature [°C] = -0.0037918 * (VALUE - 2634) + 25 OR Temperature [°C] = -0.0037918 * VALUE + 34.9876012	
	17	0x00020000		
	18	0x00040000		
	19	0x00080000		
N5	20	0x00100000		
	21	0x00200000		
	22	0x00400000		
	23	0x00800000		
N6	24	0x01000000		
	25	0x02000000		
	26	0x04000000		
	27	0x08000000		
N7	28	0x10000000		
	29	0x20000000		
	30	0x40000000		
	31	0x80000000		

The values in *Table 301: OEM-IMU-EG370N IMU status* on the previous page also apply to the PwrPak7-E2 and PwrPak7D-E2.

Table 302: Raw IMU scale factors

	Gyroscope scale factor	Acceleration scale factor
HG1700-AG58 HG1900-CA29/CA50 HG1930-AA99/CA50	2.0^{-33} rad/LSB	2.0^{-27} ft/s/LSB
HG1700-AG62	2.0^{-33} rad/LSB	2.0^{-26} ft/s/LSB
HG4930-AN01 HG4930-AN04 CPT7 CPT7700	2.0^{-33} rad/LSB	2.0^{-29} m/s/LSB
IMU-P1750	0.1 / (3600.0x256.0) rad/LSB	$0.05/2^{15}$ m/s/LSB
LN-200	2^{-19} rad/LSB	2^{-14} m/s/LSB

	Gyroscope scale factor	Acceleration scale factor
IMU-ISA-100C **IMU-µIMU-IC**	1.0E-9 rad/LSB	2.0E-8 m/s/LSB
OEM-IMU-STIM300	2^{-21} deg/LSB	2^{-22} m/s/LSB
OEM-IMU-EG320N **PwrPak7-E1** **PwrPak7D-E1** **SMART7-S**	(0.008/65536)/(DataRate) deg/LSB	(0.200/65536)*(ONE_G/1000)/(DataRate) m/s/LSB
OEM-IMU-EG370N **PwrPak7-E2** **PwrPak7D-E2**	(0.0151515/65536)/200 deg/LSB	(0.400/65536)*(ONE_G/1000)/200 m/s/LSB

LSB = Least Significant Bit
DataRate = 125 or 200 depending on configuration
ONE_G = 9.80665 m/s/s

5.44 RAWIMUX

IMU data extended

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log is an extended version of the RAWIMU log intended for use with post-processing. The extended version includes IMU information that is used by the NovAtel Inertial Explorer post-processing software.

The change in velocity (acceleration) and angle (rotation rate) scale factors for each IMU type can be found in *Table 302: Raw IMU scale factors* on page 1197. Multiply the appropriate scale factor by the count value for the velocity (field 7-9) and angle (field 10-12) increments.

To obtain acceleration in m/s/s or rotation rate in rad/s, multiply the velocity/rotation increments by the output rate of the IMU:

- 100 Hz for UIMU-HG1700-AG58, UIMU-HG1700-AG62, IMU-HG1900, OEM-HG1900, OEM-HG1930, OEM-IMU-HG4930, CPT7 and CPT7700
- 125 Hz for OEM-IMU-STIM300, OEM-IMU-EG320N, PwrPak7-E1, PwrPak7D-E1 and SMART7-S
- 200 Hz for IMU-ISA-100C, IMU-LN200, IMU-LN200C, IMU-µIMU-IC, OEM-IMU-µIMU-IC, IMU-P1750, OEM-IMU-EG370N, OEM-IMU-EG320N_200Hz, PwrPak7-E2 and PwrPak7D-E2
- 400 Hz for OEM-IMU-HG4930_400Hz, CPT7_400Hz, CPT7700_400Hz and OEM-IMU-µIMU-IC-UART

The units of acceleration and rotation rate will depend on the IMU Scale Factors.

This log is output in the IMU Body frame.

Logging restriction important notice

Logging excessive amounts of high rate data can overload the system. When configuring the output for SPAN, NovAtel recommends that only one high rate (>50Hz) message be configured for output at a time. It is possible to log more than one message at high rates, but doing so could have negative impacts on the system. Also, if logging 100/125/200/400Hz data, always use the binary format and, if possible, the short header binary format (available on most INS logs).

For optimal performance, log only one high rate output at a time. These logs could be:

- Raw data for post processing
  RAWIMUXSB ONNEW
  - RAWIMU logs are not valid with the ONTIME trigger. The raw IMU observations contained in these logs are sequential changes in velocity and rotation. As such, you can only use them for navigation if they are logged at their full rate.
- Real time INS solution
  IMURATEPVA ONNEW or IMURATEPVAS ONNEW

  Other possible INS solution logs available at high rates are: INSPVASB, INSPOSSB, INSVELSB, INSATTSB

Message ID: 1461

Log type: Asynch

Recommended input:

```
log rawimuxb onnew
```

ASCII example:

```
#RAWIMUXA,USB1,0,64.5,FINESTEERING,2209,491740.110,02000020,0dc5,16809;04,41,
2209,491740.109817,ea57fe00,329394068,-2396829,4481425,321199,257329,-936077
*cf9c035d
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RAWIMUX header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	IMU Info	IMU Info Bits Bit 0: If set, an IMU error was detected. Check the IMU Status field for details. Bit 1: If set, the IMU data is encrypted and should not be used. Bits 2 to 7: Reserved	Hex Uchar	1	H
3	IMU Type	IMU Type identifier. See *Table 271: IMU type* on page 1042.	Uchar	1	H+1

Field	Field type	Description	Format	Binary bytes	Binary offset
4	GNSS Week	GNSS Week	Ushort	2	H+2
5	GNSS Week Seconds	Seconds from week start	Double	8	H+4
6	IMU Status	The status of the IMU. This field is given in a fixed length (n) array of bytes in binary but in ASCII or Abbreviated ASCII is converted into 2 character hexadecimal pairs. For the raw IMU status, see one of the following tables: • *Table 291: HG1700 IMU status* on page 1182 • *Table 292: IMU-LN200 IMU status* on page 1183 • *Table 293: IMU-ISA-100C IMU status* on page 1184 • *Table 294: IMU-P1750 IMU status* on page 1186 • *Table 295: HG1900 and HG1930 IMU status* on page 1187 • *Table 296: OEM-IMU-HG4930 AN01 IMU status* on page 1188 • *Table 297: OEM-IMU-HG4930 AN04 IMU status* on page 1190 • *Table 298: OEM-IMU-STIM300 IMU status* on page 1191 • *Table 299: IMU-µIMU-IC IMU status* on page 1193 • *Table 300: OEM-IMU-EG320N IMU status* on page 1194 • *Table 301: OEM-IMU-EG370N IMU status* on page 1196	Hex Ulong	4	H+12
7	Z Accel	Change in velocity count along Z-axis.	Long	4	H+16
8	-(Y Accel)	- (Change in velocity count along y-axis.) A negative value implies the output is along the positive y-axis marked on the IMU. A positive value implies the change is in the direction opposite to that of the y-axis marked on the IMU.	Long	4	H+20
9	X Accel	Change in velocity count along x axis.	Long	4	H+24
10	Z Gyro	Change in angle count around z axis. Right-handed	Long	4	H+28

Field	Field type	Description	Format	Binary bytes	Binary offset
11	-(Y Gyro)	- (Change in angle count around y axis.) Right-handed A negative value implies a positive right-handed rotation about the y-axis marked on the IMU. A positive value implies a negative right-handed rotation about the y-axis marked on the IMU.	Long	4	H+32
12	X Gyro	Change in angle count around x axis. Right-handed	Long	4	H+36
13	XXXX	32-bit CRC (ASCII, Binary, and Short Binary only)	Hex	4	H+40
14	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.45 RELINSPVA

Relative INSPVA log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides the relative offset between the Base and Rover Inertial Solutions. The output solution provides the offset of where the local station is with respect to the other station.

This log should only be requested with the ONNEW trigger.

To use the **RELINSPVA** log, the receiver requires a Relative INS capable model.

Message ID: 1446

Log type: Asynch

Recommended input:

```
LOG RELINSPVAA ONNEW
```

ASCII example:

```
#RELINSPVAA,COM1,0,61.0,FINESTEERING,1805,245074.000,02000000,2338,45757;BODY,
9.285958662,-0.755483058,0.079229338,0.001739020,-0.000126304,0.001525848,
0.321033045,0.669367786,4.466250181,0.000000000,"b81V",INS_ALIGNMENT_COMPLETE,
"B20C",INS_ALIGNMENT_COMPLETE,NARROW_INT,00000000*a55bb953
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	RELINSPVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Output Frame	The current output frame (IMU body, ECEF or local level frame). The output frame is specified using the **SETRELINSOUTPUTFRAME** command (see page 1089)	Enum	4	H
3	DeltaPosX	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the X-axis ECEF = along the X-axis Local level = Northing	Double	8	H+4

Field	Field type	Description	Format	Binary bytes	Binary offset
4	DeltaPosY	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the Y-axis ECEF = along the Y-axis Local level = Easting	Double	8	H+12
5	DeltaPosZ	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the Z-axis ECEF = along the Z-axis Local level = Up	Double	8	H+20
6	DeltaVelX	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the X-axis ECEF = along the X-axis Local level = Northing	Double	8	H+28
7	DeltaVelY	Difference in velocity between two receivers (m/s). The position difference is relative to the output frame: BODY = along the Y-axis ECEF = along the Y-axis Local level = Easting	Double	8	H+36
8	DeltaVelZ	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the Z-axis ECEF = along the Z-axis Local level = Up	Double	8	H+44
9	DeltaRoll	Difference in roll between the two receivers (degrees).	Double	8	H+52
10	DeltaPitch	Difference in pitch between the two receivers (degrees).	Double	8	H+60
11	DeltaHeading	Difference in heading between the two receivers (degrees).	Double	8	H+68
12	Diff Age	Differential age in seconds.	Float	4	H+76
13	Rover ID	Rover receiver ID string.	Char[4]	4	H+80
14	Rover INSStatus	INS status of the rover receiver. See *Table 278: Inertial solution status* on page 1119	Enum	4	H+84

Field	Field type	Description	Format	Binary bytes	Binary offset
15	Base ID	Base receiver ID string.	Char[4]	4	H+88
16	Base INSStatus	INS status of the base receiver. See *Table 278: Inertial solution status* on page 1119	Enum	4	H+92
17	RTK Status	Status of the current RTK vector between base and rover. See *Table 96: Position or velocity type* on page 531	Enum	4	H+96
18	ExtStatus	Extended solution status. See *Table 303: Relative INS extended solution status* below	Hex	4	H+100
20	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+104
21	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Table 303: Relative INS extended solution status

Nibble	Bit	Mask	Description	Range
N0	0	0x00000001	Diff Criteria	0 = Delta solution is computed as Rover minus Base 1= Delta solution is computed as Base minus Rover
	1	0x00000002	Reserved	
	2	0x00000004	Reserved	
	3	0x00000008	Reserved	
N1 - N7	4 - 31	0xFFFFFFF0	Reserved	

5.46 SYNCHEAVE

Synchronous log containing the instantaneous Heave value

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Synchronous heave is available up to the rate of the IMU. It can also be logged 'on time' at lower rates.

This log also includes information about the estimated accuracy of the heave value through the standard deviation of the heave. This heave solution is calculated at the location entered in the **SETINSTRANSLATION USER** command.



You must have an inertial solution to use this log.

Refer also to information in the **SETHEAVEWINDOW** command on page 1071.

Message ID: 1708

Log type: Synch

Recommended input:

```
log syncheaveb ontime 0.05
```

ASCII example:

```
#SYNCHEAVEA,USB1,0,66.5,FINESTEERING,2209,491905.000,02000020,552e,16809;
0.012799581,0.031871900*01d2be8c
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SYNCHEAVE header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Heave	Instantaneous heave value (metres)	Double	8	H
3	Std. Dev.	Standard deviation of the heave value (metres)	Double	8	H+8
4	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+16
5	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.47 SYNCRELINSPVA

Synchronous Relative INSPVA log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides the relative offset between the base and rover inertial solutions. The output solution provides the offset of where the local station is with respect to the other station.

To use the **SYNCRELINSPVA** log, the receiver requires a Relative INS capable model.

This log is designed to provide synchronous, relative Position, Velocity and Attitude information, propagating the information between matched corrections between the base and remote solutions. It is highly recommended that the highest rate of corrections be used at all times for the most precise and robust performance.

Message ID: 1743

Log type: Synch

Recommended input:

```
LOG SYNCRELINSPVAA ONTIME 1
```

ASCII example:

```
#SYNCRELINSPVAA,COM1,0,72.5,FINESTEERING,1805,247243.000,02000000,e9c7,13005;
BODY,8.141080733,-2.779177478,2.045421773,-0.001464009,-0.001038329,0.002323548,
0.409467974,0.715633909,-6.204731538,0.000000000,"B81V",INS_ALIGNMENT_COMPLETE,
"B20C",INS_ALIGNMENT_COMPLETE,INS_PSRSP,00000000*3f79c676
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	SYNCRELINSPVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Output Frame	The current output frame (IMU body, ECEF or local level frame). The output frame is specified using the **SETRELINSOUTPUTFRAME** command (see page 1089)	Enum	4	H

Field	Field type	Description	Format	Binary bytes	Binary offset
3	DeltaPosX	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the X-axis ECEF = along the X-axis Local level = Northing	Double	8	H+4
4	DeltaPosY	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the Y-axis ECEF = along the Y-axis Local level = Easting	Double	8	H+12
5	DeltaPosZ	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the Z-axis ECEF = along the Z-axis Local level = Up	Double	8	H+20
6	DeltaVelX	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the X-axis ECEF = along the X-axis Local level = Northing	Double	8	H+28
7	DeltaVelY	Difference in velocity between two receivers (m/s). The position difference is relative to the output frame: BODY = along the Y-axis ECEF = along the Y-axis Local level = Easting	Double	8	H+36
8	DeltaVelZ	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the Z-axis ECEF = along the Z-axis Local level = Up	Double	8	H+44
9	DeltaRoll	Difference in roll between the two receivers (degrees).	Double	8	H+52
10	DeltaPitch	Difference in pitch between the two receivers (degrees).	Double	8	H+60
11	DeltaHeading	Difference in heading between the two receivers (degrees).	Double	8	H+68

Field	Field type	Description	Format	Binary bytes	Binary offset
12	Diff Age	Differential age in seconds.	Float	4	H+76
13	Rover ID	Rover receiver ID string.	Char[4]	4	H+80
14	Rover INSStatus	INS status of the rover receiver. See *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
15	Base ID	Base receiver ID string.	Char[4]	4	H+88
16	Base INSStatus	INS status of the base receiver. See *Table 278: Inertial solution status* on page 1119	Enum	4	H+92
17	RTK Status	Status of the current RTK vector between base and rover. See *Table 96: Position or velocity type* on page 531	Enum	4	H+96
18	ExtStatus	Extended solution status. See *Table 303: Relative INS extended solution status* on page 1205	Hex	4	H+100
19	xxxx	32-bit CRC (ASCII and Binary only)	Hex	4	H+104
20	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

5.48 SYNCRELINSPVACMP

Compressed synchronous Relative INSPVA log

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log contains the **SYNCRELINSPVA** log (see page 1207) information compressed into a NMEA 2000 fast packet message for CAN output. The information in the following table is the data portion of the **SYNCRELINSPVACMP** NMEA 2000 message. Refer to the *National Marine Electronics Association (NMEA) NMEA2000(r) Standard rev 2.0 - January/2013* document for full details on this message output and the NMEA 2000 fast packet protocol.

The PGN of this message is configured using the **PGNCONFIG** command (see page 290).

The computed Position, Velocity and Attitude (PVA) delta information is valid once the rover and base SPAN solutions have both reached Alignment Complete (rover INSStatus and base INSStatus are both INS_ALIGNMENT_COMPLETE, INS_SOLUTION_GOOD, INS_SOLUTION_FREE or INS_HIGH_VARIANCE). The relative PVA quality depends on the absolute INS solution quality of both the base and rover, the GNSS relative position (ALIGN) quality, latency of corrections messages from base to rover (differential age) and rate of dynamics change of each unit but not on the absolute position solution accuracy of either base or rover.

To use the **SYNCRELINSPVACMP** log, the receiver requires a Relative INS capable model.

Message ID: 2538

Log type: Synch

Rate restriction: SYNC[200Hz]

Recommended input:

```
LOG CCOM1 SYNCRELINSPVACMP ONTIME 1
```

Field	Field type	Description	Quantization	Range	Format	ASCII convert string	Scale factor
1	Message Time	Time from the beginning of the GPS week (s)	1 ms	0 – 604799.999 seconds	Ulong	–	0.001
2	DeltaPosX	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the X-axis ECEF = along the X-axis Local level = Northing	0.1 mm	±214 km	Long	%1d	0.0001

Field	Field type	Description	Quantization	Range	Format	ASCII convert string	Scale factor
3	DeltaPosY	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the Y-axis ECEF = along the Y-axis Local level = Easting	0.1 mm	±214 km	Long	%1d	0.0001
4	DeltaPosZ	Difference in the position between the two receivers (m). The position difference is relative to the output frame: BODY = along the Z-axis ECEF = along the Z-axis Local level = Up	0.1 mm	±214 km	Long	%1d	0.0001
5	DeltaVelX	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the X-axis ECEF = along the X-axis Local level = Northing	0.002 m/s	±262 m/s	18 bit signed integer	%ld	0.002
6	DeltaVelY	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the Y-axis ECEF = along the Y-axis Local level = Easting	0.002 m/s	±262 m/s	18 bit signed integer	%ld	0.002

Field	Field type	Description	Quantization	Range	Format	ASCII convert string	Scale factor
7	DeltaVelZ	Difference in velocity between the two receivers (m/s). The position difference is relative to the output frame: BODY = along the Z-axis ECEF = along the Z-axis Local level = Up	0.002 m/s	±262 m/s	18 bit signed integer	%ld	0.002
8	DeltaRoll	Difference in roll between the two receivers (degrees). Right-handed rotation around Y axis.	0.01 degrees	±180 degrees	Short	%hd	0.01
9	DeltaPitch	Difference in pitch between the two receivers (degrees). Right-handed rotation around X axis.	0.01 degrees	±180 degrees	Short	%hd	0.01
10	DeltaHeading	Difference in heading (azimuth) between the two receivers (degrees). Left-handed rotation around Z axis.	0.01 degrees	±180 degrees	Short	%hd	0.01
11	Diff Age	Differential age in seconds. (256 is 25.6 seconds or greater)	0.1 seconds	0 – 25.6 seconds	Uchar	%hhd	0.1
12	Rover ID	Rover receiver ID string, up to 4 ASCII characters in character order, pad with zeroes.	–	–	Char[4]	…	…
13	Rover INSStatus	INS status of the rover receiver.	See *Table 278: Inertial solution status* on page 1119		5 bit Enum	–	–
14	Base ID	Base receiver ID string.	–	–	Char[4]	…	…
15	Base INSStatus	INS status of the base receiver.	See *Table 278: Inertial solution status* on page 1119		5 bit Enum	–	–
16	RTK Status	Status of the current RTK vector between the base and rover.	See *Table 96: Position or velocity type* on page 531		8 bit Enum	–	–

Field	Field type	Description	Quantization	Range	Format	ASCII convert string	Scale factor
17	ExtStatus	Extended solution status.	See *Table 303: Relative INS extended solution status* on page 1205		12 bit Hex	%03hx	–
18	Output Frame	The current output frame as specified using the **SETRELINSOUTPUTFRAME** command	See **SETRELINSOUTPUTFRAME** command on page 1089		4 bit Enum	–	–

5.49 TAGGEDMARK1PVA, TAGGEDMARK2PVA, TAGGEDMARK3PVA and TAGGEDMARK4PVA

Position, velocity and attitude at a tagged Mark request

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

TAGGEDMARKxPVA contains the same information as MARKxPVA with the addition of a unique identifying number (tag).

The TAGGEDMARKxPVA logs available are dependent on the receiver used in the SPAN system. For information about the Event lines supported, see the Strobe Specifications for the receiver in the OEM7 Installation and Operation User Manual, PwrPak7 Installation and Operation User Manual or CPT7 Installation and Operation User Manual.

The user specifies a TAG for the upcoming TAGGEDMARKxPVA via the **TAGNEXTMARK** command (see page 1093). That tag shows up at the end of this message, which is otherwise identical to the MARKXPVA message.

These logs should only be requested with the ONNEW trigger.

These logs provide the position information in the selected datum. To determine the datum being used, log the **INSDATUMINFO** log (see page 1133).

Message ID: **1258 (TAGGEDMARK1PVA)**
1259 (TAGGEDMARK2PVA)
1327 (TAGGEDMARK3PVA)
1328 (TAGGEDMARK4PVA)

Log type: Synch

Recommended input:

```
log taggedmark1pva onnew
log taggedmark2pva onnew
log taggedmark3pva onnew
log taggedmark4pva onnew
```

Abbreviated ASCII example:

```
#TAGGEDMARK1PVAA,COM1,0,63.0,FINESTEERING,1732,247787.965,024c0020,ae1e,12002;
1732,247787.964913500,51.11693231436,-114.03884974751,1046.9481,0.0001,0.0007,
0.0004,1.090392628,0.766828598,244.413950146,INS_SOLUTION_GOOD,1234*07d76542
#TAGGEDMARK2PVAA,COM1,0,73.0,FINESTEERING,1732,248347.693,020500a0,2ab3,12002;
1732,248347.692695400,51.11693017508,-114.03884746120,1046.3929,0.0009,0.0014,
0.0015,0.559580646,1.121028629,255.541153133,INS_SOLUTION_GOOD,1234*2dbd1c3e
```

```
#TAGGEDMARK3PVAA,COM1,0,73.0,FINESTEERING,1732,248347.693,020500a0,2ab3,12002;
1732,248347.692695400,51.11693017508,-114.03884746120,1046.3929,0.0009,0.0014,
0.0015,0.559580646,1.121028629,255.541153133,INS_SOLUTION_GOOD,1234*5e82e635
```

```
#TAGGEDMARK4PVAA,COM1,0,73.0,FINESTEERING,1732,248347.693,020500a0,2ab3,12002;
1732,248347.692695400,51.11693017508,-114.03884746120,1046.3929,0.0009,0.0014,
0.0015,0.559580646,1.121028629,255.541153133,INS_SOLUTION_GOOD,1234*dc4c0645
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	TAGGEDMARK1PVA / TAGGEDMARK2PVA / TAGGEDMARK3PVA / TAGGEDMARK4PVA header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	Week	GNSS Week at Mark input	Ulong	4	H
3	Seconds into Week	GNSS Seconds at Mark input	Double	8	H+4
4	Latitude	Latitude at Mark input (degrees)	Double	8	H+12
5	Longitude	Longitude at Mark input (degrees)	Double	8	H+20
6	Height	Height at Mark input (metres)	Double	8	H+28
7	North Velocity	North Velocity at Mark input (metres/second)	Double	8	H+36
8	East Velocity	East Velocity at Mark input (metres/second)	Double	8	H+44
9	Up Velocity	Up Velocity at Mark input (metres/second)	Double	8	H+52
10	Roll	Roll at Mark input (degrees)	Double	8	H+60
11	Pitch	Pitch at Mark input (degrees)	Double	8	H+68
12	Azimuth	Azimuth at Mark input (degrees)	Double	8	H+76
13	Status	INS Status at Mark input. See *Table 278: Inertial solution status* on page 1119	Enum	4	H+84
14	Tag	Tag ID from the **TAGNEXTMARK** command (see page 1093), if any (default = 0)	Ulong	4	H+88
15	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+92
16	[CR][LF]	Sentence Terminator (ASCII only)	-	-	-

5.50 TSS1

TSS1 protocol for heave, roll and pitch

Platform: **OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700, SMART7-S**

This log provides heave, roll and pitch information in TSS1 protocol.



This message is in a different format than any other log output by the SPAN system.

Message ID: 1456

Log type: Synch

Recommended input:

```
log tss1a ontime 1
```

Message format:

```
:XXAAAASMHHHHQMRRRRSMPPPP<CR><LF>
```

ASCII example:

```
:00FFCA -0003F-0325  0319
```

Field	Field type	Description	Symbol	Example
1	Log header	TSS1 header	:	:
2	Horizontal Acceleration	Horizontal acceleration from 0 to 9.81 m/s^2. Shown as a one byte unsigned hex number where the least significant bit = 3.83 cm/s^2.	XX	00
3	Vertical Acceleration	Vertical acceleration from -20.48 to +20.48 m/s^2. Shown as a two byte hex number where the least significant bit = 0.0625 cm/s^2.	AAAA	FFCA
4	Space Character	A space delimiter.	S	
5	Heave Polarity	Space if positive. Minus sign (-) if negative.	M	-
6	Heave	Heave value from -99.99 to +99.99 m. Shown as a four digit integer where the least significant bit = 0.01 m.	HHHH	0003
7	Status Flag	F if INS Active. H if INS has not completed an alignment.	Q	F
8	Roll Polarity	Space if positive. Minus sign (-) if negative.	M	-

Field	Field type	Description	Symbol	Example
9	Roll	Roll value from -99.99 to +99.99 degrees. Shown as a four digit integer where the least significant bit = 0.01 degrees.	RRRR	0325
10	Space Character	A space delimiter.	S	
11	Pitch Polarity	Space if positive. Minus sign (-) if negative.	M	
12	Pitch	Pitch value from -99.99 to +99.99 degrees. Shown as a four digit integer where the least significant bit = 0.01 degrees.	PPPP	0319
13	[CR][LF]	Sentence terminator	<CR><LF>	

5.51 VARIABLELEVERARM

Display variable lever arm details

Platform: OEM719, OEM729, OEM7500, OEM7600, OEM7700, OEM7720, PwrPak7, CPT7, CPT7700

Use this log to redisplay the re-calculated variable lever arm whenever a new **INPUTGIMBALANGLE** command is received. This message is output in the IMU body frame.

The **VARIABLELEVERARM** log will not be published or used internally unless a **SETINSROTATION RBM** command is sent. See the **SETINSROTATION** command on page 1079.

This log should only be requested with the ONCHANGED or ONNEW trigger.

Message ID: 1320

Log type: Asynch

Recommended input:

```
log variableleverarma onnew
```

ASCII example:

```
#VARIABLELEVERARMA,USB1,0,63.5,FINESTEERING,2209,494406.137,02000020,4efe,16809
;0.000,0.000,0.000,0.000,0.000,0.000*25915585
```

Field	Field type	Description	Format	Binary bytes	Binary offset
1	Log header	VARIABLELEVERARM header For information about log headers, see *ASCII* on page 35, *Abbreviated ASCII* on page 37 or *Binary* on page 39.	-	H	0
2	XOffset	IMU body frame x-axis offset	Double	8	H
3	YOffset	IMU body frame y-axis offset	Double	8	H+8
4	ZOffset	IMU body frame z-axis offset	Double	8	H+16
5	XUncert	X-axis uncertainty in metres	Double	8	H+24
6	YUncert	Y-axis uncertainty in metres	Double	8	H+32
7	ZUncert	Z-axis uncertainty in metres	Double	8	H+40
8	xxxx	32-bit CRC (ASCII, Binary and Short Binary only)	Hex	4	H+48
9	[CR][LF]	Sentence terminator (ASCII only)	-	-	-

Chapter 6 Responses

The receiver is capable of outputting several responses for various conditions. Most responses are error messages to indicate when something is not correct.

The output format of the messages is dependent on the format of the input command. If the command is input as abbreviated ASCII, the output will be abbreviated ASCII. The same rule applies for both ASCII and binary formats.

Table 304: Response messages

ASCII message	Binary message ID	Meaning
OK	1	Command was received correctly
Requested log does not exist	2	The log requested does not exist
Not enough resources in system	3	The request has exceeded a limit (for example, the maximum number of logs are being generated)
Data packet doesn't verify	4	Data packet is not verified
Command failed on receiver	5	Command did not succeed in accomplishing requested task
Invalid Message ID	6	The input message ID is not valid
Invalid Message. Field = x	7	Field *x* of the input message is not correct
Invalid Checksum	8	The checksum of the input message is not correct. Only applies to ASCII and binary format messages.
Message missing field	9	A field is missing from the input message
Array size for field x exceeds max	10	Field *x* contains more array elements than allowed
parameter x is out of range	11	Field *x* of the input message is outside the acceptable limits
Message Id already exists in system	12	Message Id already exists in system
Debug token unknown	13	Debug token unknown
Trigger x not valid for this log	14	Trigger type *x* is not valid for this type of log
Authcode table full - Reload Software	15	Too many auth-codes are stored in the receiver. The receiver firmware must be reloaded

ASCII message	Binary message ID	Meaning
Invalid date format	16	This error is related to the inputting of auth-codes. Indicates the date attached to the code is not valid
Invalid Authcode entered	17	The auth-code entered is not valid
No matching model to remove	18	The model requested for removal does not exist
Not valid Auth code for that Model	19	The model attached to the auth-code is not valid
Channel is invalid	20	The selected channel is invalid
Requested rate is invalid	21	The requested rate is invalid
Word has no mask for this type	22	The word has no mask for this type of log
Channels locked due to error	23	Channels are locked due to error (the receiver must be reset or power cycled to track satellites again)
Injected time invalid	24	Injected time is invalid
Com port not supported	25	The COM or USB port is not supported
Message is incorrect	26	The message is invalid
Invalid PRN	27	The PRN is invalid
PRN not locked out	28	The PRN is not locked out
PRN lockout list is full	29	PRN lockout list is full
PRN already locked out	30	The PRN is already locked out
Message timed out	31	Message timed out
Unknown COM port requested	33	Unknown COM or USB port requested
Hex string not formatted correctly	34	Hex string not formatted correctly
Invalid baud rate	35	The baud rate is invalid
Message is invalid for this model	36	Message is invalid for this model of receiver

ASCII message	Binary message ID	Meaning
Could Not Save Configuration	38	Could Not Save Configuration
Too Many Configuration Items	39	Too Many Configuration Items
Command only valid if in NVM Fail mode	40	Command is only valid if NVM is in fail mode
Invalid offset	41	The offset is invalid
File conflict	43	File conflict
File not found	44	File not found
File open	45	File open
File not open	46	File not open
Invalid DOS FileName	47	Invalid DOS File name
File channel in use	48	File channel in use
File close fail	50	File close fail
Disk not present	51	Disk not present
Disk error	52	Disk error
Disk full	53	Disk full
NVM Write Fail	74	NVM Write Fail
NVM Read Fail	75	NVM Read Fail
Not allowed for input	77	Not allowed for input
Maximum number of user messages reached	78	Maximum number of user messages has been reached
User message decryption failed	79	User message decryption failed
GPS precise time is already known	84	GPS precise time is already known
The message could not be created	87	The message could not be created
Not enough memory to start application	113	Not enough memory to start application

ASCII message	Binary message ID	Meaning
No data available	114	No data available
Invalid handshaking	117	Invalid handshaking
Message name already exists	118	Message name already exists
Invalid message name	119	Invalid message name
The datatype is invalid	120	The data type is invalid
Message ID is reserved	121	Message ID is reserved
Message size too large	122	Message size too large
Invalid Security Key	126	Invalid security key
Hardware not available	127	Hardware not available
Requested pulse width is invalid	131	Requested pulse width is invalid
Coarse time is not achieved yet	133	Coarse time is not achieved yet
Invalid Config Code	134	Invalid Config Code
ConfigCode table full - Reload Software	135	Config Code table is full. Reload the software.
Unknown Object Type	136	Unknown object type
This operation is not valid at this time	137	This operation is not valid at this time
User VARF in use	140	User VARF in use
Must enable CLOCKADJUST	141	Must enable CLOCKADJUST. See the **CLOCKADJUST** command on page 117 for information about enabling.
Disk busy	142	Disk busy
Invalid Word Input Argument	143	Invalid Word Input Argument
Parameter %d is not valid for this model	148	The parameter specified is not valid for this model

ASCII message	Binary message ID	Meaning
IMU SPECS LOCKED FOR THIS IMU TYPE	150	SPAN allows the default specifications for a select few IMUs to be modified to support different variants. However, most IMU specifications are not allowed to change.
Invalid interface mode. Parameter %d	151	The specified Interface mode parameter is not valid.
COMMAND INVALID FOR THIS IMU	154	The entered command cannot be used with the configured IMU. For example, the **INSCALIBRATE ANT1** command is not valid for lower quality IMUs.
IMU protocol is locked for this IMU type	155	IMU protocol is locked for this IMU type
IMU TYPE IS NOT SUPPORTED WITH CURRENT MODEL	157	A firmware model upgrade is required to use the requested IMU (**CONNECTIMU** command on page 1041).
Trigger start time is invalid	159	Trigger start time is invalid
Sensor is not initialized	160	Sensor is not initialized
TRIGGER BUFFER IS FULL	161	The **TIMEDEVENTPULSE** command (see page 1094) limit of 10 events has been reached, and a new event cannot be set until an event is cleared.
Board has not achieved finesteering	162	The receiver has not achieved finesteering
SETUPSENSOR COMMAND IS LOCKED	163	The **SETUPSENSOR** command (see page 1091) cannot be modified because there are remaining trigger events queued.
Invalid Profile Name	165	Invalid Profile Name
Maximum Number Profiles Exceeded	166	The maximum number of profiles is exceeded
Failed To Delete Profile	167	Failed to delete the profile
Profile Name Already Exists	168	Profile name already exists
Total Profile Commands Size Over Limit	169	Total Profile commands size over limit

ASCII message	Binary message ID	Meaning
Cannot Change Profile When Activated	170	Cannot change a Profile when it is activated
Signature Authcode Copy Fail	171	Signature auth-code copy fail
Maximum Number of Profile Commands Exceeded	172	The maximum number of **PROFILE** commands exceeded
Profile Active, Could Not Save Configuration	173	Profile active, could not save configuration
Current PPP position has bad status and cannot be used for seeding	178	Current PPP position has bad status and cannot be used for seeding
PPP seed position failed integrity check	179	PPP seed position failed integrity check
Invalid password	180	Invalid password
Too many files	181	Too many files
Encryption key output is not allowed	186	Encryption key output is not allowed
Secure port requires login	187	Secure port requires login
NMEA2000/J1939 stack is already running on the CAN port	188	NMEA2000/J1939 stack is already running on the CAN port
No saved PPP seed position	191	No saved PPP seed position
System type is invalid for this model	192	System type is invalid for this model
Command is not supported for this model	193	Command is not supported for this model

ASCII message	Binary message ID	Meaning
Position Averaging Not Started	194	Position averaging not started
Not in GLIDE mode	200	Not in GLIDE mode
PPP seeding invalid in forced dynamics mode	201	PPP seeding invalid in forced dynamics mode
Wrong combination of parameters	202	Wrong combination of parameters
Invalid Calibration Request	203	Invalid calibration request
Active Gimbal Detected	204	Active gimbal detected
Authcode table full - Use auth erase_ table	205	Auth-code table full. An auth-code must be removed before another auth-code can be added. Refer to the **AUTH** command (see page 85) for instructions on removing auth-codes and cleaning up the auth-code table.
Profile Not Running - Profile should be activated	206	Profile not running - Profile should be activated
ID provided is already in use	208	ID provided is already in use
ID provided does not exist	209	ID provided does not exist
Calibration already in progress	210	Calibration already in progress
Filter cannot be enabled due to channel speed settings	211	Filter cannot be enabled due to channel speed settings
Notch Filter and Frequency are mismatching	212	Notch filter and frequency are mismatching
Filter can not cascade	213	Filter can not cascade
There is no RF filter applied	214	There is no RF filter applied

ASCII message	Binary message ID	Meaning
ID provided should be 4 character long	215	ID provided should be 4 characters long
Invalid subscription code	216	Invalid subscription code
Subscription table full	217	Subscription table full
Network id does not match subscription code	218	Network ID does not match the subscription code
Subscription not found	219	Subscription not found
Subscription not active	220	Subscription not active
Cannot activate expired subscription	221	Cannot activate expired subscription
Maximum number of logs exceeded. No new log added.	222	Maximum number of logs exceeded. No new log added.
Seed is too far in the past	223	Seed is too far in the past
Final log request must use the ONCE trigger	224	Final log request must use the ONCE trigger
Channel invalid for region x	225	Channel invalid for region x
Region not set	226	Region not set
Estimated RBV must be entered first	227	Initial RBV estimate is required before RBV calibration
Command failed because WIFIALIGNAUTOMATION is enabled	240	Command failed because WIFIALIGNAUTOMATION is enabled. See the **WIFIALIGNAUTOMATION** command on page 476.
Specified network not enabled with WIFINETCONFIG command	241	Specified network not enabled with WIFINETCONFIG command. See the **WIFINETCONFIG** command on page 486.

ASCII message	Binary message ID	Meaning
RESPONSE_DISPATCH_PSN_MISMATCH	271	Message is not for this receiver.
RESPONSE_DISPATCH_CHECK_FAIL	272	Message has been corrupted or is incomplete.
RESPONSE_DISPATCH_RETIRED	273	Message is older than the current message.
RESPONSE_DISPATCH_INVALID	274	The content of the message is not understood.
RESPONSE_DISPATCH_INVALID_FOR_INPUT	275	Message is not the right type to input to this receiver.
RESPONSE_DISPATCH_INPUT_LOCKED	276	Too many invalid messages recently, pause a few seconds.
RESPONSE_DISPATCH_INVALID_MODEL	281	A model specified is incompatible with this hardware.
Login temporarily suspended. (%d)	282	An incorrect password has been entered more than 5 times in a row and logins have been suspended for 5 or 10 seconds. Note that the consecutive incorrect password count is accumulated across all ports and all commands that use the Admin Password.
New password is unacceptable	283	When changing the password, the new password does not meet the password requirements.
RESPONSE_DISPATCH_UNSUPPORTED_SERVICE	285	A service is not compatible with this firmware version.

Appendix A Example of bit parsing a RANGECMP4 log

The following takes a sample RANGECMP4 log and breaks it down into its raw components.

Data was captured in both RANGE and in RANGECMP4 logs which are shown here for reference. These logs were captured at a rate of 4 Hz such that the Reference and Differential parts of the RANGECMP4 could be explained.

Some of the RANGECMP4 values will have some very slight differences (at the millicycle level) compared to the equivalent RANGE log data due to truncating the double values into integers.

Here are two RANGE logs to reference against once the RANGECMP4 logs have been determined:

```
RANGE COM1 0 88.5 FINESTEERING 1919 507977.000 02000020 5103 32768
 22
  27 0 21761200.335 0.036 -114355879.993103 0.006 1121.758 50.0 876.785 18109c04
  27 0 21761202.795 0.128 -89108485.029683 0.007 874.097 44.2 862.386 11303c0b
  27 0 21761200.306 0.007 -85395622.838987 0.004 837.685 51.7 865.845 01d03c04
  21 0 21214757.684 0.027 -111484302.588995 0.005 -1107.624 52.6 888.968
08109c24
  21 0 21214757.049 0.122 -86870882.607297 0.006 -863.084 44.6 874.389 01303c2b
  10 0 21540290.811 0.027 -113194996.162910 0.005 2288.688 52.6 889.905 08109c44
  10 0 21540293.632 0.110 -88203904.731314 0.006 1783.394 45.6 868.725 01303c4b
  10 0 21540289.869 0.006 -84528728.138216 0.004 1709.022 53.0 872.386 01d03c44
  15 0 21776375.653 0.032 -114435625.391762 0.007 -1814.485 50.9 879.586
18109c64
  15 0 21776376.038 0.129 -89170616.457446 0.007 -1413.886 44.1 862.706 11303c6b
  18 0 20493192.703 0.031 -107692454.149639 0.007 212.747 51.1 891.550 08109c84
  18 0 20493191.933 0.105 -83916195.494946 0.007 165.777 45.9 874.710 01303c8b
  61 9 20375330.794 0.104 -108956045.737322 0.006 -3039.481 46.8 891.931
08119ca4
  61 9 20375332.806 0.083 -84743599.055547 0.007 -2364.042 34.0 876.813 00b13cab
  55 4 22748433.080 0.146 -121432681.638722 0.009 4061.119 43.9 416.032 18119cc4
  55 4 22748438.602 0.021 -94447660.068923 0.009 3158.651 46.0 415.562 00b13ccb
  38 8 19781617.845 0.058 -105744080.698106 0.004 -2024.611 51.8 893.563
18119ce4
  38 8 19781623.453 0.032 -82245418.313339 0.005 -1574.698 42.2 878.833 00b13ceb
  39 3 19968976.955 0.055 -106558290.405759 0.004 2248.713 52.3 875.210 08119d04
  39 3 19968980.676 0.019 -82878686.553631 0.005 1749.000 46.9 870.890 00b13d0b
  54 11 19507573.213 0.059 -104388964.028915 0.005 1289.410 51.8 894.613
08119d24
  54 11 19507576.477 0.017 -81191427.275619 0.004 1002.874 48.0 878.832 10b13d2b


RANGE COM1 0 88.5 FINESTEERING 1919 507977.250 02000020 5103 32768
 22
  27 0 21761146.982 0.036 -114355599.642256 0.006 1121.140 49.9 877.035 18109c04
  27 0 21761149.447 0.122 -89108266.573995 0.007 873.616 44.6 862.636 11303c0b
  27 0 21761146.957 0.007 -85395413.484293 0.004 837.294 51.8 866.095 01d03c04
  21 0 21214810.390 0.027 -111484579.560955 0.005 -1108.100 52.6 889.218
08109c24
  21 0 21214809.754 0.120 -86871098.429369 0.005 -863.454 44.8 874.639 01303c2b
```

```
  10 0 21540181.949 0.027 -113194424.080322 0.005 2288.176 52.6 890.155 08109c44
  10 0 21540184.767 0.111 -88203458.952394 0.006 1782.995 45.4 868.975 01303c4b
  10 0 21540181.003 0.006 -84528300.928648 0.004 1708.751 53.0 872.636 01d03c44
  15 0 21776461.990 0.032 -114436079.084785 0.006 -1814.956 50.9 879.836
18109c64
  15 0 21776462.375 0.129 -89170969.984233 0.007 -1414.253 44.1 862.956 11303c6b
  18 0 20493182.598 0.031 -107692401.054068 0.007 212.183 51.2 891.800 08109c84
  18 0 20493181.833 0.110 -83916154.122137 0.007 165.338 45.6 874.960 01303c8b
  61 9 20375472.914 0.104 -108956805.696703 0.006 -3040.142 46.9 892.181
08119ca4
  61 9 20375474.924 0.084 -84744190.134355 0.007 -2364.555 33.9 877.063 00b13cab
  55 4 22748242.897 0.150 -121431666.427728 0.009 4060.804 43.7 416.282 18119cc4
  55 4 22748248.421 0.021 -94446870.460803 0.009 3158.405 46.0 415.812 00b13ccb
  38 8 19781712.549 0.059 -105744586.938646 0.004 -2025.149 51.8 893.813
18119ce4
  38 8 19781718.158 0.032 -82245812.055601 0.005 -1575.117 42.3 879.083 00b13ceb
  39 3 19968871.615 0.055 -106557728.318448 0.004 2248.162 52.3 875.460 08119d04
  39 3 19968875.343 0.019 -82878249.374953 0.005 1748.571 46.8 871.140 00b13d0b
  54 11 19507512.994 0.059 -104388641.780659 0.005 1288.778 51.7 894.863
08119d24
  54 11 19507516.256 0.016 -81191176.637999 0.005 1002.383 48.1 879.082 10b13d2b
```

Here are the equivalent RANGECMP4 logs which will be broken down into their individual components:

```
#RANGECMP4A,COM1,0,88.5,FINESTEERING,1919,,02000020,fb0e,32768;295,030000421204
000000009200df7688831f611fd87ca0b03a00638bbdf7b82f49b080fd0ec0ff1f091f8214ff4d4
d00a1009cbf1751f6911f5141f87fd9571a96dbd7040c8090f87f0080fcf722fe9bfa8a49a8ff4f
299d7f96fb9afefc771800fcffd0063f02cde01f3c7dd3ffb75240886f5fa2b0ff91f57f00003ed
f8b78868c882878014065dbf7d3ed6b722680d5fc0f00a4c08730fe7fecf8bffa3f003008000000
002001f03fa019f8136a11273649b8fcefab9c434c7b89e71560dbfe070030b2e04fd841f331253
20b80b0ecefa5ee21243ac0bb03e0ffc36a813fb13bbe5791a0f5ff9e3bdbffbb87f0cb8064f03f
0000e4b67dd15bc5f4a50a3a006ca72fdee53ec86405b2c0fffa3fa450f725d5bfed7c49b1fb0fb
16b45a87a9adb0740cbfe0700*8e963cf1

#RANGECMP4A,COM1,0,88.5,FINESTEERING,1919,,02000020,fb0e,32768;239,030000421204
000000009200dff688831f6102005500e70162dc977c004015c07988840f6101803a805921cedf8
b80002011207080e5f6351f003804081c2200be0808005c01620808725f93028057801822dae047
6000a00f207180fef6251700e803401c62f3bdc80600520130099 86f5f22020054004ca2053ec40
8005401ca870180410000000000980ff6306fec408004801de07c8692f5102805180f721b2e04f
600040152081804ef710250060054020220 5fe040a0086013a0938780f61020061804e224edbdb6
8002010c0498030f7411d0018047812a2d47d090a004c01a609c8544f62028052006a02*c3edfd02
```

A.1 Reference log decoding

The RANGECMP4 log at time 507977.0 will be decoded first:

```
#RANGECMP4A,COM1,0,88.5,FINESTEERING,1919,507977.000,02000020,fb0e,32768;295,
03000042120400000009200df7688831f611fd87ca0b03a00638bbdf7b82f49b080fd0ec0ff1f0
91f8214ff4d4d00a1009cbf1751f6911f5141f87fd9571a96dbd7040c8090f87f0080fcf722fe9b
fa8a49a8ff4f299d7f96fb9afefc771800fcffd0063f02cde01f3c7dd3ffb75240886f5fa2b0ff9
1f57f00003edf8b78868c882878014065dbf7d3ed6b722680d5fc0f00a4c08730fe7fecf8bffa3f
003008000000002001f03fa019f8136a11273649b8fcefab9c434c7b89e71560dbfe070030b2e04
fd841f33125320b80b0ecefa5ee21243ac0bb03e0ffc36a813fb13bbe5791a0f5ff9e3bdbffbb87
f0cb8064f03f0000e4b67dd15bc5f4a50a3a006ca72fdee53ec86405b2c0fffa3fa450f725d5bfe
d7c49b1fb0fb16b45a87a9adb0740cbfe0700*7DD8F893
```

Since this log falls on a whole second (507977.000), it is a Reference log.

At the start of the RANGECMP4 log is the identifier for how many bytes are in the log. In this case, there are 295 bytes. The rest of the message is compressed binary data and is transmitted as LSB first so the bytes must be swapped before processing.


A.1.1 Reference header

The Reference Header is sent once per message. See *Table 194: Header* on page 853 in the RANGECMP4 log section.

Decoding the bits starting with the first bytes:

GNSS Field (16 bits)

- Grab the first 2 bytes (16 bits) = 0x0300
- Swap the bytes = 0x0003
- 0x0003 in binary form = 0000 0000 0000 0011




In this example the receiver was configured to track only GPS and GLONASS systems. If other systems had been in the configuration and tracked, they would have shown here.

A.1.2 Reference satellite and signal block: GPS

This block is sent once for each bit set to 1 in the GNSS field (See *Table 194: Header* on page 853). As identified by the above GNSS field, the first system (right to left) is the GPS System. Use *Table 195: Satellite and signal block* on page 853 to determine what satellites and signals data are contained in this GPS system:

GPS Satellites field (64 bits)


- Grab the next 8 bytes (64 bits) = 0x0042120400000000
- Swap the bytes = 0x0000000004124200
- 0x0000000004124200 in binary form =



- The 1's above identify that there are 5 tracking GPS PRNs.

GPS Signals field (16 bits)

- Grab the next 2 bytes (16 bits) = 0x9200
- Swap the bytes = 0x0092
- 0x0092 in binary form =



- The 1's above identify that there are 3 tracking GPS signals: L1CA, L2Y, and L5Q.

GPS Included Signals field (5 PRNs x 3 Signals = 15 bits – Therefore need 2 bytes)

- Up to the point of processing the Included Signals field, the bytes are aligned such that the bits start and end within each batch of bytes. After processing this step, it is quite common for the Included Signals Field (mxn matrix) to not be divisible by 8 so bytes not processed will need to be carried over to the next section depending on the size of the matrix.
- Grab the next 2 bytes (16 bits) = 0xdf76
- Swap the bytes = 0x76df
- 0x76df in binary form = 0111011011011111
- Only need 15 of the 16 bits = X111011011011111
- This bit string breaks down into 5 rows (PRNs) and 3 columns (signals) as specified by the mxn (PRN x signals) parameters. Take the bit string and break it up into sets of 3 starting at the MSB. This will result with the lowest PRN being at the bottom row of the stack and the first signal (L1CA) being the far right column.

```
111
011
011
011
111
```

- This stack can be further broken apart to identify the PRNs vs. their Signals:

```
PRN    L5Q   L2Y   L1CA
27     1     1     1
21     0     1     1
18     0     1     1
15     0     1     1
10     1     1     1
```

A.1.3 Reference measurement block header: GPS

This block is sent once for each bit set to 1 in the Satellites field found in *Table 195: Satellite and signal block* on page 853. Now that the PRN's signals have been determined, the next step is to determine the specifics of the first PRN (10) and its list of signals (L1CA, L2Y, L5Q). Working from bottom right to upper left of the PRN/Signal chart above, each 1 represents a signal for a PRN. Use *Table 196: Measurement block header* on page 854 to determine the contents of each field:

GPS PRN 10 (first PRN found in the Satellites field)

We will grab enough bytes to process the whole Measurement Block Header. If this was a GLONASS System, a total of 9 bits would be required for this step (1 bit for the Data Format Flag, 3 bits for the Ref Data Block ID, plus 5 bits for the GLONASS Frequency Number). Since this is a GPS system, only 4 bits in total are required (1 bit for the Data Format Flag and 3 bits for the Ref Data Block ID).

There was 1 bit not processed in the last byte so that byte will be carried forward. Only 4 bits need to be looked at for this step so grab the next byte as well:

- Use the last byte (0x76) plus the next byte (0x88)= 0x7688
- Swap the bytes = 0x8876
- 0x8876 in binary form = 1000100001110110
- Ignore the 7 processed bits from the last step = 100010000XXXXXXX
- Ignore the 5 MSB bits leaving 4 bits for processing =

```
XXXXX0000XXXXXXX
     0          = Data Format Flag (1 bit)
   000          = Ref Data Block (3 bits)
```

The Data Format Flag identifies that this batch of data is Reference (0) data.
The Ref Data Block ID is 0x000.



The 5 MSBs have not been processed so this byte will be carried forward.

The Data Format Flag identifies if the upcoming data is Reference or Differential data. By default every log that was published on a whole second will always be Reference logs. Logs between seconds will be Differential logs but could be Reference logs depending on the compression calculations. If a discontinuity occurred that made it impossible for a Differential calculation to fit within the Differential Constraints, it will revert to a Reference log.

A.1.4 Reference measurement block: GPS

This block is sent once for each bit set to 1 in the Included Signals Field found in *Table 195: Satellite and signal block* on page 853. Use *Table 197: Primary reference signal measurement block* on page 855 and *Table 198: Secondary reference signals measurement block* on page 856 to determine the contents of each field:

A Measurement Block for a single PRN will look like the following:

Primary Parity Flag

Primary ½ Cycle Slip Flag

Primary C/No

Primary Lock Time

Primary Pseudorange Std Deviation

Primary Phaserange Std Deviation

Primary Pseudorange

Primary Phaserange - Primary Pseudorange (determines the Phaserange for the 1st Signal)

Primary Doppler

2nd Parity Flag

2nd ½ Cycle Slip Flag

2nd C/No

2nd Lock Time

2nd Pseudorange Std Deviation

2nd Phaserange Std Deviation

2nd Pseudorange - Primary Pseudorange (determines the Pseudorange for the 2nd Signal

2nd Phaserange - 2nd Pseudorange (determines the Phaserange for the 2nd Signal)

2nd Doppler - Primary Doppler (determines the Doppler for the 2nd Signal)

3rd Parity Flag

3rd ½ Cycle Slip Flag

3rd C/No

3rd Lock Time

3rd Pseudorange Std Deviation

3rd Phaserange Std Deviation

3rd Pseudorange - Primary Pseudorange (determines the Pseudorange for the 3rd Signal

3rd Phaserange - 3rd Pseudorange (determines the Phaserange for the 3rd Signal)

3rd Doppler - Primary Doppler (determines the Doppler for the 3rd Signal)

…

A.1.5 Reference primary signal measurement block: GPS PRN 10 – L1CA

The next bytes collected will be for the GPS PRN 10 - L1CA signal data. This is the primary signal of the PRN since it is the first signal. As a result, its Measurement Block consists of 111 bits as listed in *Table 197: Primary reference signal measurement block* on page 855. Since 111 bits takes up a lot of space, these bits will be split into two groups from *Table 197: Primary reference signal measurement block* on page 855: the top 25 bits for signal info followed by the bottom 86 bits for signal data.

The signal info section (top 25 bits) is processed as follows:

- With 5 bits left unprocessed from the previous byte, we calculate 25 – 5 = 20 bits which rounds up to 3 bytes. Therefore the previous last byte (0x88) plus the next 3 bytes will be needed.
  - Use the last byte (0x88) plus grab 3 bytes (x831f61) = 0x88831f61
  - Swap the bytes = 0x611f8388
  - 0x611f8388 in binary form = 01100001000111111000001110001000
  - The previous step used the 3 LSBs = 01100001000111111000001110001XXX
  - 25 bits are needed so ignore the 4 MSBs =

```
XXXX00010001111110000011100 01XXX
                          1     = Parity Flag
                         0      = ½ Cycle Slip Flag
                10000011100     = C/No
            1111                = Lock Time
        0001                    = Pseudorange Std Deviation
    0001                        = Phaserange Std Deviation
```

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 0 (Cycle Slip Not Present)
- C/No is:
  0x10000011100b = 1052 x Scaling Factor of 0.05
  = 52.60 dBHz

- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0001b = 1 which means: 0.020 m < PSR Std Dev <= 0.030 m using *Table 204: Pseudorange Std Dev* on page 862.
- The ADR Std Deviation value is:
  0x0001b = 1 which means: 0.0039 < ADR Std Dev <= 0.0052 cycles using *Table 203: ADR Std Dev* on page 861.

The signal data section (bottom 86 bits) is processed as follows:

- With 4 bits unprocessed from the previous byte, we calculate 86 – 4 = 82 bits = 11 bytes (2 bits will not be processed in the last byte).
  - Use the last byte (0x61) plus grab 11 bytes (0x1fd87ca0b03a00638bbdf7)
    = 0x611fd87ca0b03a00638bbdf7
  - Swap the bytes = 0xf7bd8b63003ab0a07cd81f61
  - 0xf7bd8b63003ab0a07cd81f61 in binary form =
    111 0111 1011 1101 1000 1011 0110 0011 0000 0000 0011 1010 1011 0000 1010 0000 0111 1100 1101 1000 0001 1111 0110 0001
  - Only need 86 bits. Ignore last 4 LSBs and first 6 MSBs =

```
xxxx xx11 1011 1101 1000 1011 0110 0011 0000 0000 0011 1010 1011 0000 1010 0000 0111 1100 1101 1000 0001 1111 0110 xxxx
                                                    0 1010 0000 0111 1100 1101 1000 0001 1111 0110      = 1st Pseudo
                                  0000 0000 0011 1010 1011 000                                          = 1st Phase - 1st Pseudo
       11 1011 1101 1000 1011 0110 0011                                                                 = 1st Doppler
```

- Use *Table 197: Primary reference signal measurement block* on page 855 to identify if a 2's Complement Conversion is needed as well as what Scale Factor should be used before these binary numbers are used in the following calculations.
- The 1st (Primary) Pseudorange is processed by:

  1st Pseudorange = 0x01010000001111100110110000000111110110b x Scaling Factor
  1st Pseudorange = 43080581622 x 0.0005
  L1CA Pseudorange for PRN 10= 21540290.811 m
- The 1st (Primary) Phaserange is a 2's Complement number (as identified by the Range column in *Table 197: Primary reference signal measurement block* on page 855) so it is processed in the following manner:

  1st Phaserange – 1st Pseudorange = 2's Complement(0x000000000011101010011000b) * Scaling Factor
  1st Phaserange – 21540290.811 m = 7512 * 0.0001
  L1CA Phaserange = 21540291.5622 m
- Convert this to ADR to check against the original RANGE log:

  ADR = 1st Phaserange * Frequency * (-1)/Speed Of Light
  ADR = 21540291.5622 m * 1575420000 Hz * (-1)/299792458 m/s
  L1CA ADR for PRN 10 = -113194996.1627158 cycles

  In the range logs, PSR and ADR have opposite signs.
- The 1st (Primary) Doppler is a 2's Complement number (as identified by the Range column in *Table 197: Primary reference signal measurement block* on page 855) so it is processed in the following manner:

1st Doppler(m/s) = 2's Complement(0x11101111011000101101100011b) x Scaling Factor
1st Doppler(m/s) = -4,355,229 x 0.0001
L1CA Doppler(m/s) = -435.5229 m/s

Convert the Doppler to Hz:

1st Doppler(Hz) = 1st Doppler(m/s) x Frequency * (-1)/Speed Of Light
L1CA Doppler(Hz) for PRN 10 = 2288.6883 Hz
1st Doppler(Hz) = -435.5229 m/s x 1575420000 Hz * (-1)/299792458 m/s

A.1.6 Reference secondary signals measurement block: GPS PRN 10 – L2Y

Signal L1CA was the 1st signal (Primary Signal) of the three PRN 10 signals found in this RANGECMP4 log data. L1CA's data is now used to determine the L2Y's signals data. Since this is the second signal block of this PRN, its data will be processed by using *Table 198: Secondary reference signals measurement block* on page 856.

With 6 bits left unprocessed from the previous byte, we will require 82 – 6 = 76 bits which rounds up to 10 bytes.

- Use the last byte (0xf7) plus grab the next 10 bytes (0xb82f49b080fd0ec0ff1f)
  = 0xf7b82f49b080fd0ec0ff1f
- Swap the bytes = 0x1fffc00efd80b0492fb8f7
- 0x1fffc00efd80b0492fb8f7 in binary form =
  0001 1111 1111 1111 1100 0000 0000 1110 1111 1101 1000 0000 1011 0000 0100 1001 0010 1111 1011 1000 1111 0111
- Only need 78 bits. The 2 LSBs are ignored as they were already processed above and the 4 MSBs are ignored so there is a total of 82 bits to process

```
xxxx 1111 1111 1111 1100 0000 0000 1110 1111 1101 1000 0000 1011 0000 0100 1001 0010 1111 1011 1000 1111 01xx
                                                                                                        1   = Parity Flag
                                                                                                       0    = ½ Cycle Slip Flag
                                                                                        011 1000 1111       = C/No
                                                                                 111 1                      = Lock Time
                                                                           010 1                            = Pseudorange Std Deviation
                                                                     001 0                                  = Phaserange Std Deviation
                                                          000 0000 1011 0000 0100 1                         = Pseudo - 1st Pseudo
                                  00 0000 0000 1110 1111 1101 1                                             = Phase - Pseudo
    1111 1111 1111 11                                                                                       = Doppler - 1st Doppler
```

Use *Table 198: Secondary reference signals measurement block* on page 856 to identify if a 2's Complement Conversion is needed as well as what Scale Factor should be used before these binary numbers are used in the following calculations.

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 0 (Cycle Slip Not Present)
- C/No is:
  0x01110001111b = 911 x Scaling factor of 0.05
  = 45.55 dBHz
- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0101b = 5 which means: 0.099 m < PSR Std Dev <= 0.148 m using *Table 204: Pseudorange Std Dev* on page 862.
- The ADR Std Deviation value is:
  0x0010b = 2 which means: 0.0052 < ADR Std Dev <= 0.0070 cycles using *Table 203: ADR Std Dev* on page 861.

- The L2Y Pseudorange is a 2's Complement number (as identified by the Range column in *Table 198: Secondary reference signals measurement block* on page 856) so it is processed in the following manner:

  Pseudorange – 1st Pseudorange = 2's Complement(0x00000001011000001001b) x Scaling Factor
  Pseudorange – 21540290.811 m = 5641 x 0.0005
  L2Y Pseudorange = 21540293.6315 m

- The L2Y Phaserange is a 2's Complement number (as identified by the Range column in *Table 198: Secondary reference signals measurement block* on page 856) so it is calculated in the following manner:

  Phaserange – Pseudorange = 2's Complement(0x000000000011101111111011b) * Scaling Factor
  Phaserange – 21540293.6315 m = 7675 * 0.0001
  L2Y Phaserange = 21540294.399 m

- Convert this to ADR to check against the original RANGE log:

  ADR = Phaserange * Frequency * (-1)/Speed Of Light
  ADR = 21540294.399 m * 1227600000 Hz * (-1)/299792458 m/s
  L2Y ADR for PRN 10 = -88203904.73002626 cycles

  In the range logs, PSR and ADR have opposite signs.

- The L2Y Doppler is a 2's Complement number (as identified by the Range Column in *Table 198: Secondary reference signals measurement block* on page 856) so it is calculated in the following manner:

  Doppler(m/s) – 1st Doppler(m/s) = 2's Complement(0x11111111111111b) x Scaling Factor
  Doppler(m/s) – (-435.5229 m/s) = (-1) x 0.0001
  L2Y Doppler(m/s) = -435.5228 m/s

  Convert the Doppler to Hz:

  Doppler(Hz) = Doppler(m/s) x Frequency * (-1)/Speed Of Light
  Doppler(Hz) = -435.5228 m/s x 1227600000 Hz * (-1)/299792458 m/s
  L2Y Doppler(Hz) for PRN 10 = 1783.3938 Hz

A.1.7 Reference third signals measurement block: GPS PRN 10 – L5Q

Signal L1CA was the 1st signal (Primary Signal) of the three PRN 10 signals found in this RANGECMP4 log data. L1CA's data is now used to determine the L5Q's signals data. Since this is the third signal block of this PRN, its data will be processed using *Table 198: Secondary reference signals measurement block* on page 856.

With 4 bits left unprocessed from the previous byte, we will require 82 – 4 = 78 bits which rounds up to 10 bytes.

- Use the last byte (0x1f) plus grab the next 10 bytes (0x091f8214ff4d4d00a100)
  = 0x1f091f8214ff4d4d00a100
- Swap the bytes = 0x00a1004d4dff14821f091f
- 0x00a1004d4dff14821f091f in binary form =
  0000 0000 1010 0001 0000 0000 0100 1101 0100 1101 1111 1111 0001 0100 1000 0010 0001 1111 0000 1001 0001 1111
- Only need 78 bits. The 4 LSBs are ignored as they were already processed above and the 2 MSBs are

ignored so there is a total of 82 bits to process

```
xx00 0000 1010 0001 0000 0000 0100 1101 0100 1101 1111 1111 0001 0100 1000 0010 0001 1111 0000 1001 0001 xxxx
                                                                                                      1      = Parity Flag
                                                                                                     0       = ½ Cycle Slip Flag
                                                                                          1 0000 1001 00     = C/No
                                                                                    1 111                    = Lock Time
                                                                              0 000                          = Pseudorange Std Deviation
                                                                        0 001                                = Phaserange Std Deviation
                                                  1 1111 1111 0001 0100 100                                  = Pseudo - 1st Pseudo
                                  0000 0000 0100 1101 0100 110                                               = Phase - Pseudo
  00 0000 1010 0001                                                                                          = Doppler - 1st Doppler
```

Use *Table 198: Secondary reference signals measurement block* on page 856 to identify if a 2's Complement Conversion is needed as well as what Scale Factor should be used before these binary numbers are used in the following calculations.

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 0 (Cycle Slip Not Present)
- C/No is:
  0x10000100100b = 1060 x Scaling Factor of 0.05
  = 53.00 dBHz
- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0000b = 0 which means: PSR Std Dev <= 0.020 m using *Table 204: Pseudorange Std Dev* on page 862.
- The ADR Std Deviation value is:
  0x0001b = 1 which means: 0.0039 < ADR Std Dev <= 0.0052 cycles using *Table 203: ADR Std Dev* on page 861.
- The L5Q Pseudorange is a 2's Complement number (as identified by Range column in *Table 198: Secondary reference signals measurement block* on page 856) so it is processed in the following manner:

  Pseudorange – 1st Pseudorange = 2's Complement(0x11111111100010100100b) x Scaling Factor
  Pseudorange – 21540290.811 m = (-1884) x 0.0005
  L5Q Pseudorange = 21540289.869 m
- The L5Q Phaserange is a 2's Complement number (as identified by the Range column in *Table 198: Secondary reference signals measurement block* on page 856) so it is calculated in the following manner:

  Phaserange – Pseudorange = 2's Complement(0x000000000100110101001l0b) * Scaling Factor
  Phaserange – 21540289.869 m = 9894 * 0.0001
  L5Q Phaserange = 21540290.8584 m
- Convert this to ADR to check against the original RANGE log:

  ADR = Phaserange * Frequency * (-1)/Speed Of Light
  ADR = 21540290.8584 m * 1176450000 Hz * (-1)/299792458 m/s
  L5Q ADR for PRN 10 = -84528728.13886692 cycles

  In the range logs, PSR and ADR have opposite signs.

- The L5Q Doppler is a 2's Complement number (as identified by the Range column *Table 198: Secondary reference signals measurement block* on page 856) so it is calculated in the following manner:

Doppler(m/s) – 1st Doppler(m/s) = 2's Complement(0x00000010100001b) x Scaling Factor
Doppler(m/s) – (-435.5229 m/s) = 80 x 0.0001
L5Q Doppler(m/s) = -435.5149 m/s

Convert the Doppler to Hz:

Doppler(Hz) = Doppler(m/s) x Frequency * (-1)/Speed Of Light
Doppler(Hz) = -435.5149 m/s x 1176450000 Hz * (-1)/299792458 m/s
L5Q Doppler(Hz) for PRN 10 = 1709.054 Hz

This concludes the processing of the signals present for PRN 10.

The next PRN as identified in the GPS Included Signals Field is PRN 15 with 2 signals. Processing of this data would be handled as described above, starting with the 4 bit Measurement Block followed by the individual signals. This would be followed by PRN 18, 21, and 27. Processing these remaining PRNs and their signals would use up the next 870 bits as shown below:

Bits required for remaining GPS PRNs and Signals:

PRN 15

- 4 bits Measurement Block header
- 111 bits - 1st Signal
- 82 bits - 2nd Signal

PRN 18

- 4 bits Measurement Block header
- 111 bits - 1st Signal
- 82 bits - 2nd Signal

PRN 21

- 4 bits Measurement Block header
- 111 bits - 1st Signal
- 82 bits - 2nd Signal

PRN 27

- 4 bits Measurement Block header
- 111 bits - 1st Signal
- 82 bits - 2nd Signal
- 82 bits - 3rd Signal

Total = 870 bits

There are 2 bits left unprocessed from the last byte of PRN 10's processing so 868 more bits (109 bytes) are required. After processing the remaining GPS data, there will be 4 bits left from the last byte to start off the next system (GLONASS as identified by the GNSS field in the Header).

After the last GPS bit, the GLONASS system will then be processed since it was identified as the next system by the GNSS field in the Header.


A.1.8 Reference satellite and signal block: GLONASS

This block is sent once for each bit set to 1 in the GNSS field found in *Table 194: Header* on page 853. As identified by the above GNSS field, the second system (right to left) is the GLONASS System. Use *Table 195:*

Satellite and signal block on page 853 to determine what satellites slots and signals data are contained in this GLONASS System:

GLONASS Satellites field (64 bits)

- Grab the next 8 bytes (64 bits) = 0x3f0030080000000020
- Swap the bytes = 0x20000000000830003f
- 0x20000000000830003f in binary form = 0010000000000000000000000000000000000000000010000011000000000000000111111
- Mask out the used 4 LSBs = 0010000000000000000000000000000000000000000010000011000000000000000011XXXX
- Determine the required 64 bits =



- The 1's above identify that there are 5 tracking GLONASS Slots.
- The present GLONASS satellite PRNs/Slot ID's (when between 1 to 24) are therefore (37 + Slot ID):

  Slot 1 = PRN 38

  Slot 2 = PRN 39

  Slot 17 = PRN 54


  Slot 18 = PRN 55

  Slot 24 = PRN 61

> If the GLONASS Slot ID was between 43 and 64, this would represent a GLONASS satellite that has an unknown Slot ID and is instead assigned a temporary one based upon 64 minus the unadjusted GLONASS Frequency Number (0 to 20). This Slot ID will be updated once the actual PRN/Slot ID has been determined.

GLONASS Signals field (16 bits)

- Append the next 2 bytes (0x01f0) to the last byte (0x20) = 0x2001f0
- Swap the bytes = 0x0f0120
- 0x0f0120 in binary form = 1111000000100100000
- Ignore the processed bits = 1111000000010010XXXX
- Determine the required 16 bits =



- The 1's above identify that there are 2 tracking GLONASS signals: L1CA and L2P.

GLONASS Included Signals field (5 Slot ID's x 2 Signals = 10 bits)

- Append the next byte (0x3f) to the last byte (0xf0) = 0xf03f
- Swap the bytes = 0x3ff0
- 0x3ff0 in binary form = 0011111111110000
- Ignore the processed bits = 001111111111XXXX
- Determine the required 10 bits = XX1111111111XXXX
- This bit string breaks down into 5 rows (Slots) and 2 columns (signals) as specified by the mxn (Slot IDs x signals) parameters. Take the bit string and break it up into sets of 2 starting at the MSB. This will result with the lowest Slot ID being at the bottom row of the stack and the first signal (L1CA) being the far right column.

  11

  11

  11

  11

  11

- This stack can be further broken apart to identify the Slot ID's vs. their Signals:

```
SLOT   L2P   L1CA
24     1     1
18     1     1
17     1     1
 2     1     1
 1     1     1
```

A.1.9 Reference measurement block header: GLONASS PRN 38

(Slot 1 which was the first Slot found in the Satellites Field)

We will grab enough bytes to process the whole Measurement Block Header. Since this is a GLONASS System, a total of 9 bits will be required for this step (1 bit for the Data Format Flag, 3 bits for the Ref Data Block ID, plus 5 bits for the GLONASS Frequency Number).

With 2 bits left unprocessed from the previous byte, we will require 9 – 2 = 7 bits which rounds up to 1 byte:

- Use the last byte (0x3f) plus the next byte (0xa0)= 0x3fa0
- Swap the bytes = 0xa03f
- 0xa03f in binary form = 1010000000111111
- Ignore the 6 processed bits from the last step = 1010000000XXXXXX
- Ignore the 1 MSB bits leaving 9 bits for processing =

```
X010000000XXXXXX
          0       = Data Format Flag (1 bit)
        000       = Ref Data Block (3 bits)
 01000            = GLONASS Freq Number (5 bits)
```

The Data Format Flag identifies that this batch of data is Reference (0) data.

The Ref Data Block ID is 0x000.

The GLONASS Frequency Number is 8 (adjusted to 1). When calculating the GLONASS Carrier frequency, this value (0 to 20) will be adjusted to its -7 to +13 value and then multiplied by that frequencies delta. Note that this field only appears in the Reference data and will not be found in the Differential data.

Special Case: When the Slot ID is between 43 and 63, the Slot ID of the GLONASS satellite is unknown. In order to keep track of which satellite it is for these calculations, the Frequency Number is used to assign this GLONASS Satellite a temporary Slot ID based on the GLONASS Frequency Numbers binary value of 0 to 20.

A.1.10 Reference primary signal measurement block: GLONASS PRN 38 – L1CA

The next bytes collected will be for the GLONASS PRN 38 - L1CA signal data. This is the primary signal of the satellite since it is the first signal. As a result, its Measurement Block consists of 111 bits as listed in *Table 197: Primary reference signal measurement block* on page 855. Since 111 bits takes up a lot of space, these bits will be split into two groups from *Table 197: Primary reference signal measurement block* on page 855: the top 25 bits for signal info followed by the bottom 86 bits for signal data.

The signal info section (top 25 bits) is processed as follows:

- With 1 bit left unprocessed from the previous byte, we calculate 25 – 1 = 24 bits which equals 3 bytes. Therefore the previous last byte (0xa0) plus the next 3 bytes will be needed.
  - Use the last byte (0xa0) plus grab 3 bytes (x19f813) = 0xa019f813
  - Swap the bytes = 0x13f819a0
  - 0x13f819a0 in binary form = 00010011111111000000110011010000 0
  - The previous step used the 7 LSBs = 00010011111111000000110011XXXXXXX
  - Need 25 bits which is exactly what is left over:

```
00010011111111000000110011XXXXXXX
                           1        = Parity Flag
                          1         = ½ Cycle Slip Flag
              10000001100           = C/No
         1111                       = Lock Time
     0011                           = Pseudorange Std Deviation
0001                                = Phaserange Std Deviation
```

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 1 (Cycle Slip Present)
- C/No is:
  0x10000001100b = 1036 x Scaling factor of 0.05
  = 51.80 dBHz
- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0011b = 3 which means: 0.045 m < PSR Std Dev <= 0.066 m using *Table 204: Pseudorange Std Dev* on page 862.
- The ADR Std Deviation value is:
  0x0001b = 1 which means: 0.0039 < ADR Std Dev <= 0.0052 cycles using *Table 203: ADR Std Dev* on page 861.

The signal data section (bottom 86 bits) is processed as follows:

- With no unprocessed bits from the previous byte, we need 86 bits which rounds up to 11 bytes.
  - Grab 11 bytes = 0x6a11273649b8fcefab9c43
  - Swap the bytes = 0x439cabeffcb8493627116a
  - 0x439cabeffcb8493627116a in binary form =

    0100 0011 1001 1100 1010 1011 1110 1111 1111 1100 1011 1000 0100 1001 0011 0110 0010 0111 0001 0001 0110 1010
  - Only need 86 bits. Ignore first 2 MSBs =

```
XX00 0011 1001 1100 1010 1011 1110 1111 1111 1100 1011 1000 0100 1001 0011 0110 0010 0111 0001 0001 0110 1010
                                                    0 1001 0011 0110 0010 0111 0001 0001 0110 1010 = 1st Pseudo
                                1111 1111 1100 1011 1000 010                                       = 1st Phase - 1st Pseudo
  00 0011 1001 1100 1010 1011 1110                                                                 = 1st Doppler
```

- Use *Table 197: Primary reference signal measurement block* on page 855 to identify if a 2's Complement Conversion is needed as well as what Scale Factor should be used before these binary numbers are used in the following calculations.
- The 1st (Primary) Pseudorange is processed by:

  1st Pseudorange = 0x0100100110110001001110001000101101010b x Scaling Factor
  1st Pseudorange = 39563235690 x 0.0005
  L1CA Pseudorange for PRN 38 = 19781617.845 m
- The 1st (Primary) Phaserange is a 2's Complement number (as identified by the Range column in *Table 197: Primary reference signal measurement block* on page 855) so it is processed in the following manner:

  1st Phaserange – 1st Pseudorange = 2's Complement(0x111111111100101111000010b) * Scaling Factor
  1st Phaserange – 19781617.845 m = -6718 * 0.0001
  L1CA Phaserange = 19781617.1732 m
- Convert this to ADR to check against the original RANGE log:

  ADR = 1st Phaserange * (Carrier Frequency + Frequency Number * 562500 Hz) * (-1)/Speed Of Light
  ADR = 19781617.1732 m * (1602000000 Hz + 1 * 562500 Hz) * (-1)/299792458 m/s
  ADR = 19781617.1732 m * 1602562500 Hz * (-1)/299792458 m/s
  L1CA ADR for PRN 38 = -105744080.6970745 cycles

  In the range logs, PSR and ADR have opposite signs.
- The 1st (Primary) Doppler is a 2's Complement number (as identified by the Range column in *Table 197: Primary reference signal measurement block* on page 855) so it is processed in the following manner:

  1st Doppler(m/s) = 2's Complement(0x00001110011100101010111110b) x Scaling Factor
  1st Doppler(m/s) = 3787454 m/s x 0.0001
  L1CA Doppler(m/s) = 378.7454 m/s

  Convert the Doppler to Hz:

  1st Doppler(Hz) = 1st Doppler(m/s) x (Carrier Frequency + Frequency Number * 562500 Hz) * (-1)/Speed Of Light
  1st Doppler(Hz) = 378.7454 m/s x (1602000000 Hz + 1 * 562500 Hz) * (-1)/299792458 m/s
  1st Doppler(Hz) = 378.7454 m/s x 1602562500 Hz * (-1)/299792458 m/s
  L1CA Doppler(Hz) for PRN 38 = -2024.6112 Hz

The rest of the GLONASS Reference Signals are handled in a similar manner as described in the above GPS section.

A.2 Differential log decoding

Logs not falling on a whole second are most likely Differential logs which are processed differently than the Reference logs. It is possible for a sub-second RANGECMP4 log to be a Reference log if the data contained within it did not fit the tight Differential Compression requirements.

Differential logs use the reference data of the same signal unlike reference logs which uses the first signal to define the other signals.

The next RANGECMP4 log is at time 507977.250:

```
#RANGECMP4A,COM1,0,88.5,FINESTEERING,1919,507977.250,02000020,fb0e,32768;239,
0300004212040000000009200dff688831f6102005500e70162dc977c004015c07988840f6101803
a805921cedf8b80002011207080e5f6351f003804081c2200be0808005c01620808725f93028057
801822dae0476000a00f207180fef6251700e803401c62f3bdc8060052013009986f5f220200540
04ca2053ec408005401ca870180410000000000980ff6306fec408004801de07c8692f51028051
80f721b2e04f600040152081804ef710250060054020220 5fe040a0086013a0938780f610200618
04e224edbdb68002010c0498030f7411d0018047812a2d47d090a004c01a609c8544f6202805200
6a02*48E189A2
```

At the start of the RANGECMP4 log is the identifier for how many bytes are in the log. In this case, there are 239 bytes (just under 20% less than a Reference Log). The rest of the message is compressed binary data and is transmitted as LSB first so the bytes must be swapped before processing.


A.2.1 Differential header

The Differential Header is sent once per message (See *Table 194: Header* on page 853).

Decoding the bits starting with the first bytes:

GNSS field (16 bits)

- Grab the first 2 bytes (16 bits) = 0x0300
- Swap the bytes = 0x0003
- 0x0003 in binary form =




In this example the receiver was configured to track only GPS and GLONASS systems. If other systems had been in the configuration and tracked, they would have shown here.

A.2.2 Differential satellite and signal block

This block is sent once for each bit set to 1 in the GNSS field found in *Table 194: Header* on page 853. As identified by the above GNSS field, the first system (right to left) is the GPS System. Use *Table 195: Satellite and signal block* on page 853 to determine what satellites and signals data are contained in this GPS System:

GPS Satellites field (64 bits)


- Grab the next 8 bytes (64 bits) = 0x0042120400000000
- Swap the bytes = 0x…0000000004124200
- 0x0000000004124200 in binary form =



- The 1's above identify that there are 5 tracking GPS PRNs.

GPS Signals field (16 bits)

- Grab the next 2 bytes (16 bits) = 0x9200
- Swap the bytes = 0x0092
- 0x0092 in binary form =



- The 1's above identify that there are 3 tracking GPS signals: L1CA, L2Y, and L5Q.

GPS Included Signals field (5 PRNs x 3 Signals = 15 bits – therefore need 2 bytes)

Up to the point of processing the Included Signals field, the bytes are aligned such that the bits start and end within each batch of bytes. After processing this step, it is quite common for the Included Signals field (mxn matrix) to not be divisible by 8 so bytes not processed will need to be carried over to the next section depending on the size of the matrix.

- Grab the next 2 bytes (16 bits) = 0xdff6
- Swap the bytes = 0xf6df
- 0xf6df in binary form = 1111011011011111
- Only need 15 of the 16 bits = X111011011011111
- This bit string breaks down into 5 rows (PRNs) and 3 columns (signals) as specified by the mxn (PRN x signals) parameters. Take the bit string and break it up into sets of 3 starting at the MSB. This will result with the lowest PRN being at the bottom row of the stack and the first signal (L1CA) being the far right column.

```
111
011
011
011
111
```

- This stack can be further broken apart to identify the PRNs vs. their Signals:

```
PRN    L5Q    L2Y    L1CA
27     1      1      1
21     0      1      1
18     0      1      1
```

```
15      0       1       1
10      1       1       1
```

A.2.3 Differential measurement block header

This block is sent once for each bit set to 1 in the Satellites field found in *Table 195: Satellite and signal block* on page 853. Now that the PRN's signals have been determined, the next step is to determine the specifics of the first PRN (10) and its list of signals (L1CA, L2Y, L5Q). Working from bottom right to upper left of the PRN/Signal chart above, each 1 represents a signal for a PRN. Use *Table 196: Measurement block header* on page 854 to determine the contents of each field:

GPS PRN 10 (first PRN found in the Satellites field)

We will grab enough bytes to process the whole Measurement Block Header. If this was a GLONASS system, a total of 9 bits would be required at this step (1 bit for the Data Format Flag, 3 bits for the Ref Data Block ID, plus 5 bits for the GLONASS Frequency Number). Since this is a GPS system, only 4 bits in total are required (1 bit for the Data Format Flag and 3 bits for the Ref Data Block ID).

There was 1 bit not processed in the last byte so that byte will be carried forward. Only 4 bits need to be looked at for this step so grab the next byte as well:

- Use the last byte (0xf6) plus the next byte (0x88)= 0xf688
- Swap the bytes = 0x88f6
- 0x88f6 in binary form = 1000 1000 1111 0110
- Ignore the processed bits from the last step = 1000 1000 1XXX XXXX
- Ignore the 5 MSB bits leaving 4 bits for processing =

```
XXXX X000 1XXX XXXX
          1          = Data Format Flag (1 bit)
     000             = Ref Data Block (3 bits)
```

The Data Format Flag identifies that this batch of data is Differential (1) data.

The Ref Data Block ID is 0x000. The Ref Data Block ID here identifies that this differential data will be calculated from the Reference data that had a Ref Data Block ID equalling 000 (which was determined in the RANGECMP4 log at time 507977.00 seconds).



The 5 MSBs have not been processed so this byte will be carried forward.

Logs between seconds will be Differential logs but could be Reference logs depending on the compression calculations. If a discontinuity occurred that made it impossible for a Differential calculation to fit within the Differential Constraints, it will revert to a Reference log.

A.2.4 Differential measurement block

This block is sent once for each bit set to 1 in the Included Signals field found in *Table 195: Satellite and signal block* on page 853. Use *Table 199: Primary differential signal measurement block* on page 857 and *Table 200: Secondary differential signals measurement block* on page 858 to determine the contents of each field:

A Measurement Block for a single PRN will look like the following:

Primary Parity Flag

Primary ½ Cycle Slip Flag

Primary C/No

Primary Lock Time

Primary Pseudorange Std Deviation

Primary Phaserange Std Deviation

Primary Pseudorange

Primary Phaserange - Primary Pseudorange (determines the Phaserange for the 1st Signal)

Primary Doppler

2nd Parity Flag

2nd ½ Cycle Slip Flag

2nd C/No

2nd Lock Time

2nd Pseudorange Std Deviation

2nd Phaserange Std Deviation

2nd Pseudorange - Primary Pseudorange (determines the Pseudorange for the 2nd Signal

2nd Phaserange – 2nd Pseudorange (determines the Phaserange for the 2nd Signal)

2nd Doppler – Primary Doppler (determines the Doppler for the 2nd Signal)

3rd Parity Flag

3rd ½ Cycle Slip Flag

3rd C/No

3rd Lock Time

3rd Pseudorange Std Deviation

3rd Phaserange Std Deviation

3rd Pseudorange - Primary Pseudorange (determines the Pseudorange for the 3rd Signal

3rd Phaserange – 3rd Pseudorange (determines the Phaserange for the 3rd Signal)

3rd Doppler – Primary Doppler (determines the Doppler for the 3rd Signal)

…

A.2.5 Differential primary signal measurement block GPS PRN 10 – L1CA

The next bytes collected will be for the GPS PRN 10 - L1CA signal data. Since this is the primary signal of the PRN, its Measurement Block consists of 78 bits as listed in *Table 199: Primary differential signal measurement block* on page 857.

The signal info section (top 25 bits) is processed as follows:

- With 5 bits left from the previous byte, we calculate 25 – 5 = 20 bits which rounds up to 3 bytes. Therefore the previous last byte (0x88) plus the next 3 bytes will be needed.
  - Use the last byte (0x88) plus grab 3 bytes (x831f61) = 0x88831f61
  - Swap the bytes = 0x611f8388

- 0x611f8388 in binary form

  = 0110 0001 0001 1111 1000 0011 1000 1000

- Only need 25 bits. The last byte uses the 5 MSBs and the first byte ignores the 4 MSBs

```
XXXX 0001 0001 1111 1000 0011 1000 1XXX
                                    1     = Parity Flag
                                   0      = ½ Cycle Slip Flag
                         1000 0011 100    = C/No
                    1111                  = Lock Time
               0001                       = Pseudorange Std Deviation
          0001                            = Phaserange Std Deviation
```

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 0 (Cycle Slip Not Present)
- C/No is:
  0x10000011100b = 1052 x Scaling factor of 0.05
  = 52.60 dBHz
- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0001b = 1 which means: 0.020 m < PSR Std Dev <= 0.030 m using *Table 204: Pseudorange Std Dev* on page 862.
- The ADR Std Deviation value is:
  0x0001b = 1 which means: 0.0039 < ADR Std Dev <= 0.0052 cycles using *Table 203: ADR Std Dev* on page 861Table 10.
- For the following calculations, the time difference between the Differential Log and the Reference log is 0.25 seconds as shown below:
  Time Difference = Current Log Time – Reference log Time
  = 507977.250 - 507977.000
  = 0.250 seconds

The signal data section (bottom 53 bits) is processed as follows:

- With 4 bits unprocessed from the previous byte, we calculate 53 – 4 = 49 bits = 7 bytes (7 bits will not be processed in the last byte).
  - Use the last byte (0x61) plus grab 7 bytes (0x02005500e70162)
    = 0x6102005500e70162
  - Swap the bytes = 0x6201e70055000261
  - 0x6201e70055000261 in binary form =

    0110 0010 0000 0001 1110 0111 0000 0000 0101 0101 0000 0000 0000 0010 0110 0001
  - Only need 53 bits. Ignore last 4 LSBs and first 7 MSBs =

```
XXXX XXX0 0000 0001 1110 0111 0000 0000 0101 0101 0000 0000 0000 0010 0110 XXXX
                                                 000 0000 0000 0010 0110      = 1st Pseudo - Predicted Pseudo
                            000 0000 0101 0101 0                              = 1st Phase - Predicted Phase
        0 0000 0001 1110 0111 0                                               = 1st Doppler - Ref Doppler
```

- Use *Table 199: Primary differential signal measurement block* on page 857 to identify if a 2's Complement Conversion is needed as well as what Scale Factor should be used before these binary numbers are used in the following calculations.

- The 1st (Primary) Differential Pseudorange is processed by:

  Predicted Pseudorange = Reference 1st Pseudorange + (1st Doppler x TimeDifference)
  = 21540181.930275 m
  = 21540290.811 m + ((-435.5229 m/s) x 0.250 s)

  1st DiffPseudorange – Predicted Pseudorange = 0x0000000000000100110b x Scaling Factor
  1st DiffPseudorange – 21540181.930275 m = 38 x 0.0005
  L1CA Pseudorange for PRN 10 = 21540181.949275 m

- The 1st (Primary) Differential Phaserange is a 2's Complement number (as identified by the Range column in *Table 199: Primary differential signal measurement block* on page 857) so it is processed in the following manner:

  Predicted Phaserange = Reference 1st DiffPhaserange + (1st Doppler x TimeDifference)
  = 21540291.5622 m + ((-435.5229 m/s) x 0.250 s)
  = 21540182.681475 m

  1st DiffPhaserange – Predicted Phaserange = 2's Complement(0x0000000010101010b) * Scaling Factor
  1st DiffPhaserange – 21540182.681475 m = 170 * 0.0001
  L1CA Phaserange = 21540182.698475 m

- Convert this to ADR to check against the original RANGE log:

  ADR = 1st DifPhaserange * Frequency * (-1)/Speed Of Light
  ADR = 21540182.698475 m * 1575420000 Hz * (-1)/299792458 m/s
  L1CA ADR for PRN 10 = -113194424.0799796 cycles

  In the range logs, PSR and ADR have opposite signs.

- The 1st (Primary) Differential Doppler is a 2's Complement number (as identified by the Range column in *Table 199: Primary differential signal measurement block* on page 857) so it is processed in the following manner:

  1st DiffDoppler(m/s)- Reference 1st Doppler = 2's Complement(0x0000000011111001110b) x Scaling Factor
  1st DiffDoppler(m/s) – (-435.5229 m/s) = 974 x 0.0001
  L1CA Doppler(m/s) = -435.4255 m/s

  Convert the Doppler to Hz:

  1st DiffDoppler(Hz) = 1st DiffDoppler(m/s) x Frequency * (-1)/Speed Of Light
  1st DiffDoppler(Hz) = -435.4255 m/s x 1575420000 Hz * (-1)/299792458 m/s
  L1CA Doppler(Hz) for PRN 10 = 2288.1764464 Hz

A.2.6 Differential secondary signals measurement block GPS PRN 10 – L2Y

Unlike Reference logs which always reflect back to the initial signal for their computations, Differential logs uses the last Reference log data of the same signal for its calculations.

- With 7 bits unprocessed from the previous byte, we will require 74 – 7 = 67 bits which rounds up to 9 bytes.
  - Use the last byte (0x62) plus grab the next 9 bytes (0xdc977c004015c07988)
    = 0x62dc977c004015c07988
  - Swap the bytes = 0x8879c01540007c97dc62

- 0x8879c01540007c97dc62 in binary form =
  1000 1000 0111 1001 1100 0000 0001 0101 0100 0000 0000 0000 0111 1100 1001 0111 1101 1100 0110 0010
- Only need 74 bits. The 1 LSB is ignored as it was already processed above and the 5 MSBs are ignored so there is a total of 74 bits to process

```
XXXX X000 0111 1001 1100 0000 0001 0101 0100 0000 0000 0000 0111 1100 1001 0111 1101 1100 0110 001X
                                                                                                1  = Parity Flag
                                                                                               0   = ½ Cycle Slip Flag
                                                                                 01 1100 0110 0    = C/No
                                                                           11 11                   = Lock Time
                                                                     01 01                         = Pseudorange Std Deviation
                                                               00 10                               = Phaserange Std Deviation
                                                  0 0000 0000 0000 0111 11                         = Pseudo - Predicted Pseudo
                                        0 0000 0001 0101 010                                       = Phase - Predicted Phase
      000 0111 1001 110                                                                            = Doppler - Ref Doppler
```

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 0 (Cycle Slip Not Present)
- C/No is:
  0x01110001100b = 908 x Scaling Factor of 0.05
  = 45.4 dBHz
- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0101b = 5 which means: 0.099 m < PSR Std Dev <= 0.148 m using *Table 204: Pseudorange Std Dev* on page 862.
- The ADR Std Deviation value is:
  0x0010b = 2 which means: 0.0052 < ADR Std Dev <= 0.0070 cycles using *Table 203: ADR Std Dev* on page 861.
- The L2Y Pseudorange is a 2's Complement number (as identified by the Range column in *Table 200: Secondary differential signals measurement block* on page 858) so it is processed in the following manner:

  Predicted Pseudorange = Reference 2nd Pseudorange + (2nd Doppler x TimeDifference)
  = 21540293.6315 m + ((-435.523 m/s) x 0.250 s)
  = 21540184.75075 m

  DiffPseudorange – Predicted Pseudorange = 2's Complement(0x0000000000000011111b) x Scaling Factor
  DiffPseudorange – 21540184.75075 m = 31 x 0.0005
  L2Y Pseudorange = 21540184.76625 m
- The L2Y Phaserange is a 2's Complement number (as identified by the Range column in *Table 200: Secondary differential signals measurement block* on page 858) so it is calculated in the following manner:

  Predicted Phaserange = Reference 2nd DiffPhaserange + (2nd Doppler x TimeDifference)
  = 21540294.399 m + ((-435.523 m/s) x 0.250 s)
  = 21540185.51825 m

  DiffPhaserange – Predicted Phaserange = 2's Complement(0x0000000010101010b) * Scaling Factor
  DiffPhaserange – 21540185.51825 m = 170 * 0.0001
  L2Y Phaserange = 21540185.53525 m
- Convert this to ADR to check against the original RANGE log:

ADR = Phaserange * Frequency * (-1)/Speed Of Light
ADR = 21540185.53525 m * 1227600000 Hz * (-1)/299792458 m/s
L2Y ADR for PRN 10 = -88203458.95116848 cycles

In the range logs, PSR and ADR have opposite signs.

- The L2Y Doppler is a 2's Complement number (as identified by the Range column in *Table 200: Secondary differential signals measurement block* on page 858) so it is calculated in the following manner:

  DiffDoppler(m/s) – Ref 2nd Doppler(m/s) = 2's Complement(0x00001111001110b) x Scaling Factor
  DiffDoppler(m/s) – (-435.5229 m/s) = (974) x 0.0001
  L2Y Doppler(m/s) = -435.4255 m/s

  Convert the Doppler to Hz:

  Doppler(Hz) = Doppler(m/s) x Frequency * (-1)/Speed Of Light
  Doppler(Hz) = -435.4255 m/s x 1227600000 Hz * (-1)/299792458 m/s
  L2Y Doppler(Hz) for PRN 10 = 1782.994633 Hz

A.2.7 Differential third signals measurement block GPS PRN 10 – L5Q

Unlike Reference logs which always reflect back to the initial signal for their computations, Differential logs uses the last Reference log data of the same signal for its calculations.

- With 3 bits unprocessed from the previous byte, we will require 74 – 3 = 71 bits which rounds up to 9 bytes.
  - Use the last byte (0x88) plus grab the next 9 bytes (0x 840f6101803a805921) = 0x88840f6101803a805921
  - Swap the bytes = 0x2159803a8001610f8488
  - 0x2159803a8001610f8488 in binary form = 0010 0001 0101 1001 1000 0000 0011 1010 1000 0000 0000 0001 0110 0001 0000 1111 1000 0100 1000 1000
  - Only need 74 bits. The 3 LSBs are ignored as they were already processed and the 3 MSBs are ignored so there is a total of 74 bits to process.

```
XXX0 0001 0101 1001 1000 0000 0011 1010 1000 0000 0000 0001 0110 0001 0000 1111 1000 0100 1000 1XXX
                                                                                          1     = Parity Flag
                                                                                        0       = ½ Cycle Slip Flag
                                                                          1000 0100 100         = C/No
                                                                     1111                       = Lock Time
                                                                0000                            = Pseudorange Std Deviation
                                                           0001                                 = Phaserange Std Deviation
                                          000 0000 0000 0001 0110                               = Pseudo - Predicted Pseudo
                          000 0000 0011 1010 1                                                  = Phase - Predicted Phase
   0 0001 0101 1001 1                                                                           = Doppler - Ref Doppler
```

- Parity flag is a 1 (Parity Known)
- ½ Cycle Slip flag is a 0 (Cycle Slip Not Present)
- C/No is:
  0x10000100100b = 1060 x Scaling factor of 0.05
  = 53.0 dBHz
- The Lock Time value is:
  0x1111b = 15 which means that this signal has been locked for 262144 ms or more.
- The Pseudorange Std Deviation value is:
  0x0000b = 0 which means: PSR Std Dev <= 0.020 m using *Table 204: Pseudorange Std Dev* on page

862.

- The ADR Std Deviation value is:
  0x0001b = 1 which means: 0.0039 < ADR Std Dev <= 0.0052 cycles using *Table 203: ADR Std Dev* on page 861.
- The L5Q Pseudorange is a 2's Complement number (as identified by the Range column in *Table 200: Secondary differential signals measurement block* on page 858) so it is processed in the following manner:

  Predicted Pseudorange = Reference 3rd Pseudorange + (3rd Doppler x TimeDifference)
  = 21540289.869 m + ((-435.5149 m/s) x 0.250 s)
  = 21540180.990275 m

  DiffPseudorange – Predicted Pseudorange = 2's Complement(0x000 0000 0000 0001 0110b) x Scaling Factor
  DiffPseudorange – 21540180.990275 m = 22 x 0.0005
  L5Q Pseudorange = 21540181.001275 m
- The L5Q Phaserange is a 2's Complement number (as identified by the Range column in *Table 200: Secondary differential signals measurement block* on page 858) so it is calculated in the following manner:

  Predicted Phaserange = Reference 3rd DiffPhaserange + (3rd Doppler x TimeDifference)
  = 21540290.8584 m + ((-435.5149 m/s) x 0.250 s)
  = 21540181.979675 m

  DiffPhaserange – Predicted Phaserange = 2's Complement(0x0000000001110101b) * Scaling Factor
  DiffPhaserange – 21540181.979675 m = 117 * 0.0001
  L5Q Phaserange = 21540181.991375 m
- Convert this to ADR to check against the original RANGE log:

  ADR = Phaserange * Frequency * (-1)/Speed Of Light
  ADR = 21540181.991375 m * 1176450000 Hz * (-1)/299792458 m/s
  L5Q ADR for PRN 10 = -84528300.92127641 cycles

  In the range logs, PSR and ADR have opposite signs.
- The L5Q Doppler is a 2's Complement number (as identified by the Range column in *Table 200: Secondary differential signals measurement block* on page 858) so it is calculated in the following manner:

  DiffDoppler(m/s) – Ref 3rd Doppler(m/s) = 2's Complement(0x00001010110011b) x Scaling Factor
  DiffDoppler(m/s) – (-435.5149 m/s) = 691 x 0.0001
  L5Q Doppler(m/s) = -435.4458 m/s

  Convert this to Hz:

  Doppler(Hz) = Doppler(m/s) x Frequency * (-1)/Speed Of Light
  Doppler(Hz) = -435.4458 m/s x 1176450000 Hz * (-1)/299792458 m/s
  L5Q Doppler(Hz) for PRN 10 = 1708.78285 Hz

This concludes the decoding of the Differential Log for PRN 10 (signals L1CA, L2Y, and L5Q). The rest of the decoding for the other PRNs and systems are handled in the same manner.


HEXAGON
NovAtel